



Vinculums **SF Palo Alto 061** Looking Northaast from Middlefield Road
Adjacent to 1221 Middlefield Road Palo Alto, CA **View #1**
9/3/20 Applied Imagination SID 9144890



Vinculums **SF Palo Alto 061** Looking East from Middlefield Road
Adjacent to 1221 Middlefield Road Palo Alto, CA **View #2**
9/3/20 Applied Imagination SID 9144890

verizon

2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

Vinculums

575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500

ALL STATES
ENGINEERING & SURVEYING
A ZALZALI & ASSOCIATES COMPANY

23675 BIRTCHER DRIVE
LAKE FOREST, CA 92630
PHONE: (949) 273-0996

PROJECT ID:	P-334882
DRAWN BY:	RF
CHECKED BY:	DW

2	08/31/2020	100% CD'S FOR SUBMITTAL	MG
1	06/11/2020	100% CD'S FOR SUBMITTAL	RF
0	05/22/2020	100% CD'S FOR APPROVAL	RF
B	05/04/2020	95% CD'S FOR REDLINE	RF
A	04/29/2020	90% CD'S FOR REDLINE	RF
REV	DATE	DESCRIPTION	

REGISTERED PROFESSIONAL ENGINEER
WISSAM ZALZALI
71655
CIVIL
STATE OF CALIFORNIA


IT IS A VIOLATION OF LAW FOR ANY PERSON,
UNLESS THEY ARE ACTING UNDER THE
DIRECTION OF A LICENSED PROFESSIONAL
ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 061
LIC R.O.W. ADJACENT TO:
1221 MIDDLEFIELD RD.
PALO ALTO, 94301
LOCATION CODE: 425208

SHEET TITLE
PHOTOSIMS


SHEET NUMBER
T-2

T-3




LEGEND

U.G. UTILITY VAULT	BLDG	TOP OF BUILDING
MANHOLE	MON	MONUMENT
UTILITY POLE	FL	FLOW LINE
SPOT ELEVATION	EOP	EDGE OF PAVEMENT
WATER VALVE	R.O.W.	RIGHT OF WAY
FOUND MONUMENT	R/W	RIGHT OF WAY
GEODETIC MARKER	SCO	SEWER CLEAN-OUT
CHAIN LINK FENCE	PS	PARKING STRIPE
WOOD FENCE	SW	SIDEWALK
OVERHEAD LINE	VLT	U.G. UTILITY VAULT
METAL FENCE	OHE	OVERHEAD ELECTRICAL
GRADE BREAK	SVC	SERVICE
RIGHT OF WAY LINE	AC	ASPHALTIC CONCRETE
CENTER LINE	AP	ASPHALT PAVING
EASEMENT LINE	CONC	CONCRETE
MASONRY WALL	PED	PEDESTAL
WATER VALVE	OH	OVERHEAD
UTILITY POLE	PUE	PUBLIC UTILITY EASEMENT
LIGHT POLE	FC	FACE OF CURB
LUMINAIRE	BOL	BOLLARD
NATURAL GRADE	TOP	TOP OF ITEM
	BOT	BOTTOM OF ITEM



RIGHT OF WAY NOTE:
ROAD CENTERLINES SHOWN ON
THIS SURVEY HAVE BEEN PLACED
BY SPLIT OF IMPROVEMENTS.



VICINITY MAP

TITLE REPORT

NOT APPLICABLE (RIGHT-OF-WAY)

LEGAL DESCRIPTION

NOT APPLICABLE (RIGHT-OF-WAY)

ASSESSOR'S PARCEL NO.

NOT APPLICABLE (RIGHT-OF-WAY)

UTILITY NOTE:

SURVEYOR DOES NOT GUARANTEE THAT ALL UTILITIES ARE SHOWN OR THEIR LOCATIONS ARE DEFINITE. IT IS THE RESPONSIBILITY OF THE CONTRACTOR AND DEVELOPER TO CONTACT BLUE STAKE AND ANY OTHER INVOLVED AGENCIES TO LOCATE ALL UTILITIES PRIOR TO CONSTRUCTION. REMOVAL, RELOCATION AND/ OR REPLACEMENT IS THE RESPONSIBILITY OF THE CONTRACTOR.

NOTES:

- THIS IS NOT A BOUNDARY SURVEY. THIS IS A SPECIALIZED RIGHT OF WAY MAP. THE PROPERTY LINES AND EASEMENTS SHOWN HEREON ARE FROM RECORD INFORMATION AS NOTED HEREON. ALL STATES ENGINEERING & SURVEYING/ZALZALI & ASSOCIATES, INC. TRANSLATED THE TOPOGRAPHIC SURVEY TO RECORD INFORMATION USING MONUMENT(S)/LANDMARK(S) SHOWN HEREON. NO TITLE RESEARCH WAS PERFORMED BY ALL STATES ENGINEERING & SURVEYING/ZALZALI & ASSOCIATES, INC.
- ANY CHANGES MADE TO THE INFORMATION ON THIS PLAN, WITHOUT THE WRITTEN CONSENT OF ALL STATES ENGINEERING & SURVEYING / ZALZALI & ASSOCIATES, INC. RELIEVES ALL STATES ENGINEERING & SURVEYING/ ZALZALI & ASSOCIATES, INC. OF ANY AND ALL LIABILITY.
- THESE DRAWINGS & SPECIFICATIONS ARE THE PROPERTY & COPYRIGHT OF ALL STATES ENGINEERING & SURVEYING / ZALZALI & ASSOCIATES, INC. & SHALL NOT BE USED ON ANY OTHER WORK EXCEPT BY AGREEMENT WITH THE SURVEYOR. WRITTEN DIMENSIONS SHALL TAKE PREFERENCE OVER SCALED & SHALL BE VERIFIED ON THE JOB SITE. ANY DISCREPANCY SHALL BE BROUGHT TO THE NOTICE OF THE SURVEYOR PRIOR TO COMMENCEMENT OF ANY WORK.
- THIS SITE IS PROPOSED TO BE DEVELOPED ON A STREET LIGHT POLE LOCATED WITHIN THE PUBLIC RIGHT OF WAY.

SURVEY DATE

08/16/2020

BASIS OF BEARING

BEARINGS SHOWN HEREON ARE BASED UPON U.S. STATE PLANE NAD83 COORDINATE SYSTEM CALIFORNIA STATE PLANE COORDINATE ZONE THREE, DETERMINED BY GPS OBSERVATIONS.

BENCHMARK

RTCM-REF 3270
NORTHING: 1970498.865
EASTING: 6082238.002
+248.11' (A.M.S.L.)

REFERENCE MAPS

- 868 - RS - 41

verizon

2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

Vinculum

575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500

ALLSTATES
ENGINEERING & SURVEYING

23675 BIRTCHEER DRIVE
LAKE FOREST, CA 92630

PROJECT NO: SF PALO ALTO 061

DRAWN BY: MG

CHECKED BY: BC/WZ/DW

O	08/27/2020	FINAL SURVEY	MA
A	08/27/2020	PRELIMINARY SURVEY	MG
REV	DATE	DESCRIPTION	



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 061
R.O.W. ADJACENT TO:
1221 MIDDLEFIELD RD
PALO ALTO, CA 94301
NEW BUILD-SMALL CELL

SHEET TITLE

SITE SURVEY

SHEET NUMBER

LS-1

TREE NOTES:

1. THERE WILL BE NO TREE PRUNING WITHOUT THE SPECIFIC APPROVAL OF THE PALO ALTO URBAN FORESTRY DEPARTMENT ON ALL REGULATED TREES. ANY VIOLATION TO THIS POLICY WILL BE SUBJECT TO PENALTY. CONTACT THE PALO ALTO URBAN FORESTRY DEPARTMENT AT (650) 496-5953.
2. THIS CONSTRUCTION PROJECT TRIGGERS MANDATORY TREE PROTECTION MEASURES. SEE TREE PROTECTION PLAN & CONTACT THE PALO ALTO URBAN FORESTRY DEPARTMENT. AT (650) 496-5953 WITH ANY QUESTIONS.
3. EXCAVATION ACTIVITIES ASSOCIATED WITH THE PROPOSED SCOPE OF WORK SHALL OCCUR NO CLOSER THAN 10-FEET FROM THE EXISTING STREET TREE, OR AS APPROVED BY THE URBAN FORESTRY DIVISION CONTACT 650-496-5953. ANY CHANGES SHALL BE APPROVED BY THE SAME.
4. PROJECT ARBORIST:
KATHERINE NAEGELE
KATHERINE@ANDERSONTREECARE.COM
PHONE: (408) 590-5976
5. NO FEASIBLE GREEN SCREEN OPPORTUNITIES EXIST

NOTES:

1. METAL SURFACES REQUIRING PAINT TO BE PAINTED WITH A MUNSELL GREEN PAINT.
2. ANY CONSTRUCTION WITHIN THE CITY'S PUBLIC ROAD RIGHT-OF-WAY SHALL HAVE AN APPROVED PERMIT FOR CONSTRUCTION IN THE PUBLIC STREET PRIOR TO COMMENCEMENT OF THIS WORK

TREE TABLE


PALO ALTO TREE #	CITY TREE ID:	SPECIES:	COMMON NAME:	GROW SPACE:	TRUNK DIA. AT BREAST HT.:	DRIP LINE:	DISTANCE TO CONST.	PROTECTION MEASURES REQUIRED
PALO ALTO TREE #1	-	TILIA CORDATA	LITTLELEAF LINDEN	-	3.9"	3' 3"	-	-
PALO ALTO TREE #2	-	TILIA CORDATA	LITTLELEAF LINDEN	-	15.9"	13' 3"	-	TYPE 2

NEW TREE TABLE

TREE	CITY TREE ID:	SPECIES:	COMMON NAME:	COMMENTS:
PROPOSED TREE #1	TBD	HETEROMELES ARBUTIFOLIA OR MYRICA CALIFORNIA	TOYON OR PACIFIC WAX MYRTLE	REPLACEMENT FOR STREET TREE #1

NOTE:

ALL ITEMS AND DIMENSIONS SHOULD BE VERIFIED IN THE FIELD, PRIOR TO STARTING CONSTRUCTION.



SITE PLAN

24"x36" SCALE: 3/32" = 1'-0"
11"x17" SCALE: 3/64" = 1'-0"
8" 4" 0" 8" 1

verizon

2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

Vinculums

575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500

ALL STATES
ENGINEERING & SURVEYING
A ZALZALI & ASSOCIATES COMPANY


23675 BIRTCHER DRIVE
LAKE FOREST, CA 92630
PHONE: (949) 273-0996

PROJECT ID: P-334882

DRAWN BY: RF

CHECKED BY: DW

REV	DATE	DESCRIPTION	
2	08/31/2020	100% CD'S FOR SUBMITTAL	MG
1	06/11/2020	100% CD'S FOR SUBMITTAL	RF
0	05/22/2020	100% CD'S FOR APPROVAL	RF
B	05/04/2020	95% CD'S FOR REDLINE	RF
A	04/29/2020	90% CD'S FOR REDLINE	RF



IT IS A VIOLATION OF LAW FOR ANY PERSON,
UNLESS THEY ARE ACTING UNDER THE
DIRECTION OF A LICENSED PROFESSIONAL
ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 061
LIC R.O.W. ADJACENT TO:
1221 MIDDLEFIELD RD.
PALO ALTO, 94301
LOCATION CODE: 425208

SHEET TITLE

SITE PLAN

SHEET NUMBER

A-1



23675 BIRTCHER DRIVE
LAKE FOREST, CA 92630
PHONE: (949) 273-0996

CHECKED BY: DW

2	08/31/2020	100% CD'S FOR SUBMITTAL	MG
1	06/11/2020	100% CD'S FOR SUBMITTAL	RF
0	05/22/2020	100% CD'S FOR APPROVAL	RF
B	05/04/2020	96% CD'S FOR REDLINE	RF
A	04/29/2020	90% CD'S FOR REDLINE	RF
REV	DATE	DESCRIPTION	




IT IS A VIOLATION OF LAW FOR ANY PERSON,
UNLESS THEY ARE ACTING UNDER THE
DIRECTION OF A LICENSED PROFESSIONAL
ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 061
LIC R.O.W. ADJACENT TO:
1221 MIDDLEFIELD RD.
PALO ALTO, 94301
LOCATION CODE: 425208

SHEET TITLE
EXISTING UTILITY
SITE PLAN

SHEET NUMBER

A-1.1



EXISTING UTILITY SITE PLAN

24"x36" SCALE: $\frac{3}{32}" = 1'-0"$
11"x17" SCALE: $\frac{3}{64}" = 1'-0"$

1

Kingsley Ave

Middlefield Rd



1-800-227-2600
UNDERGROUND SERVICE ALERT

THIS MAP IS PROVIDED FOR REFERENCE ONLY.
THE CITY OF PALO ALTO DOES NOT WARRANTY
THE ACCURACY OF THIS MAP



- ### Legend
- Assessment Parcel (AP)
 - Building Roof Outline (BL)
 - Address Label (AP)
 - Curb Face (RF)
 - Curb Edge (RF)
 - Curb Edge, Rooted (RF)
 - Pavement Edge (RF)
 - Sidewalk Edge (RF)
 - Road Centerline Small Text (TC)
 - Easement Boundary Line (CG)
 - Dimensions (AP)
 - Easement Text (CG)
 - Pipeline (SD)
 - Catch Basin (SD)
 - Manhole (SD)
 - Pipe, Main (TB WT)
 - Pipe, Service (TB WT)
 - Crossing Casing (TB WT)NAD
 - Hydrant (TB WT)
 - Valve (TB WT):
 - Fire Service
 - Hydrant Branch
 - Main
 - Service
 - Buried Alive
 - Meter, Main (TB WT)NAD
 - Meter, Service (TB WT)NAD
 - Wet (TB WT)NAD
 - Air Relief Valve (TB WT)
 - Valve Blowoff (TB WT)
 - Riser (TB GS)
 - Pipe, Service (TB GS)
 - Casing (TB GS)NAD
 - Fence (TB UF)NAD
 - Meter (TB GS):
 - Above Ground Service
 - Curb Service
 - Pipe, Main (TB GS)
 - Valve (TB GS):
 - Main
 - Service
 - Dead End One Way
 - Emergency Shut Off Valve (ESV)
 - Buried Alive
 - Pipe, Lateral (TB WW)
 - Pipe, Main (TB WW)
 - Crossing Casing (TB WW)
 - Crossing, Lateral (TB WW)
 - Structure, Main (TB WW):
 - Manhole
 - Cleanout
 - Lamp Hole
 - Flushing Inlet
 - Pipe cap
 - Concrete plug
 - Non-structural node
 - Point Tap (TB WW)
 - Text (TB WW)

CPA WGW Utility Information
1221 Middlefield Rd
NODE 061
For Reference Use Only

This map is a product of the
City of Palo Alto GIS

olejand, 2020-03-23 17:40:52
New Base Map Req (loc-maps\Encompass\Admin\Personals\olejand.mxd)

This document is a graphic representation only of best available sources.
The City of Palo Alto assumes no responsibility for any errors. ©1989 to 2016 City of Palo Alto

verizon
2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

Vinculums
575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500

ALL STATES
ENGINEERING & SURVEYING
A ZALZALI & ASSOCIATES COMPANY
23675 BIRTCHE DRIVE
LAKE FOREST, CA 92630
PHONE: (949) 273-0996

PROJECT ID:	P-334882
DRAWN BY:	RF
CHECKED BY:	DW

2	08/31/2020	100% CD'S FOR SUBMITTAL	MG	
1	06/11/2020	100% CD'S FOR SUBMITTAL	RF	
0	05/22/2020	100% CD'S FOR APPROVAL	RF	
B	05/04/2020	95% CD'S FOR REDLINE	RF	
A	04/29/2020	90% CD'S FOR REDLINE	RF	
REV	DATE	DESCRIPTION		


REGISTERED PROFESSIONAL ENGINEER
WESAM ZALZALI
71655
CIVIL
STATE OF CALIFORNIA

IT IS A VIOLATION OF LAW FOR ANY PERSON,
UNLESS THEY ARE ACTING UNDER THE
DIRECTION OF A LICENSED PROFESSIONAL
ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 061
LIC R.O.W. ADJACENT TO:
1221 MIDDLEFIELD RD.
PALO ALTO, 94301
LOCATION CODE: 425208

SHEET TITLE
UTILITY PLAN
(FOR REFERENCE)

SHEET NUMBER
A-1.2



LOCATION MAP

24"x36" SCALE: 1" = 80'-0"
11"x17" SCALE: 1" = 160'-0"



verizon

2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

Vinculums

575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500

ALL STATES
ENGINEERING & SURVEYING
A ZALZALI & ASSOCIATES COMPANY

23675 BIRTCHER DRIVE
LAKE FOREST, CA 92630
PHONE: (949) 273-0996

PROJECT ID:	P-334882
DRAWN BY:	RF
CHECKED BY:	DW

2	08/31/2020	100% CD'S FOR SUBMITTAL	MG	
1	06/11/2020	100% CD'S FOR SUBMITTAL	RF	
0	05/22/2020	100% CD'S FOR APPROVAL	RF	
B	05/04/2020	95% CD'S FOR REDLINE	RF	
A	04/29/2020	90% CD'S FOR REDLINE	RF	
REV	DATE	DESCRIPTION		

REGISTERED PROFESSIONAL ENGINEER
NASSAM ZALZALI
71655
CIVIL
STATE OF CALIFORNIA

IT IS A VIOLATION OF LAW FOR ANY PERSON,
UNLESS THEY ARE ACTING UNDER THE
DIRECTION OF A LICENSED PROFESSIONAL
ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 061
LIC R.O.W. ADJACENT TO:
1221 MIDDLEFIELD RD.
PALO ALTO, 94301
LOCATION CODE: 425208

SHEET TITLE
LOCATION MAP

SHEET NUMBER
A-1.3

- ## ② NOTES




















Sawcutting & Asphalt/Concrete Removal

- ☐ Protect storm drain inlets during saw cutting.
- ☐ If saw cut slurry enters a catch basin, clean it up immediately.
- ☐ Shovel or vacuum saw cut slurry deposits and remove from the site. When making saw cuts, use as little water as possible. Sweep up, and properly dispose of all residues.

VICINITY MAP

PROJECT SPECIFIC PERMIT INFORMATION		
DESCRIPTION	QTY	UNIT
PLACE (1) 4" SCH 40 CONDUIT	10	LF
PLACE (1) 2" SCH 40 CONDUIT	4	LF
REMOVE AND RESTORE SOIL	160	FT³




- | | | | | | | | |
|---|--------------------|-------|--------------------|---|------------------|---|-----------------|
|  | U.G. UTILITY VAULT | BOL | BOLLARD | FL | FLOW LINE |  | WATER |
|  | MANHOLE | TOP | TOP OF ITEM | EOP | EDGE OF PAVEMENT |  | SANITARY SEWER |
|  | UTILITY POLE | BOT | BOTTOM OF ITEM | R.O.W. | RIGHT OF WAY |  | STORM DRAIN |
|  | SPOT ELEVATION | BLDG | TOP OF BUILDING | AW | ASPHALT |  | GAS |
|  | WATER VALVE | LP | LIGHT POLE | SW | SIDEWALK |  | COMMUNICATION |
|  | FOUND MONUMENT | --- | LIMITS OF PROPERTY |  | OVERHEAD LINE |  | ELECTRIC |
|  | GEODETTIC MARKER | — x — | CHAIN LINK FENCE |  | METAL FENCE |  | UNKNOWN UTILITY |
|  | MASONRY WALL | — | WOOD FENCE |  | GRADE BREAK |  | IRRIGATION |

- NOTES:**
1. EXCAVATION RESTRICTIONS APPLY (TTM, SEC. 2.20 C & D). ANY APPROVED GRADING, DIGGING OR TRENCHING BENEATH A TREE CANOPY SHALL BE PERFORMED USING "AIR-SPADE" METHOD AS A PREFERENCE, WITH MANUAL HAND SHOVEL AS A BACKUP. FOR UTILITY TRENCHING, INCLUDING SEWER LINE, ROOTS EXPOSED WITH DIAMETER OF 1.5 INCHES AND GREATER SHALL REMAIN INTACT AND NOT BE DAMAGED.
 2. SEE ATTACHED TREE PROTECTION PLAN FOR INSTRUCTIONS ON TREE PROTECTION.

NOTE:

ALL PROPOSED POWER RUNS TO
MAINTAIN A MIN. 2' CLR. ALL
AROUND AS REQUIRED BY CPAU



LEGEND



2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598



575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500

 **ALLSTATES**
ENGINEERING & SURVEYING
23675 BIRCHER DRIVE
LAKE FOREST, CA 92630

PROJECT ID: P-334882

DRAWN BY: RF

CHECKED BY: DW

O	08/17/2020	FINAL BORING PLAN	SS
A	08/14/2020	PRELIMINARY BORING PLAN	SS
REV	DATE	DESCRIPTION	



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS
THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED
PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 061


LIC R.O.W. ADJACENT TO:
1221 MIDDLEFIELD RD.
PALO ALTO, 94301
LOCATION CODE: 425208

SHEET TITLE


BORING SITE PLAN

SHEET NUMBER


A-1.4




7 CITY STANDARD DWG 401
N.T.S.




6 CITY STANDARD DWG 403
N.T.S.




5 CITY STANDARD DWG 402
N.T.S.




4 CHRISTY N16 ELECTRICAL BOX
N.T.S.



3 BORE PIT & RECEIVER PIT
N.T.S.



2 DIRECTION BORE MEHOD
CROSS SECTION - PRIVATE
N.T.S.



1 IN DIRT - PRIVATE
N.T.S.

verizon

2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

Vinculum

575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500

ALLSTATES
ENGINEERING & SURVEYING
23675 BIRTCHE DRIVE
LAKE FOREST, CA 92630

PROJECT ID: P-334882
DRAWN BY: RF
CHECKED BY: DW

REV	DATE	DESCRIPTION	
0	08/17/2020	FINAL BORING PLAN	SS
A	08/14/2020	PRELIMINARY BORING PLAN	SS



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS
THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED
PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 061
LIC R.O.W. ADJACENT TO:
1221 MIDDLEFIELD RD.
PALO ALTO, 94301
LOCATION CODE: 425208

SHEET TITLE
CITY STANDARDS
& DETAILS

SHEET NUMBER

A-1.5

- ▶ Grade fills over 6-inches or impervious overlay shall incorporate an approved permanent aeration system, permeable material or other approved mitigation.
- ▶ Grade cuts exceeding 4-inches shall incorporate retaining walls or an appropriate transition equivalent.

C. Trenching, Excavation and Equipment Use

*Trenching, excavation or boring activity within the TPZ is restricted to the following activities, conditions and requirements if approved by the City Arborist. (See Restriction Zones for Excavation, Trenching or Boring Near Regulated Trees, Image 2.20-1 through 2.20-3). Mitigating measures shall include prior notification to and direct supervision by the **project arborist**.*

1. **Notification.** Contractor shall notify the *project arborist* a minimum of 24 hours in advance of the activity in the TPZ.
2. **Root Severance.** Roots that are encountered shall be cut to sound wood and repaired (see *Root Injury, Section 2.25 A-1*). Roots 2-inches and greater must remain injury free.
3. **Excavation.** Any approved excavation, demolition or extraction of material shall be performed with equipment sitting outside the TPZ. Methods permitted are by hand digging, hydraulic or pneumatic air excavation technology. Avoid excavation within the TPZ during hot, dry weather.
 - ▶ If excavation or *trenching* for drainage, utilities, irrigation lines, etc., it is the duty of the contractor to tunnel under any roots 2-inches in diameter and greater.
 - ▶ Prior to excavation for foundation/footings/walls, grading or *trenching* within the TPZ, roots shall first be severed cleanly 1-foot outside the TPZ and to the depth of the future excavation. The trench must then be hand dug and roots pruned with a saw, sawzall, narrow trencher with sharp blades or other approved root pruning equipment.
4. **Heavy Equipment.** Use of backhoes, steel tread tractors or any heavy vehicles within the TPZ is prohibited unless approved by the *City Arborist*. If allowed, a protective *root buffer* (see *Root Buffer and Damage to Trees, Section 2.25.A-1*) is required. The protective buffer shall consist of a base course of tree chips spread over the root area to a minimum of 6-inch depth, layered by 3/4-inch quarry gravel to stabilize 3/4-inch plywood on top. This buffer within the TPZ shall be maintained throughout the entire construction process.
 - ▶ **Structural design.** If injurious activity or interference with roots greater than 2-inches will occur within the TPZ, plans shall specify a design of special foundation, footing, walls, concrete slab or pavement designs subject to *City Arborist* approval. Discontinuous foundations such as concrete pier and structural grade beam must maintain natural grade (not to exceed a 4-inch cut), to minimize root loss and allow the tree to use the existing soil.

notes:


Required Practices

- Basement excavations shall be designed outside the TPZ of all *protected* and *designated* trees (see *Excavation*, Section 2.20-3) and shall not be harmful to other mature or neighboring property trees.

D. Tunneling & Directional Drilling

If **trenching** or pipe installation has been approved within the TPZ, then the trench shall be either cut by hand, air-spade, hydraulic vac-on excavation or, by mechanically boring the tunnel under the roots with a horizontal directional drill and hydraulic or pneumatic air excavation technology. In all cases, install the utility pipe immediately, backfill with soil and soak within the same day. Installation of private utility improvements shall be tunnel bored beneath the tree and roots per *Trenching Tunneling & Distance Matrix* in Table 2-1.

TABLE 2-1
Trenching & Tunneling Distance

TRENCHING DISTANCE	
	
When the Tree Diameter At 4.5 Ft Is:	Trenching will be Replaced with Boring at this Minimum Distance (10x tree dia.) from the Face of the Tree in any Direction:
6-9" Measured At 6"	à 6-9'
10-14" Measured At 54"	à 10-14'
15-19" Measured At 54"	à 15-19'
Over 19" Measured At 54"	à 20' +

Bore Pits Shall Be Located At A Minimum Distance As Specified By The Trenching Distance Table Above.

1. **Public Utilities**
Underground public utility improvements or repairs shall be performed in accordance with the *Utility Standards for Excavation, Trenching or Boring, Section 02200.309*; and per *Restriction Zones Near Regulated Trees (see Images 2.20-1 through 2.20-3)*.
2. **Street Trees**
Exclusions for *street trees* in the publicly owned right-of-way (ROW).
 - ▶ *Street Trees* that are in conflict with utility infrastructure where the conflict cannot be resolved may be removed if approved by Public Works Operations (e.g., a tree planted directly on top of a damaged sewer lateral.)

notes:

Required Practices



2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598



575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500



PROJECT ID: P-334882

DRAWN BY: RF

CHECKED BY: DW

O	08/17/2020	FINAL BORING PLAN	SS
A	08/14/2020	PRELIMINARY BORING PLAN	SS
REV	DATE	DESCRIPTION	



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS
HEY ARE ACTING UNDER THE DIRECTION OF A LICENSED
PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.


SF PALO ALTO 061
LIC P.O.W. ADJACENT TO:
1221 MIDDLEFIELD RD.
PALO ALTO, 94301
LOCATION CODE: 425208

SHEET TITLE
CITY STANDARDS
& DETAILS

SHEET NUMBER


A-1.6

- NOTES:
- 1. METAL SURFACES REQUIRING PAINT TO BE PAINTED MUNSELL GREEN.
 - 2. THE CONTRACTOR MAY BE REQUIRED TO SUBMIT A LOGISTICS PLAN TO THE PUBLIC WORKS DEPARTMENT PRIOR TO COMMENCING WORK THAT ADDRESSES ALL IMPACTS TO THE CITY'S RIGHT-OF-WAY, INCLUDING, BUT NOT LIMITED TO: PEDESTRIAN CONTROL, TRAFFIC CONTROL, TRUCK ROUTES, MATERIAL DELIVERIES, CONTRACTOR'S PARKING, CONCRETE POURS, CRANE LIFTS, WORK HOURS, NOISE CONTROL, DUST CONTROL, STORM WATER POLLUTION PREVENTION, CONTRACTOR'S CONTACT, NOTICING OF AFFECTED SURROUNDING PROPERTIES, AND SCHEDULE OF WORK. THE REQUIREMENT TO SUBMIT A LOGISTICS PLAN WILL BE DEPENDENT ON THE NUMBER OF APPLICATIONS PUBLIC WORKS ENGINEERING RECEIVES WITHIN CLOSE PROXIMITY TO HELP MITIGATE AND CONTROL THE IMPACT TO THE PUBLIC-RIGHT-OF-WAY. IF NECESSARY, PUBLIC WORKS MAY REQUIRE A LOGISTICS PLAN DURING CONSTRUCTION.
 - 3. TREES MAY NOT BE PLANTED WITHIN 10 FEET OF EXISTING WATER, GAS OR WASTEWATER MAINS/SERVICES OR METERS; LESSER DISTANCES REQUIRE A PERMANENT IMPERMEABLE ROOT-BARRIER A MINIMUM OF 3' HORIZONTAL FROM WATER, GAS AND WASTEWATER SERVICES/MAINS/METERS.



ENLARGED SITE PLAN

24"x36" SCALE: 1" = 1'-0"
11"x17" SCALE: 1/2" = 1'-0"



ENLARGED SITE PLAN

24"x36" SCALE: 1/2" = 1'-0"
11"x17" SCALE: 1/4" = 1'-0"

APN: 003-43-047
1221 MIDDLEFIELD RD

TREE TABLE

PALO ALTO TREE #	CITY TREE ID:	SPECIES:	COMMON NAME:	GROW SPACE:	TRUNK DIA. AT BREAST HT.:	DRIP LINE:	DISTANCE TO CONST.:	PROTECTION MEASURES REQUIRED
PALO ALTO TREE #1	-	TILIA CORDATA	LITTLELEAF LINDEN	-	3.9"	3' 3"	-	-
PALO ALTO TREE #2	-	TILIA CORDATA	LITTLELEAF LINDEN	-	15.9"	13' 3"	-	TYPE 2

NEW TREE TABLE

TREE	CITY TREE ID:	SPECIES:	COMMON NAME:	COMMENTS:
PROPOSED TREE #1	TBD	HETEROMELES ARBUTIFOLIA OR MYRICA CALIFORNIA	TOYON OR PACIFIC WAX MYRTLE	REPLACEMENT FOR STREET TREE #1

NOTE:
ALL ITEMS AND DIMENSIONS SHOULD BE VERIFIED IN THE FIELD, PRIOR TO STARTING CONSTRUCTION.

verizon

2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

Vinculums

575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500

ALL STATES
ENGINEERING & SURVEYING
A ZALZALI & ASSOCIATES COMPANY

23675 BIRTCHE DRIVE
LAKE FOREST, CA 92630
PHONE: (949) 273-0996

PROJECT ID:	P-334882
DRAWN BY:	RF
CHECKED BY:	DW

REV	DATE	DESCRIPTION	
2	08/31/2020	100% CD'S FOR SUBMITTAL	MG
1	06/11/2020	100% CD'S FOR SUBMITTAL	RF
0	05/22/2020	100% CD'S FOR APPROVAL	RF
B	05/04/2020	95% CD'S FOR REDLINE	RF
A	04/29/2020	90% CD'S FOR REDLINE	RF




IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 061
LIC R.O.W. ADJACENT TO:
1221 MIDDLEFIELD RD.
PALO ALTO, 94301
LOCATION CODE: 425208

SHEET TITLE
ENLARGED SITE PLAN


SHEET NUMBER

A-2



EXISTING SOUTHEAST ELEVATION

24"x36" SCALE: 1/2" = 1'-0"
11"x17" SCALE: 1/4" = 1'-0"



PROPOSED SOUTHEAST ELEVATION

24"x36" SCALE: 1/2" = 1'-0"
11"x17" SCALE: 1/4" = 1'-0"

NOTES:

1. NEW LIGHT POLE TO BE PAINTED WITH MUNSELL GREEN PAINT.
2. NEW RADIOS AND HARDWARE TO BE PAINTED MUNSELL GREEN OR WRAPPED AS ALLOWED BY THE MANUFACTURER.

TOTAL ANETNNA/RADIO VOLUME (CU. FT.)		
MODEL	TOTAL	TOTAL VOLUME (CU. FT.)
SM6701	3	±1.4

verizon

2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

Vinculums

575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500

ALL STATES
ENGINEERING & SURVEYING
A ZALZALI & ASSOCIATES COMPANY

23675 BIRTCHER DRIVE
LAKE FOREST, CA 92630
PHONE: (949) 273-0996

PROJECT ID:	P-334882
DRAWN BY:	RF
CHECKED BY:	DW

REV	DATE	DESCRIPTION	
2	08/31/2020	100% CD'S FOR SUBMITTAL	MG
1	06/11/2020	100% CD'S FOR SUBMITTAL	RF
0	05/22/2020	100% CD'S FOR APPROVAL	RF
B	05/04/2020	95% CD'S FOR REDLINE	RF
A	04/29/2020	90% CD'S FOR REDLINE	RF




IT IS A VIOLATION OF LAW FOR ANY PERSON,
UNLESS THEY ARE ACTING UNDER THE
DIRECTION OF A LICENSED PROFESSIONAL
ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 061
LIC R.O.W. ADJACENT TO:
1221 MIDDLEFIELD RD.
PALO ALTO, 94301
LOCATION CODE: 425208


SHEET TITLE
ELEVATIONS

SHEET NUMBER
A-3



EXISTING SOUTHWEST ELEVATION

24"x36" SCALE: 1/2" = 1'-0"
11"x17" SCALE: 1/4" = 1'-0"




2




- NOTES:
- NEW LIGHT POLE TO BE PAINTED WITH MUNSELL GREEN PAINT.
 - NEW RADIOS AND HARDWARE TO BE PAINTED MUNSELL GREEN OR WRAPPED AS ALLOWED BY THE MANUFACTURER.

TOTAL ANETNNA/RADIO VOLUME (CU. FT.)		
MODEL	TOTAL	TOTAL VOLUME (CU. FT.)
SM6701	3	±1.4

PROPOSED SOUTHWEST ELEVATION



24"x36" SCALE: 1/2" = 1'-0"
11"x17" SCALE: 1/4" = 1'-0"



1

verizon

2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

Vinculums

575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500

ALL STATES
ENGINEERING & SURVEYING
A ZALZALI & ASSOCIATES COMPANY

23675 BIRTCHER DRIVE
LAKE FOREST, CA 92630
PHONE: (949) 273-0996

PROJECT ID:	P-334882
DRAWN BY:	RF
CHECKED BY:	DW

REV	DATE	DESCRIPTION	
2	08/31/2020	100% CD'S FOR SUBMITTAL	MG
1	06/11/2020	100% CD'S FOR SUBMITTAL	RF
0	05/22/2020	100% CD'S FOR APPROVAL	RF
B	05/04/2020	95% CD'S FOR REDLINE	RF
A	04/29/2020	90% CD'S FOR REDLINE	RF



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 061
LIC R.O.W. ADJACENT TO:
1221 MIDDLEFIELD RD.
PALO ALTO, 94301
LOCATION CODE: 425208

SHEET TITLE

ELEVATIONS


SHEET NUMBER

A-3.1


ERICSSON 6701 POLE ATTACHMENT SHROUD
PART NO. 30311
(OR APPROVED EQUAL)

NOTES:

1. FULL SHROUD PAINTABLE TO MATCH COLOR OF EXISTING STRUCTURE.
2. COLOR-MATCHED 3M FILM TO BE APPLIED TO ANTENNA EMITTER FACE.
3. SHROUD DRY WEIGHT = 18 LBS.
4. TOTAL WEIGHT INCLUDING ANTENNA = 49LBS.




DETAIL A (SECTOR 1 RADIO HIDDEN FOR CLARITY)



OLDCASTLE N36 UTILITY BOX
(OR APPROVED EQUAL)

- ETCHED POLYPROPYLENE FACE
- FACE ANCHORED IN CONCRETE
- ULTRA-VIOLET INHIBITOR
- EXCEEDS ASTM-D1693 STANDARDS FOR ENVIRONMENTAL STRESS CRACKING RESISTANCE



A HIGH DENSITY REINFORCED CONCRETE BOX WITH NON-SETTING SHOULDERS POSITIONED TO MAINTAIN GRADE AND FACILITATE BACK FILLING. APPROXIMATE DIMENSIONS AND WEIGHT SHOWN.


OLDCASTLE ORDERING CODE	ITEM	APPROX SHIPPING WEIGHT	DESCRIPTION
N36BOX	BOX	172 lbs.	N36 UTILITY BOX (17-1/8"x30-1/4") - 8 PER PALLET
N36R	LID	76 lbs.	R-SERIES COMPOSITE LID WITH POLYPROPYLENE RING (ORDER N90 BOLT DOWN KIT SEPARATELY)
N36D	LID	35 lbs.	FIBRELYTE LID, NON-CONCRETE
N36E	LID	96 lbs.	REINFORCED CONCRETE WITH 7"x13-1/2" CONCRETE READING LID
N36G	LID	78 lbs.	REINFORCED CONCRETE WITH 5"x8" CAST IRON, SELF-CLOSING, READING LID WITH FRAME
N36RP	LID	76 lbs.	R-SERIES COMPOSITE LID W/ POLYPROPYLENE RING W/ 2"Ø PROBE HOLE FOR METER READING PROBE (ORDER N90 BOLT DOWN KIT SEPARATELY)
N36-6ID	COVER	56 lbs.	STEEL CHECKER PLATE
N36-6IG	COVER	60 lbs.	STEEL CHECKER PLATE WITH 8" ROUND, SELF-CLOSING READING LID
N36X12	EXTENSION	189 lbs.	12" REINFORCED CONCRETE - 8 PER PALLET
B36SL	SLAB	104 lbs.	REINFORCED CONCRETE (20"x34")

GALVANIZING AVAILABLE ON ALL STEEL COVERS

N36 UTILITY BOX DETAIL


24"x36" SCALE: NTS
11"x17" SCALE: NTS

6



AC POWER DISCONNECT WIRE DIAGRAM

5




SHUTDOWN SIGN ON DISCONNECT

24"x36" SCALE: NTS
11"x17" SCALE: NTS

4

Raycap RSCAC-1333-PH-240 AC POWER DISCONNECT
(OR APPROVED EQUAL)

- DIMENSIONS: 10.43"L x 8.59"W x 5.06"D
- WEIGHT: ±8 lbs (3.62 Kg)



RSCAC-1333-PH-240


NEMA 6P AC POWER DISCONNECT

24"x36" SCALE: NTS
11"x17" SCALE: NTS

3

CONTRACTOR NOTE:

- SITE ID WILL BE SWITCH #, SITE # AND SITE NAME.
- NODE NUMBER WILL BE MARKET#-NODE.B#-SMALL CELL NAME.



NOTE:

INSTALL EME NOTICE SIGN 3' BELOW STREET MACRO UNITS.

GO95 RF SIGNAGE

24"x36" SCALE: NTS
11"x17" SCALE: NTS


2

STREET MACRO 6701

- DIMENSION W/ PROTRUDING ITEMS INCL GPS ANT: 21.2"H x 8.1"W x 5.1"D
- TOTAL RADIO AREA (CU. IN.): 875.77 CU. IN.
- WEIGHT: ±31 lbs

RADIO AREA (CU. FT.)			
RADIO MODEL	TOTAL RADIO(S)	TOTAL RADIO AREA (CU. IN.)	TOTAL RADIO AREA (CU. FT.)
MACRO 6701	1	875.77 CU. IN.	0.50 CU. FT.

NEW GPS ATTACHED ON TOP OF SM 6701 (PRE INSTALLED BY MANUFACTURER) (1) TOTAL (MAX. MEASUREMENTS WILL NOT EXCEED)



STREET MACRO 6701

24"x36" SCALE: NTS
11"x17" SCALE: NTS

1

verizon
2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

Vinculums
575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500

ALL STATES
ENGINEERING & SURVEYING
A ZALZALI & ASSOCIATES COMPANY
23675 BIRTCHE DRIVE
LAKE FOREST, CA 92630
PHONE: (949) 273-0996

PROJECT ID: P-334882

DRAWN BY: RF

CHECKED BY: DW

REV	DATE	DESCRIPTION	
2	08/31/2020	100% CD'S FOR SUBMITTAL	MG
1	06/11/2020	100% CD'S FOR SUBMITTAL	RF
0	05/22/2020	100% CD'S FOR APPROVAL	RF
B	05/04/2020	95% CD'S FOR REDLINE	RF
A	04/29/2020	90% CD'S FOR REDLINE	RF

REGISTERED PROFESSIONAL ENGINEER
MUSAM ZALZALI
71655
CIVIL
STATE OF CALIFORNIA
IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 061
LIC R.O.W. ADJACENT TO:
1221 MIDDLEFIELD RD.
PALO ALTO, 94301
LOCATION CODE: 425208


SHEET TITLE
DETAILS


SHEET NUMBER
D-1

SM6701 SHROUD & MOUNTING DETAILS

24"x36" SCALE: NTS
11"x17" SCALE: NTS

7





ADDITIONAL NOTES:
1.ASSIST RESIDENCE WITH IN/OUT ACCESS TO DRIVEWAYS ALONG THE CLOSURE WHEN SAFE TO DO SO.

- LEGEND:**
- CHANNELIZING DEVICE WITH K-RAIL/WATER FILLED BARRIERS
 - CLIP-ON SIGN
 - CHANNELIZING DEVICE
 - SIGN
 - WORK ZONE
 - DIRECTION OF TRAFFIC
 - TYPE 1 BARRICADE
 - TYPE 1 BARRICADE W/SIGN
 - TYPE 3 BARRICADE
 - TYPE 3 BARRICADE W/SIGN
 - TEMP RAISED MARKERS
 - ARROW BOARD MARKER
 - PEDESTRIAN BARRICADES
 - CERTIFIED FLAGGER
 - CRASH BARRELS
 - MESSAGE BOARD (PCMS)
 - FLASHING ARROWBOARD
 - CRASH ATTENUATORS
 - FLASHING BEACON/BARRICADE LIGHT

***POST TEMPORARY NO PARKING SIGN ON TYPE 1 BARRICADE 72 HRS IN ADVANCED.**

NOTE: Please contact B.A.T.S 72 hrs in advance in case if we are to install "TEMPORARY NO PARKING" signs.

- NOTES**
- Traffic control shall conform with the most current CAMUTCD part 6 and/or Caltrans Standards
 - One lane of traffic in each direction and all high volume turning lanes shall be maintained at all times on all streets at a minimum lane width of 10 feet.
 - Contractor shall notify local authorities once signs are posted.
 - All advanced warning signs shall be equipped with 2 (18" orange flags)
 - Certified Traffic Control Workers shall have Type II vests, work shoes, and hard hats.
 - Temporary no parking signs shall be placed a min of 72 hrs prior of work.
 - Driveways shall be monitored and maintained at all times during work hours.
 - Distance between sign and work area will be determined on speed limit.
 - Roadway shall not be opened until safe for public use. All open trenches must be plated or backfilled prior to public usage.
 - All Devices shall be removed when no longer required.

MEANING OF LETTER CODES ON TYPICAL APPLICATION DIAGRAMS

ROAD TYPE	DISTANCE BETWEEN SIGNS		
	A	B	C
Urban (Low Speed) - 25 mph or less	100 ft	100 ft	100 ft
Urban (Low Speed) + 25 to 40 mph	250 ft	250 ft	250 ft
Urban (High Speed) + 40 mph	350 ft	350 ft	350 ft
Rural	500 ft	500 ft	500 ft
Expressway / Freeway	1,000 ft	1,500 ft	2,640 ft



SCALE:	NOT TO SCALE
DATE REQSTD:	4/24/20
DATE COMPLTD:	7/27/20
PROJECT LOCATION:	1211 MIDDLEFIELD RD., PALO ALTO, CA
PO#	SF PALO ALTO 061
PAGE#	1/1 (REVISION 1)

REQUEST BY:

YVONNE WASHINGTON
VINCULUMS
925-999-5523
YWASHINGTON@VINCULUMS.COM

PLAN 1
TEMP TRAFFIC CONTROL PLAN

**AFTER HOURS
EMERGENCY**
510-299-5666

Drawn By:
DREW PATEL
CSLB# 917034
Office: 510-657-2543
Fax: 510-657-2544
44800 Industrial Drive Fremont, CA 94538
WWW.BATSTRAFFICSOLUTIONS.COM

B.A.T.S. TRAFFIC SOLUTIONS



VERIZON
PALO ALTO_061

All States Engineering & Surveying
Project No: 64 - CLUSTER-6IPALO_ALTO_061

Structural Analysis Report

ROW Adjacent to 1221 Middlefield Rd. Palo Alto, 94301
Proposed 29'-0" AGL "Downtown" Style Aluminum Light Pole & Foundation



Rev. #	Reason for Revision	Total # of Sheets	Prepared By	Checked By	Approved /Accepted	Date
2	CD's Revised	19	LeT	LeT	WZ	9/25/2020

	Quantity/Type /Shape	Strength (min.)	Dimensions	Thickness /Depth	Capacity Utilization
Pole Shaft	Aluminum / 8-sided tapered	25 ksi*	5.73"Ø at top 10.0"Ø at bottom	0.219"	44.6 % PASS
Anchor Bolts	4	36 ksi	1" Ø	-	44.0 % PASS
Base Plate	1	36 ksi	13.6" Cast Base	-	ADEQUATE
Foundation	Circular Caisson	3.25 ksi	36" Dia.	7'-0"***	ADEQUATE

* Pole grade is 6061-T6 per provided specs.

** Required depth of caisson (Unrestrained at G/L) - This analysis was performed without a soil report, and minimum soil properties from ISC-18 were used. Required pole foundation embedment depth may change with a soil report from the proposed pole location.

Professional Engineering Firm
ARCHITECTURAL, CIVIL, STRUCTURAL, ELECTRICAL, GEOTECHNICAL SURVEYING
www.allstatesengineering.com

ATC Hazards by Location

Search Information

Address: 6011 Brannon Ln., Bakersfield, CA 93309, USA
Coordinates: 35.3281277, -119.0741019
Elevation: 380 ft
Timestamp: 2020-05-21T19:06:22.686Z
Feature Type: Wind



ASCE 7-16		ASCE 7-10		ASCE 7-05	
MR 10-Year	65 mph	MR 10-Year	72 mph	ASCE 7-05 Wind Speed	85 mph
MR 15-Year	71 mph	MR 15-Year	79 mph		
MR 50-Year	78 mph	MR 50-Year	86 mph		
MR 100-Year	81 mph	MR 100-Year	91 mph		
Risk Category I	88 mph	Risk Category I	100 mph		
Risk Category II	94 mph	Risk Category II	110 mph		
Risk Category III	101 mph	Risk Category III-IV	115 mph		
Risk Category IV	105 mph				

The results indicated here DO NOT reflect any state or local amendments to the values or any definition lines made during the building code adoption process. Users should confirm any output obtained from this tool with the local Authority Having Jurisdiction before proceeding with design.

Disclaimer

Hazard loads are interpolated from data provided in ASCE 7 and rounded up to the nearest whole integer. Per ASCE 7, islands and coastal areas outside the last contour should use the last wind speed contour of the coastal area - in some cases, this website will extrapolate past the last wind speed contour and therefore, provide a wind speed that is slightly higher. NOTE: For queries near wind-some debris region boundaries, the resulting determination is sensitive to rounding which may affect whether or not it is considered to be within a wind-some debris region.

Mountainous terrain, gorges, ocean promontories, and special wind regions shall be examined for unusual wind conditions.

While the information presented on this website is believed to be correct, ATC and its sponsors and contributors assume no responsibility or liability for its accuracy. The material presented in the report should not be used or relied upon for any specific application without competent examination and verification of its accuracy, suitability and applicability by engineers or other licensed professionals. ATC does not intend that the use of this information replace the sound judgment of each competent professional, having experience and know edge in the field of practice, nor is substitution for the standard of care required of each professional in interpreting and applying the results of the report provided by this website. Users of the information from this website assume all liability arising from such use. Use of the output of this website does not imply approval by the governing building code bodies responsible for building code approval and interpretation for the building use described by the building code location in the report.

Steel Decorated Pole
Palo Alto
PALO_ALTO_061



Project Description:
All States Engineering & Surveying (ASES) is pleased to submit this "Structural Analysis Report" to determine the structural integrity of the metal pole.
The purpose of the analysis is to determine acceptability of the pole stress level. Based on our analysis we have determined the metal pole stress level for the structure and anchorage, under the following load case:

LC: Proposed Pole + Proposed Equipment
(Please see page 5 for details)

All modifications and equipment proposed in this report shall be installed in accordance with the attached drawings for the determined available structural capacity to be effective.

Structural Analysis Parameters:
This analysis has been performed in accordance with AASHTO 2013 guidelines.


- Wind Speed: 85 mph per AASHTO 2013
- Exposure Category: C
- Risk Category: II
- Topographical: I
- Crest Height = 0
- Ice Thickness = 0 in
- Min. Soil Lateral Bearing = 100 psf/ft*2 = 200 psf/ft per CRC & IRC 1806.3.4
- Min. Soil Bearing = 1500 psf

We at All States Engineering & Surveying appreciate the opportunity of providing our continuing professional services to you. If you have any questions or need further assistance on this or any other projects, please give us a call.

PROJECT: PALO ALTO 061 CLIENT: 102 - Sequoia VZW Bakersfield DESIGN BY: LeT REVIEW BY: LeT DATE: 9/25/2020

Pole Wind & Seismic Analysis Based on AASHTO 2013

Proposed Elevation



1. NEW LIGHT POLE TO BE PAINTED WITH FUNSELL GREEN PAINT	
2. NEW RADIOS AND HARDWARE TO BE PAINTED FUNSELL GREEN OR WRAPPED AS ALLOWED BY THE MANUFACTURER.	

TOTAL ANETNNA/RADIO VOLUME (CU. FT.)		
MODEL	TOTAL	TOTAL VOLUME (CU. FT.)
19'6"	3	11.4

ATC Hazards by Location

Search Information

Address: 1221 Middlefield Rd., Palo Alto, 94301
Coordinates: 37.446156, -122.1475279
Elevation: 30 ft
Timestamp: 2020-05-28T22:43:13.268Z
Feature Type: Seismic
Reference Document: ASCE7-16
Risk Category: I
Site Class: C-0/soft



Basic Parameters

Name	Value	Description
S _g	1.582	MCE _g ground motion (period=0.2s)
S ₁	0.8	MCE _g ground motion (period=1.0s)
S _{MS}	1.898	Site-modified spectral acceleration value
S _{M1}	* null	Site-modified spectral acceleration value
S _{MS}	1.265	Normalized design value at 0.2s SA
S _{M1}	* null	Normalized design value at 1.0s SA

* See Section 11.4.6

Additional Information

Name	Value	Description
S _{DC}	* null	Seismic design category
F _a	1.2	Site amplification factor at 0.2s
F _v	* null	Site amplification factor at 1.0s
C _W	0.825	Coefficient of risk (0.2s)
C _W	0.808	Coefficient of risk (1.0s)
P _{GA}	0.65	MCE _g peak ground acceleration
P _{GA}	1.2	Site amplification factor at P _{GA}
P _{GA}	0.78	Site modified peak ground acceleration
T _L	12	Long-period transition period (s)
S _{W17}	1.903	Probabilistic risk-targeted ground motion (0.2s)
S _{W1H}	2.139	Factored uniform-hazard spectral acceleration (2% probability of exceedance in 50 years)
S _W	1.882	Factored deterministic acceleration value (0.2s)
S _{W17}	0.772	Probabilistic risk-targeted ground motion (1.0s)
S _{W1H}	0.891	Factored uniform-hazard spectral acceleration (2% probability of exceedance in 50 years)
S _W	0.6	Factored deterministic acceleration value (1.0s)
P _{GA}	0.65	Factored deterministic acceleration value (P _{GA})


* See Section 11.4.6

The results indicated here DO NOT reflect any state or local amendments to the values or any definition lines made during the building code adoption process. Users should confirm any output obtained from this tool with the local Authority Having Jurisdiction before proceeding with design.

ATC Hazards by Location

Search Information

Address: 1221 Middlefield Rd., Palo Alto, 94301
Coordinates: 37.446156, -122.1475279
Elevation: 30 ft
Timestamp: 2020-05-28T22:43:13.268Z
Feature Type: Seismic



PROPOSED COMPONENTS		QUANTITY	MOUNT TYPE
27'-6"	(N) Ericsson SM6701 Antennas	3	Pole Mounted
17'-6"	Reserved 30" x 72" Banner	1	
8'-10"	(E) Street Sign	1	
-	(N) RF Signage	1	Inside Pole
-	(N) & (E) Conduit, Wire, & In-line Fuse	-	

WIND PRESSURE DERIVATION (AASHTO 2013)	
Height of Pole	h = 29.0 ft
Wind Speed	V = 85 mph
Wind Exposure (B, C or D)	C
Wind Directionality (Pole)	K _d = 0.95
Gust Effect Factor	G _f = 1.14
3-sec Gust Exponent	g = 9.50
Atmospheric Height	Z _a = 900 ft
Vel. Pressure Coeff. (Min)	K _z = 0.84
Velocity Pressure Coeff.	K _z = 2.0(z/Z _a) ^{2.67} = 0.97
Wind Force @ Pole top	F _w = 0.00259K _d G _f V ³ (C _f A) = 19.4 psf * C _f A
Total Applied Shear	V _s = 1143 lbs
Total Applied Moment	M _s = 17007 lb-ft

CALCULATION OF WIND DRAG COEFFICIENTS (Cd) FROM AASHTO 2013, TABLE 3.8.7-1					
Appertenance	Height (ft)	Width (in)	Depth (in)	d (ft)	C _d V _s
(N) Ericsson SM6701 Antennas	32.2	10.2	7.3	1.05	1.70
(E) Round Luminaire	2.9	88.0	-	0.24	0.50
(E) Round Pole	348	7.85	-	0.65	56

SEISMIC LOAD ANALYSIS (ASCE 7-16)	
Total Pole Weight	W = P _s = 642 lbs
Spectral Response (Short)	S _s = 1.582
Spectral Response (1 sec.)	S ₁ = 0.600
Importance Factor	I _s = 1.0
Response Factor	R = 1.5
Seismic Response Coeff	C _s = 0.04AS _s /I _s = 0.070
Seismic Response Coeff	C _s = 0.85/(R/I _s) = 0.320
Seismic Response Coeff	C _s = S ₁ /(R/I _s) = 1.055
Lateral Seismic Force	V _s = MAX(C _s W) = 1.055 * W
Total Applied Shear	V _s = 677 lbs
Total Applied Moment	M _s = V _s (2/3h) = 13091 lb-ft

(Wind Loads Governing For Pole Shaft Capacity Check)



PROJECT ID: P-334882
DRAWN BY: RF
CHECKED BY: DW

REV	DATE	DESCRIPTION	
2	08/31/2020	100% CD'S FOR SUBMITTAL	MG
1	06/11/2020	100% CD'S FOR SUBMITTAL	RF
0	05/22/2020	100% CD'S FOR APPROVAL	RF
B	05/04/2020	95% CD'S FOR REDLINE	RF
A	04/29/2020	90% CD'S FOR REDLINE	RF



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 061
LIC R.O.W. ADJACENT TO:
1221 MIDDLEFIELD RD.
PALO ALTO, 94301
LOCATION CODE: 425208

SHEET TITLE

CALCS

SHEET NUMBER

C-1



MATERIAL STRENGTH					
GRADE	Fy	Fu	GRADE	Fy	Fu
A572-50	50 ksi	65 ksi			

1. Tower is located in Santa Clara County, California.
2. Tower designed for Exposure C to the AASHTO 2013 Standard.
3. Tower designed for a 85 mph basic wind in accordance with the AASHTO 2013 Standard.
4. Deflections are based upon a 60 mph wind.
5. Tower Structure Class II.
6. Topographic Category 1 with Crest Height of 0.00 ft
7. TOWER RATING, 44.6%.

Basic wind speed of 85 mph.
Structure Class II.
Exposure Category C.
Topographic Category 1.
Crest Height 0.00 ft.
Deflections calculated using a wind speed of 60 mph.

Tower Section	Tower Elevation	Face	A_x	A_y	$C_x A_x$ In Face	$C_y A_y$ Out Face	Weight
			\bar{y}^2	\bar{y}^2	\bar{y}^2	\bar{y}^2	\bar{y}
L1	29.00-0.00	A	0.000	0.000	0.000	0.000	0.00
		B	0.000	0.000	0.000	0.000	0.00
		C	0.000	0.000	0.000	1.638	3.90
		D	0.000	0.000	0.000	0.000	0.00

All States Engineering & Surveying 23675 Britcher Drive Lake Forest, CA 92630 Phone: (949) 273-0998 FAX: (949) 806-7222	Palo Alto Light Pole PALO ALTO_061 64 - Venzulum VZW AASHTO 2013 06/10/20
--	--

Location	Condition	Obs. Local Comb.	Vertical, Z in	Horizontal, X in	Horizontal, Z in
Pole	Max. Vert.	4	681.74	-568.52	568.52
	Max. H.	3	441.31	-1103.22	1103.22
	Max. M.	3	481.31	-1103.22	1103.22
	Max. M.	2	1614.04	-2103.21	2103.21
	Max. M.	7	15168.98	-1103.19	-229.19
	Max. H.	5	613.73	-668.50	668.50
	Min. Vert.	7	481.31	-1103.19	-229.19
	Min. H.	4	641.74	-1103.22	-229.21
	Min. H.	6	641.74	-1103.22	-229.21
	Min. M.	7	-4242.78	-1103.19	-229.19
	Min. M.	2	-2372.16	-229.21	1103.21
	Min. Torsion	1	0.06	-0.45	-0.43


Lead Combination	Fertical		Shear		Overturning Moment, M_x		Overturning Moment, M_y		Torque	
	μ	μ	μ	μ	μ	μ	μ	μ	μ	μ
Dead Only	534.78		0.43	0.43	-415.78		433.18			
1.2 Dead+1.6 Wind 0 deg - No ice	641.74		-299.21	-1103.21	-1641.04		535.16		-317.41	
0.9 Dead+1.6 Wind 0 deg - No ice	481.31		-299.21	-1103.22	-15948.28		5202.28		-3189.18	
1.2 Dead+1.6 Wind 45 deg - No ice	641.74	568.52		-568.52	-8154.36		-7106.98		-489.18	180.90
0.9 Dead+1.6 Wind 45 deg - No ice	481.31	568.50		-568.50	-7991.78		-7212.79		-451.73	173.40
1.2 Dead+1.6 Wind 90 deg - No ice	641.74	1103.22		299.21	4330.87		-15094.41		-317.34	180.90
0.9 Dead+1.6 Wind 90 deg - No ice	481.31	1103.19		299.19	4423.78		-15516.98		-319.16	180.90
Dead-Wind 0 deg - Service	534.78	-83.32		-83.27	-2746.74		1782.95		-128.79	
Dead-Wind 45 deg - Service	534.79	158.35		-158.25	-2545.54		-1678.95		-85.79	
Dead-Wind 90 deg - Service	534.79	83.36		83.36	-2746.74		1782.95		-128.79	

Pole Design Data									
Section No.	Elevation	Size	L	L_m	KL/r	A	P_n	ϕP_n	Ratio $\frac{P_n}{\phi P_n}$
	β		β	β		in^2	lb	lb	
L1	29 + 0 (1)	TP10x5.73x0.219	29.00	29.00	97.7	7.1116	-639.51	128668.00	0.005

Section No.	Elevation ft	Component Type	Size	Critical Element	P lb	σ_{allow}^c lb	% Capacity	Pass/Fail
L1	29'-0"	Pole	TP10x5.73x0.219	I	-639.51	128668.00	44.6	Pass
							Summary	
							Pole (L1)	44.6 Pass
							Base Plate	42.0 Pass
							RATING =	44.6 Pass

Section	Elevation	Component	Condition	Gen. Load	Actual	Major Axis Moment	Minor Axis Moment
No.	θ	Type		Comb.	lb	lb-ft	lb-ft
L1	29.0	Pole	Max. Tension	1	0.00	-0.00	-0.00
			Max. Compression	4	-608.72	-7096.83	8154.49
			Max. My	7	-479.23	-15160.03	-4423.59
			Max. My	2	-639.51	5357.37	8160.97
			Max. Vy	6	1104.34	-15094.46	-8310.68
			Max. Vy	2	-1104.38	5357.37	16140.97
			Max. Torque	5			457.57

2	08/31/2020	100% CD'S FOR SUBMITTAL	MG
1	06/11/2020	100% CD'S FOR SUBMITTAL	RF
0	05/22/2020	100% CD'S FOR APPROVAL	RF
B	05/04/2020	95% CD'S FOR REDLINE	RF
A	04/29/2020	90% CD'S FOR REDLINE	RF
REV	DATE	DESCRIPTION	



C-2

GENERAL CONSTRUCTION NOTES

1. ALL WORK SHALL CONFORM TO THE REQUIREMENTS OF THE LOCAL BUILDING CODE, THE LATEST EDITION AND ALL OTHER APPLICABLE CODES AND ORDINANCES.
2. CONTRACTOR SHALL CONSTRUCT SITE IN ACCORDANCE WITH THESE DRAWINGS AND CONSTRUCTION SPECIFICATIONS 80-TI196-1 REV H. THE SPECIFICATION IS THE RULING DOCUMENT AND ANY DISCREPANCIES BETWEEN THE SPECIFICATION AND THESE DRAWINGS SHOULD BE BROUGHT TO THE ATTENTION OF THE ENGINEER PRIOR TO PROCEEDING WITH CONSTRUCTION
3. CONTRACTOR SHALL VISIT THE JOB SITE AND SHALL FAMILIARIZE HIMSELF WITH ALL CONDITIONS AFFECTING THE PROPOSED WORK (ROOF FRAMING, ELECTRICAL SERVICE, LOCAL PLANNING CODES, ETC.) AND SHALL MAKE PROVISIONS AS TO THE COST THEREOF. CONTRACTOR SHALL BE RESPONSIBLE FOR FAMILIARIZING HIMSELF WITH ALL CONTRACT DOCUMENTS, FIELD CONDITIONS AND DIMENSIONS AND CONFIRMING THAT THE WORK MAY BE ACCOMPLISHED AS SHOWN PRIOR TO PROCEEDING WITH CONSTRUCTION. ANY DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE ENGINEER PRIOR TO THE COMMENCEMENT OF WORK. NO COMPENSATION WILL BE AWARDED BASED ON CLAIM OF LACK OF KNOWLEDGE OF FIELD CONDITIONS
4. PLANS ARE NOT TO BE SCALED. THESE PLANS ARE INTENDED TO BE A DIAGRAMMATIC OUTLINE ONLY UNLESS OTHERWISE NOTED. THE WORK SHALL INCLUDE FURNISHING MATERIALS, EQUIPMENT AND APPURTENANCES, AND LABOR NECESSARY TO EFFECT ALL INSTALLATIONS AS INDICATED ON THE DRAWINGS. OWNER PROVIDED MATERIALS WILL INCLUDE THE FOLLOWING, UNLESS NOTED OTHERWISE:

A) TRANSMITTER

B) RF FILTER

C) MFTS RACK

D) AUXILIARY EQUIPMENT IN MFTS RACK

E) PUMP ASSEMBLY

F) HEAT EXCHANGER

G) HOSE AND HOSE MANIFOLDS (ANY COPPER OR STEEL SECTIONS PROVIDE BY CONTRACTOR)

H) UHF ANTENNA AND MOUNTING BRACKETS, GPS ANTENNAS AND KU ANTENNAS

I) UHF COAX AND HANGERS

K) 480-208 # 208-400 ELECTRICAL TRANSFORMERS (RE: E-2 FOR SPECIALIZED TRANSFORMERS PROVIDED BY CONTRACTOR)

L) AUTOMATIC TRANSFER SWITCH AND GENERATOR

M) EQUIPMENT SHELTER (SHELTERS FURNISHED IN FACTORY W/ HVAC EQUIPMENT AND ELECTRICAL DISTRIBUTION PANEL)

N) INTEGRATED LOAD CENTER
5. DIMENSIONS SHOWN ARE TO FINISH SURFACES UNLESS OTHERWISE NOTED. SPACING BETWEEN EQUIPMENT IS REQUIRED CLEARANCE. THEREFORE, IT IS CRITICAL TO FIELD VERIFY DIMENSIONS; SHOULD THERE BE ANY QUESTIONS REGARDING THE CONTRACT DOCUMENTS, EXISTING CONDITIONS AND/OR DESIGN INTENT, THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING THE WORK.
6. DETAILS ARE INTENDED TO SHOW DESIGN INTENT. MODIFICATIONS MAY BE REQUIRED TO SUIT JOB DIMENSIONS OR CONDITIONS, AND SUCH MODIFICATIONS SHALL BE INCLUDED AS PART OF THE WORK.
7. CONTRACTOR SHALL RECEIVE CLARIFICATION IN WRITING, AND SHALL RECEIVE IN WRITING AUTHORIZATION TO PROCEED BEFORE STARTING WORK ON ANY ITEMS NOT CLEARLY DEFINED OR IDENTIFIED BY THE CONTRACT DOCUMENTS.
8. CONTRACTOR SHALL SUPERVISE AND DIRECT THE WORK USING THE BEST CONSTRUCTION SKILLS AND ATTENTION. CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES AND PROCEDURES AND FOR COORDINATING ALL PORTIONS OF THE WORK UNDER CONTRACT, UNLESS OTHERWISE NOTED.
9. CONTRACTOR SHALL BE RESPONSIBLE FOR THE SAFETY OF THE WORK AREA, ADJACENT AREAS AND BUILDING OCCUPANTS THAT ARE LIKELY TO BE AFFECTED BY THE WORK UNDER THIS CONTRACT. WORK SHALL CONFORM TO ALL OSHA REQUIREMENTS.
10. CONTRACTOR SHALL COORDINATE HIS WORK WITH THE SUPERINTENDENT OF BUILDINGS & GROUNDS AND SCHEDULE HIS ACTIVITIES AND WORKING HOURS IN ACCORDANCE WITH THE REQUIREMENTS.
11. CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING HIS WORK WITH THE WORK OF OTHERS AS IT MAY RELATE TO RADIO EQUIPMENT, ANTENNAS AND ANY OTHER PORTIONS OF THE WORK.
12. INSTALL ALL EQUIPMENT AND MATERIALS IN ACCORDANCE WITH MANUFACTURERS RECOMMENDATIONS UNLESS SPECIFICALLY OTHERWISE INDICATED OR WHERE LOCAL CODES OR REGULATIONS TAKE PRECEDENCE.
13. MAKE NECESSARY PROVISIONS TO PROTECT EXISTING SURFACES, EQUIPMENT, IMPROVEMENTS, PIPING ETC. AND IMMEDIATELY REPAIR ANY DAMAGE THAT OCCURS DURING CONSTRUCTION.
14. IN DRILLING HOLES INTO CONCRETE WHETHER FOR FASTENING OR ANCHORING PURPOSES, OR PENETRATIONS THROUGH THE FLOOR FOR CONDUIT RUNS, PIPE RUNS, ETC., MUST BE CLEARLY UNDERSTOOD THAT REINFORCING STEEL SHALL NOT BE DRILLED INTO, CUT OR DAMAGED UNDER ANY CIRCUMSTANCES (UNLESS NOTED OTHERWISE). LOCATIONS OF REINFORCING STEEL ARE NOT DEFINITELY KNOWN AND THEREFORE MUST BE SEARCHED FOR BY APPROPRIATE METHODS AND EQUIPMENT.
15. REPAIR ALL EXISTING WALL SURFACES DAMAGED DURING CONSTRUCTION SUCH THAT THEY MATCH AND BLEND IN WITH ADJACENT SURFACES.
16. SEAL PENETRATIONS THROUGH FIRE RATED AREAS WITH U.L. LISTED AND FIRE CODE APPROVED MATERIALS.
17. KEEP CONTRACT AREA CLEAN, HAZARD FREE, AND DISPOSE OF ALL DIRT, DEBRIS, AND RUBBISH. EQUIPMENT NOT SPECIFIED AS REMAINING ON THE PROPERTY OF THE OWNER SHALL BE REMOVED. LEAVE PREMISES IN CLEAN CONDITION AND FREE FROM PAINT SPOTS, DUST, OR SMUDGES OF ANY NATURE. CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING ALL ITEMS UNTIL COMPLETION OF CONSTRUCTION.
18. MINIMUM BEND RADIUS OF ANTENNA CABLES SHALL BE IN ACCORDANCE WITH CABLE MANUFACTURERS RECOMMENDATIONS.
19. ALL EXISTING INACTIVE SEWER, WATER, GAS, ELECTRIC AND OTHER UTILITIES, WHICH INTERFERE WITH THE EXECUTION OF THE WORK, SHALL BE REMOVED AND/OR CAPPED, PLUGGED OR OTHERWISE DISCONTINUED AT POINTS WHICH WILL NOT INTERFERE WITH THE EXECUTION OF THE WORK, SUBJECT TO APPLICABLE REGULATORY AUTHORITIES
20. CONTRACTOR SHALL MINIMIZE DISTURBANCE TO EXISTING SITE DURING CONSTRUCTION. EROSION CONTROL MEASURES, IF REQUIRED DURING CONSTRUCTION SHALL BE IN CONFORMANCE WITH JURISDICTIONAL OR STATE AND LOCAL GUIDELINES FOR EROSION AND SEDIMENT CONTROL AND COORDINATED WITH LOCAL REGULATORY AUTHORITIES.
21. ALL CONSTRUCTION IS TO ADHERE TO VERIZON'S INTEGRATED CONSTRUCTION STANDARDS UNLESS CALIFORNIA CODE IS MORE STRINGENT.
22. THE INTENT OF THE PLANS AND SPECIFICATIONS IS TO PERFORM THE CONSTRUCTION IN ACCORDANCE WITH THE CALIFORNIA BUILDING STANDARDS CODE, TITLES 19 AND 24, CALIFORNIA CODE OF REGULATIONS. SHOULD ANY CONDITIONS DEVELOP NOT COVERED BY THE APPROVED PLANS AND SPECIFICATIONS WHEREIN THE FINISHED WORK WILL NOT COMPLY WITH TITLE 24, CALIFORNIA CODE OF REGULATIONS, A CHANGE ORDER DETAILING AND SPECIFYING THE REQUIRED WORK SHALL BE SUBMITTED TO AND APPROVED BY THE JURISDICTION BEFORE PROCEEDING WITH THE WORK.

SITE WORK NOTES

1. DO NOT EXCAVATE OR DISTURB BEYOND THE PROPERTY LINES OR LEASE LINES, UNLESS OTHERWISE NOTED.
2. DO NOT SCALE BUILDING DIMENSIONS FROM DRAWING.
3. SIZE, LOCATION AND TYPE OF ANY UNDERGROUND UTILITIES OR IMPROVEMENTS SHALL BE ACCURATELY NOTED AND PLACED ON AS-BUILT DRAWINGS BY GENERAL CONTRACTOR AND ISSUED TO ARCHITECT/ENGINEER AT COMPLETION OF PROJECT.
4. ALL EXISTING UTILITIES, FACILITIES, CONDITIONS AND THEIR DIMENSIONS SHOWN ON PLANS HAVE BEEN PLOTTED FROM AVAILABLE RECORDS. THE ENGINEER AND OWNER ASSUME NO RESPONSIBILITY WHATSOEVER AS TO THE SUFFICIENCY OR ACCURACY OF THE INFORMATION SHOWN ON THE PLANS OR THE MANNER OF THEIR REMOVAL OR ADJUSTMENT. CONTRACTOR SHALL BE RESPONSIBLE FOR DETERMINING EXACT LOCATION OF ALL EXISTING UTILITIES AND FACILITIES PRIOR TO START OF CONSTRUCTION. CONTRACTOR SHALL ALSO OBTAIN FROM EACH UTILITY COMPANY DETAILED INFORMATION RELATIVE TO WORKING SCHEDULES AND METHODS OF REMOVING OR ADJUSTING EXISTING UTILITIES.
5. CONTRACTOR SHALL VERIFY ALL EXISTING UTILITIES BOTH HORIZONTALLY AND VERTICALLY PRIOR TO START OF CONSTRUCTION. ANY DISCREPANCIES OR DOUBTS AS TO THE INTERPRETATION OF PLANS SHALL BE IMMEDIATELY REPORTED TO THE ARCHITECT/ENGINEER FOR RESOLUTION AND INSTRUCTION, AND NO FURTHER WORK SHALL BE PERFORMED UNTIL THE DISCREPANCY IS CHECKED AND CORRECTED BY THE ARCHITECT/ENGINEER. FAILURE TO SECURE SUCH INSTRUCTION MEANS CONTRACTOR WILL HAVE WORKED AT HIS/HER OWN RISK AND EXPENSE. CONTRACTOR SHALL CALL LOCAL DIGGER HOT LINE FOR UTILITY LOCATIONS 48 HOURS PRIOR TO START OF CONSTRUCTION.
6. ALL NEW AND EXISTING UTILITY STRUCTURES ON SITE AND IN AREAS TO BE DISTURBED BY CONSTRUCTION SHALL BE ADJUSTED TO FINISH ELEVATIONS PRIOR TO FINAL INSPECTION OF WORK.
7. GRADING OF THE SITE WORK AREA IS TO BE SMOOTH AND CONTINUOUS IN SLOPE AND IS TO FEATHER INTO EXISTING GRADES AT THE GRADING LIMITS.
8. ALL TEMPORARY EXCAVATIONS FOR THE INSTALLATION OF FOUNDATIONS, UTILITIES, ETC., SHALL BE PROPERLY LAID BACK OR BRACED IN ACCORDANCE WITH CORRECT OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION (OSHA) REQUIREMENTS.
9. STRUCTURAL FILLS SUPPORTING PAVEMENTS SHALL BE COMPACTED TO 95% OF MAXIMUM STANDARD PROCTOR DRY DENSITY.
10. NEW GRADES NOT IN BUILDING AND DRIVEWAY IMPROVEMENT AREA TO BE ACHIEVED BY FILLING WITH APPROVED CLEAN FILL AND COMPACTED TO 95% OF STANDARD PROCTOR DENSITY.
11. ALL FILL SHALL BE PLACED IN UNIFORM LIFTS. THE LIFTS THICKNESS SHOULD NOT EXCEED THAT WHICH CAN BE PROPERLY COMPACTED THROUGHOUT ITS ENTIRE DEPTH WITH THE EQUIPMENT AVAILABLE.
12. ANY FILLS PLACED ON EXISTING SLOPES THAT ARE STEEPER THAN 10 HORIZONTAL TO 1 VERTICAL SHALL BE PROPERLY BENCHED INTO THE EXISTING SLOPE AS DIRECTED BY A GEOTECHNICAL ENGINEER.
13. CONTRACTOR SHALL CLEAN ENTIRE SITE AFTER CONSTRUCTION SUCH THAT NO PAPERS, TRASH, WEEDS, BRUSH OR ANY OTHER DEPOSITS WILL REMAIN. ALL MATERIALS COLLECTED DURING CLEANING OPERATIONS SHALL BE DISPOSED OF OFF-SITE BY THE GENERAL CONTRACTOR.
14. ALL TREES AND SHRUBS WHICH ARE NOT IN DIRECT CONFLICT WITH THE IMPROVEMENTS SHALL BE PROTECTED BY THE GENERAL CONTRACTOR.
15. ALL SITE WORK SHALL BE CAREFULLY COORDINATED BY GENERAL CONTRACTOR WITH LOCAL UTILITY COMPANY, TELEPHONE COMPANY, AND ANY OTHER UTILITY COMPANIES HAVING JURISDICTION OVER THIS LOCATION.

ENVIRONMENTAL NOTES

1. ALL WORK PERFORMED SHALL BE DONE IN ACCORDANCE WITH ISSUED PERMITS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PAYMENT OF FINES AND PROPER CLEAN UP FOR AREAS IN VIOLATION.
2. CONTRACTOR AND/OR DEVELOPER SHALL BE RESPONSIBLE FOR CONSTRUCTION AND MAINTENANCE OF EROSION AND SEDIMENTATION CONTROLS DURING CONSTRUCTION FOR PROTECTION OF ADJACENT PROPERTIES, ROADWAYS AND WATERWAYS AND SHALL BE MAINTAINED IN PLACE THROUGH FINAL JURISDICTIONAL INSPECTION & RELEASE OF SITE.
3. CONTRACTOR SHALL INSTALL/CONSTRUCT ALL NECESSARY SEDIMENT/SILT CONTROL FENCING AND PROTECTIVE MEASURES WITHIN THE LIMITS OF SITE DISTURBANCE PRIOR TO CONSTRUCTION.
4. NO SEDIMENT SHALL BE ALLOWED TO EXIT THE PROPERTY. THE CONTRACTOR IS RESPONSIBLE FOR TAKING ADEQUATE MEASURES FOR CONTROLLING EROSION. ADDITIONAL SEDIMENT CONTROL FENCING MAY BE REQUIRED IN ANY AREAS SUBJECT TO EROSION.
5. THE CONTRACTOR IS RESPONSIBLE FOR MAINTAINING POSITIVE DRAINAGE ON THE SITE AT ALL TIMES WITH SILT AND EROSION CONTROL MEASURES MAINTAINED ON THE DOWNSTREAM SIDE OF SITE DRAINAGE. ANY DAMAGE TO ADJACENT PROPERTY AS A RESULT OF EROSION WILL BE CORRECTED AT THE CONTRACTORS EXPENSE.
6. CONTRACTOR SHALL BE RESPONSIBLE FOR DAILY INSPECTIONS AND ANY REPAIRS OF ALL SEDIMENT CONTROL MEASURES INCLUDING SEDIMENT REMOVAL AS NECESSARY.
7. CLEARING OF VEGETATION AND TREE REMOVAL SHALL BE ONLY AS PERMITTED AND BE HELD TO A MINIMUM. ONLY TREES NECESSARY FOR CONSTRUCTION OF THE FACILITIES SHALL BE REMOVED.
8. SEEDING AND MULCHING AND/OR SODDING OF THE SITE WILL BE ACCOMPLISHED AS SOON AS POSSIBLE AFTER COMPLETION OF THE PROJECT FACILITIES AFFECTING LAND DISTURBANCE.
9. CONTRACTOR SHALL PROVIDE ALL EROSION AND SEDIMENTATION CONTROL MEASURES AS REQUIRED BY LOCAL, COUNTY AND STATE CODES AND ORDINANCES TO PROTECT EMBANKMENTS FROM SOIL LOSS AND TO PREVENT ACCUMULATION OF SOIL AND SILT IN STREAMS AND DRAINAGE PATHS LEAVING THE CONSTRUCTION AREA. THIS MAY INCLUDE SUCH MEASURES AS SILT FENCES, STRAW BALE SEDIMENT BARRIERS, AND CHECK DAMS.
10. RIP RAP OF SIZES INDICATED SHALL CONSIST OF CLEAN, HARD, SOUND, DURABLE, UNIFORM IN QUALITY STONE FREE OF ANY DETRIMENTAL QUANTITY OF SOFT, FRIABLE, THIN, ELONGATED OR LAMINATED PIECES, DISINTEGRATED MATERIAL, ORGANIC MATTER, OIL, ALKALI, OR OTHER DELETERIOUS SUBSTANCES

GENERAL NOTES

1. THESE NOTES SHALL BE CONSIDERED A PART OF THE WRITTEN SPECIFICATIONS, CONTRACT AND CONSTRUCTION DOCUMENTS.
2. THE WORK SHALL INCLUDE FURNISHING MATERIALS, EQUIPMENT, APPURTENANCES, AND LABOR NECESSARY TO COMPLETE ALL INSTALLATIONS AS INDICATED ON THESE PLANS AND IN THE CONTRACT DOCUMENTS.
3. PRIOR TO THE SUBMISSION OF BIDS, THE CONTRACTOR(S) SHALL VISIT THE JOB SITE(S) AND BE RESPONSIBLE FOR ALL CONTRACT DOCUMENTS, FIELD CONDITIONS AND DIMENSIONS, AND CONFIRM THAT THE WORK MAY BE ACCOMPLISHED PER THE CONTRACT DOCUMENTS. ANY DISCREPANCIES ARE TO BE BROUGHT TO THE ATTENTION OF THE IMPLEMENTATION ENGINEER AND ARCHITECT/ENGINEER PRIOR TO BID SUBMITTAL
4. THE CONTRACTOR SHALL RECEIVE WRITTEN AUTHORIZATION TO PROCEED ON ANY WORK NOT CLEARLY DEFINED OR IDENTIFIED IN THE CONTRACT AND CONSTRUCTION DOCUMENTS BEFORE STARTING ANY WORK.
5. ALL WORK PERFORMED AND MATERIALS INSTALLED SHALL BE IN STRICT ACCORDANCE WITH ALL APPLICABLE CODES, REGULATIONS, AND ORDINANCES, INCLUDING APPLICABLE MUNICIPAL AND UTILITY COMPANY SPECIFICATIONS.
6. THE CONTRACTOR SHALL INSTALL ALL EQUIPMENT AND MATERIALS IN ACCORDANCE WITH MANUFACTURER RECOMMENDATIONS. IF THESE RECOMMENDATIONS ARE IN CONFLICT WITH THE CONTRACT AND CONSTRUCTION DOCUMENTS AND/OR APPLICABLE CODES OR REGULATIONS, REVIEW AND RESOLVE THE CONFLICT WITH DIRECTION FROM THE IMPLEMENTATION ENGINEER AND ARCHITECT/ENGINEER PRIOR TO PROCEEDING.
7. THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR ALL CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES AND FOR COORDINATION OF ALL PORTIONS OF THE WORK UNDER THE CONTRACT INCLUDING CONTACT AND COORDINATION WITH THE IMPLEMENTATION ENGINEER AND WITH THE AUTHORIZED REPRESENTATIVE OF ANY OUTSIDE POLE OR PROPERTY OWNER.
8. THE CONTRACTOR SHALL MAKE NECESSARY PROVISIONS TO PROTECT EXISTING IMPROVEMENTS, INCLUDING BUT NOT LIMITED TO PAVING, CURBS, VEGETATION, GALVANIZED SURFACE OR OTHER EXISTING ELEMENTS AND UPON COMPLETION OF THE WORK, REPAIR ANY DAMAGE THAT OCCURRED DURING CONSTRUCTION TO THE SATISFACTION OF VERIZON.
9. CONTRACTOR IS TO KEEP THE GENERAL AREA CLEAN, HAZARD FREE, AND DISPOSE OF ALL DIRT, DEBRIS, RUBBISH, AND REMOVE EQUIPMENT NOT SPECIFIED AS REMAINING ON THE PROPERTY. LEAVE PREMISES IN CLEAN CONDITION DAILY.
10. PLANS ARE INTENDED TO BE DIAGRAMMATIC ONLY AND SHOULD NOT BE SCALED UNLESS OTHERWISE NOTED. RELY ONLY ON ANNOTATED DIMENSIONS AND REQUEST INFORMATION IF ADDITIONAL DIMENSIONS ARE REQUIRED.
11. THE EXISTENCE AND LOCATION OF UTILITIES AND OTHER AGENCY'S FACILITIES WERE OBTAINED BY A SEARCH OF AVAILABLE RECORDS. OTHER FACILITIES MAY EXIST. CONTRACTOR SHALL VERIFY LOCATIONS PRIOR TO START OF CONSTRUCTION AND USE EXTREME CARE AND PROTECTIVE MEASURES TO PREVENT DAMAGE TO THESE FACILITIES. CONTRACTOR IS RESPONSIBLE FOR THE PROTECTION OF UTILITIES OR OTHER AGENCY'S FACILITIES WITHIN THE LIMITS OF THE WORK, WHETHER THEY ARE IDENTIFIED IN THE CONTRACT DOCUMENTS OR NOT.
12. THE CONTRACTOR SHALL NOTIFY UNDERGROUND SERVICE ALERT (800) 227-2600, AT LEAST TWO WORKING DAYS PRIOR TO THE START OF ANY EXCAVATION.

DEFINITIONS

1. "TYPICAL" OR "TYP" MEANS THAT THIS ITEM IS SUBSTANTIALLY THE SAME ACROSS SIMILAR CONDITIONS. "TYP." SHALL BE UNDERSTOOD TO MEAN "TYPICAL WHERE OCCURS" AND SHALL NOT BE CONSIDERED AS WITHOUT EXCEPTION OR CONSIDERATION OF SPECIFIC CONDITIONS.
2. "SIMILAR" MEANS COMPARABLE TO CHARACTERISTICS FOR THE CONDITION NOTED. VERIFY DIMENSIONS AND ORIENTATION ON PLAN.
3. "AS REQUIRED" MEANS AS REQUIRED BY REGULATORY REQUIREMENTS, BY REFERENCED STANDARDS, BY EXISTING CONDITIONS, BY GENERALLY ACCEPTED CONSTRUCTION PRACTICE, OR BY THE CONTRACT DOCUMENTS.
4. "ALIGN" MEANS ACCURATELY LOCATE FINISH FACES OF MATERIALS IN THE SAME PLANE.
5. THE TERM "VERIFY" OR "V.I.F." SHALL BE UNDERSTOOD TO MEAN "VERIFY IN FIELD WITH ENGINEER" AND REQUIRES THAT THE CONTRACTOR CONFIRM INTENTION REGARDING NOTED CONDITION AND PROCEED ONLY AFTER RECEIVING DIRECTION.
6. WHERE THE WORDS "OR EQUAL" OR WORDS OF SIMILAR INTENT FOLLOW A MATERIAL SPECIFICATION, THEY SHALL BE UNDERSTOOD TO REQUIRE SIGNED APPROVAL OF ANY DEVIATION TO SAID SPECIFICATION PRIOR TO CONTRACTOR'S ORDERING OR INSTALLATION OF SUCH PROPOSED EQUAL PRODUCT.
7. FURNISH: SUPPLY ONLY, OTHERS TO INSTALL.
INSTALL: INSTALL ITEMS FURNISHED BY OTHERS.
PROVIDE: FURNISH AND INSTALL.

811

USA North

Know what's below.
Call before you dig.

California and Nevada
Call Two Working Days Before You Dig!
811 / 800-227-2600

verizon

2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

Vinculums

575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500

ALL STATES
ENGINEERING & SURVEYING
A ZALZALI & ASSOCIATES COMPANY

23675 BIRTCHER DRIVE
LAKE FOREST, CA 92630
PHONE: (949) 273-0996

PROJECT ID:	P-334882
DRAWN BY:	RF
CHECKED BY:	DW

2	08/31/2020	100% CD'S FOR SUBMITTAL	MG
1	06/11/2020	100% CD'S FOR SUBMITTAL	RF
0	05/22/2020	100% CD'S FOR APPROVAL	RF
B	05/04/2020	95% CD'S FOR REDLINE	RF
A	04/29/2020	90% CD'S FOR REDLINE	RF
REV	DATE	DESCRIPTION	

REGISTERED PROFESSIONAL ENGINEER
MUSAM ZALZALI
71655
CIVIL
STATE OF CALIFORNIA

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 061

LIC R.O.W. ADJACENT TO:
1221 MIDDLEFIELD RD.
PALO ALTO, 94301
LOCATION CODE: 425208

SHEET TITLE

GENERAL NOTES

SHEET NUMBER

GN-1

- ELECTRICAL CONTRACTOR SHALL SUPPLY AND INSTALL ANY/ELECTRICAL WORK INDICATED. ANY/ALL CONSTRUCTION SHALL BE IN ACCORDANCE W/DRAWINGS AND ANY/ALL APPLICABLE SPECIFICATIONS. IF ANY PROBLEMS ARE ENCOUNTERED BY COMPLYING WITH THESE REQUIREMENTS, CONTRACTOR SHALL NOTIFY 'CONSTRUCTION MANAGER' AS SOON AS POSSIBLE, AFTER THE DISCOVERY OF THE PROBLEMS, AND SHALL NOT PROCEED WITH THAT PORTION OF WORK, UNTIL THE 'CONSTRUCTION MANAGER' HAS DIRECTED THE CORRECTIVE ACTIONS TO BE TAKEN.
2. ELECTRICAL CONTRACTOR SHALL VISIT THE JOB SITE AND FAMILIARIZE HIMSELF WITH ANY/ALL CONDITIONS AFFECTING ELECTRICAL AND COMMUNICATION INSTALLATION AND MAKE PROVISIONS AS TO THE COST THEREOF. ALL EXISTING CONDITIONS OF ELECTRICAL EQUIP., LIGHT FIXTURES, ETC., THAT ARE PART OF THE FINAL SYSTEM, SHALL BE VERIFIED BY THE CONTRACTOR, PRIOR TO THE SUBMITTING OF HIS BID. FAILURE TO COMPLY WITH THIS PARAGRAPH WILL IN NO WAY RELIEVE CONTRACTOR OF PERFORMING ALL WORK NECESSARY FOR A COMPLETE AND WORKING SYSTEM.
3. ALL WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE LATEST EDITION OF THE NEC AND ALL CODES AND LOCAL ORDINANCES OF THE LOCAL POWER & TELEPHONE COMPANIES HAVING JURISDICTION AND SHALL INCLUDE BUT NOT BE LIMITED TO:
 - A. UL - UNDERWRITERS LABORATORIES
 - B. NEC - NATIONAL ELECTRICAL CODE
 - C. NEMA - NATIONAL ELECTRICAL MANUFACTURERS ASSOC.
 - D. OSHA - OCCUPATIONAL SAFETY AND HEALTH ACT
 - E. SBC - STANDARD BUILDING CODE
4. DO NOT SCALE ELECTRICAL DRAWINGS, REFER TO SITE PLANS AND ELEVATIONS FOR EXACT LOCATIONS OF ALL EQUIPMENT, AND CONFIRM WITH 'CONSTRUCTION MANAGER' ANY SIZES AND LOCATIONS WHEN NEEDED.
5. EXISTING SERVICES: CONTRACTOR SHALL NOT INTERRUPT EXISTING SERVICES WITHOUT WRITTEN PERMISSION OF THE OWNER.
6. CONTRACTOR SHALL PAY FOR ANY/ALL PERMITS, FEES, INSPECTIONS AND TESTING. CONTRACTOR IS TO OBTAIN PERMITS AND APPROVED SUBMITTALS PRIOR TO THE WORK BEGINNING OR ORDERING EQUIPMENT.
7. THE TERM "PROVIDE" USED IN CONSTRUCTION DOCUMENTS AND SPECIFICATIONS, INDICATES THAT THE CONTRACTOR SHALL FURNISH AND INSTALL.
8. CONTRACTOR SHALL CONFIRM WITH LOCAL UTILITY COMPANY ANY/ALL REQUIREMENTS SUCH AS THE LUG SIZE RESTRICTIONS, CONDUIT ENTRY, SIZE OF TRANSFORMERS, SCHEDULED DOWNTIME FOR THE OWNERS' CONFIRMATION, ETC... ANY/ALL CONFLICTS SHALL BE BROUGHT TO THE ATTENTION OF THE CONSTRUCTION MANAGER, PRIOR TO BEGINNING ANY WORK.
9. MINIMUM WIRE SIZE SHALL BE #12 AWG, NOT INCLUDING CONTROL WIRING, UNLESS NOTED OTHERWISE. ALL CONDUCTORS SHALL BE COPPER WITH THWN INSULATION.
10. OUTLET BOXES SHALL BE PRESSED STEEL IN DRY LOCATIONS, CAST ALLOY WITH THREADED HUBS IN WET/DAMP LOCATIONS AND SPECIAL ENCLOSURES FOR OTHER CLASSIFIED AREAS.
11. IT IS NOT THE INTENT OF THESE PLANS TO SHOW EVERY MINOR DETAIL OF THE CONSTRUCTION. CONTRACTOR IS EXPECTED TO FURNISH AND INSTALL ALL ITEMS FOR A COMPLETE ELECTRICAL SYSTEM AND PROVIDE ALL REQUIREMENTS FOR THE EQUIPMENT TO BE PLACED IN PROPER WORKING ORDER.
12. ELECTRICAL SYSTEM SHALL BE AS COMPLETELY AND EFFECTIVELY GROUNDED, AS REQUIRED BY SPECIFICATIONS, SET FORTH BY VERIZON.
13. ALL WORK SHALL BE PERFORMED BY A LICENSED ELECTRICAL CONTRACTOR IN A FIRST CLASS, WORKMANLIKE MANNER. THE COMPLETED SYSTEM SHALL BE FULLY OPERATIVE AND SUBJECT TO REGULATORY INSPECTION AND APPROVAL BY CONSTRUCTION MANAGER.
14. ALL WORK SHALL BE COORDINATED WITH OTHER TRADES TO AVOID INTERFERENCE WITH THE PROGRESS OF CONSTRUCTION.
15. CONTRACTOR SHALL GUARANTEE ANY/ALL MATERIALS AND WORK FREE FROM DEFECTS FOR A PERIOD OF NOT LESS THAN ONE YEAR FROM DATE OF ACCEPTANCE.
16. THE CORRECTION OF ANY DEFECTS SHALL BE COMPLETED WITHOUT ANY ADDITIONAL CHARGE AND SHALL INCLUDE THE REPLACEMENT OR THE REPAIR OF ANY OTHER PHASE OF THE INSTALLATION, WHICH MAY HAVE BEEN DAMAGED THEREIN.
17. ADEQUATE AND REQUIRED LIABILITY INSURANCE SHALL BE PROVIDED FOR PROTECTION AGAINST PUBLIC LOSS AND ANY/ALL PROPERTY DAMAGE FOR THE DURATION OF WORK.
18. PROVIDE AND INSTALL CONDUIT, CONDUCTORS, PULL WIRES, BOXES, COVER PLATES AND DEVICES FOR ALL OUTLETS AS INDICATED.
19. DITCHING AND BACK FILL: CONTRACTOR SHALL PROVIDE FOR ALL UNDERGROUND INSTALLED CONDUIT AND/OR CABLES INCLUDING EXCAVATION AND BACKFILLING AND COMPACTION. REFER TO NOTES AND REQUIREMENTS 'EXCAVATION, AND BACKFILLING.
20. MATERIALS, PRODUCTS AND EQUIPMENT, INCLUDING ALL COMPONENTS THEREOF, SHALL BE NEW AND SHALL APPEAR ON THE LIST OF U.L. APPROVED ITEMS AND SHALL MEET OR EXCEED THE REQUIREMENTS OF THE NEC, NEMA AND IECE.
21. CONTRACTOR SHALL SUBMIT SHOP DRAWINGS OR MANUFACTURERS CATALOG INFORMATION OF ANY/ALL LIGHTING FIXTURES, SWITCHES AND ALL OTHER ELECTRICAL ITEMS FOR APPROVAL BY THE CONSTRUCTION MANAGER PRIOR TO INSTALLATION.
22. ANY CUTTING OR PATCHING DEEMED NECESSARY FOR ELECTRICAL WORK IS THE ELECTRICAL CONTRACTORS RESPONSIBILITY AND SHALL BE INCLUDED IN THE COST FOR INSTALL AND PERFORMED TO THE SATISFACTION OF THE 'CONSTRUCTION MANAGER' UPON FINAL ACCEPTANCE.
23. THE ELECTRICAL CONTRACTOR SHALL LABEL ALL PANELS WITH ONLY TYPEWRITTEN DIRECTORIES. ALL ELECTRICAL WIRING SHALL BE THE RESPONSIBILITY OF THE ELECTRICAL CONTRACTOR.
24. DISCONNECT SWITCHES SHALL BE H.P. RATED HEAVY-DUTY, QUICK-MAKE AND QUICK-BREAK ENCLOSURES, AS REQUIRED BY EXPOSURE TYPE.
25. ALL CONNECTIONS SHALL BE MADE WITH A PROTECTIVE COATING OF AN ANTI-OXIDE COMPOUND SUCH AS 'NO-OXIDE A' BY DEARBORNE CHEMICAL CO. COAT ALL WIRE SURFACES BEFORE CONNECTING. EXPOSED COPPER SURFACES, INCLUDING GROUND BARS, SHALL BE TREATED - NO SUBSTITUTIONS.
26. RACEWAYS: CONDUIT SHALL BE SCHEDULE 40 PVC MEETING OR EXCEEDING NEMA TC2 - 1990. CONTRACTOR SHALL PLUG AND CAP EACH END OF SPARE AND EMPTY CONDUITS AND PROVIDE TWO SEPARATE PULL STRINGS - 200 LBS TEST POLYETHYLENE CORD. ALL CONDUIT BENDS SHALL BE A MINIMUM OF 2 FT. RADIUS. RGS CONDUITS WHEN SPECIFIED, SHALL MEET UL-6 FOR GALVANIZED STEEL. ALL FITTINGS SHALL BE SUITABLE FOR USE WITH THREADED RIGID CONDUIT. COAT ALL THREADS WITH 'BRITE ZINC' OR 'GOLD GALV'.
27. SUPPORT OF ALL ELECTRICAL WORK SHALL BE AS REQUIRED BY NEC.

- ALL DETAILS ARE SHOWN IN GENERAL TERMS. ACTUAL GROUNDING INSTALLATION AND CONSTRUCTION MAY VARY DUE TO SITE SPECIFIC CONDITIONS.
10. GROUND ALL ANTENNA BASES, FRAMES, CABLE RUNS, AND OTHER METALLIC COMPONENTS USING #2 GROUND WIRES AND CONNECT TO SURFACE MOUNTED GROUND BUS BARS AS SHOWN. FOLLOW ANTENNA AND BTS MANUFACTURER'S PRACTICES FOR GROUNDING REQUIREMENTS. GROUND COAX SHIELD AT BOTH ENDS USING MANUFACTURERS PRACTICES. ALL UNDERGROUND WATER PIPES, METAL CONDUITS AND GROUNDS THAT ARE A PART OF THIS SYSTEM SHALL BE BONDED TOGETHER.
11. ALL GROUND CONNECTIONS SHALL BE #2 AWG U.N.O. ALL WIRES SHALL BE COPPER THHN/THWN. ALL GROUND WIRE SHALL BE SOLID TIN COATED OR STRANDED GREEN INSULATED WIRE.
12. CONTRACTOR TO VERIFY AND TEST GROUND TO SOURCE, 5 OHMS MAXIMUM. PROVIDE SUPPLEMENT GROUNDING RODS AS REQUIRED TO ACHIEVE SPECIFIED OHMS READING. GROUNDING AND OTHER OPTIONAL TESTING WILL BE WITNESSED BY THE VERIZON REPRESENTATIVE.
13. NOTIFY ARCHITECT/ENGINEER IF THERE ARE ANY DIFFICULTIES INSTALLING GROUNDING SYSTEM DUE TO SITE SOIL CONDITIONS.
14. BARE GROUNDING CONDUCTOR SHALL BE HARD DRAWN TINNED COPPER SIZES AS NOTED ON PLAN.
15. ALL HORIZONTALLY RUN GROUNDING CONDUCTORS SHALL BE INSTALLED MINIMUM 12" BELOW GRADE/FROST-LINE IN TRENCH, U.N.O., AND BACK FILL SHALL BE COMPACTED AS REQUIRED BY ARCHITECT.
16. ALL GROUND CONDUCTORS SHALL BE RUN AS STRAIGHT AND SHORT AS POSSIBLE, WITH A MINIMUM 12" BENDING RADIUS NOT LESS THAN 90 DEGREES.
17. ALL SUPPORT STRUCTURES, CABLE CHANNEL WAYS OR WIRE GUIDES SHALL BE BONDED TO GROUND SYSTEM AT A POINT NEAREST THE MAIN GROUNDING BUS "MGB" (OR DIRECTLY TO GROUND-RING).
18. ACCEPTABLE CONNECTIONS FOR GROUNDING SYSTEM SHALL BE:
 - a. BURNDY, HY-GRADE U.L. LISTED CONNECTORS FOR INDOOR USE OR AS APPROVED BY VERIZON PROJECT MANAGER.
 - b. CADWELD, EXOTHERMIC WELDS (WELDED CONNECTIONS).
 - c. TWO -(2)-HOLE TINNED COPPER COMPRESSION (LONG BARREL) FITTINGS (BUS BAR CONNECTIONS).
19. ALL CRIMPED CONNECTIONS SHALL HAVE EMBOSSED MANUFACTURER'S DIEMARK VISIBLE AT THE CRIMP (RESULTING FROM USE OF PROPER CRIMPING DEVICES).
20. PRIOR TO ANY LUG-BUSSBAR CONNECTIONS, THE BUSSBAR SHALL BE CLEANED BY USE OF "SCOTCH-BRITE" OR PLAIN STEEL WOOL AS TO REMOVE ALL SURFACE OXIDATION AND CONTAMINANTS. A COATING OF "NO-OX-ID" SHALL BE APPLIED TO THE CONNECTION SURFACES.
21. ALL CONNECTION HARDWARE SHALL BE TYPE 316 SS (NOT ATTRACTED TO MAGNETS).
22. THE GROUND RING SHALL BE INSTALLED 24" MINIMUM BEYOND ANY BUILDING DRIP LINE.
23. ELECTRICAL SERVICE EQUIPMENT GROUNDING SHALL COMPLY WITH NEC, ARTICLE 250-82 AND SHALL BOND ALL EXISTING AND NEW GROUNDING ELECTRODES. NEW GROUNDING ELECTRODE SHALL INCLUDE BUT NOT LIMITED TO GROUND RODS, GROUND RING IF SERVICE IS WITHIN THE RADIO EQUIPMENT LOCATION, BUILDING STEEL IF APPLICABLE, COLD WATER CONNECTIONS MUST BE MADE ON THE STREET SIDE OF MAIN SHUT-OFF VALVE.

2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500

23675 BIRTCHER DRIVE
LAKE FOREST, CA 92630
PHONE: (949) 273-0996

2	08/31/2020	100% CD'S FOR SUBMITTAL	M
1	06/11/2020	100% CD'S FOR SUBMITTAL	R
0	05/22/2020	100% CD'S FOR APPROVAL	R
B	05/04/2020	95% CD'S FOR REDLINE	R
A	04/24/2020	90% CD'S FOR REDLINE	R
REV	DATE	DESCRIPTION	



SF PALO ALTO 061
LIC R.O.W. ADJACENT TO:
1221 MIDDLEFIELD RD.
PALO ALTO, 94301
LOCATION CODE: 425208

SHEET TITLE

GENERAL NOTES

SHEET NUMBER

GN-2

NOTE:
ANY CONSTRUCTION WITHIN THE CITY'S
PUBLIC ROAD RIGHT-OF-WAY SHALL
HAVE AN APPROVED PERMIT FOR
CONSTRUCTION IN THE PUBLIC STREET
PRIOR TO COMMENCEMENT OF THIS WORK

City of Palo Alto
Tree Protection - It's Part of the Plan!

Make sure your crews and subs do the job right!

Fenced enclosures around trees are essential to protect them by keeping the foliage canopy and branching structure clear from contact by equipment, materials and activities, preserving roots and soil conditions in an intact and non-compacted state, and identifying the Tree Protection Zone (TPZ) in which no soil disturbance is permitted and activities are restricted, unless otherwise approved. **An approved tree protection report must be added to this sheet when project activity occurs within the TPZ of a regulated tree.**

For detailed information on Palo Alto's regulated trees and protection during development, review the **City Tree Technical Manual (TTM)** found at www.cityofpaloalto.org/trees/

For written specifications associated with illustrations below, see Public Works Specification Section 31.

Detailed specifications are found in the Palo Alto Tree Technical Manual (TTM) (www.aityofpalto.org/tree/)

Two Protection Zone (TPZ) shown in grey¹ extends at least 10 feet from the trunk of the tree to the nearest adjacent sidewalk or street.²

- ◆ Retention work by area – see Tree Technical Manual Sec 2.2(IV).
- ◆ Restricting trenching area – see Tree Technical Manual Sec 2.2(IV)(c), any proposed trench or ditch work within TPZ of a protected tree requires approval from Public Works Operations. Call 650-406-5955.

Type I Tree Protection

Note: [1] A Retention Protection Wall and Mitigation... [2] Any excavation or trenching... require engineering as designed on the plans.

Note: Obstruction Protected & Designated Trees: Issuance of a permit requires applicant's project arborist written verification Type I is installed correctly according to the plans and Tree Preservation Report

Type II Tree Protection

Note: Street Trees: Issuance of a permit requires Public Works Operations inspection and signed approval on the Street Tree Verification (STV) form provided.

Type III Tree Protection

(to be used only with approval of Public Works Operations)

Tree fencing is required and shall be erected before demolition, grading or construction begins.

Year	Sig.	Date
'97	070001	12/14/97
'01	010101	09/04/01
'02	020101	08/01/02
Current TTM's		

Tree Protection During Construction

City of Palo Alto Standard

Approved by:	Dave Dockter
PF No.	
Date	2006
Order	605

Table 2-2

Palo Alto Tree Technical Manual

CONTRACTOR & ARBOREST INSPECTION SCHEDULE

Reference: the Palo Alto Tree Technical Manual is available at www.cityofpaloalto.org/environment/

ALL CHECKED ITEMS APPLY TO THIS PROJECT:

1. ☒ **Inspection of Protective Tree Fencing:** For Public Trees, the Street Tree Verification Form shall be signed by the City Arborist. For Protected Trees, the project site arborist shall provide an initial Monthly Tree Activity Report form with a photograph verifying that he has conducted a field inspection of the trees and that the correct type of protective fencing is in place around the designated tree protection zone (TPZ) prior to issuance of a demolition, grading, or building permit (see TTM, Verification of Tree Protection, Section 1.19).
2. ☒ **Pre-Construction Meeting:** Prior to commencement of construction, the applicant or contractor shall conduct a pre-construction meeting to discuss tree protection with the job site superintendent, grading operator, project site arborist, City Arborist, and, if a city arborist is not available, the City Manager (Contract 650-498-6062).
3. ☒ **Inspection of Rough Grading or Trenching:** Contractor shall ensure the project site arborist performs an inspection during the course of grading in trenching adjacent to or within the TPZ to ensure trees will not be injured by compaction, cut or fill, damage and trenching, and if required, install aeration systems, use walkways, drains and special paving. The contractor shall provide the project arborist at least 24 hours advance notice of such activity.
4. ☒ **Monthly Tree Activity Report Inspections:** The project site arborist shall perform a minimum monthly activity inspection to monitor and advise on conditions, tree health and protection or, immediately if there are any deviations to the approved plans or protective measures. The Tree Technical Manual Monthly Tree Activity Report format shall be used and sent to the Planning Dept. landscape review staff no later than 14 days after issuance of building permit date. Fax to: (859) 329-2154. (see TTM, Monthly Tree Activity Inspection Report, Addendum 11.1 and version 1.17).
5. ☒ **Special activity within the Tree Protection Zone:** Work in the TPZ area (see also #1 below) requires the direct on-site supervision of the project arborist (see TTM, Trenching, Excavation & Equipment, Section 2.20 C).
6. ☐ **Landscape Architect Inspection:** For discretionary development projects, prior to temporary or final occupancy the applicant or contractor shall arrange for the Landscape Architect to perform an on-site inspection of all plant stock, quality of the materials and planting (see TTM, Planting Quality, Section 5.20.1 A) and that the irrigation is functioning consistent with the approved construction plans. The Planning Dept. landscape review staff shall be in receipt of written verification of the Landscape Architect approval prior to scheduling the final inspection, unless otherwise approved.
7. ☐ **List Other (please describe as called out in the site Tree Preservation Report, Sheet T-1, T-2, etc.)**
 - * _____
 - * _____

Arborist Firm Data Here:

ADDENDUM 11

SCADA Certified Arborist Firm
Contractor Use

Monthly Tree Activity Report- Construction Site

Inspection Date:	Site address:	Contractor- Main Site Contact Information	#1 Job site Superintendent, Company
Inspection #	PALO ALTO, CA		Email:
			Job site Office:
			Cell:
			Mail:
		Also present:	
Distribution:	1 City of Palo Alto	Attn: Dave Gouker	<u>Dave.gouker@cityofpaloalto.net</u> 650.320-3480
	2 Others		

Provide the requested minimum information with each report, estimate as necessary. To be completed for project site arborists. Send monthly to city arborist at above address until project completion. Site additional sheets as needed.

1. Assignment Activity (Demolition-grading-sewer-trenching-foundation-list relevant visits)
 - a. Pre-construction meeting requirement with sub-contractors
 - b. Inspect to verify that tree protection measures are in place
 - c. Determine if field adjustments, watering or plan revisions will be needed
2. Field Observations (general site-wide and list by individual tree number)
 - a. Tree Protection Fences (TPF) are
 - b. Trenching laws will occur
3. Action Items (list site-wide, by tree number and date to be satisfied) and One Due
 - a. Tree Protection Fence (TPF) needs adjusting (tree # x x, x)
 - b. Root zone/buffer material (wood chips) can be installed next
 - c. Schedule sewer trench, foundation dig with
4. Photographs (use often)
5. Tree Location Map (mandatory 8.5 x 11 sheet)
6. Recommendations, notes or monitor items for project/staff/schedule
 -
7. Past visits (list carry-over items satisfied/still outstanding)
 -

Respectfully Submitted,

Project site arborist
 Co-ordinator contact information (Include email, cell# and mailing)
 CC

Enter Date:

CPA Monthly Tree Activity Report: Type site address here

Page #5 of 11

PALO ALTO STREET TREE PROTECTION INSTRUCTIONS —SECTION 31—

APPENDIX J

31-1 General

- a. Tree protection has three primary functions: (1) to keep the foliage canopy and branching structure clear from utilities by equipment maintainers and activities; (2) to preserve trees and soil conditions in an urban and/or semi-urban setting; and (3) to identify the Tree Protection Zone (TPZ) in which no soil disturbance, construction, permitted and activities are restricted, unless otherwise approved.
- b. The Tree Protection Zone (TPZ) is a restricted zone around the base of the tree with a radius of treatment no less than the diameter of the tree trunk to its base, whichever is greater, or 10 feet.

31-2 References/Documents

- a. Detail of all dimensions of situations described below
- b. Tree Technical Manual (TTM) Form (<http://www.ci.paloalto.ca.us/ftp/tpz>)
 1. Tree/Planting Restrictions Zones (11-13, <http://www.ci.paloalto.ca.us/ftp/tpz>)
 2. Submittal Reporting Form (TPZ) (<http://www.ci.paloalto.ca.us/ftp/tpz>)
 3. Site Plan Requirements (12-24, <http://www.ci.paloalto.ca.us/ftp/tpz>)
 4. Tree Disclosure Statement (12-74, <http://www.ci.paloalto.ca.us/ftp/tpz>)
- c. Street Tree Verification (STV) Form (<http://www.ci.paloalto.ca.us/ftp/tpz>)

31-3 Exceptions

- a. **Type I Tree Protection:** The fence shall enclose the entire TPZ of the tree(s) to be protected throughout the life of the construction project. In non-urban areas, if funding is provided for planting in a street and soil is degraded, sign the post(s) can be supported by an appropriate grade-level concrete curb. If approved by Public Works Department.
- b. **Type II Tree Protection:** For trees situated within a planting strip, only the planting strip and yard side of the TPZ shall be enclosed with the required chain link protective fencing in order to keep the sidewalks and street open for public use.
- c. **Type III Tree Protection:** To be used only with approval of Public Works Department. Trees situated on a residential lot with sidewalks, planter pits, shall be wrapped with 2-inches of orange plastic fencing from the ground to the first branch and overlaid with 2-inches thick wooden slats bound together (slats shall be fastened to the tree with knots). During installation of the plastic fencing, caution shall be used to avoid damaging any branches. Markers shall also enclose plastic fencing as directed by the City Arborist.
- d. **Size, type and area to be fenced:** All trees to be preserved shall be protected with six (6") foot high chain link fences. Fences will be installed on a ten-inch diameter piloted iron posts, driven into the ground to a depth of at least 24-in; at no more than 10-foot spacing. Fencing shall extend to the outer branching, unless specifically approved on the STV Form.
- e. **Warning signs:** A warning sign shall be weather proof and prominently displayed on each fence at 70-foot intervals. The sign shall be minimum 8.5-inches x 11-inches and clearly state in bold black ink letters "WARNING: Tree Protection Zone - This fence shall not be removed or be subject to a fine according to PAMC Section 8.10110".
- f. **Durability:** Tree fencing shall be secured behind downspouts/gutters or construction barriers and designed in place until final inspection of the project, except for trees specifically identified in the TPZ. Work at and disturbance to the TPZ requires approval by the project arborealist or City Arborist file the use of work around Street Trees. Enclosures within the public right of way require a Street Work Permit from Public Works.


31-4 During construction

1. All neighbor's trees that overhang the project site shall be protected from injury of any kind.
2. The applicant shall be responsible for the repair or replacement plus penalty of any publicly owned trees that are damaged during the course of construction, pursuant to Section 8.10 of the Palo Alto Municipal Code.
3. The following tree preservation measures apply to all trees to be protected:
 - a. No storage of material, liquid, or equipment shall be permitted within the TPZ.
 - b. The ground under and around the tree canopy area shall not be altered.
 - c. Trees in an encased shall be repaired, secured and maintained as necessary to ensure survival.

END OF SECTION

City of Palo Alto 2009 Standard Documents and Specifications
Street Tree Verification of Permit, PWS, Section 31

Revised 08/06

	City of Palo Alto Tree Department Public Works Operations PG Box 10250 Palo Alto, CA 94303 (650)496-5863 FAX: (650)496-7289 treeprotection@cityofpaloalto.org	<h2 style="margin: 0;">Verification of Street Tree Protection</h2>
<i>Applicant Instructions: Complete upper portion of this form. Mail or FAX this form along with signed Tree Disclosure Statement to Public Works Dept. Public Works Tree Staff will inspect and notify applicant.</i>		
APPLICANT DATE:		
ADDRESS/LOCATION OF STREET TREES TO BE PROTECTED:		
APPLICANT'S NAME:		
APPLICANT'S ADDRESS:		
APPLICANT'S TELEPHONE & FAX NUMBERS:		
<i>This section to be filled out by City Tree Staff</i>		
1 The Street Trees at the above addresses are adequately protected. The type of protection used is:	YES <input type="checkbox"/> NO* <input type="checkbox"/> * If NO, go to #2 below	
Inspected by:		
Date of Inspection:		
2. The Street Trees at the above address are NOT adequately protected. The following modifications are required:	<hr/> <hr/> <hr/> <hr/> <hr/> <hr/> <hr/> <hr/> <hr/> <hr/>	
Indicate how the required modifications were communicated to the applicant: <hr/> <hr/> <hr/> <hr/> <hr/> <hr/> <hr/> <hr/> <hr/> <hr/>		
Subsequent Inspection		
Street trees at above address were found to be adequately protected:	YES <input type="checkbox"/> NO* <input type="checkbox"/> * If NO, indicate in "Notes" below the disposition of case.	
Inspected by:		
Date of Inspection:		
Notes: List City street trees by species, size, condition and type of tree protection installed. Also note if pictures were taken. Use back of sheet if necessary.		
Return approved sheet to Applicant for demolition or building permit issuance. <small>(DO NOT REPLY TO THIS E-MAIL)</small>		

1/1/06

---WARNING---

Tree Protection Zone

This fencing shall not be removed without City Arborist approval (650-496-5953)

Removal without permission is subject to a \$500 fine per day*

****Palo Alto Municipal Code Section 8.10.110***


City of Palo Alto Tree Protection Instructions are located at <http://www.city.palo-alto.ca.us/tree/technical-manual.html>

SPECIAL INSPECTIONS	PLANNING DEPARTMENT
TREE PROTECTION INSPECTIONS MANDATORY	
<p>PAMC 8.10 PROTECTED TREES: CONTRACTOR SHALL ENSURE PROJECT SITE ARBORIST IS PERFORMING REQUIRED TREE INSPECTION AND SITE MONITORING. PROVIDE WRITTEN MONTHLY TREE ACTIVITY REPORTS TO THE PLANNING DEPARTMENT LANDSCAPE REVIEW STAFF BEGINNING 14 DAYS AFTER BUILDING PERMIT ISSUANCE.</p>	
<p>BUILDING PERMIT DATE: _____</p>	
<p>DATE OF #1 TREE ACTIVITY REPORT: _____</p>	
<p>CITY STAMP: _____</p>	
<p>REPORTING DETAILS OF THE MONTHLY TREE ACTIVITY REPORT SHALL CONFORM TO SHEET T-1 FORMAT. VERIFY THAT ALL TREE PROTECTION MEASURES ARE IMPLEMENTED AND WILL INCLUDE ALL CONTRACTOR ACTIVITY, SCHEDULED OR UNSCHEDULED, WITHIN A TREE PROTECTION ROOT ZONE. NON-COMPLIANCE IS SUBJECT TO VIOLATION OF PAMC 8.10.080. REFERENCE: PALO ALTO TREE TECHNICAL MANUAL, SECTION 2.20 AND ADDENDUM 4.1.</p>	

Apply Tree Protection Report on sheet(s) T-2

Use additional "T" sheets as needed

City of Palo Alto
750 Hamilton Avenue, Palo Alto, CA 94301



Search: Advanced Search

Home > Planning & Community Environment > **Tree Technical Manual**

Home
City Government Home
[Privately-owned Trees]
About the Tree Ordinance
Tree ID Kit
[Purchase Trees]
Forms
Tree Technical Manual
FAQs
Contact Us
Resources

Tree Technical Manual

To purchase the Tree Technical Manual

June, 2001 First Edition

View by section:

- * Table of Contents (PDF, 679K)
- * Intent and Purpose (PDF, 1.05MB)
- * Introduction - Use of Manual (PDF, 1.05MB)
 - * Section 1.0 - Definitions (PDF, 96KB)
- * Section 2.0 - Protection of Trees During Construction (PDF, 259KB)
- * Section 3.0 - Removal, Replacement & Planting of Trees (PDF, 11.9KB)
- * Section 4.0 - Hazardous Trees (PDF, 105KB)
- * Section 5.0 - Tree Maintenance Guidelines (PDF, 110KB)
- * Section 6.0 - Tree Reports (PDF, 84KB)

View ALL sections:

- * Tree Technical Manual - Full (PDF, 1.84MB)

APPENDICES

- A. Palo Alto Municipal Code Chapter 8.10, Tree Preservation & Management Regulations
- B. True City - USA
- C. ISA Hazard Evaluation Form
- D. List of Inherent Failure Patterns for Selected Species (Reference source)
- E. ISA Tree Pruning Guidelines (ref. 1 asme)
- F. Tree Care Safety Standards, ANSI Z133.1-1994 (Reference source)
- G. Pruning Performance Standards, ANSI A309-1995 (Reference source)
- H. Tree Planting Details, Diagram S04 & S05
- I. Tree Disclosure Statement
- J. Palo Alto Standard Tree Protection Instructions

verizon[✓]

2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598



Vinculums

575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500

ALL STATES
ENGINEERING & SURVEYING
A ZALZALI & ASSOCIATES COMPANY

23675 BIRTCHER DRIVE
LAKE FOREST, CA 92630
PHONE: (949) 273-0996

PROJECT ID:	P-334882
DRAWN BY:	RF
CHECKED BY:	DW

2	08/31/2020	100% CD'S FOR SUBMITTAL	MG	
1	06/11/2020	100% CD'S FOR SUBMITTAL	RF	
0	05/22/2020	100% CD'S FOR APPROVAL	RF	
B	05/04/2020	95% CD'S FOR REDLINE	RF	
A	04/29/2020	90% CD'S FOR REDLINE	RF	
REV	DATE	DESCRIPTION		

REGISTERED PROFESSIONAL ENGINEER
WISSAM ZALZALI
71655
CIVIL
STATE OF CALIFORNIA

IT IS A VIOLATION OF LAW FOR ANY PERSON,
UNLESS THEY ARE ACTING UNDER THE
DIRECTION OF A LICENSED PROFESSIONAL
ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 061
LIC R.O.W. ADJACENT TO:
 1221 MIDDLEFIELD RD.
 PALO ALTO, 94301
 LOCATION CODE: 425208

SHEET TITLE
PALO ALTO TREE
PROTECTION

SHEET NUMBER

L-1

POLLUTION PREVENTION — IT'S PART OF THE PLAN

Construction projects are required to implement year-round stormwater BMPs, as they apply to your project.

Runoff from streets and other paved areas is a major source of pollution to San Francisco Bay. Construction activities can directly affect the health of the Bay unless contractors and crews plan ahead to keep construction dirt, debris, and other pollutants out of storm drains and local creeks. Following these guidelines will ensure your compliance with City of Palo Alto Ordinance requirements.



MATERIALS & WASTE MANAGEMENT

Non-Hazardous Materials

- ☐ Berm and cover stockpiles of sand, dirt or other construction material with tarps when rain is forecast or when they are not in use.
- ☐ Use (but don't overuse) reclaimed water for dust control.
- ☐ Ensure dust control water doesn't leave site or discharge to storm drains.

Hazardous Materials

- ☐ Label all hazardous materials and hazardous wastes (such as pesticides, paints, thinners, solvents, fuel, oil, and antifreeze) in accordance with city, county, state and federal regulations.
- ☐ Store hazardous materials and wastes in water tight containers, store in appropriate secondary containment, and cover them at the end of every work day or during wet weather or when rain is forecast.
- ☐ Follow manufacturer's application instructions for hazardous materials and do not use more than necessary. Do not apply chemicals outdoors when rain is forecast within 24 hours.
- ☐ Arrange for appropriate disposal of all hazardous wastes.

Waste Management

- ☐ Cover and maintain dumpsters. Check frequently for leaks. Place dumpsters under roofs or cover with tarps or plastic sheeting secured around the outside of the dumpster. A plastic liner is recommended to prevent leaks. Never clean out a dumpster by hosing it down on the construction site.
- ☐ Place portable toilets away from storm drains. Make sure they are in good working order. Check frequently for leaks.
- ☐ Dispose of all wastes and demolition debris properly. Recycle materials and wastes that can be recycled, including solvents, water-based paints, vehicle fluids, broken asphalt and concrete, wood, and cleared vegetation.
- ☐ Dispose of liquid residues from paints, thinners, solvents, glues, and cleaning fluids as hazardous waste.
- ☐ Keep site clear of litter (e.g. lunch items, cigarette butts).
- ☐ Prevent litter from uncovered loads by covering loads that are being transported to and from site.

Construction Entrances and Perimeter

- ☐ Establish and maintain effective perimeter controls and stabilize all construction entrances and exits to sufficiently control erosion and sediment discharges from site and tracking off site.
- ☐ Sweep or vacuum any street tracking immediately and secure sediment source to prevent further tracking. Never hose down streets to clean up tracking.



EQUIPMENT MANAGEMENT & SPILL CONTROL

Maintenance and Parking

- ☐ Designate an area of the construction site, well away from streams or storm drain inlets and fitted with appropriate BMPs, for auto and equipment parking, and storage.
- ☐ Perform major maintenance, repair jobs, and vehicle and equipment washing off site.
- ☐ If refueling or vehicle maintenance must be done onsite, work in a bermed area away from storm drains and over a drip pan or drop cloths big enough to collect fluids. Recycle or dispose of fluids as hazardous waste.
- ☐ If vehicle or equipment cleaning must be done onsite, clean with water only in a bermed area that will not allow rinse water to run into gutters, streets, storm drains, or surface waters.
- ☐ Do not clean vehicle or equipment onsite using soaps, solvents, degreasers, or steam cleaning equipment, and do not use diesel oil to lubricate equipment or parts onsite.

Spill Prevention and Control

- ☐ Keep spill cleanup materials (e.g., rags, absorbents and cat litter) available at the construction site at all times.
- ☐ Maintain all vehicles and heavy equipment. Inspect frequently for and repair leaks. Use drip pans to catch leaks until repairs are made.
- ☐ Clean up leaks, drips and other spills immediately and dispose of cleanup materials properly.
- ☐ Use dry cleanup methods whenever possible (absorbent materials, cat litter and/or rags).
- ☐ Sweep up spilled dry materials immediately. Never attempt to "wash them away" with water, or bury them.
- ☐ Clean up spills on dirt areas by digging up and properly disposing of contaminated soil.
- ☐ Report any hazardous materials spills immediately! Call City of Palo Alto Communications, (650) 329-2413. If the spill poses a significant hazard to human health and safety, property or the environment, you must report it to the State Office of Emergency Services, (800) 852-7550 (24 hours).



EARTHMOVING

Grading and Earthwork

- ☐ Schedule grading and excavation work during dry weather.
- ☐ Stabilize all denuded areas, install and maintain temporary erosion controls (such as erosion control fabric or bonded fiber matrix) until vegetation is established.
- ☐ Remove existing vegetation only when absolutely necessary, plant temporary vegetation for erosion control on slopes or where construction is not immediately planned.
- ☐ Prevent sediment from migrating offsite and protect storm drain inlets, drainage courses and streams by installing and maintaining appropriate BMPs (e.g., silt fences, gravel bags, fiber rolls, temporary swales, etc.).
- ☐ Keep excavated soil on site and transfer it to dump trucks on site, not in the streets.

Contaminated Soils

- ☐ If any of the following conditions are observed, test for contamination and contact the Regional Water Quality Control Board:
 - Unusual soil conditions, discoloration, or odor.
 - Abandoned underground tanks.
 - Abandoned wells.
 - Buried barrels, debris, or trash.
- ☐ If the above conditions are observed, document any signs of potential contamination and clearly mark them so they are not disturbed by construction activities.

Landscaping

- ☐ Protect stockpiled landscaping materials from wind and rain by storing them under tarps all year-round.
- ☐ Stack bagged material on pallets and under cover.
- ☐ Discontinue application of any erodible landscape material within 2 days before a forecast rain event or during wet weather.



CONCRETE MANAGEMENT & DEWATERING

Concrete Management

- ☐ Store both dry and wet materials under cover, protected from rainfall and runoff and away from storm drains or waterways. Store materials off the ground, on pallets. Protect dry materials from wind.
- ☐ Wash down exposed aggregate concrete only when the wash water can (1) flow onto a dirt area; (2) drain onto a bermed surface from which it can be pumped and disposed of properly; or (3) block any storm drain inlets and vacuum washwater from the gutter. If possible, sweep first.
- ☐ Wash-out concrete equipment/trucks offsite or in a designated washout area, where the water will flow into a temporary waste pit, and make sure wash water does not leach into the underlying soil. (See CASQA Construction BMP Handbook for properly designed concrete washouts.)

Dewatering

- ☐ Reuse water for dust control, irrigation or another on-site purpose to the greatest extent possible.
- ☐ Be sure to obtain a Permit for Construction in the Public Street from Public Works Engineering before discharging water to a street, gutter, or storm drain. Call the Regional Water Quality Control Plant (RWQCP) at (650) 329-2598 for an inspection prior to commencing discharge. Use filtration or diversion through a basin, tank, or sediment trap as required by the approved dewatering plan. Dewatering is not permitted from October to April.
- ☐ In areas of known contamination, testing is required prior to reuse or discharge of groundwater. Consult with the City inspector to determine what testing to do and to interpret results. Contaminated groundwater must be treated or hauled off-site for proper disposal.



PAVING/ASPHALT WORK

Paving

- ☐ Avoid paving and seal coating in wet weather or when rain is forecast, to prevent materials that have not cured from contacting stormwater runoff.
- ☐ Cover storm drain inlets and manholes when applying seal coat, slurry seal, fog seal, or similar materials.
- ☐ Collect and recycle or appropriately dispose of excess abrasive gravel or sand. Do NOT sweep or wash it into gutters.

Sawcutting & Asphalt/Concrete Removal

- ☐ Protect storm drain inlets during saw cutting.
- ☐ If saw cut slurry enters a catch basin, clean it up immediately.
- ☐ Shovel or vacuum saw cut slurry deposits and remove from the site. When making saw cuts, use as little water as possible. Sweep up, and properly dispose of all residues.



PAINTING & PAINT REMOVAL

Painting Cleanup and Removal

- ☐ Never clean brushes or rinse paint containers into a street, gutter, storm drain, or stream.
- ☐ For water-based paints, paint out brushes to the extent possible, and rinse into a drain that goes to the sanitary sewer. Never pour paint down a storm drain.
- ☐ For oil-based paints, paint out brushes to the extent possible and clean with thinner or solvent in a proper container. Filter and reuse thinners and solvents. Dispose of excess liquids as hazardous waste.
- ☐ Sweep up or collect paint chips and dust from non-hazardous dry stripping and sand blasting into plastic drop cloths and dispose of as trash.
- ☐ Chemical paint stripping residue and chips and dust from marine paints or paints containing lead, mercury, or tributyltin must be disposed of as hazardous waste. Lead based paint removal requires a state certified contractor.



STORM DRAIN POLLUTERS MAY BE LIABLE FOR FINES OF UP TO \$10,000 PER DAY!

250 Hamilton Avenue
Palo Alto, CA 94301
650.329.2211
cityofpaloalto.org



verizon

2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

Vinculums

575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500

ALL STATES
ENGINEERING & SURVEYING
A ZALZALI & ASSOCIATES COMPANY

23675 BIRTCHER DRIVE
LAKE FOREST, CA 92630
PHONE: (949) 273-0996

PROJECT ID:	P-334882
DRAWN BY:	RF
CHECKED BY:	DW

2	08/31/2020	100% CD'S FOR SUBMITTAL	MG
1	06/11/2020	100% CD'S FOR SUBMITTAL	RF
0	05/22/2020	100% CD'S FOR APPROVAL	RF
B	05/04/2020	95% CD'S FOR REDLINE	RF
A	04/29/2020	90% CD'S FOR REDLINE	RF
REV	DATE	DESCRIPTION	

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 061
LIC R.O.W. ADJACENT TO:
1221 MIDDLEFIELD RD.
PALO ALTO, 94301
LOCATION CODE: 425208

SHEET TITLE
PALO ALTO POLLUTION
PREVENTION CHECKLIST


SHEET NUMBER
L-2

EROSION AND SEDIMENT CONTROL NOTES:


TEMPORARY EROSION/SEDIMENT CONTROL, PRIOR TO COMPLETION OF FINAL IMPROVEMENTS, SHALL BE PERFORMED BY THE CONTRACTOR OR QUALIFIED PERSON AS INDICATED BELOW:

- ALL REQUIREMENTS OF THE CITY "LAND DEVELOPMENT MANUAL, STORM WATER STANDARDS" MUST BE INCORPORATED INTO THE DESIGN AND CONSTRUCTION OF THE PROPOSED PUBLIC IMPROVEMENTS CONSISTENT WITH THE EROSION CONTROL PLAN AND/OR WATER POLLUTION CONTROL PLAN (WPCP), IF APPLICABLE.
- FOR STORM DRAIN INLETS, PROVIDE A GRAVEL BAG SILT BASIN IMMEDIATELY UPSTREAM OF INLET AS INDICATED ON DETAILS.
- THE CONTRACTOR OR QUALIFIED PERSON SHALL BE RESPONSIBLE FOR CLEANUP OF SILT AND MUD ON ADJACENT STREET(S) AND STORM DRAIN SYSTEM DUE TO CONSTRUCTION ACTIVITY.
- THE CONTRACTOR SHALL REMOVE SILT AND DEBRIS AFTER EACH MAJOR RAINFALL.
- EQUIPMENT AND WORKERS FOR EMERGENCY WORK SHALL BE MADE AVAILABLE AT ALL TIMES DURING THE RAINY SEASON.
- THE CONTRACTOR SHALL RESTORE ALL EROSION/SEDIMENT CONTROL DEVICES TO WORKING ORDER TO THE SATISFACTION OF THE CITY ENGINEER OR RESIDENT ENGINEER AFTER EACH RUN-OFF PRODUCING RAINFALL.
- THE CONTRACTOR SHALL INSTALL ADDITIONAL EROSION/SEDIMENT CONTROL MEASURES AS MAY THE CONTRACTOR SHALL INSTALL ADDITIONAL EROSION/SEDIMENT CONTROL MEASURES AS MAY BE REQUIRED BY THE RESIDENT ENGINEER DUE TO UNFORESEEN CIRCUMSTANCES, WHICH MAY ARISE.
- EROSION/SEDIMENT CONTROL MEASURES PROVIDED PER THE APPROVED IMPROVEMENT PLAN SHALL BE INCORPORATED HEREON. ALL EROSION/SEDIMENT CONTROL FOR INTERIM CONDITIONS SHALL BE DONE TO THE SATISFACTION OF THE RESIDENT ENGINEER.
- ALL REMOVABLE PROTECTIVE DEVICES SHOWN SHALL BE IN PLACE AT THE END OF EACH WORKING DAY WHEN RAIN IS IMMINENT.
- THE CONTRACTOR SHALL ARRANGE FOR WEEKLY MEETINGS DURING OCTOBER 1ST TO APRIL 30TH FOR PROJECT TEAM (GENERAL CONTRACTOR, QUALIFIED PERSON, EROSION CONTROL SUBCONTRACTOR IF ANY, ENGINEER OF WORK, OWNER/DEVELOPER AND THE RESIDENT ENGINEER) TO EVALUATE THE ADEQUACY OF THE EROSION/SEDIMENT CONTROL MEASURES AND OTHER RELATED CONSTRUCTION ACTIVITIES.

STORM DRAIN INLET PROTECTION



TYPICAL PROTECTION FOR INLET WITH OPPOSING FLOW DIRECTIONS



TYPICAL PROTECTION FOR INLET WITH SINGLE FLOW DIRECTION

NOTES:

- INTENDED FOR SHORT-TERM USE.
- USE TO INHIBIT NON-STORM WATER FLOW.
- ALLOW FOR PROPER MAINTENANCE AND CLEANUP.
- BAGS MUST BE REMOVED AFTER ADJACENT OPERATION IS COMPLETED.
- NOT APPLICABLE IN AREAS WITH HIGH SILTS AND CLAYS WITHOUT FILTER FABRIC.

NOTES:

- CONTRACTOR TO POTHOLE ALL UTILITY CROSSINGS.
- CONTRACTOR TO PLACE SANDBAGS AROUND ANY/ALL STORM DRAIN INLETS TO PREVENT CONTAMINATED WATER.
- SPOILS PILE WILL BE COVERED AND CONTAINED AND STREET WILL BE SWEEPED AND CLEANED AS NEEDED.
- CONTRACTOR TO REPAIR DAMAGED PUBLIC IMPROVEMENTS TO THE CONTRACTOR TO REPAIR DAMAGED PUBLIC IMPROVEMENTS TO THE SATISFACTION OF THE CITY ENGINEER.
- SIDEWALK TO BE REPLACED CURB & GUTTER TO BE PROTECTED IN PLACE. SIDEWALK TO BE REPLACED TO THE SATISFACTION OF THE CITY ENGINEER.
- THE CONTRACTOR SHALL RESTORE THE ROADWAY BACK TO ITS ORIGINAL CONDITION SATISFACTORY TO THE CITY ENGINEER INCLUDING, BUT NOT LIMITED TO PAVING, STRIPING, BIKE LANES, PAVEMENT LEGENDS, SIGNS, AND TRAFFIC LOOP DETECTORS.
- SIDEWALK SHALL BE RESTORED/REPLACED PER CITY STANDARD DRAWINGS.
- PEDESTRIAN RAMP WILL NOT BE DISTURBED. PEDESTRIAN RAMP WILL NOT BE DISTURBED.

GENERAL CONTRACTOR NOTES:

- STREET USE PERMIT SHALL BE OBTAINED BY CONTRACTOR PRIOR TO COMMENCING WORK.
- ALL WORK TO BE CONDUCTED IN THE RIGHT OF WAY.
- ALL DISTURBED LANDSCAPING SHALL BE REPLACED TO SIMILAR EXISTING CONDITION.
- ANY SIDEWALK CLOSURE SHALL BE COORDINATED WITH THE CITY AND PROPER SIGNING WILL BE PLACED.
- NO MATERIALS OR EQUIPMENT SHALL BE STORED ON PRIVATE PROPERTY OR BLOCK ACCESS TO PRIVATE PROPERTY.
- CLEANUP OF SITE WILL BE COMPLETED EACH EVENING AND THE SITE WILL BE RETURNED TO EXISTING CONDITIONS AT THE COMPLETION OF CONSTRUCTION AT EACH SITE.
- CONTRACTOR SHALL VERIFY ALL PLANS AND EXISTING DIMENSIONS AND CONDITIONS ON THE JOB SITE AND SHALL IMMEDIATELY NOTIFY THE ENGINEER IN WRITING OF ANY DISCREPANCIES BEFORE PROCEEDING WITH THE WORK OR RESPONSIBLE FOR SAME.

R.O.W. GROUND CONSTRUCTION NOTES:

- GROUND CONSTRUCTION TO REMOVE/CLEAN ALL DEBRIS, NAILS, STAPLES, GROUND CONSTRUCTION TO REMOVE/CLEAN ALL DEBRIS, NAILS, STAPLES, OR NON-USED VERTICALS OFF THE POLE.
- ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH MUNICIPAL, COUNTY, STATE, FEDERAL, G095 AND G0128 STANDARDS AND REGULATIONS.
- CALL USA 48 HOURS PRIOR TO EXCAVATING AT (800) 227-2600 OR 811.
- ALL LANDSCAPING TO BE RESTORED TO ORIGINAL CONDITION OR BETTER.
- ALL EQUIPMENT TO BE BONDED. ALL EQUIPMENT TO BE BONDED.
- METERING CABINET REQUIRES 36" CLEARANCE AT DOOR OPENING.
- CAULK CABINET BASE AT PAD.

CALIFORNIA STATE CODE COMPLIANCE:

ALL WORK AND MATERIALS SHALL BE PREFORMED AND INSTALLED IN ACCORDANCE WITH THE CURRENT EDITIONS OF THE FOLLOWING CODES AS ADOPTED BY THE LOCAL GOVERNING AUTHORITIES. NOTHING IN THESE PLANS IS TO BE CONSTRUCTED TO PERMIT WORK NOT CONFORMING TO THESE CODES:

- CALIFORNIA ADMINISTRATIVE CODE (INCLUDING TITLES 24 & 25) 2016
- 2016 CALIFORNIA BUILDING CODES WHICH ADOPTS THE 2015 IBC, 2015 IMC, 2015 IPC AND THE 2014 NEC, AND SHALL INCLUDE 2016 CBC, CFC, CMC, CEC, CPC, CGBSC.
- BUILDING OFFICIALS & CODE ADMINISTRATORS (BOCA) CURRENT NATIONAL CODES
- ANSI/EIA-222-G (2009 - 2ND EDITION)
- NFPA-101 - LIFE SAFETY CODE / CAL-05HA - TITLE 8 / FCR - TITLE 29
- LOCAL BUILDING CODE
- CITY/COUNTY ORDINANCES
- ACCESSIBILITY REQUIREMENTS:
- FCC RF/EMF EXPOSURE/EMITTANCE COMPLIANCE:


**FCC NOTE: THIS WIRELESS COMMUNICATION FACILITY COMPLIES WITH FEDERAL STANDARDS FOR RADIO FREQUENCY IN ACCORDANCE WITH THE TELECOMMUNICATION ACT OF 1996 AND SUBSEQUENT AMENDMENTS AND ANY OTHER REQUIREMENTS IMPOSED BY STATE OR FEDERAL REGULATORY AGENCIES.

CITY OF PALO ALTO UTILITIES ENGINEERING NOTES:

- APPLICANT SHALL TAP ELECTRIC SERVICE TO THE SMALL CELL DISTRIBUTED ANTENNA SYSTEM FROM THE LOCATIONS JOINTLY IDENTIFIED DURING THE FIELD INVESTIGATION.
- SERVICE VOLTAGE TO ALL THE PROPOSED LOCATIONS MAY NOT BE THE SAME. APPLICANT SHALL DESIGN THEIR SYSTEM TO OPERATE AT THE AVAILABLE VOLTAGE IN THE VICINITY.
- IF BRAND NEW POLES NEED TO BE INSTALLED FOR APPLICANT'S SYSTEM THEN THE POLES MUST MATCH EXISTING POLES IN THE DOWN TOWN AREA.
- AFTER EXCAVATION IS COMPLETED ON THE PUBLIC RIGHT OF WAY, EXISTING STREETS INCLUDING SIDEWALKS/ CURB/ GUTTER OR ANY DECORATIVE PATHS MUST BE BROUGHT TO ITS ORIGINAL CONDITION AND MUST BE APPROVED BY PUBLIC WORKS ENGINEERING DEPARTMENT'S INSPECTOR. POTHOLING MUST BE DONE AND ALL THE UTILITIES MUST BE IDENTIFIED PRIOR TO COMMENCING EXCAVATION.
- EXCAVATION AND RESTORATION WORK MUST BE IN COMPLIANCE WITH PUBLIC WORKS ENGINEERING STANDARDS AND SPECIFICATIONS THAT ARE AVAILABLE ON THE FOLLOWING WEBSITE: <http://www.cityofpaloalto.org/news/displaynews.asp?NewsID=1834&TargetID=145>
- APPLICANTS SHALL BE RESPONSIBLE FOR MAINTAINING THEIR SYSTEM INCLUDING SUBSTRUCTURE. IN CASE OF KNOCK DOWNS, THE CITY WILL RE-INSTALL ITS STREET LIGHTING POLES BUT NOT APPLICANT'S EQUIPMENT ON OR OFF THE POLE.
- A FIELD MEETING IS RECOMMENDED WITH UTILITIES ENGINEERING PRIOR TO COMMENCING THE WORK.
- PLANS SHALL INCLUDE A NOTE: CONTRACTOR TREE INSPECTION REQUIREMENTS: MODIFIED TYPE III TRUNK WRAPPING SHALL BE VERIFIED BY URBAN FORESTRY PRIOR TO ANY WORK IN THE VICINITY. FOR EACH TREE SITE WRAPPED FOR PROTECTION WITHIN 15' OF ANY WORK ZONE OR CONCRETE FORM SECTION, A BILLABLE TREE INSPECTION BY URBAN FORESTRY (650-496-5953, 24-HOUR ADVANCE IS REQUIRED) SHALL BE COMPLETED PRIOR TO DEMOLITION, DRILLING, EXCAVATING, FORMING OR STREET LIGHT ACTIVITY. CONTRACTOR SHALL ARRANGE PAYMENTS AT THE DEVELOPMENT CENTER, 285 HAMILTON AVE, PALO ALTO, CA.
- THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE UTILITIES DEPARTMENT 650/329-2413 OR 650/496-6982 IF THE EXISTING WATER, WASTEWATER OR GAS MAINS ARE DISTURBED OR DAMAGED. A QUALIFIED CONTRACTOR MAY PERFORM REPAIRS ON CITY WATER AND WASTEWATER MAINS UNDER THE DIRECT SUPERVISION OF THE WGW UTILITIES INSPECTOR. FOR WATER REPAIRS ALL THE DISINFECTION REQUIREMENTS OF THE WGW UTILITY STANDARDS AND THESE CONDITIONS SHALL BE ADHERED TO. ALL REPAIRS TO THE CITY GAS SYSTEM MUST BE PERFORMED BY THE CITY OF PALO ALTO UTILITIES.
- NO WATER VALVES OR OTHER FACILITIES OWNED BY UTILITIES DEPARTMENT SHALL BE OPERATED FOR ANY PURPOSE BY THE APPLICANT'S CONTRACTOR. ALL REQUIRED OPERATION WILL ONLY BE PERFORMED BY AUTHORIZED UTILITIES DEPARTMENT PERSONNEL. WATER VALVES MAY BE OPERATED BY THE CONTRACTOR UNDER THE DIRECT SUPERVISION OF THE WGW UTILITIES INSPECTOR. THE APPLICANT'S CONTRACTOR SHALL NOTIFY THE UTILITIES DEPARTMENT NOT LESS THAN FORTY- EIGHT (48) HOURS IN ADVANCE OF THE TIME THAT SUCH OPERATION IS REQUIRED.

NORMAL LOCATION OF UNDERGROUND UTILITIES NOTES:

- LOCATION AND DEPTH OF EXISTING AND PROPOSED UTILITIES MUST BE PROVIDED BY THE SUBDIVIDER AND SHOWN ON ANY PLANS SUBMITTED TO THE DEPT. OF PUBLIC WORKS FOR APPROVAL.
- CHANGES MAY BE PERMITTED BY THE DEPT. OF PUBLIC WORKS IN CASES OF CONFLICTING FACILITIES.
- CONFLICTS BETWEEN UTILITY COMPANIES FACILITIES, EXISTING AND PROPOSED, MUST BE MUTUALLY RESOLVED BY THE UTILITY COMPANIES.
- FOR COMMERCIAL SIDEWALKS, THE FIRE HYDRANT SHALL BE PLACED WITHIN THE SIDEWALK 1'-6" BEHIND FACE OF CURB.
- MAXIMUM 2" DIAMETER GAS MAINS MAY BE PLACED IN JOINT UTILITIES TRENCH SUBJECT TO APPROVAL OF CITY ENGINEER (IN TRACTS).



Rev	By	Date	Conduit Location Detail Telecommunications	Approved by:
0	DWH	7/16/98		72158
1	MMN	7/20/04		01/10/18
Scale: NTS			City of Palo Alto Standard	Dwg No. 402

verizon

2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

Vinculums

575 LENNON LANE #125
LAKE FOREST, CA 92630
OFFICE: (925) 482-8500

ALL STATES
ENGINEERING & SURVEYING
A ZALZALI & ASSOCIATES COMPANY

23675 BIRTCHER DRIVE
LAKE FOREST, CA 92630
PHONE: (949) 273-0996

PROJECT ID:	P-334882
DRAWN BY:	RF
CHECKED BY:	DW

2	08/31/2020	100% CD'S FOR SUBMITTAL	MG	
1	06/11/2020	100% CD'S FOR SUBMITTAL	RF	
0	05/22/2020	100% CD'S FOR APPROVAL	RF	
B	05/04/2020	95% CD'S FOR REDLINE	RF	
A	04/29/2020	90% CD'S FOR REDLINE	RF	
REV	DATE	DESCRIPTION		



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 061
LIC R.O.W. ADJACENT TO:
1221 MIDDLEFIELD RD.
PALO ALTO, 94301
LOCATION CODE: 425208

SHEET TITLE
PALO ALTO EROSION
CONTROL AND CONDUIT
LOCATION DETAILS & NOTES

SHEET NUMBER

L-3



SITE ID:

PROJECT NAME:

POLE#:

LOCATION CODE:

ADJACENT APN:

SITE ADDRESS:

COUNTY:

SITE TYPE:

ROADWAY TYPE:

HISTORIC STATUS OR DISTRICT:

SF PALO ALTO 203

VZW PALO ALTO SMALL CELL

53

566802

120-03-058

519 WEBSTER STREET

PALO ALTO, 94301

SANTA CLARA

STREET LIGHT POLE

LOCAL

N/A

verizon

2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

Vinculums

575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500

ALLSTATES
ENGINEERING & SURVEYING
23675 BIRTCHE DRIVE
LAKE FOREST, CA 92630

PROJECT ID: TBD

DRAWN BY: RF

CHECKED BY: DW

REV	DATE	DESCRIPTION	
2	09/10/2020	100% CD'S FOR SUBMITTAL	MG
1	06/11/2020	100% CD'S FOR SUBMITTAL	RF
0	05/22/2020	100% CD'S FOR APPROVAL	RF
B	05/04/2020	95% CD'S FOR REDLINE	RF
A	04/14/2020	90% CD'S FOR REDLINE	RF



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 203
PUBLIC R.O.W. ADJACENT TO:
519 WEBSTER STREET
PALO ALTO, 94301
LOCATION CODE: 566802

SHEET TITLE

TITLE SHEET

SHEET NUMBER

T-1

PROJECT DESCRIPTION

VERIZON WIRELESS PROPOSES TO INSTALL A NEW WIRELESS COMMUNICATION SITE ON A NEW/REPLACEMENT STREET LIGHT POLE. THE SCOPE WILL CONSIST OF THE FOLLOWING:

- REMOVE (1) EXISTING STREET LIGHT/POLE #53 IN WEBSTER ST. PUBLIC R.O.W.
- INSTALL (1) NEW 'DOWNTOWN' ROADWAY LIGHTING POLE W/ LED LAMP IN
- PLACE OF REMOVED LIGHT POLE #53, PER LIGHTING STYLE PLACEMENT GUIDE
- RE-CONNECT CPA STREET LIGHT POWER TO NEW/REPLACEMENT STREET LIGHT
- INSTALL (3) NEW ERICSSON 5M-6701 RADIO/ANTENNAS ATOP NEW POLE
- INSTALL (1) NEW NEMA 6P AC DISCONNECT WITHIN NEW U.G. POWER HANDHOLE
- INSTALL (1) NEW 5/8"Ø x10'L. GROUND ROD WITHIN U.G. POWER HANDHOLE
- INSTALL NEW AC POWER CABLES FROM POC, TO DISCONNECT, TO RADIOS
- INSTALL NEW GROUND CABLES FROM DISCONNECT/RADIOS/POLE TO GROUND ROD
- INSTALL NEW FIBER CABLES FROM DEMARC TO RADIOS
- INSTALL NEW RF NOTICE AND EMERGENCY SHUT-DOWN SIGNAGE AS REQUIRED
- INSTALL NEW U.G. PATH FROM POWER POC TO NEW U.G. POWER HANDHOLE

ADMINISTRATIVE REQUIREMENTS


SUBCONTRACTOR SHALL VERIFY ALL PLANS, EXISTING DIMENSIONS & FIELD CONDITIONS ON THE JOB SITE & SHALL IMMEDIATELY NOTIFY THE ENGINEER IN WRITING OF ANY DISCREPANCIES BEFORE PROCEEDING WITH THE WORK OR BE RESPONSIBLE FOR SAME.

VICINITY MAP



SYMBOLS/ABBREVIATIONS LEGEND

ADD'L A.F.G. ANT. ASS'Y. AWG. BLDG. BTCW. CLR. CONC. CONN. CONST. CONT. DBL. D.F. DIA. DIM. EA. ELEV EMT. (E) F.G. FT.(') GA. HT. IN.(') LB.(#) L.F.	ADDITIONAL ABOVE FINISHED GRADE ANTENNA ASSEMBLY AMERICAN WIRE GAUGE BUILDING BARE TINNED COPPER WIRE CLEAR CONCRETE CONNECTION(OR) CONSTRUCTION CONTINUOUS DOUBLE DOUGLAS FIR DIAMETER DIMENSION EACH ELEVATION ELECTRICAL METALLIC TUBING EXISTING FINISH GRADE FOOT (FEET) GAUGE HEIGHT INCH(ES) POUND(S) LINEAR FEET (FOOT)	L. MAX. MFR. MIN. (N) NTS O.C. P.T. RAD.(R) REQ'D RGS. SCH. SIM. SQ. S.S. STD. TEMP. THK. TYP. U.G. U.L. U.N.O. V.I.F. W w/ WD. W.P.	LONG(ITUDINAL) MAXIMUM MANUFACTURER MINIMUM NEW NOT TO SCALE ON CENTER PRESSURE TREATED RADIUS REQUIRED RIGID GALVANIZED STEEL SCHEDULE SIMILAR SQUARE STAINLESS STEEL STANDARD TEMPORARY THICK(NESS) TYPICAL UNDER GROUND UNDERWRITERS LABORATORY UNLESS NOTED OTHERWISE VERIFY IN FIELD WIDE (WIDTH) WITH WOOD WEATHERPROOF
--	---	--	---



CONCRETE (SURFACE)	X	CHAIN LINK FENCE
CONCRETE (CUT)	□	WOOD FENCE
EARTH	○	WROUGHT IRON FENCE
GRAVEL	OH	OVERHEAD WIRES
PLYWOOD	E	POWER CONDUIT
STEEL	— · — · — · —	GROUND CONDUCTOR
EXISTING GRASS	— — — — —	PROPERTY LINE
ELEVATION DATUM	±0'	CENTERLINE

PROJECT TEAM

APPLICANT:
VERIZON WIRELESS
575 LENNON LANE SUITE 125
WALNUT CREEK, CA 94598
CONTACT: JEREMY STROUP
PHONE: (925) 202-8654
EMAIL: jstroup@vinculums.com

LEASING CONTACT:
VINCULUMS SERVICES
575 LENNON LANE SUITE 125
WALNUT CREEK, CA 94598
CONTACT: JEREMY STROUP
PHONE: (925) 202-8654
EMAIL: jstroup@vinculums.com

A&E PROJECT MANAGER:
ZALZALI & ASSOCIATES INC.
dba ALL STATES ENGINEERING
& SURVEYING
23675 BIRTCHE DRIVE
LAKE FOREST, CA 92630
PM: DEAN WALKER
PHONE: (714) 230-5714
EMAIL: dean@zalzali.com

CONSTRUCTION MANAGER:
VINCULUMS SERVICES
575 LENNON LANE SUITE 125
WALNUT CREEK, CA 94598
CONTACT: CURTIS GARDNER
PHONE: (510) 552-2944
EMAIL: cgardner@vinculums.com

ARBORIST CONTACT:
PROJECT ARBORIST
121 N 27TH STREET,
SAN JOSE, CA 95116
CONTACT: KATHERINE NAEGELE
PHONE: (408) 590-5976
EMAIL: katherine@andersonstreecare.com

SITE INFORMATION

LATITUDE:
N 37° 26' 57.54" (37.449317)

LONGITUDE:
W 122° 9' 27.29" (-122.157582)

ELEVATION:
+39' AMSL

ZONING:
RM-40

JURISDICTION:
CITY OF PALO ALTO

ASSESSORS PARCEL NUMBER:
ADJACENT TO 120-03-058

PROPERTY LEGAL DESCRIPTION:
N/A PUBLIC RIGHT OF WAY

ADA COMPLIANCE:
N/A

DIG ALERT



DO NOT SCALE DRAWINGS

CONTRACTOR SHALL VERIFY ALL PLANS & (E) DIMENSIONS & CONDITIONS ON THE JOB SITE & SHALL IMMEDIATELY NOTIFY THE ENGINEER IN WRITING OF ANY DISCREPANCIES BEFORE PROCEEDING WITH THE WORK OR BE RESPONSIBLE FOR SAME IF USING 11"x17" PLOT, DRAWINGS WILL BE HALF SCALE.

CODE COMPLIANCE

ALL WORK AND MATERIALS SHALL BE PERFORMED AND INSTALLED IN ACCORDANCE WITH THE CURRENT EDITIONS OF THE FOLLOWING CODES AS ADOPTED BY THE LOCAL GOVERNING AUTHORITIES. NOTHING IN THESE PLANS IS TO BE CONSTRUCTED TO PERMIT WORK NOT CONFORMING TO THESE CODES.

2019 TITLE 24, CALIFORNIA CODE OF REGULATIONS

2019 CALIFORNIA BUILDING CODE

2019 CALIFORNIA ELECTRICAL CODE

2019 CALIFORNIA MECHANICAL CODE

2019 GREEN BUILDING CODE

2019 CALIFORNIA ENERGY CODE

*AS AMENDED BY CITY OF PALO ALTO AND MADE EFFECTIVE JANUARY 1ST, 2020 AS PER CURRENT CITY OF PALO ALTO MUNICIPAL CODE ORDINANCES GENERAL ORDER 95 (v.2018)



Vinculums **CA SJ Palo Alto 203** Looking East from Webster Street
519 Webster Street
Palo Alto, CA **View #1**
9/3/20 Approved Imagination S10 914-0500



Vinculums **CA SJ Palo Alto 203** Looking Northwest from Webster Street
519 Webster Street
Palo Alto, CA **View #2**
9/3/20 Approved Imagination S10 914-0500

verizon

2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

Vinculums

575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500

ALLSTATES
ENGINEERING & SURVEYING
23675 BIRCHER DRIVE
LAKE FOREST, CA 92630

PROJECT ID: TBD
DRAWN BY: RF
CHECKED BY: DW

REV	DATE	DESCRIPTION	
2	09/10/2020	100% CD'S FOR SUBMITTAL	MG
1	06/11/2020	100% CD'S FOR SUBMITTAL	RF
0	05/22/2020	100% CD'S FOR APPROVAL	RF
B	05/04/2020	95% CD'S FOR REDLINE	RF
A	04/14/2020	90% CD'S FOR REDLINE	RF




















IT IS A VIOLATION OF LAW FOR ANY PERSON,
UNLESS THEY ARE ACTING UNDER THE
DIRECTION OF A LICENSED PROFESSIONAL
ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 203
PUBLIC R.O.W. ADJACENT TO:
519 WEBSTER STREET
PALO ALTO, 94301
LOCATION CODE: 566802

SHEET TITLE
PHOTOSIMS

SHEET NUMBER
T-2



	U.G. UTILITY VAULT	BLDG	TOP OF BUILDING
	MANHOLE	MON	MONUMENT
	UTILITY POLE	FL	FLOW LINE
	SPOT ELEVATION	EOP	EDGE OF PAVEMENT
	WATER VALVE	R.O.W.	RIGHT OF WAY
	FOUND MONUMENT	R/W	RIGHT OF WAY
	GEODETIC MARKER	SCO	SEWER CLEAN-OUT
	CHAIN LINK FENCE	PS	PARKING STRIPE
	WOOD FENCE	SW	SIDEWALK
	OVERHEAD LINE	VLТ	U.G. UTILITY VAULT
	METAL FENCE	OHE	OVERHEAD ELECTRICAL
	GRADE BREAK	SVC	SERVICE
	RIGHT OF WAY LINE	AC	ASPHALTIC CONCRETE
	CENTER LINE	AP	ASPHALT PAVING
	EASEMENT LINE	CONC	CONCRETE
	MASONRY WALL	PED	PEDESTAL
	WATER VALVE	OH	OVERHEAD
UP	UTILITY POLE	PUE	PUBLIC UTILITY EASEMENT
LP	LIGHT POLE	FC	FACE OF CURB
LUM	LUMINAIRE	BOL	BOLLARD
NG	NATURAL GRADE	TOP _	TOP OF ITEM
		BOT _	BOTTOM OF ITEM



- 905 – PM – 47
- 283 – PM – 4
- 718 – RS – 25
- 120 – APN MAP – 3

O	08/27/2020	FINAL SURVEY	MA
A	08/27/2020	PRELIMINARY SURVEY	MG
REV	DATE	DESCRIPTION	



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS
THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED
PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 203
R.O.W. ADJACENT TO:
519 WEBSTER ST
PALO ALTO, CA 94301
NEW BUILD—SMALL CELL

SITE SURVEY

LS-1

TREE NOTES:


1. THERE WILL BE NO TREE PRUNING WITHOUT THE SPECIFIC APPROVAL OF THE PALO ALTO URBAN FORESTRY DEPARTMENT ON ALL REGULATED TREES. ANY VIOLATION TO THIS POLICY WILL BE SUBJECT TO PENALTY. CONTACT THE PALO ALTO URBAN FORESTRY DEPARTMENT AT (650) 496-5953.
2. THIS CONSTRUCTION PROJECT TRIGGERS MANDATORY TREE PROTECTION MEASURES. SEE TREE PROTECTION PLAN & CONTACT THE PALO ALTO URBAN FORESTRY DEPARTMENT. AT (650) 496-5953 WITH ANY QUESTIONS.
3. EXCAVATION ACTIVITIES ASSOCIATED WITH THE PROPOSED SCOPE OF WORK SHALL OCCUR NO CLOSER THAN 10-FEET FROM THE EXISTING STREET TREE, OR AS APPROVED BY THE URBAN FORESTRY DIVISION CONTACT 650-496-5953. ANY CHANGES SHALL BE APPROVED BY THE SAME.
4. PROJECT ARBORIST:
KATHERINE NAEGELE
KATHERINE@ANDERSONTREECARE.COM
PHONE: (408) 590-5976
5. NO FEASIBLE GREEN SCREEN OPPORTUNITIES EXIST

NOTES:

1. METAL SURFACES REQUIRING PAINT SHALL BE PAINTED MUNSELL GREEN.
2. ANY CONSTRUCTION WITHIN THE CITY'S PUBLIC ROAD RIGHT-OF-WAY SHALL HAVE AN APPROVED PERMIT FOR CONSTRUCTION IN THE PUBLIC STREET PRIOR TO COMMENCEMENT OF THIS WORK

NOTE:

ALL ITEMS AND DIMENSIONS SHOULD BE VERIFIED IN THE FIELD, PRIOR TO STARTING CONSTRUCTION.



SITE PLAN

24"x36" SCALE: 3/32" = 1'-0"
11"x17" SCALE: 3/64" = 1'-0"
8' 4' 0" 8'

verizon

2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

Vinculums

575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500

ALLSTATES
ENGINEERING & SURVEYING
23675 BIRTCHE DRIVE
LAKE FOREST, CA 92630

PROJECT ID:	TBD
DRAWN BY:	RF
CHECKED BY:	DW

2	09/10/2020	100% CD'S FOR SUBMITTAL	MG	
1	06/11/2020	100% CD'S FOR SUBMITTAL	RF	
0	05/22/2020	100% CD'S FOR APPROVAL	RF	
B	05/04/2020	95% CD'S FOR REDLINE	RF	
A	04/14/2020	90% CD'S FOR REDLINE	RF	
REV	DATE	DESCRIPTION		




IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 203
PUBLIC R.O.W. ADJACENT TO:
519 WEBSTER STREET
PALO ALTO, 94301
LOCATION CODE: 566802

SHEET TITLE
SITE PLAN

SHEET NUMBER
A-1



EXISTING UTILITY SITE PLAN

24"x36" SCALE: 3/32" = 1'-0"
11"x17" SCALE: 3/64" = 1'-0"

verizon

2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

Vinculums

575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500

ALLSTATES

ENGINEERING & SURVEYING
23675 BIRTCHE DRIVE
LAKE FOREST, CA 92630

PROJECT ID:	TBD
DRAWN BY:	RF
CHECKED BY:	DW

REV	DATE	DESCRIPTION	
2	09/10/2020	100% CD'S FOR SUBMITTAL	MG
1	06/11/2020	100% CD'S FOR SUBMITTAL	RF
0	05/22/2020	100% CD'S FOR APPROVAL	RF
B	05/04/2020	95% CD'S FOR REDLINE	RF
A	04/14/2020	90% CD'S FOR REDLINE	RF

REGISTERED PROFESSIONAL ENGINEER
WISSAM ZALZALI
71655
CIVIL
STATE OF CALIFORNIA

Wissam Zalzal

IT IS A VIOLATION OF LAW FOR ANY PERSON,
UNLESS THEY ARE ACTING UNDER THE
DIRECTION OF A LICENSED PROFESSIONAL
ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 203
PUBLIC R.O.W. ADJACENT TO:
519 WEBSTER STREET
PALO ALTO, 94301
LOCATION CODE: 566802

SHEET TITLE
EXISTING UTILITY SITE PLAN

SHEET NUMBER
A-1.1



2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500



ALL STATES
ENGINEERING & SURVEYING
23675 BIRTCHE DRIVE
LAKE FOREST, CA 92630

PROJECT ID:	TBD
DRAWN BY:	RF
CHECKED BY:	DW

2	09/10/2020	100% CD'S FOR SUBMITTAL	MG
I	06/11/2020	100% CD'S FOR SUBMITTAL	RF
O	05/22/2020	100% CD'S FOR APPROVAL	RF
B	05/04/2020	95% CD'S FOR REDLINE	RF
A	04/14/2020	90% CD'S FOR REDLINE	RF
REV	DATE	DESCRIPTION	




IT IS A VIOLATION OF LAW FOR ANY PERSON,
UNLESS THEY ARE ACTING UNDER THE
DIRECTION OF A LICENSED PROFESSIONAL
ENGINEER, TO ALTER THIS DOCUMENT.


SF PALO ALTO 203
PUBLIC R.O.W. ADJACENT TO:
519 WEBSTER STREET
PALO ALTO, 94301
LOCATION CODE: 566802

SHEET TITLE
UTILITY PLAN
(FOR REFERENCE)

SHEET NUMBER

A-1.2





LOCATION MAP

24"x36" SCALE: 1" = 80'-0"
11"x17" SCALE: 1" = 160'-0"
80' 40' 0' 80'

verizon

2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

Vinculums

575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500

ALLSTATES

ENGINEERING & SURVEYING
23675 BIRCHER DRIVE
LAKE FOREST, CA 92630

PROJECT ID:	TBD
DRAWN BY:	RF
CHECKED BY:	DW

2	09/10/2020	100% CD'S FOR SUBMITTAL	MG
1	06/11/2020	100% CD'S FOR SUBMITTAL	RF
0	05/22/2020	100% CD'S FOR APPROVAL	RF
B	05/04/2020	95% CD'S FOR REDLINE	RF
A	04/14/2020	90% CD'S FOR REDLINE	RF
REV	DATE	DESCRIPTION	

REGISTERED PROFESSIONAL ENGINEER
WISSAM ZALZALI
71655
CIVIL
STATE OF CALIFORNIA

IT IS A VIOLATION OF LAW FOR ANY PERSON,
UNLESS THEY ARE ACTING UNDER THE
DIRECTION OF A LICENSED PROFESSIONAL
ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 203

PUBLIC R.O.W. ADJACENT TO:
519 WEBSTER STREET
PALO ALTO, 94301
LOCATION CODE: 566802

SHEET TITLE

LOCATION MAP

SHEET NUMBER


A-1.3

1. ALL WORK SHALL COMPLY WITH THE CITY OF PALO ALTO 2018 STANDARD DRAWINGS AND SPECIFICATIONS BORING, TRENCHING, POTHOLING AND DEWATERING, SECTION 17.
2. THE LOCATION OF EXISTING UTILITY MAINS AND LATERAL LINES INCLUDING STORM DRAIN, SANITARY SEWER, WATER, GAS, UNDERGROUND ELECTRICAL AND COMMUNICATION CONDUITS CROSSING THE TRENCH EXCAVATION SHALL BE VERIFIED BY THE CONTRACTOR. THE CONTRACTOR SHALL BE RESPONSIBLE FOR NOTIFYING UNDERGROUND SERVICES ALERT (USA) AT 811 OR 800-642-2444 AT LEAST FIVE (5) WORKING DAYS PRIOR TO BEGINNING UNDERGROUND WORK SO THAT EXISTING UTILITIES CAN BE MARKED IN THE FIELD, UNLESS OTHERWISE STATED BY CITY CONTRACT.
3. EXCAVATION SHALL BE SUPPORTED AND EXCAVATION OPERATIONS CONDUCTED IN ACCORDANCE WITH THE RULES OF THE CALIFORNIA OCCUPATIONAL SAFETY & HEALTH ADMINISTRATION (OSHA). IF IN THE OPINION OF THE ENGINEER, THERE EXISTS A SITUATION OF IMMINENT DANGER TO THE WORKERS, THE ENGINEER MAY ORDER THE WORK STOPPED AND THE CONTRACTOR SHALL COMPLY WITH RULES OF THE CALIFORNIA OCCUPATIONAL SAFETY & HEALTH ADMINISTRATION (OSHA).
4. BACKFILL SHALL BE SAND OR GRANULAR MATERIAL FALLING WITHIN THE LIMITS DESCRIBED IN THE STANDARD DRAWING 401. AGGREGATE BASE, ASPHALT CONCRETE, PORTLAND CEMENT CONCRETE SHALL CONFORM TO THE REQUIREMENTS WITHIN THESE SPECIFICATIONS.
5. THE CONTRACTOR SHALL INSTALL THE CONDUIT IN ACCORDANCE WITH THE APPROVED STREET WORK PERMIT. ALL CONDUITS SHALL BE INSTALLED UNDERGROUND USING DIRECTIONAL BORING METHOD. MICRO-TUNNELING OR OTHER METHODS SHALL BE APPROVED BY THE PUBLIC WORKS ENGINEERING DIVISION. THE CONDUITS SHALL BE INSTALLED WITH TRACER WIRE APPROVED BY THE ENGINEER PER CITY OF PALO ALTO UTILITIES DEPARTMENT WATER, GAS AND WASTEWATER UTILITY STANDARDS. REFER TO STANDARD DRAWING 402.
6. TRENCHES SHALL NOT BE LEFT OPEN AT THE END OF THE DAY. ADEQUATE PROVISIONS SHALL BE MADE FOR THE PLACING OF TEMPORARY STEEL PLATES IN ADDITION TO BARRICADES, SIGNING AND LIGHTING. STOCKPILING OF EXCAVATED MATERIAL WITHIN THE PUBLIC RIGHT-OF-WAY SHALL NOT BE ALLOWED. A MAXIMUM OF THREE-HUNDRED (300) FEET OR ONE (1) CITY BLOCK OF TRENCH, WHICHEVER IS GREATER, MAY BE OPENED AT ONE TIME. FOR TEMPORARY PATCHING, A MINIMUM THICKNESS OF TWO (2) INCHES OF CUTBACK WILL BE USED.
7. PRIOR TO EXCAVATION OF TRENCHING, POTHOLING OR SENDING/RECEIVING PITS, THE ASPHALT CONCRETE OR PORTLAND CEMENT CONCRETE SHALL BE CUT OR MILL TO A NEAT LINE FULL DEPTH WITH A SAW-CUTTING OR MILLING DEVICE APPROVED BY THE ENGINEER.
8. BACKFILL MATERIAL SHALL BE COMPACTED TO 90 PERCENT MINIMUM RELATIVE COMPACTION EXCEPT THE TOP TWENTY-FOUR (24) INCHES, WHICH SHALL BE MECHANICALLY COMPACTED TO 95 PERCENT MINIMUM RELATIVE COMPACTION. MECHANICALLY COMPACTED LIFTS USING ALTERNATIVE EQUIPMENT, COMPLYING WITH MANUFACTURE'S SPECIFICATION, WILL REQUIRE THE APPROVAL OF THE ENGINEER. USE OF ALTERNATIVE COMPACTION EQUIPMENT SHALL NOT RELIEVE THE CONTRACTOR FROM RESPONSIBILITY FOR ANY DAMAGE TO THE CONDUIT, SURROUNDING GROUND, OR EXISTING AND NEW IMPROVEMENTS.


2 NOTES

Sawcutting & Asphalt/Concrete Removal

- Protect storm drain inlets during saw cutting.
- If saw cut slurry enters a catch basin, clean it up immediately.
- Shovel or vacuum saw cut slurry deposits and remove from the site. When making saw cuts, use as little water as possible. Sweep up, and properly dispose of all residues.



VICINITY MAP



NOTES:

- EXCAVATION RESTRICTIONS APPLY (ITM, SEC. 2.20 C & D). ANY APPROVED GRADING, DIGGING OR TRENCHING BENEATH A TREE CANOPY SHALL BE PERFORMED USING 'AIR-SPADE' METHOD AS A PREFERENCE, WITH MANUAL HAND SHOVEL AS A BACKUP. FOR UTILITY TRENCHING, INCLUDING SEWER LINE, ROOTS EXPOSED WITH DIAMETER OF 1.5 INCHES AND GREATER SHALL REMAIN INTACT AND NOT BE DAMAGED.
- SEE ATTACHED TREE PROTECTION PLAN FOR INSTRUCTIONS ON TREE PROTECTION.

NOTE:

ALL PROPOSED POWER RUNS TO MAINTAIN A MIN. 2' CLR. ALL AROUND AS REQUIRED BY CPAU

1 LIGHT POLE
1 inch = 2ft.

2' 1' 0' 2'

LEGEND

U.G. UTILITY VAULT	BOL BOLLARD	FL FLOW LINE	W WATER
MANHOLE	TOP TOP OF ITEM	EOP EDGE OF PAVEMENT	SS SANITARY SEWER
UTILITY POLE	BOT BOTTOM OF ITEM	R.O.W. RIGHT OF WAY	SD STORM DRAIN
SPOT ELEVATION	BLDG TOP OF BUILDING	AP ASPHALT	G GAS
WATER VALVE	LP LIGHT POLE	SW SIDEWALK	C COMMUNICATION
FOUND MONUMENT	--- LIMITS OF PROPERTY	O/H OVERHEAD LINE	E ELECTRIC
GEODETIC MARKER	- x - CHAIN LINK FENCE	METAL FENCE	U UNKNOWN UTILITY
MASONRY WALL	WOOD FENCE	GRADE BREAK	IRR IRRIGATION

811 USA North
Know what's below.
Call before you dig.
California and Nevada
Call Two Working Days Before You Dig!
811 / 800-227-2600



verizon

2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

Vinculum

575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500

ALLSTATES
ENGINEERING & SURVEYING
23675 BIRTCHE DRIVE
LAKE FOREST, CA 92630

PROJECT ID:	TBD
DRAWN BY:	RF
CHECKED BY:	DW

REV	DATE	DESCRIPTION	
1	08/31/2020	RELOCATED LIGHT POLE	SS
O	08/17/2020	FINAL BORING PLAN	SS
A	08/14/2020	PRELIMINARY BORING PLAN	SS




IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 203
PUBLIC R.O.W. ADJACENT TO:
519 WEBSTER STREET
PALO ALTO, 94301
LOCATION CODE: 566802


SHEET TITLE
BORING SITE PLAN

SHEET NUMBER


A-1.4




7 CITY STANDARD DWG 401
N.T.S.




6 CITY STANDARD DWG 403
N.T.S.




5 CITY STANDARD DWG 402
N.T.S.




4 CHRISTY N16 ELECTRICAL BOX
N.T.S.



3 BORE PIT & RECEIVER PIT
N.T.S.



2 DIRECTION BORE METHOD
CROSS SECTION - PRIVATE
N.T.S.



1 IN DIRT - PRIVATE
N.T.S.

verizon

2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

Vinculums

575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500

ALLSTATES
ENGINEERING & SURVEYING
23675 BIRTCHE DRIVE
LAKE FOREST, CA 92630

PROJECT ID: TBD
DRAWN BY: RF
CHECKED BY: DW

REV	DATE	DESCRIPTION	
1	08/31/2020	RELOCATED LIGHT POLE	SS
0	08/17/2020	FINAL BORING PLAN	SS
A	08/14/2020	PRELIMINARY BORING PLAN	SS

REGISTERED PROFESSIONAL ENGINEER
WISSAM ZALALI
71655
CIVIL
STATE OF CALIFORNIA

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS
THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED
PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 203
PUBLIC R.O.W. ADJACENT TO:
519 WEBSTER STREET
PALO ALTO, 94301
LOCATION CODE: 566802

SHEET TITLE
CITY STANDARDS
& DETAILS

SHEET NUMBER

A-1.5

- ▶ Grade fills over 6-inches or impervious overlay shall incorporate an approved permanent aeration system, permeable material or other approved mitigation.
- ▶ Grade cuts exceeding 4-inches shall incorporate retaining walls or an appropriate transition equivalent.

C. Trenching, Excavation and Equipment Use

Trenching, excavation or boring activity within the TPZ is restricted to the following activities, conditions and requirements if approved by the City Arborist. (See Restriction Zones for Excavation, Trenching or Boring Near Regulated Trees, Image 2.20-1 through 2.20-3). Mitigating measures shall include prior notification to and direct supervision by the project arborist.

1. Notification. Contractor shall notify the project arborist a minimum of 24 hours in advance of the activity in the TPZ.
2. Root Severance. Roots that are encountered shall be cut to sound wood and repaired (see Root Injury, Section 2.25 A-1). Roots 2-inches and greater must remain injury free.
3. Excavation. Any approved excavation, demolition or extraction of material shall be performed with equipment sitting outside the TPZ. Methods permitted are by hand digging, hydraulic or pneumatic air excavation technology. Avoid excavation within the TPZ during hot, dry weather.
 - ▶ If excavation or trenching for drainage, utilities, irrigation lines, etc., it is the duty of the contractor to tunnel under any roots 2-inches in diameter and greater.
 - ▶ Prior to excavation for foundation/footings/walls, grading or trenching within the TPZ, roots shall first be severed cleanly 1-foot outside the TPZ and to the depth of the future excavation. The trench must then be hand dug and roots pruned with a saw, sawzall, narrow trencher with sharp blades or other approved root pruning equipment.
4. Heavy Equipment. Use of backhoes, steel tread tractors or any heavy vehicles within the TPZ is prohibited unless approved by the City Arborist. If allowed, a protective root buffer (see Root Buffer and Damage to Trees, Section 2.25.A-1) is required. The protective buffer shall consist of a base course of tree chips spread over the root area to a minimum of 6-inch depth, layered by 3/4-inch quarry gravel to stabilize 3/4-inch plywood on top. This buffer within the TPZ shall be maintained throughout the entire construction process.
 - ▶ Structural design. If injurious activity or interference with roots greater than 2-inches will occur within the TPZ, plans shall specify a design of special foundation, footing, walls, concrete slab or pavement designs subject to City Arborist approval. Discontinuous foundations such as concrete pier and structural grade beam must maintain natural grade (not to exceed a 4-inch cut), to minimize root loss and allow the tree to use the existing soil.

notes:

Required Practices

- ▶ Basement excavations shall be designed outside the TPZ of all protected and designated trees (see Excavation, Section 2.20-3) and shall not be harmful to other mature or neighboring property trees.

D. Tunneling & Directional Drilling

If trenching or pipe installation has been approved within the TPZ, then the trench shall be either cut by hand, air-spade, hydraulic vac-on excavation or, by mechanically boring the tunnel under the roots with a horizontal directional drill and hydraulic or pneumatic air excavation technology. In all cases, install the utility pipe immediately, backfill with soil and soak within the same day. Installation of private utility improvements shall be tunnel bored beneath the tree and roots per Trenching Tunneling & Distance Matrix in Table 2-1.

notes:

Required Practices

TABLE 2-1
Trenching & Tunneling Distance

TRENCHING DISTANCE	
When the Tree Diameter At 4.5 Ft Is:	
6-9" Measured At 6"	6-9'
10-14" Measured At 54"	10-14'
15-19" Measured At 54"	15-19'
Over 19" Measured At 54"	20' +
Trenching will be Replaced with Boring at this Minimum Distance (10x tree dia.) from the Face of the Tree in any Direction:	
DEPTH OF TUNNELING	
Tree Diameter	Depth of Tunneling
9" Or Less Measured At 6"	2.5'
10-14" Measured At 54"	3.0'
15-19" Measured At 54"	3.5'
More Than 19" Measured At 54"	4.0'

Bore Pits Shall Be Located At A Minimum Distance As Specified By The Trenching Distance Table Above.

1. Public Utilities
Underground public utility improvements or repairs shall be performed in accordance with the Utility Standards for Excavation, Trenching or Boring, Section 02200.309; and per Restriction Zones Near Regulated Trees (see Images 2.20-1 through 2.20-3).
2. Street Trees
Exclusions for street trees in the publicly owned right-of-way (ROW).
 - ▶ Street Trees that are in conflict with utility infrastructure where the conflict cannot be resolved may be removed if approved by Public Works Operations (e.g., a tree planted directly on top of a damaged sewer lateral.)

verizon

2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

Vinculums

575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500

ALLSTATES
ENGINEERING & SURVEYING
23675 BIRTCHE DRIVE
LAKE FOREST, CA 92630

PROJECT ID:	TBD
DRAWN BY:	RF
CHECKED BY:	DW

1	08/31/2020	RELOCATED LIGHT POLE	SS
0	08/17/2020	FINAL BORING PLAN	SS
A	08/14/2020	PRELIMINARY BORING PLAN	SS
REV	DATE	DESCRIPTION	




IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 203
PUBLIC R.O.W. ADJACENT TO:
519 WEBSTER STREET
PALO ALTO, 94301
LOCATION CODE: 566802

SHEET TITLE
CITY STANDARDS
& DETAILS


SHEET NUMBER
A-1.6

- NOTES:
- 1. METAL SURFACES REQUIRING PAINT TO BE PAINTED MUNSELL GREEN.
 - 2. THE CONTRACTOR MAY BE REQUIRED TO SUBMIT A LOGISTICS PLAN TO THE PUBLIC WORKS DEPARTMENT PRIOR TO COMMENCING WORK THAT ADDRESSES ALL IMPACTS TO THE CITY'S RIGHT-OF-WAY, INCLUDING, BUT NOT LIMITED TO: PEDESTRIAN CONTROL, TRAFFIC CONTROL, TRUCK ROUTES, MATERIAL DELIVERIES, CONTRACTORS PARKING, CONCRETE POURS, CRANE LIFTS, WORK HOURS, NOISE CONTROL, DUST CONTROL, STORM WATER POLLUTION PREVENTION, CONTRACTORS CONTACT, NOTICING OF AFFECTED SURROUNDING PROPERTIES, AND SCHEDULE OF WORK. THE REQUIREMENT TO SUBMIT A LOGISTICS PLAN WILL BE DEPENDENT ON THE NUMBER OF APPLICATIONS PUBLIC WORKS ENGINEERING RECEIVES WITHIN CLOSE PROXIMITY TO HELP MITIGATE AND CONTROL THE IMPACT TO THE PUBLIC-RIGHT-OF-WAY. IF NECESSARY, PUBLIC WORKS MAY REQUIRE A LOGISTICS PLAN DURING CONSTRUCTION.
 - 3. TREES MAY NOT BE PLANTED WITHIN 10 FEET OF EXISTING WATER, GAS OR WASTEWATER MAINS/SERVICES OR METERS; LESSER DISTANCES REQUIRE A PERMANENT IMPERMEABLE ROOT-BARRIER A MINIMUM OF 3' HORIZONTAL FROM WATER, GAS AND WASTEWATER SERVICES/MAINS/METERS.




ENLARGED SITE PLAN

24"x36" SCALE: 3/4" = 1'-0"
11"x17" SCALE: 3/8" = 1'-0"




2

ENLARGED SITE PLAN



24"x36" SCALE: 1/2" = 1'-0"
11"x17" SCALE: 1/4" = 1'-0"



1

verizon
2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

Vinculums
575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500

ALLSTATES
ENGINEERING & SURVEYING
23675 BIRTCHER DRIVE
LAKE FOREST, CA 92630

PROJECT ID:	TBD
DRAWN BY:	RF
CHECKED BY:	DW

REV	DATE	DESCRIPTION	
2	09/10/2020	100% CD'S FOR SUBMITTAL	MG
1	06/11/2020	100% CD'S FOR SUBMITTAL	RF
0	05/22/2020	100% CD'S FOR APPROVAL	RF
B	05/04/2020	95% CD'S FOR REDLINE	RF
A	04/14/2020	90% CD'S FOR REDLINE	RF


REGISTERED PROFESSIONAL ENGINEER
WISSAM ZALZALI
71655
CIVIL
STATE OF CALIFORNIA

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 203
PUBLIC R.O.W. ADJACENT TO:
519 WEBSTER STREET
PALO ALTO, 94301
LOCATION CODE: 566802

SHEET TITLE
ENLARGED SITE PLAN

SHEET NUMBER
A-2



EXISTING SOUTHEAST ELEVATION

24"x36" SCALE: 1/2" = 1'-0"
11"x17" SCALE: 1/4" = 1'-0"



2

- NOTES:
1. NEW LIGHT POLE TO BE PAINTED WITH MUNSELL GREEN PAINT.
 2. NEW RADIOS AND HARDWARE TO BE PAINTED WITH MUNSELL GREEN PAINT.

- TOP OF PROPOSED LIGHT POLE: ±25'-0" A.G.L.
- TOP OF PROPOSED VERIZON RADIO/ANTENNAS: ±25'-0" A.G.L.
- CENTERLINE OF PROPOSED VERIZON ANTENNA: ±23'-8" A.G.L.
- PROPOSED CABLE ACCESS HOLES (PER POLE SPECS): ±22'-8" A.G.L.

- LUMINAIRE ARM CONNECTION: ±19'-4" A.G.L.

- BOTTOM OF PHILIPS RNS20 LAMP (43 lbs): ±17'-10" A.G.L.

- ARM CONNECTION: ±16'-8" A.G.L.

- ARM CONNECTION: ±10'-9" A.G.L.


- CENTERLINE OF PROPOSED VERIZON SIGNAGE: ±8'-10" A.G.L.

- FINISHED GRADE: ±0'-0" A.G.L.

PROPOSED SOUTHEAST ELEVATION

TOTAL ANETNNA/RADIO VOLUME (CU. FT.)

MODEL	TOTAL	TOTAL VOLUME (CU. FT.)
SM6701	3	±1,4



24"x36" SCALE: 1/2" = 1'-0"
11"x17" SCALE: 1/4" = 1'-0"



1

verizon

2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

Vinculums

575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500

ALLSTATES
ENGINEERING & SURVEYING
23675 BIRCHER DRIVE
LAKE FOREST, CA 92630

PROJECT ID:	TBD
DRAWN BY:	RF
CHECKED BY:	DW

REV	DATE	DESCRIPTION	
2	09/10/2020	100% CD'S FOR SUBMITTAL	MG
1	06/11/2020	100% CD'S FOR SUBMITTAL	RF
0	05/22/2020	100% CD'S FOR APPROVAL	RF
B	05/04/2020	95% CD'S FOR REDLINE	RF
A	04/14/2020	90% CD'S FOR REDLINE	RF




IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 203
PUBLIC R.O.W. ADJACENT TO:
519 WEBSTER STREET
PALO ALTO, 94301
LOCATION CODE: 566802


SHEET TITLE
ELEVATIONS

SHEET NUMBER
A-3




EXISTING SOUTHWEST ELEVATION

24"x36" SCALE: 1/2" = 1'-0"
11"x17" SCALE: 1/4" = 1'-0"




2




- NOTES:
- NEW LIGHT POLE TO BE PAINTED WITH MUNSELL GREEN PAINT.
 - NEW RADIOS AND HARDWARE TO BE PAINTED WITH MUNSELL GREEN PAINT.

TOTAL ANETNNA/RADIO VOLUME (CU. FT.)		
MODEL	TOTAL	TOTAL VOLUME (CU. FT.)
SM6701	3	±1.4

PROPOSED SOUTHWEST ELEVATION



24"x36" SCALE: 1/2" = 1'-0"
11"x17" SCALE: 1/4" = 1'-0"



1

verizon

2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

Vinculums

575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500

ALLSTATES

ENGINEERING & SURVEYING
23675 BIRCHER DRIVE
LAKE FOREST, CA 92630

PROJECT ID:	TBD
DRAWN BY:	RF
CHECKED BY:	DW

REV	DATE	DESCRIPTION	
2	09/10/2020	100% CD'S FOR SUBMITTAL	MG
1	06/11/2020	100% CD'S FOR SUBMITTAL	RF
0	05/22/2020	100% CD'S FOR APPROVAL	RF
B	05/04/2020	95% CD'S FOR REDLINE	RF
A	04/14/2020	90% CD'S FOR REDLINE	RF

REGISTERED PROFESSIONAL ENGINEER
MUSAM ZALZALI
71655
CIVIL
STATE OF CALIFORNIA

Musam Zalzal

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 203
PUBLIC R.O.W. ADJACENT TO:
519 WEBSTER STREET
PALO ALTO, 94301
LOCATION CODE: 566802


SHEET TITLE
ELEVATIONS

SHEET NUMBER
A-3.1

ERICSSON 6701 POLE ATTACHMENT SHROUD
PART NO. 30311
(OR APPROVED EQUAL)

NOTES:


1. FULL SHROUD PAINTABLE TO MATCH COLOR OF EXISTING STRUCTURE.
2. COLOR-MATCHED 3M FILM TO BE APPLIED TO ANTENNA EMITTER FACE.
3. SHROUD DRY WEIGHT = 18 LBS.
4. TOTAL WEIGHT INCLUDING ANTENNA = 49LBS.



DETAIL A (SECTOR 1 RADIO HIDDEN FOR CLARITY)

BRACKET ID & OD
DEPENDENT ON POLE
DIMENSIONS

RADIO MOUNT RING BRACKET
ADJUSTMENT SLOTS (360°
AZIMUTH ADJUSTMENT)




DETAIL B

2x RADIO MOUNT
RING BRACKET

TAPERED & FLUTED
POLE RADIO SHROUD
MOUNTING CHANNEL

POLE VENDOR TO
PROVIDE POLE MAX &
MIN OD AT EACH OF
THESE MOUNTING
HEIGHTS




SECTION C-C

OLDCASTLE N36 UTILITY BOX
(OR APPROVED EQUAL)

- ETCHED POLYPROPYLENE FACE
- FACE ANCHORED IN CONCRETE
- ULTRA-VIOLET INHIBITOR

- EXCEEDS ASTM-D1693 STANDARDS FOR ENVIRONMENTAL STRESS CRACKING RESISTANCE



A HIGH DENSITY REINFORCED CONCRETE BOX WITH NON-SETTING SHOULDERS POSITIONED TO MAINTAIN GRADE AND FACILITATE BACK FILLING. APPROXIMATE DIMENSIONS AND WEIGHT SHOWN.

OLDCASTLE ORDERING CODE	ITEM	APPROX SHIPPING WEIGHT	DESCRIPTION
N36BOX	BOX	172 lbs.	N36 UTILITY BOX (17-1/8"x30-1/4") - 8 PER PALLET
N36R	LID	76 lbs.	R-SERIES COMPOSITE LID WITH POLYPROPYLENE RING (ORDER N90 BOLT DOWN KIT SEPARATELY)
N36D	LID	35 lbs.	FIBRELYTE LID, NON-CONCRETE
N36E	LID	96 lbs.	REINFORCED CONCRETE WITH 7"x13-1/2" CONCRETE READING LID
N36G	LID	78 lbs.	REINFORCED CONCRETE WITH 5"x8" CAST IRON, SELF-CLOSING, READING LID WITH FRAME
N36RP	LID	76 lbs.	R-SERIES COMPOSITE LID W/ POLYPROPYLENE RING W/ 2"Ø PROBE HOLE FOR METER READING PROBE (ORDER N90 BOLT DOWN KIT SEPARATELY)
N36-6ID	COVER	56 lbs.	STEEL CHECKER PLATE
N36-6IG	COVER	60 lbs.	STEEL CHECKER PLATE WITH 8" ROUND, SELF-CLOSING READING LID
N36X12	EXTENSION	189 lbs.	12" REINFORCED CONCRETE - 8 PER PALLET
B36SL	SLAB	104 lbs.	REINFORCED CONCRETE (20"x34")

GALVANIZING AVAILABLE ON ALL STEEL COVERS

N36 UTILITY BOX DETAIL


24"x36" SCALE: NTS
11"x17" SCALE: NTS

6




AC POWER DISCONNECT WIRE DIAGRAM

5



NOTE:
NEW PHENOLIC SIGN TO BE
ATTACHED TO DISCONNECT




SHUTDOWN SIGN ON DISCONNECT

24"x36" SCALE: NTS
11"x17" SCALE: NTS

4

Raycap RSCAC-1333-PH-240 AC POWER DISCONNECT
(OR APPROVED EQUAL)

- DIMENSIONS: 10.43"L x 8.59"W x 5.06"D
- WEIGHT: ±8 lbs (3.62 Kg)



RSCAC-1333-PH-240

NEMA 6P AC POWER DISCONNECT

24"x36" SCALE: NTS
11"x17" SCALE: NTS

3

CONTRACTOR NOTE:

- SITE ID WILL BE SWITCH #, SITE # AND SITE NAME.
- NODE NUMBER WILL BE MARKET#-NODE.B#-SMALL CELL NAME.



NOTE:

INSTALL EME NOTICE SIGN 3'
BELOW STREET MACRO UNITS.

GO95 RF SIGNAGE

24"x36" SCALE: NTS
11"x17" SCALE: NTS

2

STREET MACRO 6701

ERICSSON

- DIMENSION W/ PROTRUDING ITEMS INCL GPS ANT: 21.2"H x 8.1"W x 5.1"D
- TOTAL RADIO AREA (CU. IN.): 875.77 CU. IN.
- WEIGHT: ±31 lbs

RADIO AREA (CU. FT.)			
RADIO MODEL	TOTAL RADIO(S)	TOTAL RADIO AREA (CU. IN.)	TOTAL RADIO AREA (CU. FT.)
MACRO 6701	1	875.77 CU. IN.	0.50 CU. FT.

NEW GPS ATTACHED ON TOP OF
SM 6701 (PRE INSTALLED BY
MANUFACTURER) (1) TOTAL (MAX.
MEASUREMENTS WILL NOT EXCEED)



STREET MACRO 6701

24"x36" SCALE: NTS
11"x17" SCALE: NTS

1

SM6701 SHROUD & MOUNTING DETAILS

24"x36" SCALE: NTS
11"x17" SCALE: NTS

7

verizon

2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

Vinculums

575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500

ALLSTATES
ENGINEERING & SURVEYING
23675 BIRTCHE DRIVE
LAKE FOREST, CA 92630

PROJECT ID: TBD

DRAWN BY: RF

CHECKED BY: DW

REV	DATE	DESCRIPTION	
2	09/10/2020	100% CD'S FOR SUBMITTAL	MG
1	06/11/2020	100% CD'S FOR SUBMITTAL	RF
0	05/22/2020	100% CD'S FOR APPROVAL	RF
B	05/04/2020	95% CD'S FOR REDLINE	RF
A	04/14/2020	90% CD'S FOR REDLINE	RF



IT IS A VIOLATION OF LAW FOR ANY PERSON,
UNLESS THEY ARE ACTING UNDER THE
DIRECTION OF A LICENSED PROFESSIONAL
ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 203
PUBLIC R.O.W. ADJACENT TO:
519 WEBSTER STREET
PALO ALTO, 94301
LOCATION CODE: 566802

SHEET TITLE

DETAILS

SHEET NUMBER

D-1

POLE SPECS



RNS20 (Reference=L23638-3)



RNS20 (Reference=L23638-3)



3. **Notes:** These guidelines do not apply to people with needs for the LCD in large ranges shown. Requirements of bulk always be confirmed with a structuralist layout.
Note: Due to rapid change in technology with new LCD technology, LCD is a trademark subject to change without notice and without liability of Philips.

1

verizon

2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

Vinculums

575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500

ALLSTATES
ENGINEERING & SURVEYING
23675 BIRCHER DRIVE
LAKE FOREST, CA 92630

PROJECT ID: TBD
DRAWN BY: RF
CHECKED BY: DW

REV	DATE	DESCRIPTION	
2	09/10/2020	100% CD'S FOR SUBMITTAL	MG
1	06/11/2020	100% CD'S FOR SUBMITTAL	RF
0	05/22/2020	100% CD'S FOR APPROVAL	RF
B	05/04/2020	95% CD'S FOR REDLINE	RF
A	04/14/2020	90% CD'S FOR REDLINE	RF


REGISTERED PROFESSIONAL ENGINEER
WESAM ZALZALI
71655
CIVIL
STATE OF CALIFORNIA

IT IS A VIOLATION OF LAW FOR ANY PERSON,
UNLESS THEY ARE ACTING UNDER THE
DIRECTION OF A LICENSED PROFESSIONAL
ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 203
PUBLIC R.O.W. ADJACENT TO:
519 WEBSTER STREET
PALO ALTO, 94301
LOCATION CODE: 566802

SHEET TITLE
TRAFFIC CONTROL PLAN

SHEET NUMBER
TCP-1



- LEGEND:**
- CHANNELIZING DEVICE
 - TRAFFIC CONE W/CLIP ON SIGN
 - SIGN
 - WORK ZONE
 - DIRECTION OF TRAFFIC
 - TYPE 1 BARRICADE
 - TYPE 1 BARRICADE W/SIGN
 - TYPE 3 BARRICADE
 - TYPE 3 BARRICADE W/SIGN
 - AUTOMATED FLAGGER ASSISTANCE DEVICE (AFAD)
 - CERTIFIED FLAGGER
 - TEMPORARY ADA RAMP
 - TEMPORARY RAISED PAVEMENT MARKERS
 - MESSAGE BOARD (PCMS)
 - FLASHING ARROWBOARD
 - TEMP NO PARKING SIGNS
 - FLASHING BEACON/BARRICADE LIGHT
 - K-RAIL/WATER FILLED BARRIER
 - PEDESTRIAN BARRICADE

ADDITIONAL NOTES:
1. ASSIST RESIDENTS WITH IN/OUT ACCESS TO DRIVEWAYS ALONG THE CLOSURE WHEN SAFE TO DO SO.

- NOTES**
- Traffic control shall conform with the most current CAMUTCD part 6 and/or Caltrans Standards
 - One lane of traffic in each direction and all high volume turning lanes shall be maintained at all times on all streets at a minimum lane width of 10 feet.
 - Contractor shall notify local authorities once signs are posted.
 - All advanced warning signs shall be equipped with 2 (16" orange flags)
 - Certified Traffic Control Workers shall have Type II vests, work shoes, and hard hats.

- Temporary no parking signs shall be placed a min of 72 hrs prior of work.
- Driveways shall be monitored and maintained at all times during work hours.
- Distance between sign and work area will be determined on speed limit.
- Roadway shall not be opened until safe for public use. All open trenches must be plated or backfilled prior to public usage.
- All Devices shall be removed when no longer required.

ROAD TYPE	DISTANCE BETWEEN SIGNS		
	A	B	C
Urban (Low Speeds) - 25 mph or less	100 ft	150 ft	100 ft
Urban (Low Speeds) - 25 to 40 mph	250 ft	250 ft	250 ft
Urban (High Speeds) - 40 mph	350 ft	350 ft	350 ft
Rural	500 ft	500 ft	500 ft
Expressway / Freeway	1,000 ft	1,500 ft	2,000 ft



SCALE:
NOT TO SCALE

DATE REVISION:
4-13-20

DATE COMPLETED:
7-27-20

REV 1

PROJECT LOCATION:
519 WEBSTER AVE
PALO ALTO

JOB#:
SF PALO ALTO 203

TAB#:
1/1

REQUEST BY:
YVONNE WASHINGTON
VINCULUMS SERVICES
925-999-5523
YWASHINGTON@VINCULUMS.COM

B.A.T.S. AFTER HOURS EMERGENCY 510-299-5666

Drawn By:
Andie Tonn
CSLB# 917034
Office: 510-657-2543
Fax: 510-657-2544
44800 Industrial Drive Fremont, CA 94538
WWW.BATSTRAFFICSOLUTIONS.COM





VERIZON
PALO ALTO_203

All States Engineering & Surveying
Project No: 84 - CLUSTER-6PALO ALTO_203

Structural Analysis Report
ROW Adjacent to 519 Webster St. Palo Alto, 94301
Proposed 25'-0" AGL 'Downtown' Style Aluminum Light Pole & Foundation



Rev. #	Reason for Revision	Total # of Sheets	Prepared By	Checked By	Approved /Accepted	Date
2	Updated CDs	19	LeT	LeT	WZ	9/25/2020

	Quantity/Type /Shape	Strength (min.)	Dimensions	Thickness /Depth	Capacity Utilization
Pole Shaft	Aluminum / 8-sided tapered	25 ksi*	5.73"Ø at top 10.0"Ø at bottom	0.219"	37.3% PASS
Anchor Bolts	4	36 ksi	1" Ø	-	39.0% PASS
Base Plate	1	36 ksi	13.6" Cast Base	-	ADEQUATE
Foundation	Circular Caisson	3.25 ksi	36" Dia.	7'-0" **	ADEQUATE

* Pole grade is 6061-T6 per provided specs.
** Required depth of caisson (Unrestrained at G/L) - This analysis was performed without a soil report, and minimum soil properties from B3C-18 were used. Required pole foundation embedment depth may change with a soil report from the proposed pole location.

Professional Engineering Firm
ARCHITECTURAL, CIVIL, STRUCTURAL, ELECTRICAL, GEOTECHNICAL, SURVEYING
www.allstatesengineering.com

ATC Hazards by Location

Search Information
Address: 519 Webster St., Palo Alto, 94301
Coordinates: 37.44943000000001, -122.167396
Elevation: 47 ft
Timestamp: 2020-08-02T21:02:23.626Z
Feature Type: Seismic



ASCE 7-16	ASCE 7-10	ASCE 7-05
Min 10-Year: 63 mph	Min 10-Year: 72 mph	ASCE 7-05 Wind Speed: 85 mph
Min 25-Year: 70 mph	Min 25-Year: 79 mph	
Min 50-Year: 74 mph	Min 50-Year: 86 mph	
Min 100-Year: 78 mph	Min 100-Year: 91 mph	
Risk Category I: 86 mph	Risk Category I: 100 mph	
Risk Category II: 91 mph	Risk Category II: 110 mph	
Risk Category III: 96 mph	Risk Category III-V: 115 mph	
Risk Category IV: 102 mph		

The results indicated here DO NOT reflect any state or local amendments to the values or any definition lines made during the building code adoption process. Users should confirm any output obtained from this tool with the local Authority Having Jurisdiction before proceeding with design.

Disclaimer

Forward looks are interpreted from data provided in ASCE 7 and rounded up to the nearest whole integer. The ASCE 7, tables and coastal areas outside the tool contour should use the last wind speed contour of the coastal area - in some cases, this website will extrapolate past the last wind speed contour and therefore, provide a wind speed that is slightly higher. NOTE: For queries near wind-borne debris region boundaries, the resulting determination is sensitive to rounding which may affect whether or not it is considered to be within a wind-borne debris region.

Mountainous terrain, gorges, ocean promontories, and special wind regions shall be examined for unusual wind conditions.

While the information presented on this website is believed to be correct, ATC and its sponsors and contributors assume no responsibility or liability for its accuracy. The material presented in this report should not be used or relied upon for any specific application without competent examination and verification of its accuracy, suitability and applicability by engineers or other licensed professionals. ATC does not intend that the use of this information replace the sound judgment of such competent professionals, having experience and knowledge in the field of practice, nor to substitute for the standard of care required of such professionals in interpreting and applying the results of the report provided by this website. Users of the information from this website assume all liability arising from such use. Use of the output of this website does not imply approval by the governing building code bodies responsible for building code approval and interpretation for the building site described by latitude/longitude location in the report.

Steel Decorated Pole
Palo Alto
PALO ALTO_203



Project Description:
All States Engineering & Surveying (ASES) is pleased to submit this "Structural Analysis Report" to determine the structural integrity of the metal pole.
The purpose of the analysis is to determine acceptability of the pole stress level. Based on our analysis we have determined the metal pole stress level for the structure and anchorage, under the following load case:
LC: Proposed Pole + Proposed Equipment
(Please see page 5 for details)

All modifications and equipment proposed in this report shall be installed in accordance with the attached drawings for the determined available structural capacity to be effective.

Structural Analysis Parameters:

This analysis has been performed in accordance with AASHTO 2013 guidelines.

- Wind Speed: 85 mph per AASHTO 2013
- Exposure Category: C
- Risk Category: II
- Topographical: I
- Crest Height: 0
- Ice Thickness: 0 in
- Min. Soil Lateral Bearing = 100 psf/ft * 2 = 200 psf/ft per CBC & IBC 1806.3.4
- Min. Soil Bearing = 1500 psf

We at All States Engineering & Surveying appreciate the opportunity of providing our continuing professional services to you. If you have any questions or need further assistance on this or any other projects, please give us a call.

ATC Hazards by Location

Search Information
Address: 519 Webster St., Palo Alto, 94301
Coordinates: 37.44943000000001, -122.167396
Elevation: 47 ft
Timestamp: 2020-08-02T21:02:23.626Z
Feature Type: Seismic
Reference Document: ASCE7-16
Risk Category: I
Site Class: D-Default



Basic Parameters

Name	Value	Description
S ₀	1.586	MCES ground motion (period=0.2s)
S ₁	0.606	MCES ground motion (period=1.0s)
S _{MS}	1.218	Site-modified spectral acceleration value
S _{M1}	1.218	Site-modified spectral acceleration value
S _S	1.277	Uniform seismic design value at 0.2s SA
S ₁	1.218	Uniform seismic design value at 1.0s SA

* See Section 11.4.6

***Additional Information**

Name	Value	Description
SDC	II	Seismic design category
F _s	1.2	Site amplification factor at 0.2s
F ₀	1.2	Site amplification factor at 1.0s
C _{PS}	0.823	Coefficient of risk (0.2s)
C _{PS}	0.906	Coefficient of risk (1.0s)
PGA	0.606	MCES peak ground acceleration
F _{PGA}	1.2	Site amplification factor at PGA
PGA _s	0.727	Site modified peak ground acceleration
T _L	12	Long-period transition period (s)
S _{MT}	1.972	Probabilistic risk-targeted ground motion (0.2s)
S _{MT}	2.137	Federal uniform-hazard spectral acceleration (2% probability of exceedance in 50 years)
S _{MT}	1.586	Federal deterministic acceleration value (0.2s)
S _{MT}	0.783	Probabilistic risk-targeted ground motion (1.0s)
S _{MT}	0.866	Federal uniform-hazard spectral acceleration (2% probability of exceedance in 50 years)
S _{MT}	0.606	Federal deterministic acceleration value (1.0s)
PGA _s	0.606	Federal deterministic acceleration value (PGA)

* See Section 11.4.6


The results indicated here DO NOT reflect any state or local amendments to the values or any definition lines made during the building code adoption process. Users should confirm any output obtained from this tool with the local Authority Having Jurisdiction before proceeding with design.

PROJECT: PALO ALTO_203
CLIENT: 102 - Sequoia VZW Bakersfield
DESIGN BY: LeT
REVIEW BY: WZ
DATE: 9/25/2020

Pole Wind & Seismic Analysis Based on AASHTO 2013 Proposed Elevation

NOTES:
1. NEW LIGHT POLE TO BE PAINTED WITH PUNNELL GREEN PAINT.
2. NEW RADON AND HARDWARE TO BE PAINTED WITH PUNNELL GREEN PAINT.

TOTAL ANENNA/RADIO VOLUME (CU. FT.)		
FEES	TOTAL	TOTAL VOLUME (CU. FT.)
DPN/TO	3	0.4



PROPOSED SOUTHEAST ELEVATION

PROJECT: PALO ALTO_203
CLIENT: 102 - Sequoia VZW Bakersfield
DESIGN BY: LeT
REVIEW BY: WZ
DATE: 9/25/2020

Pole Wind & Seismic Analysis Based on AASHTO 2013 Loading

PROPOSED COMPONENTS		QUANTITY	MOUNT TYPE
Rad Center	Component Type		
23'-0"	(N) Ericsson SM701 Antennas	3	Pole Mounted
13'-9"	Reserved 30" x 72" Banner	1	
9'-0"	(E) Street Sign	1	
-	(N) RF Signage	1	Inside Pole
-	(N) & (E) Conduit, Wire & In-line Fuse	-	

WIND PRESSURE DERIVATION (AASHTO 2013)

Height of Pole	h = 25.0 ft	(AASHTO 2013)
Wind Speed	V = 85 mph	(AASHTO 2013)
Wind Exposure (B, C or D)	C	
Wind Directionality (Pole)	K _d = 0.95	(AASHTO 2013, Table 3.8.5-1)
Gust Effect Factor	G = 1.14	(AASHTO 2013, Sec. 3.8.6)
3-sec Gust Exponent	α = 0.50	(ASCE 7-16, Table 26.11-1)
Atmospheric Height	Z _a = 600 ft	(ASCE 7-16, Table 26.11-1)
Vel. Pressure Coeff. (Min)	K _z = 0.84	(ASCE 7-16, Table 29.10-1)
Velocity Pressure Coeff.	K _z = 2.01Z _a ^{-0.28} = 0.94	(AASHTO 2013, Equation 3.8-4.1)
Wind Force @ Pole Top	F _u = 0.0025K _z G _f V ² (C _d) = 19.8 psf * C _d A	(Wind Pressure Input For O-Calc Analysis)

Total Applied Shear: V_u = 1075 lbs (From TNX Report)

Total Applied Moment: M_u = 14208 lb-ft (From TNX Report)

CALCULATION OF WIND DRAG COEFFICIENTS (C_d) FROM AASHTO 2013, TABLE 3.8.7-1

Appurtenance	Height (in)	Width (in)	Depth (in)	d (in)	C _d V _u	C _d
(N) Ericsson SM701 Antennas	32.2	10.2	7.3	1.05	-	1.70
(E) Round Luminaire	2.9	88.0	-	0.24	20	0.50
(E) Round Pole	300	7.85	-	0.65	60	0.69

SEISMIC LOAD ANALYSIS (ASCE 7-16)

Total Pole Weight	W = P _u = 621 lbs	(Approximate W _u Including Pole With (N) Components)
Spectral Response (Short)	G _s = 1.582	(ATC Hazards Design Maps Summary)
Spectral Response (1 sec)	S ₁ = 0.600	(ATC Hazards Design Maps Summary)
Importance Factor	I _s = 1.0	(ASCE 7-16, Section 15.4.1.1)
Response Factor	R = 1.5	(ASCE 7-16, Table 15.4.2)
Seismic Response Coeff	C _s = 0.044S ₁ I _s = 0.070	(ASCE 7-16, Section 15.4.2)
Seismic Response Coeff	C _s = 0.8S ₁ (R/I _s) = 0.320	(ASCE 7-16, Section 15.4.2)
Seismic Response Coeff	C _s = S ₁ (R/I _s) = 1.055	(ASCE 7-16, Section 15.4.2)
Lateral Seismic Force	V _u = MAX(C _s W) = 1.055 *W	(ASCE 7-16, Section 12.8-2)
Total Applied Shear	V _u = 655 lbs	
Total Applied Moment	M _u = V _u (2.0h) = 10915 lb-ft	

(Wind Loads Governing For Pole Shaft Capacity Check)



PROJECT ID:	TBD
DRAWN BY:	RF
CHECKED BY:	DW

REV	DATE	DESCRIPTION	
2	09/10/2020	100% CD'S FOR SUBMITTAL	MG
1	06/11/2020	100% CD'S FOR SUBMITTAL	RF
0	05/22/2020	100% CD'S FOR APPROVAL	RF
B	05/04/2020	95% CD'S FOR REDLINE	RF
A	04/14/2020	90% CD'S FOR REDLINE	RF



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.


SF PALO ALTO 203
PUBLIC R.O.W. ADJACENT TO:
519 WEBSTER STREET
PALO ALTO, 94301
LOCATION CODE: 566802

SHEET TITLE

CALCS

SHEET NUMBER

C-1



DESIGNED APPURTENANCE LOADING			
TYPE	ELEVATION	TYPE	ELEVATION
Decorative Top Cap	15	1" x 1" x 1" C.I. Light Fixture	15.5
Light Fixture	15.5	1" x 1" x 1" C.I. Light Fixture	15.5
Light Fixture	15.5	1" x 1" x 1" C.I. Light Fixture	15.5
Light Fixture	15.5	1" x 1" x 1" C.I. Light Fixture	15.5
Light Fixture	15.5	1" x 1" x 1" C.I. Light Fixture	15.5
Light Fixture	15.5	1" x 1" x 1" C.I. Light Fixture	15.5
Light Fixture	15.5	1" x 1" x 1" C.I. Light Fixture	15.5
Light Fixture	15.5	1" x 1" x 1" C.I. Light Fixture	15.5
Light Fixture	15.5	1" x 1" x 1" C.I. Light Fixture	15.5
Light Fixture	15.5	1" x 1" x 1" C.I. Light Fixture	15.5

TOWER DESIGN NOTES			
1.	Tower is located in Santa Clara County, California.		
2.	Tower designed for Exposure C to the AASHTO 2013 Standard.		
3.	Tower designed for a 85 mph basic wind in accordance with the AASHTO 2013 Standard.		
4.	Deflections are based upon a 30 mph wind.		
5.	Tower Structure Class II.		
6.	Topographic Category I with Crest Height of 0.00 ft.		
7.	TOWER RATING: 37.3%		

ALL REACTIONS
ARE FACTORED

AXIAL
927 lb

SHEAR
1076 lb

MOMENT
14208 ft-lb

TORQUE
546 ft-lb

REACTIONS - 10 mph WIND

All States Engineering & Surveying
25875 Birtcher Drive
Lake Forest, CA 92650
Phone: (949) 375-0604
FAX: (949) 829-7222

Palo Alto Light Pole
PALO ALTO_203
Sta. 0+00.00, 0+20.00
AASHTO 2013
08/25/20
N13
0+10.00

Steel Decorated Pole
Palo Alto
PALO ALTO_203

Maximum Member Forces							
Section No.	Elevation ft	Component Type	Condition	Dist. Local Const. ft	Dist. Member ft	Dist. Member Moment ft-lb	Dist. Member Moment ft-lb
L1	25 - 0	Pole	Max. Tension	1	0.00	0.00	0.00
			Max. Compression	4	-420.00	-5496.98	-6653.22
			Max. Mx	7	-464.69	-12332.54	-3768.29
			Max. My	2	-619.90	-4791.22	-13376.13
			Max. Vy	6	-1032.86	-12220.10	-3376.13
			Max. Vx	2	-1032.91	-4791.22	-3376.13
			Max. Torque	5			551.08

Maximum Reactions					
Location	Condition	Dist. Local Const. ft	Vertical lb	Horizontal, X lb	Horizontal, Z lb
Pole	Max. Vert	2	621.41	304.94	1032.11
	Max. Hx	2	621.41	304.94	1032.11
	Max. Hy	2	621.41	304.94	1032.11
	Max. Mx	2	13376.13	304.94	1032.11
	Max. My	7	12332.49	-1032.10	-304.93
	Max. Tension	5	545.44	-514.18	514.18
	Min. Vert	3	466.06	304.93	1032.09
	Min. Hx	7	466.06	-1032.10	-304.93
	Min. Hy	7	466.06	-1032.10	-304.93
	Min. Mx	7	-3768.45	-1032.10	-304.93
	Min. My	2	-4791.04	304.94	1032.11
	Min. Tension	1	0.00	-0.10	-0.10

Tower Mast Reaction Summary						
Load Combination	Vertical lb	Shear, X lb	Shear, Y lb	Overswringing Moment, Mx ft-lb	Overswringing Moment, My ft-lb	Torque ft-lb
Dead Only	517.84	0.10	0.10	-469.19	486.81	-0.05
1.2 Dead + 1.6 Wind 0 deg - No Ice	621.41	-304.94	-1032.11	-13376.13	4791.04	-384.48
0.9 Dead + 1.6 Wind 0 deg - No Ice	466.06	-304.93	-1032.09	-13193.80	4629.59	-385.36
1.2 Dead + 1.6 Wind 45 deg - No Ice	621.41	514.18	-514.18	-6653.11	-5497.11	-544.15
0.9 Dead + 1.6 Wind 45 deg - No Ice	466.06	514.18	-514.18	-6490.26	-5628.66	-545.44
1.2 Dead + 1.6 Wind 90 deg - No Ice	621.41	1032.09	304.93	3635.52	-12220.06	-384.76
0.9 Dead + 1.6 Wind 90 deg - No Ice	466.06	1032.10	304.93	3768.45	-12332.49	-385.68
Dead + Wind 0 deg - Service	517.85	-84.93	-287.51	-4032.12	1657.13	-107.48
Dead + Wind 45 deg - Service	517.85	143.25	-143.16	-2161.38	-1203.13	-151.95
Dead + Wind 90 deg - Service	517.85	287.49	84.97	697.93	-3071.89	-107.48

Steel Decorated Pole
Palo Alto
PALO ALTO_203

Tower Input Data

The tower is a monopole.
This tower is designed using the AASHTO 2013 standard.
The following design criteria apply:
Tower is located in Santa Clara County, California.
Basic wind speed of 85 mph.
Structure Class II.
Exposure Category C.
Topographic Category I.
Crest Height 0.00 ft.
Deflections calculated using a wind speed of 60 mph.

Tapered Pole Section Geometry

Section	Elevation ft	Section Length ft	Splice Length ft	Number of Sides	Top Diameter in	Bottom Diameter in	Wall Thickness in	Band Radius in	Pole Grade
L1	25.00-0.00	25.00		8	5.7300	10.0000	0.2190	0.8760	6063-T6 (23 ksi)

Tapered Pole Properties

Section	Tip Dia in	Area in ²	I in ⁴	r in	C in	J in ⁴	I/C in ³	J/C in ³	w in	w t in
L1	6.0217	4.0060	16.0550	2.0060	3.0999	5.1791	32.8863	1.9529	1.4636	6.692
	10.6435	7.1116	89.7569	3.5603	5.4100	16.5909	183.8543	3.4661	3.2333	14.764

Tower Elevation ft	Gusset Area (per face) in ²	Gusset Thickness in	Gusset Grade	Adjust. Factor A ₁	Adjust. Factor A ₂	Weight Mult.	Double Angle Stanch Bolt Spacing in	Double Angle Stanch Bolt Spacing in	Double Angle Stanch Bolt Spacing in
L1 25.00-0.00				1	1	1			

Feed Line/Linear Appurtenances - Entered As Area

Description	Face or Leg	Allow. Shield From Torque Calculation	Component Type	Placement ft	Total ft	C _A A ₁ ft ²	Weight lb
Existing Cable Inside Pole	C	No	Yes	C/A ₁ (Out Of Face)	24.50 + 0.00	1	No Ice 0.06

Feed Line/Linear Appurtenances Section Areas

Tower Section	Tower Elevation ft	Face	A ₁ ft ²	A ₂ ft ²	C _A A ₁ In Face ft ²	C _A A ₂ Out Face ft ²	Weight lb
L1	25.00-0.00	A	0.000	0.000	0.000	0.000	0.00
		B	0.000	0.000	0.000	0.000	0.00
		C	0.000	0.000	0.000	1.544	3.67
		D	0.000	0.000	0.000	0.000	0.00

Steel Decorated Pole
Palo Alto
PALO ALTO_203

Compression Checks

Pole Design Data

Section No.	Elevation ft	Size	L in	L _u in	K/L _u	A in ²	F _a lb	Φ _a lb	Ratio
L1	25 - 0 (1)	TP10x5.73x0.219	25.00	25.00	84.3	7.1116	-619.90	143808.00	0.004

Pole Bending Design Data

Section No.	Elevation ft	Size	M _u ft-lb	Φ _u ft-lb	Ratio M _u /Φ _u	M _y ft-lb	Φ _y ft-lb	Ratio M _y /Φ _y
L1	25 - 0 (1)	TP10x5.73x0.219	14208.33	38373.92	0.368	0.00	38373.92	0.000

Pole Shear Design Data

Section No.	Elevation ft	Size	Actual V _u lb	Φ _v lb	Ratio V _u /Φ _v	Actual T _u lb	Φ _t lb	Ratio T _u /Φ _t
L1	25 - 0 (1)	TP10x5.73x0.219	1077.09	99206.40	0.011	384.44	80323.58	0.005

Pole Interaction Design Data

Section No.	Elevation ft	Ratio V _u /Φ _v	Ratio M _u /Φ _u	Ratio T _u /Φ _t	Ratio M _y /Φ _y	Ratio T _x /Φ _x	Comb. Stress Ratio	Allow. Stress Ratio	Criteria
L1	25 - 0 (1)	0.004	0.368	0.000	0.011	0.005	0.373	1.000	4.8.2 ✓

Section Capacity Table

Section No.	Elevation ft	Component Type	Size	Critical Element	P lb	Φ _P lb	% Capacity	Pass/Fail
L1	25 - 0	Pole	TP10x5.73x0.219	1	-619.90	143808.00	37.3	Pass
							Summary	
							Pole (L1)	37.3
							Base Plate	35.2
							RATING =	37.3
								Pass

Steel Decorated Pole
Palo Alto
PALO ALTO_203

Discrete Tower Loads

Description	Face or Leg	Offset Type	Offset: Horizontal ft	Offset: Vertical ft	Placement ft	C _A A ₁ Front ft ²	C _A A ₂ Side ft ²	Weight lb
Decorative Top Cap	A	From Leg	6.50	0.000	25.00	No Ice 1.37	0.53	10.00
Light Luminaire	A	From Leg	0.00	0.000	19.50	No Ice 2.36	2.36	55.00
8" x 2.875" O.D. Light Pole Arm	A	From Leg	0.00	0.000	19.50	No Ice 1.92	0.06	65.00
FCC RF Notice Signage	C	From Leg	4.00	0.000	18.00	No Ice 0.33	0.01	0.20
SM6701 with Shroud	C	From Leg	0.25	0.000	23.67	No Ice 2.80	2.08	40.00
SM6701 with Shroud	B	From Leg	0.25	0.000	23.67	No Ice 2.80	2.08	40.00
SM6701 with Shroud	D	From Leg	0.25	0.000	23.67	No Ice 2.80	2.08	40.00
30"x72" Banner w/ Mount	C	From Leg	1.50	0.000	13.75	No Ice 18.00	0.13	15.00
30"x30" Street Sign	C	From Leg	0.00	0.000	9.00	No Ice 7.50	0.65	5.00
2PC Cast Alum. Huntington Clumbell	C	None	0.000	0.000	1.42	No Ice 2.01	2.01	50.00

Load Combinations

Comb. No.	Description
1	Dead Only
2	1.2 Dead + 1.6 Wind 0 deg - No Ice
3	0.9 Dead + 1.6 Wind 0 deg - No Ice
4	1.2 Dead + 1.6 Wind 45 deg - No Ice
5	0.9 Dead + 1.6 Wind 45 deg - No Ice
6	1.2 Dead + 1.6 Wind 90 deg - No Ice
7	0.9 Dead + 1.6 Wind 90 deg - No Ice
8	Dead + Wind 0 deg - Service
9	Dead + Wind 45 deg - Service
10	Dead + Wind 90 deg - Service

HILTI
Hilti PROFIS Engineering 3.0.65

www.hilti.com

Company: All State Eng. & Surveying
Address: 23875 Birtcher Dr. Lake Forest, CA 92650
Phone / Fax: 9492730906
Design: Concrete - Sep 9, 2020
Fastening point:

Page: 1
Specifier: 9/25/2020
E-Mail: Date:


Spooler's comments:

1 Input data

Anchor type and diameter: Heavy Hex Head ASTM F1554 GR. 36 1
Item number: not available
Effective embedment depth: h_{ef} = 24.000 in
Material: ASTM F1554
Pilot: Design Method ACI 318-08 / CIP
Slotted off installation: without clamping (anchors), restraint level (anchor plate) 1.00, s₁ = 1.250 in, t = 0.000 in
Anchor plate⁶: L x t = 12.000 in. x 12.000 in. x 0.500 in.; (Recommended plate thickness: not calculated)
Profile: Round HSS (AISC), HSS10X.188, (L x W x T) = 10.000 in. x 10.000 in. x 0.188 in
Base material: cracked concrete, (f'_c) = 3,250 psi, h = 84.000 in
Reinforcement: tension: condition A, shear: condition B, anchor reinforcement: tension
edge reinforcement: > No. 4 bar with stirrups
Seismic loads (cat. C, D, E, or F): no

⁶ - The anchor calculation is based on a rigid anchor plate assumption.

Geometry [in.] & Loading [lb, ft, lb]



Input data and results must be checked for conformity with the existing conditions and for practicality!
PROFIS Engineering (c) 2009-2020 Hilti AG, FL 9494 Schaan. Hilti is a registered trademark of Hilti AG, Schaan.

verizon

2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

Vinculum

575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500

ALLSTATES
ENGINEERING & SURVEYING
23675 BIRTCHER DRIVE
LAKE FOREST, CA 92630

PROJECT ID: TBD

DRAWN BY: RF

CHECKED BY: DW

REV	DATE	DESCRIPTION	
2	09/10/2020	100% CD'S FOR SUBMITTAL	MG
1	06/11/2020	100% CD'S FOR SUBMITTAL	RF
0	05/22/2020	100% CD'S FOR APPROVAL	RF
B	05/04/2020	95% CD'S FOR REDLINE	RF
A	04/14/2020	90% CD'S FOR REDLINE	RF



IT IS A VIOLATION OF LAW FOR ANY PERSON,
UNLESS THEY ARE ACTING UNDER THE
DIRECTION OF A LICENSED PROFESSIONAL
ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 203
PUBLIC R.O.W. ADJACENT TO:
519 WEBSTER STREET
PALO ALTO, 94301
LOCATION CODE: 566802

SHEET TITLE

CALCS

SHEET NUMBER

C-2

Company:	All State Eng. & Surveying	Page:	2
Address:	23675 Birtcher Dr. Lake Forest, CA 92630	Specifier:	
Phone / Fax:	9492730996 /	E-Mail:	
Design:	Concrete - Sep 9, 2020	Date:	9/25/2020
Fastening point:			

Case	Description	Forces (lb) / Moments (ft-lb)	Seismic	Max. Util. Anchor (%)
1	Combination 1	N = 621. V _x = 0. V _y = 1.076; M _x = 14,204.000; M _y = 0.000; M _z = 0.000;	no	39

Company:	All State Eng. & Surveying	Page:	3
Address:	23675 Birtcher Dr. Lake Forest, CA 92630	Specifier:	
Phone / Fax:	9492730996 /	E-Mail:	
Design:	Concrete - Sep 9, 2020	Date:	9/25/2020
Fastening point:			

Loading	Proof	Design values (lb)	Utilization	Status
Tension	Steel Strength	10,182	26.361	OK
Shear	Steel failure (with lever arm)	269	881	OK

Loading	P _u	P _y	ζ	Utilization P _u (%)	Status
Combined tension and shear loads	0.385	0.305	5/3	35	OK

3 Warnings

Please consider all details and hints/warnings given in the detailed report!

Fastening meets the design criteria!

Concrete
File: Caisson Depth.dwg
User: R. W. 06/09/18
Copyright: ENEC/CALC, INC. 1985-2018, Rev. 02/18/17
Zatzal & Associates, Inc.

Code References
Calculations per ACI 318-14, IBC 2018, CBC 2019, ASCE 7-16
Load Combinations Used: ASCE 7-16

General Information
Concrete 28 day strength = 3,250 ksi
E = 3,122.0 ksi
Density = 150.0 pcf
β = 0.850
f _y - Main Rebar = 60.0 ksi
f _y - Main Rebar = 29,000.0 ksi
Allow. Reinforcing Limits
Min. Reinf. = 0.250 %
Max. Reinf. = 8.0 %

Caisson Dimensions: 36.0 in Diameter, Column Edge to Rebar
Edge Cover = 3.0 in

Caisson Reinforcing: 12 - #5 bars

Applied Loads
Caisson self weight included: 7,422.01 lb * Dead Load Factor

AXIAL LOADS
Reaction from Pole: Axial Load at 7.0 ft above base: U = 0.8210 k
REINFORCING LOADS
Reaction from Pole: Lat. Point Load at 7.0 ft offsetting M_x = 1.793 k
Reaction from Pole: Moment acting about X-X axis at 7.0 ft, W = 23.616 k-ft

DESIGN SUMMARY
Load Combination: 0.90D+1.60H
Location of max. above base: 6.953 ft
Maximum Stress Ratio
Ratio = (P_u/P_n + M_u/M_n) / (P_n/P_n + M_u/M_n) = 0.0611

P_u = 7.239 k
P_n = 121.846 k
M_u = 23.592 k-ft
M_n = -391.819 k-ft

M_u Angle = 0.0 deg
M_n at Angle = 23.592 k-ft
M_n at Angle = 386.205 k-ft

Caisson Capacities
P_n & M_n values located at P_n-M_n vector intersection with capacity curve
P_n max: Nominal Max. Compressive Axial Capacity: 3,024.81 k
P_n min: Nominal Min. Tension Axial Capacity: 3.720 k
P_n max: Usable Compressive Axial Capacity: 1,799.76 k
P_n min: Usable Tension Axial Capacity: 0 k

Company:	All State Eng. & Surveying	Page:	4
Address:	23675 Birtcher Dr. Lake Forest, CA 92630	Specifier:	
Phone / Fax:	9492730996 /	E-Mail:	
Design:	Concrete - Sep 9, 2020	Date:	9/25/2020
Fastening point:			

4 Remarks; Your Cooperation Duties

- All information and data contained in the Software concern solely the use of Hilti products and are based on the principles, formulas and security regulations in accordance with Hilti's technical directions and operating, mounting and assembly instructions, etc., that must be strictly complied with by the user. All figures contained therein are average figures, and therefore use-specific tests are to be conducted prior to using the relevant Hilti product. The results of the calculations carried out by means of the Software are based essentially on the data you put in. Therefore, you bear the sole responsibility for having the results of the calculation checked and cleared by an expert, particularly with regard to compliance with applicable norms and permits, prior to using them for your specific facility. The Software serves only as an aid to interpret norms and permits without any guarantee as to the absence of errors, the correctness and the relevance of the results or suitability for a specific application.
- You must take all necessary and reasonable steps to prevent or limit damage caused by the Software. In particular, you must arrange for the regular backup of programs and data and, if applicable, carry out the updates of the Software offered by Hilti on a regular basis. If you do not use the AutoUpdate function of the Software, you must ensure that you are using the current and thus up-to-date version of the Software in each case by carrying out manual updates via the Hilti Website. Hilti will not be liable for consequences, such as the recovery of lost or damaged data or programs, arising from a culpable breach of duty by you.

Input data and results must be checked for conformity with the existing conditions and for plausibility!
PROFIS Engineering 3.0.63-2020 Hilti AG, FL 9434 Schaan. Hilti is a registered trademark of Hilti AG, Schaan.

Concrete Caisson
File: Caisson Depth.dwg
User: R. W. 06/09/18
Copyright: ENEC/CALC, INC. 1985-2018, Rev. 02/18/17
Zatzal & Associates, Inc.

Governing Load Combination Results

Material	Dist. from	Axial Load	Bending Analysis	Utilization
X-X	Y-Y	Base	ft	ft
+1.40D+1.60H		6.50	11.26	1,190.76
+1.20D+1.60H+1.60H		6.50	9.85	100.71
+0.90D+1.60H		6.50	7.24	121.85

Maximum Reactions
Load Combination: 0.90D+1.60H
0.90D+1.60H+1.60H
0.90D+1.60H+1.60H

Maximum Moment Reactions
Load Combination: 0.90D+1.60H
0.90D+1.60H+1.60H
0.90D+1.60H+1.60H

Maximum Deflections for Load Combinations
Load Combination: 0.90D+1.60H
0.90D+1.60H+1.60H
0.90D+1.60H+1.60H

Sketches

Entered loads are factored per load combinations specified by user.

Interaction Diagrams

General Section Information: ρ = 0.70, β = 0.850, θ = 0.800

ρ = % Reinforcing: 0.3655 %
Reinforcing Area: 3.720 in²
Concrete Area: 1,017.88 in²

Maximum SERVICE Load Reactions
Top along Y-Y: 0.0 k
Bottom along Y-Y: 0.0 k
Top along X-X: 0.0 k
Bottom along X-X: 1.076 k

Maximum SERVICE Load Deflections
Along Y-Y: -0.002469 in
Along X-X: 0.0 in

General Section Information: ρ = 0.70, β = 0.850, θ = 0.800

ρ = % Reinforcing: 0.3655 %
Reinforcing Area: 3.720 in²
Concrete Area: 1,017.88 in²

Pole Footing Embedded in Soil
File: Caisson Depth.dwg
User: R. W. 06/09/18
Copyright: ENEC/CALC, INC. 1985-2018, Rev. 02/18/17
Zatzal & Associates, Inc.

DESCRIPTION: Proposed Caisson embedment (soil values from IBC Table 1806.2 with lateral bearing load increase from IBC 1806.3.4)

Code References
Calculations per IBC 2018 1807.3, CBC 2019, ASCE 7-16
Load Combinations Used: ASCE 7-16

General Information
Pole Footing Shape: Circular
Pole Footing Diameter: 36.0 in
Calculate Min. Depth for Allowable Pressures
No Lateral Restraint at Ground Surface
Allow Passive: 200.0 psf
Allow Active: 1,500.0 psf

Controlling Values
Governing Load Combination: 0.90D+1.60H
Lateral Load: 1.076 k
Lateral Moment: 14,203 k-in
Pressures at 1.0 Depth: 425.346 psf
Actual: 427.025 psf

Minimum Required Depth
6.50 ft

Footing Base Area: 7.099 ft²
Maximum Soil Pressure: 0.06135 ksi

Applied Loads
Lateral Concentrated Load (k): 1.076
Lateral Distributed Loads (k/ft): 14.203
Vertical Load (k): 0.8210

Load Combination Results
Load Combination: 0.90D+1.60H
Forces @ Ground Surface: 1.076 k, 14.203 k/ft
Required Depth (ft): 6.50
Pressure at 1.0 Depth: 425.3 k/ft²
Actual: 427.0 k/ft²
Allow: 427.0 k/ft²
Soil Pressure Factor: 1.000

NOTE:
THIS INFORMATION MAY NOT CONTAIN ALL DETAILS REQUIRED FOR CONSTRUCTION. APPROPRIATE MODIFICATION MAY BE REQUIRED TO ENSURE SUITABILITY OF THESE DRAWINGS FOR THE SPECIFIC APPLICATION. IT IS THE USER'S RESPONSIBILITY TO ENSURE INSTALLATION OF THE EQUIPMENT/SYSTEM IS IN ACCORDANCE WITH BUILDING/PROJECT SPECIFICATIONS, APPLICABLE CODES AND STANDARDS.

MAX FACTORED LOADING
MOMENT: 14.2 kip-ft
SHEAR: 1.1 kips
AXIAL: 0.7 kips

FOUNDATION DETAIL
DO NOT SCALE DRAWINGS
ALLSTATES ENGINEERING & SURVEYING
Zatzal & Associates, Inc.
23675 Birtcher Drive
Lake Forest, CA 92630

Vinculums
575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500

REGISTERED PROFESSIONAL ENGINEER
WESAM ZATZAL
71655
CIVIL
STATE OF CALIFORNIA

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 203
PUBLIC R.O.W. ADJACENT TO:
519 WEBSTER STREET
PALO ALTO, 94301
LOCATION CODE: 566802

SHEET TITLE
CALCS

SHEET NUMBER
C-3

GENERAL CONSTRUCTION NOTES

1. ALL WORK SHALL CONFORM TO THE REQUIREMENTS OF THE LOCAL BUILDING CODE, THE LATEST EDITION AND ALL OTHER APPLICABLE CODES AND ORDINANCES.
2. CONTRACTOR SHALL CONSTRUCT SITE IN ACCORDANCE WITH THESE DRAWINGS AND CONSTRUCTION SPECIFICATIONS 80-TI196-1 REV H. THE SPECIFICATION IS THE RULING DOCUMENT AND ANY DISCREPANCIES BETWEEN THE SPECIFICATION AND THESE DRAWINGS SHOULD BE BROUGHT TO THE ATTENTION OF THE ENGINEER PRIOR TO PROCEEDING WITH CONSTRUCTION
3. CONTRACTOR SHALL VISIT THE JOB SITE AND SHALL FAMILIARIZE HIMSELF WITH ALL CONDITIONS AFFECTING THE PROPOSED WORK (ROOF FRAMING, ELECTRICAL SERVICE, LOCAL PLANNING CODES, ETC.) AND SHALL MAKE PROVISIONS AS TO THE COST THEREOF. CONTRACTOR SHALL BE RESPONSIBLE FOR FAMILIARIZING HIMSELF WITH ALL CONTRACT DOCUMENTS, FIELD CONDITIONS AND DIMENSIONS AND CONFIRMING THAT THE WORK MAY BE ACCOMPLISHED AS SHOWN PRIOR TO PROCEEDING WITH CONSTRUCTION. ANY DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE ENGINEER PRIOR TO THE COMMENCEMENT OF WORK. NO COMPENSATION WILL BE AWARDED BASED ON CLAIM OF LACK OF KNOWLEDGE OF FIELD CONDITIONS
4. PLANS ARE NOT TO BE SCALED. THESE PLANS ARE INTENDED TO BE A DIAGRAMMATIC OUTLINE ONLY UNLESS OTHERWISE NOTED. THE WORK SHALL INCLUDE FURNISHING MATERIALS, EQUIPMENT AND APPURTENANCES, AND LABOR NECESSARY TO EFFECT ALL INSTALLATIONS AS INDICATED ON THE DRAWINGS. OWNER PROVIDED MATERIALS WILL INCLUDE THE FOLLOWING, UNLESS NOTED OTHERWISE:

A) TRANSMITTER

B) RF FILTER

C) MFTS RACK

D) AUXILIARY EQUIPMENT IN MFTS RACK

E) PUMP ASSEMBLY

F) HEAT EXCHANGER

G) HOSE AND HOSE MANIFOLDS (ANY COPPER OR STEEL SECTIONS PROVIDE BY CONTRACTOR)

H) UHF ANTENNA AND MOUNTING BRACKETS, GPS ANTENNAS AND KU ANTENNAS

I) UHF COAX AND HANGERS

K) 480-208 # 208-400 ELECTRICAL TRANSFORMERS (RE: E-2 FOR SPECIALIZED TRANSFORMERS PROVIDED BY CONTRACTOR)

L) AUTOMATIC TRANSFER SWITCH AND GENERATOR

M) EQUIPMENT SHELTER (SHELTERS FURNISHED IN FACTORY W/ HVAC EQUIPMENT AND ELECTRICAL DISTRIBUTION PANEL)

N) INTEGRATED LOAD CENTER
5. DIMENSIONS SHOWN ARE TO FINISH SURFACES UNLESS OTHERWISE NOTED. SPACING BETWEEN EQUIPMENT IS REQUIRED CLEARANCE. THEREFORE, IT IS CRITICAL TO FIELD VERIFY DIMENSIONS; SHOULD THERE BE ANY QUESTIONS REGARDING THE CONTRACT DOCUMENTS, EXISTING CONDITIONS AND/OR DESIGN INTENT, THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING THE WORK.
6. DETAILS ARE INTENDED TO SHOW DESIGN INTENT. MODIFICATIONS MAY BE REQUIRED TO SUIT JOB DIMENSIONS OR CONDITIONS, AND SUCH MODIFICATIONS SHALL BE INCLUDED AS PART OF THE WORK.
7. CONTRACTOR SHALL RECEIVE CLARIFICATION IN WRITING, AND SHALL RECEIVE IN WRITING AUTHORIZATION TO PROCEED BEFORE STARTING WORK ON ANY ITEMS NOT CLEARLY DEFINED OR IDENTIFIED BY THE CONTRACT DOCUMENTS.
8. CONTRACTOR SHALL SUPERVISE AND DIRECT THE WORK USING THE BEST CONSTRUCTION SKILLS AND ATTENTION. CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES AND PROCEDURES AND FOR COORDINATING ALL PORTIONS OF THE WORK UNDER CONTRACT, UNLESS OTHERWISE NOTED.
9. CONTRACTOR SHALL BE RESPONSIBLE FOR THE SAFETY OF THE WORK AREA, ADJACENT AREAS AND BUILDING OCCUPANTS THAT ARE LIKELY TO BE AFFECTED BY THE WORK UNDER THIS CONTRACT. WORK SHALL CONFORM TO ALL OSHA REQUIREMENTS.
10. CONTRACTOR SHALL COORDINATE HIS WORK WITH THE SUPERINTENDENT OF BUILDINGS & GROUNDS AND SCHEDULE HIS ACTIVITIES AND WORKING HOURS IN ACCORDANCE WITH THE REQUIREMENTS.
11. CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING HIS WORK WITH THE WORK OF OTHERS AS IT MAY RELATE TO RADIO EQUIPMENT, ANTENNAS AND ANY OTHER PORTIONS OF THE WORK.
12. INSTALL ALL EQUIPMENT AND MATERIALS IN ACCORDANCE WITH MANUFACTURERS RECOMMENDATIONS UNLESS SPECIFICALLY OTHERWISE INDICATED OR WHERE LOCAL CODES OR REGULATIONS TAKE PRECEDENCE.
13. MAKE NECESSARY PROVISIONS TO PROTECT EXISTING SURFACES, EQUIPMENT, IMPROVEMENTS, PIPING ETC. AND IMMEDIATELY REPAIR ANY DAMAGE THAT OCCURS DURING CONSTRUCTION.
14. IN DRILLING HOLES INTO CONCRETE WHETHER FOR FASTENING OR ANCHORING PURPOSES, OR PENETRATIONS THROUGH THE FLOOR FOR CONDUIT RUNS, PIPE RUNS, ETC., MUST BE CLEARLY UNDERSTOOD THAT REINFORCING STEEL SHALL NOT BE DRILLED INTO, CUT OR DAMAGED UNDER ANY CIRCUMSTANCES (UNLESS NOTED OTHERWISE). LOCATIONS OF REINFORCING STEEL ARE NOT DEFINITELY KNOWN AND THEREFORE MUST BE SEARCHED FOR BY APPROPRIATE METHODS AND EQUIPMENT.
15. REPAIR ALL EXISTING WALL SURFACES DAMAGED DURING CONSTRUCTION SUCH THAT THEY MATCH AND BLEND IN WITH ADJACENT SURFACES.
16. SEAL PENETRATIONS THROUGH FIRE RATED AREAS WITH U.L. LISTED AND FIRE CODE APPROVED MATERIALS.
17. KEEP CONTRACT AREA CLEAN, HAZARD FREE, AND DISPOSE OF ALL DIRT, DEBRIS, AND RUBBISH. EQUIPMENT NOT SPECIFIED AS REMAINING ON THE PROPERTY OF THE OWNER SHALL BE REMOVED. LEAVE PREMISES IN CLEAN CONDITION AND FREE FROM PAINT SPOTS, DUST, OR SMUDGES OF ANY NATURE. CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING ALL ITEMS UNTIL COMPLETION OF CONSTRUCTION.
18. MINIMUM BEND RADIUS OF ANTENNA CABLES SHALL BE IN ACCORDANCE WITH CABLE MANUFACTURERS RECOMMENDATIONS.
19. ALL EXISTING INACTIVE SEWER, WATER, GAS, ELECTRIC AND OTHER UTILITIES, WHICH INTERFERE WITH THE EXECUTION OF THE WORK, SHALL BE REMOVED AND/OR CAPPED, PLUGGED OR OTHERWISE DISCONTINUED AT POINTS WHICH WILL NOT INTERFERE WITH THE EXECUTION OF THE WORK, SUBJECT TO APPLICABLE REGULATORY AUTHORITIES
20. CONTRACTOR SHALL MINIMIZE DISTURBANCE TO EXISTING SITE DURING CONSTRUCTION. EROSION CONTROL MEASURES, IF REQUIRED DURING CONSTRUCTION SHALL BE IN CONFORMANCE WITH JURISDICTIONAL OR STATE AND LOCAL GUIDELINES FOR EROSION AND SEDIMENT CONTROL AND COORDINATED WITH LOCAL REGULATORY AUTHORITIES.
21. ALL CONSTRUCTION IS TO ADHERE TO VERIZON'S INTEGRATED CONSTRUCTION STANDARDS UNLESS CALIFORNIA CODE IS MORE STRINGENT.
22. THE INTENT OF THE PLANS AND SPECIFICATIONS IS TO PERFORM THE CONSTRUCTION IN ACCORDANCE WITH THE CALIFORNIA BUILDING STANDARDS CODE, TITLES 19 AND 24, CALIFORNIA CODE OF REGULATIONS. SHOULD ANY CONDITIONS DEVELOP NOT COVERED BY THE APPROVED PLANS AND SPECIFICATIONS WHEREIN THE FINISHED WORK WILL NOT COMPLY WITH TITLE 24, CALIFORNIA CODE OF REGULATIONS, A CHANGE ORDER DETAILING AND SPECIFYING THE REQUIRED WORK SHALL BE SUBMITTED TO AND APPROVED BY THE JURISDICTION BEFORE PROCEEDING WITH THE WORK.

SITE WORK NOTES

1. DO NOT EXCAVATE OR DISTURB BEYOND THE PROPERTY LINES OR LEASE LINES, UNLESS OTHERWISE NOTED.
2. DO NOT SCALE BUILDING DIMENSIONS FROM DRAWING.
3. SIZE, LOCATION AND TYPE OF ANY UNDERGROUND UTILITIES OR IMPROVEMENTS SHALL BE ACCURATELY NOTED AND PLACED ON AS-BUILT DRAWINGS BY GENERAL CONTRACTOR AND ISSUED TO ARCHITECT/ENGINEER AT COMPLETION OF PROJECT.
4. ALL EXISTING UTILITIES, FACILITIES, CONDITIONS AND THEIR DIMENSIONS SHOWN ON PLANS HAVE BEEN PLOTTED FROM AVAILABLE RECORDS. THE ENGINEER AND OWNER ASSUME NO RESPONSIBILITY WHATSOEVER AS TO THE SUFFICIENCY OR ACCURACY OF THE INFORMATION SHOWN ON THE PLANS OR THE MANNER OF THEIR REMOVAL OR ADJUSTMENT. CONTRACTOR SHALL BE RESPONSIBLE FOR DETERMINING EXACT LOCATION OF ALL EXISTING UTILITIES AND FACILITIES PRIOR TO START OF CONSTRUCTION. CONTRACTOR SHALL ALSO OBTAIN FROM EACH UTILITY COMPANY DETAILED INFORMATION RELATIVE TO WORKING SCHEDULES AND METHODS OF REMOVING OR ADJUSTING EXISTING UTILITIES.
5. CONTRACTOR SHALL VERIFY ALL EXISTING UTILITIES BOTH HORIZONTALLY AND VERTICALLY PRIOR TO START OF CONSTRUCTION. ANY DISCREPANCIES OR DOUBTS AS TO THE INTERPRETATION OF PLANS SHALL BE IMMEDIATELY REPORTED TO THE ARCHITECT/ENGINEER FOR RESOLUTION AND INSTRUCTION, AND NO FURTHER WORK SHALL BE PERFORMED UNTIL THE DISCREPANCY IS CHECKED AND CORRECTED BY THE ARCHITECT/ENGINEER. FAILURE TO SECURE SUCH INSTRUCTION MEANS CONTRACTOR WILL HAVE WORKED AT HIS/HER OWN RISK AND EXPENSE. CONTRACTOR SHALL CALL LOCAL DIGGER HOT LINE FOR UTILITY LOCATIONS 48 HOURS PRIOR TO START OF CONSTRUCTION.
6. ALL NEW AND EXISTING UTILITY STRUCTURES ON SITE AND IN AREAS TO BE DISTURBED BY CONSTRUCTION SHALL BE ADJUSTED TO FINISH ELEVATIONS PRIOR TO FINAL INSPECTION OF WORK.
7. GRADING OF THE SITE WORK AREA IS TO BE SMOOTH AND CONTINUOUS IN SLOPE AND IS TO FEATHER INTO EXISTING GRADES AT THE GRADING LIMITS.
8. ALL TEMPORARY EXCAVATIONS FOR THE INSTALLATION OF FOUNDATIONS, UTILITIES, ETC., SHALL BE PROPERLY LAID BACK OR BRACED IN ACCORDANCE WITH CORRECT OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION (OSHA) REQUIREMENTS.
9. STRUCTURAL FILLS SUPPORTING PAVEMENTS SHALL BE COMPACTED TO 95% OF MAXIMUM STANDARD PROCTOR DRY DENSITY.
10. NEW GRADES NOT IN BUILDING AND DRIVEWAY IMPROVEMENT AREA TO BE ACHIEVED BY FILLING WITH APPROVED CLEAN FILL AND COMPACTED TO 95% OF STANDARD PROCTOR DENSITY.
11. ALL FILL SHALL BE PLACED IN UNIFORM LIFTS. THE LIFTS THICKNESS SHOULD NOT EXCEED THAT WHICH CAN BE PROPERLY COMPACTED THROUGHOUT ITS ENTIRE DEPTH WITH THE EQUIPMENT AVAILABLE.
12. ANY FILLS PLACED ON EXISTING SLOPES THAT ARE STEEPER THAN 10 HORIZONTAL TO 1 VERTICAL SHALL BE PROPERLY BENCHED INTO THE EXISTING SLOPE AS DIRECTED BY A GEOTECHNICAL ENGINEER.
13. CONTRACTOR SHALL CLEAN ENTIRE SITE AFTER CONSTRUCTION SUCH THAT NO PAPERS, TRASH, WEEDS, BRUSH OR ANY OTHER DEPOSITS WILL REMAIN. ALL MATERIALS COLLECTED DURING CLEANING OPERATIONS SHALL BE DISPOSED OF OFF-SITE BY THE GENERAL CONTRACTOR.
14. ALL TREES AND SHRUBS WHICH ARE NOT IN DIRECT CONFLICT WITH THE IMPROVEMENTS SHALL BE PROTECTED BY THE GENERAL CONTRACTOR.
15. ALL SITE WORK SHALL BE CAREFULLY COORDINATED BY GENERAL CONTRACTOR WITH LOCAL UTILITY COMPANY, TELEPHONE COMPANY, AND ANY OTHER UTILITY COMPANIES HAVING JURISDICTION OVER THIS LOCATION.

ENVIRONMENTAL NOTES

1. ALL WORK PERFORMED SHALL BE DONE IN ACCORDANCE WITH ISSUED PERMITS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PAYMENT OF FINES AND PROPER CLEAN UP FOR AREAS IN VIOLATION.
2. CONTRACTOR AND/OR DEVELOPER SHALL BE RESPONSIBLE FOR CONSTRUCTION AND MAINTENANCE OF EROSION AND SEDIMENTATION CONTROLS DURING CONSTRUCTION FOR PROTECTION OF ADJACENT PROPERTIES, ROADWAYS AND WATERWAYS AND SHALL BE MAINTAINED IN PLACE THROUGH FINAL JURISDICTIONAL INSPECTION & RELEASE OF SITE.
3. CONTRACTOR SHALL INSTALL/CONSTRUCT ALL NECESSARY SEDIMENT/SILT CONTROL FENCING AND PROTECTIVE MEASURES WITHIN THE LIMITS OF SITE DISTURBANCE PRIOR TO CONSTRUCTION.
4. NO SEDIMENT SHALL BE ALLOWED TO EXIT THE PROPERTY. THE CONTRACTOR IS RESPONSIBLE FOR TAKING ADEQUATE MEASURES FOR CONTROLLING EROSION. ADDITIONAL SEDIMENT CONTROL FENCING MAY BE REQUIRED IN ANY AREAS SUBJECT TO EROSION.
5. THE CONTRACTOR IS RESPONSIBLE FOR MAINTAINING POSITIVE DRAINAGE ON THE SITE AT ALL TIMES WITH SILT AND EROSION CONTROL MEASURES MAINTAINED ON THE DOWNSTREAM SIDE OF SITE DRAINAGE. ANY DAMAGE TO ADJACENT PROPERTY AS A RESULT OF EROSION WILL BE CORRECTED AT THE CONTRACTORS EXPENSE.
6. CONTRACTOR SHALL BE RESPONSIBLE FOR DAILY INSPECTIONS AND ANY REPAIRS OF ALL SEDIMENT CONTROL MEASURES INCLUDING SEDIMENT REMOVAL AS NECESSARY.
7. CLEARING OF VEGETATION AND TREE REMOVAL SHALL BE ONLY AS PERMITTED AND BE HELD TO A MINIMUM. ONLY TREES NECESSARY FOR CONSTRUCTION OF THE FACILITIES SHALL BE REMOVED.
8. SEEDING AND MULCHING AND/OR SODDING OF THE SITE WILL BE ACCOMPLISHED AS SOON AS POSSIBLE AFTER COMPLETION OF THE PROJECT FACILITIES AFFECTING LAND DISTURBANCE.
9. CONTRACTOR SHALL PROVIDE ALL EROSION AND SEDIMENTATION CONTROL MEASURES AS REQUIRED BY LOCAL, COUNTY AND STATE CODES AND ORDINANCES TO PROTECT EMBANKMENTS FROM SOIL LOSS AND TO PREVENT ACCUMULATION OF SOIL AND SILT IN STREAMS AND DRAINAGE PATHS LEAVING THE CONSTRUCTION AREA. THIS MAY INCLUDE SUCH MEASURES AS SILT FENCES, STRAW BALE SEDIMENT BARRIERS, AND CHECK DAMS.
10. RIP RAP OF SIZES INDICATED SHALL CONSIST OF CLEAN, HARD, SOUND, DURABLE, UNIFORM IN QUALITY STONE FREE OF ANY DETRIMENTAL QUANTITY OF SOFT, FRIABLE, THIN, ELONGATED OR LAMINATED PIECES, DISINTEGRATED MATERIAL, ORGANIC MATTER, OIL, ALKALI, OR OTHER DELETERIOUS SUBSTANCES

GENERAL NOTES

1. THESE NOTES SHALL BE CONSIDERED A PART OF THE WRITTEN SPECIFICATIONS, CONTRACT AND CONSTRUCTION DOCUMENTS.
2. THE WORK SHALL INCLUDE FURNISHING MATERIALS, EQUIPMENT, APPURTENANCES, AND LABOR NECESSARY TO COMPLETE ALL INSTALLATIONS AS INDICATED ON THESE PLANS AND IN THE CONTRACT DOCUMENTS.
3. PRIOR TO THE SUBMISSION OF BIDS, THE CONTRACTOR(S) SHALL VISIT THE JOB SITE(S) AND BE RESPONSIBLE FOR ALL CONTRACT DOCUMENTS, FIELD CONDITIONS AND DIMENSIONS, AND CONFIRM THAT THE WORK MAY BE ACCOMPLISHED PER THE CONTRACT DOCUMENTS. ANY DISCREPANCIES ARE TO BE BROUGHT TO THE ATTENTION OF THE IMPLEMENTATION ENGINEER AND ARCHITECT/ENGINEER PRIOR TO BID SUBMITTAL
4. THE CONTRACTOR SHALL RECEIVE WRITTEN AUTHORIZATION TO PROCEED ON ANY WORK NOT CLEARLY DEFINED OR IDENTIFIED IN THE CONTRACT AND CONSTRUCTION DOCUMENTS BEFORE STARTING ANY WORK.
5. ALL WORK PERFORMED AND MATERIALS INSTALLED SHALL BE IN STRICT ACCORDANCE WITH ALL APPLICABLE CODES, REGULATIONS, AND ORDINANCES, INCLUDING APPLICABLE MUNICIPAL AND UTILITY COMPANY SPECIFICATIONS.
6. THE CONTRACTOR SHALL INSTALL ALL EQUIPMENT AND MATERIALS IN ACCORDANCE WITH THE MANUFACTURER RECOMMENDATIONS. IF THESE RECOMMENDATIONS ARE IN CONFLICT WITH THE CONTRACT AND CONSTRUCTION DOCUMENTS AND/OR APPLICABLE CODES OR REGULATIONS, REVIEW AND RESOLVE THE CONFLICT WITH DIRECTION FROM THE IMPLEMENTATION ENGINEER AND ARCHITECT/ENGINEER PRIOR TO PROCEEDING.
7. THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR ALL CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES AND FOR COORDINATION OF ALL PORTIONS OF THE WORK UNDER THE CONTRACT INCLUDING CONTACT AND COORDINATION WITH THE IMPLEMENTATION ENGINEER AND WITH THE AUTHORIZED REPRESENTATIVE OF ANY OUTSIDE POLE OR PROPERTY OWNER.
8. THE CONTRACTOR SHALL MAKE NECESSARY PROVISIONS TO PROTECT EXISTING IMPROVEMENTS, INCLUDING BUT NOT LIMITED TO PAVING, CURBS, VEGETATION, GALVANIZED SURFACE OR OTHER EXISTING ELEMENTS AND UPON COMPLETION OF THE WORK, REPAIR ANY DAMAGE THAT OCCURRED DURING CONSTRUCTION TO THE SATISFACTION OF VERIZON.
9. CONTRACTOR IS TO KEEP THE GENERAL AREA CLEAN, HAZARD FREE, AND DISPOSE OF ALL DIRT, DEBRIS, RUBBISH, AND REMOVE EQUIPMENT NOT SPECIFIED AS REMAINING ON THE PROPERTY. LEAVE PREMISES IN CLEAN CONDITION DAILY.
10. PLANS ARE INTENDED TO BE DIAGRAMMATIC ONLY AND SHOULD NOT BE SCALED UNLESS OTHERWISE NOTED. RELY ONLY ON ANNOTATED DIMENSIONS AND REQUEST INFORMATION IF ADDITIONAL DIMENSIONS ARE REQUIRED.
11. THE EXISTENCE AND LOCATION OF UTILITIES AND OTHER AGENCY'S FACILITIES WERE OBTAINED BY A SEARCH OF AVAILABLE RECORDS. OTHER FACILITIES MAY EXIST. CONTRACTOR SHALL VERIFY LOCATIONS PRIOR TO START OF CONSTRUCTION AND USE EXTREME CARE AND PROTECTIVE MEASURES TO PREVENT DAMAGE TO THESE FACILITIES. CONTRACTOR IS RESPONSIBLE FOR THE PROTECTION OF UTILITIES OR OTHER AGENCY'S FACILITIES WITHIN THE LIMITS OF THE WORK, WHETHER THEY ARE IDENTIFIED IN THE CONTRACT DOCUMENTS OR NOT.
12. THE CONTRACTOR SHALL NOTIFY UNDERGROUND SERVICE ALERT (800) 227-2600, AT LEAST TWO WORKING DAYS PRIOR TO THE START OF ANY EXCAVATION.

DEFINITIONS

1. "TYPICAL" OR "TYP" MEANS THAT THIS ITEM IS SUBSTANTIALLY THE SAME ACROSS SIMILAR CONDITIONS. "TYP." SHALL BE UNDERSTOOD TO MEAN "TYPICAL WHERE OCCURS" AND SHALL NOT BE CONSIDERED AS WITHOUT EXCEPTION OR CONSIDERATION OF SPECIFIC CONDITIONS.
2. "SIMILAR" MEANS COMPARABLE TO CHARACTERISTICS FOR THE CONDITION NOTED. VERIFY DIMENSIONS AND ORIENTATION ON PLAN.
3. "AS REQUIRED" MEANS AS REQUIRED BY REGULATORY REQUIREMENTS, BY REFERENCED STANDARDS, BY EXISTING CONDITIONS, BY GENERALLY ACCEPTED CONSTRUCTION PRACTICE, OR BY THE CONTRACT DOCUMENTS.
4. "ALIGN" MEANS ACCURATELY LOCATE FINISH FACES OF MATERIALS IN THE SAME PLANE.
5. THE TERM "VERIFY" OR "V.I.F." SHALL BE UNDERSTOOD TO MEAN "VERIFY IN FIELD WITH ENGINEER" AND REQUIRES THAT THE CONTRACTOR CONFIRM INTENTION REGARDING NOTED CONDITION AND PROCEED ONLY AFTER RECEIVING DIRECTION.
6. WHERE THE WORDS "OR EQUAL" OR WORDS OF SIMILAR INTENT FOLLOW A MATERIAL SPECIFICATION, THEY SHALL BE UNDERSTOOD TO REQUIRE SIGNED APPROVAL OF ANY DEVIATION TO SAID SPECIFICATION PRIOR TO CONTRACTOR'S ORDERING OR INSTALLATION OF SUCH PROPOSED EQUAL PRODUCT.
7. FURNISH: SUPPLY ONLY, OTHERS TO INSTALL.
INSTALL: INSTALL ITEMS FURNISHED BY OTHERS.
PROVIDE: FURNISH AND INSTALL.

811

USA North

Know what's below.
Call before you dig.

California and Nevada
Call Two Working Days Before You Dig!
811 / 800-227-2600

verizon

2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

Vinculums

575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500

ALLSTATES

ENGINEERING & SURVEYING
23675 BIRTCHER DRIVE
LAKE FOREST, CA 92630

PROJECT ID:	TBD
DRAWN BY:	RF
CHECKED BY:	DW

2	09/10/2020	100% CD'S FOR SUBMITTAL	MG
1	06/11/2020	100% CD'S FOR SUBMITTAL	RF
0	05/22/2020	100% CD'S FOR APPROVAL	RF
B	05/04/2020	95% CD'S FOR REDLINE	RF
A	04/14/2020	90% CD'S FOR REDLINE	RF
REV	DATE	DESCRIPTION	

REGISTERED PROFESSIONAL ENGINEER
WISSAM ZALZALI
71655
CIVIL
STATE OF CALIFORNIA

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 203

PUBLIC R.O.W. ADJACENT TO:
519 WEBSTER STREET
PALO ALTO, 94301
LOCATION CODE: 566802

SHEET TITLE

GENERAL NOTES

SHEET NUMBER

GN-1

ELECTRICAL NOTES

1.

ELECTRICAL CONTRACTOR SHALL SUPPLY AND INSTALL ANY/ALL ELECTRICAL WORK INDICATED. ANY/ALL CONSTRUCTION SHALL BE IN ACCORDANCE W/DRAWINGS AND ANY/ALL APPLICABLE SPECIFICATIONS. IF ANY PROBLEMS ARE ENCOUNTERED BY COMPLYING WITH THESE REQUIREMENTS, CONTRACTOR SHALL NOTIFY 'CONSTRUCTION MANAGER' AS SOON AS POSSIBLE, AFTER THE DISCOVERY OF THE PROBLEMS, AND SHALL NOT PROCEED WITH THAT PORTION OF WORK, UNTIL THE 'CONSTRUCTION MANAGER' HAS DIRECTED THE CORRECTIVE ACTIONS TO BE TAKEN.
2.

ELECTRICAL CONTRACTOR SHALL VISIT THE JOB SITE AND FAMILIARIZE HIMSELF WITH ANY/ALL CONDITIONS AFFECTING ELECTRICAL AND COMMUNICATION INSTALLATION AND MAKE PROVISIONS AS TO THE COST THEREOF. ALL EXISTING CONDITIONS OF ELECTRICAL EQUIP., LIGHT FIXTURES, ETC., THAT ARE PART OF THE FINAL SYSTEM, SHALL BE VERIFIED BY THE CONTRACTOR, PRIOR TO THE SUBMITTING OF HIS BID. FAILURE TO COMPLY WITH THIS PARAGRAPH WILL IN NO WAY RELIEVE CONTRACTOR OF PERFORMING ALL WORK NECESSARY FOR A COMPLETE AND WORKING SYSTEM.
3.

ALL WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE LATEST EDITION OF THE NEC AND ALL CODES AND LOCAL ORDINANCES OF THE LOCAL POWER & TELEPHONE COMPANIES HAVING JURISDICTION AND SHALL INCLUDE BUT NOT BE LIMITED TO:
C - NATIONAL FIRE CODES
A. UL - UNDERWRITERS LABORATORIES
B. NEC - NATIONAL ELECTRICAL CODE
C. NEMA - NATIONAL ELECTRICAL MANUFACTURERS ASSOC.
D. OSHA - OCCUPATIONAL SAFETY AND HEALTH ACT
E. SBC - STANDARD BUILDING CODE
4.

DO NOT SCALE ELECTRICAL DRAWINGS, REFER TO SITE PLANS AND ELEVATIONS FOR EXACT LOCATIONS OF ALL EQUIPMENT, AND CONFIRM WITH 'CONSTRUCTION MANAGER' ANY SIZES AND LOCATIONS WHEN NEEDED.
5.

EXISTING SERVICES: CONTRACTOR SHALL NOT INTERRUPT EXISTING SERVICES WITHOUT WRITTEN PERMISSION OF THE OWNER.
6.

CONTRACTOR SHALL PAY FOR ANY/ALL PERMITS, FEES, INSPECTIONS AND TESTING. CONTRACTOR IS TO OBTAIN PERMITS AND APPROVED SUBMITTALS PRIOR TO THE WORK BEGINNING OR ORDERING EQUIPMENT.
7.

THE TERM "PROVIDE" USED IN CONSTRUCTION DOCUMENTS AND SPECIFICATIONS, INDICATES THAT THE CONTRACTOR SHALL FURNISH AND INSTALL.
8.

CONTRACTOR SHALL CONFIRM WITH LOCAL UTILITY COMPANY ANY/ALL REQUIREMENTS SUCH AS THE: LUG SIZE RESTRICTIONS, CONDUIT ENTRY, SIZE OF TRANSFORMERS, SCHEDULED DOWNTIME FOR THE OWNERS' CONFIRMATION, ETC... ANY/ALL CONFLICTS SHALL BE BROUGHT TO THE ATTENTION OF THE CONSTRUCTION MANAGER, PRIOR TO BEGINNING ANY WORK.
9.

MINIMUM WIRE SIZE SHALL BE #12 AWG, NOT INCLUDING CONTROL WIRING, UNLESS NOTED OTHERWISE. ALL CONDUCTORS SHALL BE COPPER WITH THWN INSULATION.
10.

OUTLET BOXES SHALL BE PRESSED STEEL IN DRY LOCATIONS, CAST ALLOY WITH THREADED HUBS IN WET/DAMP LOCATIONS AND SPECIAL ENCLOSURES FOR OTHER CLASSIFIED AREAS.
11.

IT IS NOT THE INTENT OF THESE PLANS TO SHOW EVERY MINOR DETAIL OF THE CONSTRUCTION. CONTRACTOR IS EXPECTED TO FURNISH AND INSTALL ALL ITEMS FOR A COMPLETE ELECTRICAL SYSTEM AND PROVIDE ALL REQUIREMENTS FOR THE EQUIPMENT TO BE PLACED IN PROPER WORKING ORDER.
12.

ELECTRICAL SYSTEM SHALL BE AS COMPLETELY AND EFFECTIVELY GROUNDED, AS REQUIRED BY SPECIFICATIONS, SET FORTH BY VERIZON.
13.

ALL WORK SHALL BE PERFORMED BY A LICENSED ELECTRICAL CONTRACTOR IN A FIRST CLASS, WORKMANLIKE MANNER. THE COMPLETED SYSTEM SHALL BE FULLY OPERATIVE AND SUBJECT TO REGULATORY INSPECTION AND APPROVAL BY CONSTRUCTION MANAGER.
14.

ALL WORK SHALL BE COORDINATED WITH OTHER TRADES TO AVOID INTERFERENCE WITH THE PROGRESS OF CONSTRUCTION.
15.

CONTRACTOR SHALL GUARANTEE ANY/ALL MATERIALS AND WORK FREE FROM DEFECTS FOR A PERIOD OF NOT LESS THAN ONE YEAR FROM DATE OF ACCEPTANCE.
16.

THE CORRECTION OF ANY DEFECTS SHALL BE COMPLETED WITHOUT ANY ADDITIONAL CHARGE AND SHALL INCLUDE THE REPLACEMENT OR THE REPAIR OF ANY OTHER PHASE OF THE INSTALLATION, WHICH MAY HAVE BEEN DAMAGED THEREIN.
17.

ADEQUATE AND REQUIRED LIABILITY INSURANCE SHALL BE PROVIDED FOR PROTECTION AGAINST PUBLIC LOSS AND ANY/ALL PROPERTY DAMAGE FOR THE DURATION OF WORK.
18.

PROVIDE AND INSTALL CONDUIT, CONDUCTORS, PULL WIRES, BOXES, COVER PLATES AND DEVICES FOR ALL OUTLETS AS INDICATED.
19.

DITCHING AND BACK FILL: CONTRACTOR SHALL PROVIDE FOR ALL UNDERGROUND INSTALLED CONDUIT AND/OR CABLES INCLUDING EXCAVATION AND BACKFILLING AND COMPACTION. REFER TO NOTES AND REQUIREMENTS 'EXCAVATION, AND BACKFILLING.
20.

MATERIALS, PRODUCTS AND EQUIPMENT, INCLUDING ALL COMPONENTS THEREOF, SHALL BE NEW AND SHALL APPEAR ON THE LIST OF U.L. APPROVED ITEMS AND SHALL MEET OR EXCEED THE REQUIREMENTS OF THE NEC, NEMA AND IECE.
21.

CONTRACTOR SHALL SUBMIT SHOP DRAWINGS OR MANUFACTURES CATALOG INFORMATION OF ANY/ALL LIGHTING FIXTURES, SWITCHES AND ALL OTHER ELECTRICAL ITEMS FOR APPROVAL BY THE CONSTRUCTION MANAGER PRIOR TO INSTALLATION.
22.

ANY CUTTING OR PATCHING DEEMED NECESSARY FOR ELECTRICAL WORK IS THE ELECTRICAL CONTRACTORS RESPONSIBILITY AND SHALL BE INCLUDED IN THE COST FOR WORK AND PERFORMED TO THE SATISFACTION OF THE 'CONSTRUCTION MANAGER' UPON FINAL ACCEPTANCE.
23.

THE ELECTRICAL CONTRACTOR SHALL LABEL ALL PANELS WITH ONLY TYPEWRITTEN DIRECTORIES. ALL ELECTRICAL WIRING SHALL BE THE RESPONSIBILITY OF THE ELECTRICAL CONTRACTOR.
24.

DISCONNECT SWITCHES SHALL BE H.P. RATED HEAVY-DUTY, QUICK-MAKE AND QUICK-BREAK ENCLOSURES, AS REQUIRED BY EXPOSURE TYPE.
25.

ALL CONNECTIONS SHALL BE MADE WITH A PROTECTIVE COATING OF AN ANTI-OXIDE COMPOUND SUCH AS "NO-OXIDE A" BY DEARBORNE CHEMICAL CO. COAT ALL WIRE SURFACES BEFORE CONNECTING. EXPOSED COPPER SURFACES, INCLUDING GROUND BARS, SHALL BE TREATED - NO SUBSTITUTIONS.
26.

RACEWAYS: CONDUIT SHALL BE SCHEDULE 40 PVC MEETING OR EXCEEDING NEMA TC2 - 1990. CONTRACTOR SHALL PLUG AND CAP EACH END OF SPARE AND EMPTY CONDUITS AND PROVIDE TWO SEPARATE PULL STRINGS - 200 LBS TEST POLYETHYLENE CORD. ALL CONDUIT BENDS SHALL BE A MINIMUM OF 2 FT. RADIUS. RGS CONDUITS WHEN SPECIFIED, SHALL MEET UL-6 FOR GALVANIZED STEEL. ALL FITTINGS SHALL BE SUITABLE FOR USE WITH THREADED RIGID CONDUIT. COAT ALL THREADS WITH 'BRITE ZINC' OR 'GOLD GALV'.
27.

SUPPORT OF ALL ELECTRICAL WORK SHALL BE AS REQUIRED BY NEC.

28.

CONDUCTORS: CONTRACTOR SHALL USE 98% CONDUCTIVITY COPPER WITH TYPE THWN INSULATION, 800 VOLT, COLOR CODED. USE SOLID CONDUCTORS FOR WIRE UP TO AND INCLUDING NO. 8 AWG. USE STRANDED CONDUCTORS FOR WIRE ABOVE NO. 8 AWG.
29.

CONNECTORS FOR POWER CONDUCTORS: CONTRACTOR SHALL USE PRESSURE TYPE INSULATED TWIST-ON CONNECTORS FOR NO. 10 AWG AND SMALLER. USE SOLDERLESS MECHANICAL TERMINAL LUGS FOR NO. 8 AWG AND LARGER.
30.

SERVICE: 240/120V, SINGLE PHASE, 3 WIRE CONNECTION AVAILABLE FROM UTILITY COMPANY. OWNER OR OWNERS AGENT WILL APPLY FOR POWER.
31.

TELEPHONE SERVICE: CONTRACTOR SHALL PROVIDE EMPTY CONDUITS WITH PULL STRINGS AS INDICATED ON DRAWINGS.
32.

ELECTRICAL AND TELCO RACEWAYS TO BE BURIED A MINIMUM OF 2' DEPTH.
33.

CONTRACTOR SHALL PLACE TWO LENGTHS OF WARNING TAPE AT A DEPTH OF 12" BELOW GROUND AND DIRECTLY ABOVE ELECTRICAL AND TELCO SERVICE CONDUITS. CAUTIONS TAPE TO READ "CAUTION BURIED ELECTRIC" OR "BURIED TELECOMM".
34.

ALL BOLTS SHALL BE STAINLESS STEEL

GROUNDING NOTES

1.

COMPRESSION CONNECTIONS (2), 2 AWG BARE TINNED SOLID COPPER CONDUCTORS TO GROUNDING BAR. ROUTE CONDUCTORS TO BURIED GROUNDING RING AND PROVIDE PARALLEL EXOTHERMIC WELD.
2.

EC SHALL USE PERMANENT MARKER TO DRAW THE LINES BETWEEN EACH SECTION AND LABEL EACH SECTION ("P", "A", "N", "I") WITH 1" HIGH LETTERS.
3.

ALL HARDWARE 18-8 STAINLESS STEEL, INCLUDING LOCK WASHERS, COAT ALL SURFACES WITH AN ANTI-OXIDANT COMPOUND BEFORE MATING. ALL HARDWARE SHALL BE STAINLESS STEEL 3/8 INCH DIAMETER OR LARGER.
4.

FOR GROUND BOND TO STEEL ONLY: INSERT A CADMIUM FLAT WASHER BETWEEN LUG AND STEEL, COAT ALL SURFACES WITH AN ANTI-OXIDANT COMPOUND BEFORE MATING.
5.

NUT & WASHER SHALL BE PLACED ON THE FRONT SIDE OF THE GROUNDING BAR AND BOLTED ON THE BACK SIDE.
6.

NUMBER OF GROUNDING BARS MAY VARY DEPENDING ON THE TYPE OF TOWER, ANTENNA LOCATION, AND CONNECTION ORIENTATION. PROVIDE AS REQUIRED.
7.

WHEN THE SCOPE OF WORK REQUIRES THE ADDITION OF A GROUNDING BAR TO AN EXISTING TOWER,THE SUBCONTRACTOR SHALL OBTAIN APPROVAL FROM THE TOWER OWNER PRIOR TO MOUNTING THE GROUNDING BAR TO THE TOWER.
8.

ALL ELECTRICAL AND GROUNDING AT THE CELL SITE SHALL COMPLY WITH THE NATIONAL ELECTRICAL CODE (NEC), NATIONAL FIRE PROTECTION ASSOCIATION (NFFA) 780 (LATEST EDITION), AND MANUFACTURER.

ADDITIONAL NOTES:

9.

ALL DETAILS ARE SHOWN IN GENERAL TERMS. ACTUAL GROUNDING INSTALLATION AND CONSTRUCTION MAY VARY DUE TO SITE SPECIFIC CONDITIONS.
10.

GROUND ALL ANTENNA BASES, FRAMES, CABLE RUNS, AND OTHER METALLIC COMPONENTS USING #2 GROUND WIRES AND CONNECT TO SURFACE MOUNTED GROUND BUS BARS AS SHOWN. FOLLOW ANTENNA AND BTS MANUFACTURER'S PRACTICES FOR GROUNDING REQUIREMENTS. GROUND COAX SHIELD AT BOTH ENDS USING MANUFACTURERS PRACTICES. ALL UNDERGROUND WATER PIPES, METAL CONDUITS AND GROUNDS THAT ARE A PART OF THIS SYSTEM SHALL BE BONDED TOGETHER.
11.

ALL GROUND CONNECTIONS SHALL BE #2 AWG U.N.O. ALL WIRES SHALL BE COPPER THHN/THWN. ALL GROUND WIRE SHALL BE SOLID TIN COATED OR STRANDED GREEN INSULATED WIRE.
12.

CONTRACTOR TO VERIFY AND TEST GROUND TO SOURCE, 5 OHMS MAXIMUM. PROVIDE SUPPLEMENT GROUNDING RODS AS REQUIRED TO ACHIEVE SPECIFIED OHMS READING. GROUNDING AND OTHER OPTIONAL TESTING WILL BE WITNESSED BY THE VERIZON REPRESENTATIVE.
13.

NOTIFY ARCHITECT/ENGINEER IF THERE ARE ANY DIFFICULTIES INSTALLING GROUNDING SYSTEM DUE TO SITE SOIL CONDITIONS.
14.

BARE GROUNDING CONDUCTOR SHALL BE HARD DRAWN TINNED COPPER SIZES AS NOTED ON PLAN.
15.

ALL HORIZONTALLY RUN GROUNDING CONDUCTORS SHALL BE INSTALLED MINIMUM 12" BELOW GRADE/FROST-LINE IN TRENCH, U.N.O., AND BACK FILL SHALL BE COMPACTED AS REQUIRED BY ARCHITECT.
16.

ALL GROUND CONDUCTORS SHALL BE RUN AS STRAIGHT AND SHORT AS POSSIBLE, WITH A MINIMUM 12" BENDING RADIUS NOT LESS THAN 90 DEGREES.
17.

ALL SUPPORT STRUCTURES, CABLE CHANNEL WAYS OR WIRE GUIDES SHALL BE BONDED TO GROUND SYSTEM AT A POINT NEAREST THE MAIN GROUNDING BUS "MGB" (OR DIRECTLY TO GROUND-RING).
18.

ACCEPTABLE CONNECTIONS FOR GROUNDING SYSTEM SHALL BE:
a. BURNDY, HY-GRADE U.L. LISTED CONNECTORS FOR INDOOR USE OR AS APPROVED BY VERIZON PROJECT MANAGER.
b. CADWELD, EXOTHERMIC WELDS (WELDED CONNECTIONS).
c. TWO -(2) HOLE TINNED COPPER COMPRESSION (LONG BARREL) FITTINGS (BUS BAR CONNECTIONS).
19.

ALL CRIMPED CONNECTIONS SHALL HAVE EMBOSSED MANUFACTURER'S DIEMARK VISIBLE AT THE CRIMP (RESULTING FROM USE OF PROPER CRIMPING DEVICES).
20.

PRIOR TO ANY LUG-BUSSBAR CONNECTIONS, THE BUSSBAR SHALL BE CLEANED BY USE OF 'SCOTCH-BRITE' OR PLAIN STEEL WOOL AS TO REMOVE ALL SURFACE OXIDATION AND CONTAMINANTS. A COATING OF 'NO-OX-ID' SHALL BE APPLIED TO THE CONNECTION SURFACES.
21.

ALL CONNECTION HARDWARE SHALL BE TYPE 316 SS (NOT ATTRACTED TO MAGNETS).
22.

THE GROUND RING SHALL BE INSTALLED 24" MINIMUM BEYOND ANY BUILDING DRIP LINE.
23.

ELECTRICAL SERVICE EQUIPMENT GROUNDING SHALL COMPLY WITH NEC, ARTICLE 250-82 AND SHALL BOND ALL EXISTING AND NEW GROUNDING ELECTRODES. NEW GROUNDING ELECTRODE SHALL INCLUDE BUT NOT LIMITED TO GROUND RODS, GROUND RING IF SERVICE IS WITHIN THE RADIO EQUIPMENT LOCATION, BUILDING STEEL IF APPLICABLE, COLD WATER CONNECTIONS MUST BE MADE ON THE STREET SIDE OF MAIN SHUT-OFF VALVE.

verizon

2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

Vinculum

575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500

ALL STATES

ENGINEERING & SURVEYING

23675 BIRTCHER DRIVE
LAKE FOREST, CA 92630

PROJECT ID:		TBD	
DRAWN BY:		RF	
CHECKED BY:		DW	
2	09/10/2020	100% CD'S FOR SUBMITTAL	MG
1	06/11/2020	100% CD'S FOR SUBMITTAL	RF
0	05/22/2020	100% CD'S FOR APPROVAL	RF
B	05/04/2020	95% CD'S FOR REDLINE	RF
A	04/14/2020	90% CD'S FOR REDLINE	RF
REV	DATE	DESCRIPTION	

REGISTERED PROFESSIONAL ENGINEER

WISSAM ZALZALI

71655

CIVIL

STATE OF CALIFORNIA

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 203

PUBLIC R.O.W. ADJACENT TO:

519 WEBSTER STREET

PALO ALTO, 94301

LOCATION CODE: 566802

SHEET TITLE

GENERAL NOTES

SHEET NUMBER

GN-2

NOTE:
ANY CONSTRUCTION WITHIN THE CITY'S
PUBLIC ROAD RIGHT-OF-WAY SHALL
HAVE AN APPROVED PERMIT FOR
CONSTRUCTION IN THE PUBLIC STREET
PRIOR TO COMMENCEMENT OF THIS WORK

City of Palo Alto
Tree Protection - It's Part of the Plan!

Make sure your crews and subs do the job right!

Fenced enclosures around trees are essential to protect them by keeping the foliage canopy and branching structure clear from contact by equipment, materials and activities, preserving roots and soil conditions in an intact and non-compacted state, and identifying the Tree Protection Zone (TPZ) in which no soil disturbance is permitted and activities are restricted, unless otherwise approved. **An approved tree protection report must be added to this sheet when project activity occurs within the TPZ of a regulated tree.** For detailed information on Palo Alto's regulated trees and protection during development, review the **City Tree Technical Manual (TTM)** found at www.cityofpaloalto.org/trees/.

For written specifications associated with illustrations below, see Public Works Specifications Section 31

Detailed specifications are found in the Palo Alto Tree Technical Manual (TTM) (www.cityofpaloalto.org/trees/)

Tree Protection Zone (TPZ) shown in gray *includes* all TPZ-related elements shown on this form. *See* (1) TTM, subsection 2.1 (a)(1); (2) TTM, subsection 2.1 (a)(2); (3) TTM, subsection 2.1 (a)(3); (4) TTM, subsection 2.1 (a)(4); (5) TTM, subsection 2.1 (a)(5); (6) TTM, subsection 2.1 (a)(6); (7) TTM, subsection 2.1 (a)(7); (8) TTM, subsection 2.1 (a)(8); (9) TTM, subsection 2.1 (a)(9); (10) TTM, subsection 2.1 (a)(10); (11) TTM, subsection 2.1 (a)(11); (12) TTM, subsection 2.1 (a)(12); (13) TTM, subsection 2.1 (a)(13); (14) TTM, subsection 2.1 (a)(14); (15) TTM, subsection 2.1 (a)(15); (16) TTM, subsection 2.1 (a)(16); (17) TTM, subsection 2.1 (a)(17); (18) TTM, subsection 2.1 (a)(18); (19) TTM, subsection 2.1 (a)(19); (20) TTM, subsection 2.1 (a)(20); (21) TTM, subsection 2.1 (a)(21); (22) TTM, subsection 2.1 (a)(22); (23) TTM, subsection 2.1 (a)(23); (24) TTM, subsection 2.1 (a)(24); (25) TTM, subsection 2.1 (a)(25); (26) TTM, subsection 2.1 (a)(26); (27) TTM, subsection 2.1 (a)(27); (28) TTM, subsection 2.1 (a)(28); (29) TTM, subsection 2.1 (a)(29); (30) TTM, subsection 2.1 (a)(30); (31) TTM, subsection 2.1 (a)(31); (32) TTM, subsection 2.1 (a)(32); (33) TTM, subsection 2.1 (a)(33); (34) TTM, subsection 2.1 (a)(34); (35) TTM, subsection 2.1 (a)(35); (36) TTM, subsection 2.1 (a)(36); (37) TTM, subsection 2.1 (a)(37); (38) TTM, subsection 2.1 (a)(38); (39) TTM, subsection 2.1 (a)(39); (40) TTM, subsection 2.1 (a)(40); (41) TTM, subsection 2.1 (a)(41); (42) TTM, subsection 2.1 (a)(42); (43) TTM, subsection 2.1 (a)(43); (44) TTM, subsection 2.1 (a)(44); (45) TTM, subsection 2.1 (a)(45); (46) TTM, subsection 2.1 (a)(46); (47) TTM, subsection 2.1 (a)(47); (48) TTM, subsection 2.1 (a)(48); (49) TTM, subsection 2.1 (a)(49); (50) TTM, subsection 2.1 (a)(50); (51) TTM, subsection 2.1 (a)(51); (52) TTM, subsection 2.1 (a)(52); (53) TTM, subsection 2.1 (a)(53); (54) TTM, subsection 2.1 (a)(54); (55) TTM, subsection 2.1 (a)(55); (56) TTM, subsection 2.1 (a)(56); (57) TTM, subsection 2.1 (a)(57); (58) TTM, subsection 2.1 (a)(58); (59) TTM, subsection 2.1 (a)(59); (60) TTM, subsection 2.1 (a)(60); (61) TTM, subsection 2.1 (a)(61); (62) TTM, subsection 2.1 (a)(62); (63) TTM, subsection 2.1 (a)(63); (64) TTM, subsection 2.1 (a)(64); (65) TTM, subsection 2.1 (a)(65); (66) TTM, subsection 2.1 (a)(66); (67) TTM, subsection 2.1 (a)(67); (68) TTM, subsection 2.1 (a)(68); (69) TTM, subsection 2.1 (a)(69); (70) TTM, subsection 2.1 (a)(70); (71) TTM, subsection 2.1 (a)(71); (72) TTM, subsection 2.1 (a)(72); (73) TTM, subsection 2.1 (a)(73); (74) TTM, subsection 2.1 (a)(74); (75) TTM, subsection 2.1 (a)(75); (76) TTM, subsection 2.1 (a)(76); (77) TTM, subsection 2.1 (a)(77); (78) TTM, subsection 2.1 (a)(78); (79) TTM, subsection 2.1 (a)(79); (80) TTM, subsection 2.1 (a)(80); (81) TTM, subsection 2.1 (a)(81); (82) TTM, subsection 2.1 (a)(82); (83) TTM, subsection 2.1 (a)(83); (84) TTM, subsection 2.1 (a)(84); (85) TTM, subsection 2.1 (a)(85); (86) TTM, subsection 2.1 (a)(86); (87) TTM, subsection 2.1 (a)(87); (88) TTM, subsection 2.1 (a)(88); (89) TTM, subsection 2.1 (a)(89); (90) TTM, subsection 2.1 (a)(90); (91) TTM, subsection 2.1 (a)(91); (92) TTM, subsection 2.1 (a)(92); (93) TTM, subsection 2.1 (a)(93); (94) TTM, subsection 2.1 (a)(94); (95) TTM, subsection 2.1 (a)(95); (96) TTM, subsection 2.1 (a)(96); (97) TTM, subsection 2.1 (a)(97); (98) TTM, subsection 2.1 (a)(98); (99) TTM, subsection 2.1 (a)(99); (100) TTM, subsection 2.1 (a)(100); (101) TTM, subsection 2.1 (a)(101); (102) TTM, subsection 2.1 (a)(102); (103) TTM, subsection 2.1 (a)(103); (104) TTM, subsection 2.1 (a)(104); (105) TTM, subsection 2.1 (a)(105); (106) TTM, subsection 2.1 (a)(106); (107) TTM, subsection 2.1 (a)(107); (108) TTM, subsection 2.1 (a)(108); (109) TTM, subsection 2.1 (a)(109); (110) TTM, subsection 2.1 (a)(110); (111) TTM, subsection 2.1 (a)(111); (112) TTM, subsection 2.1 (a)(112); (113) TTM, subsection 2.1 (a)(113); (114) TTM, subsection 2.1 (a)(114); (115) TTM, subsection 2.1 (a)(115); (116) TTM, subsection 2.1 (a)(116); (117) TTM, subsection 2.1 (a)(117); (118) TTM, subsection 2.1 (a)(118); (119) TTM, subsection 2.1 (a)(119); (120) TTM, subsection 2.1 (a)(120); (121) TTM, subsection 2.1 (a)(121); (122) TTM, subsection 2.1 (a)(122); (123) TTM, subsection 2.1 (a)(123); (124) TTM, subsection 2.1 (a)(124); (125) TTM, subsection 2.1 (a)(125); (126) TTM, subsection 2.1 (a)(126); (127) TTM, subsection 2.1 (a)(127); (128) TTM, subsection 2.1 (a)(128); (129) TTM, subsection 2.1 (a)(129); (130) TTM, subsection 2.1 (a)(130); (131) TTM, subsection 2.1 (a)(131); (132) TTM, subsection 2.1 (a)(132); (133) TTM, subsection 2.1 (a)(133); (134) TTM, subsection 2.1 (a)(134); (135) TTM, subsection 2.1 (a)(135); (136) TTM, subsection 2.1 (a)(136); (137) TTM, subsection 2.1 (a)(137); (138) TTM, subsection 2.1 (a)(138); (139) TTM, subsection 2.1 (a)(139); (140) TTM, subsection 2.1 (a)(140); (141) TTM, subsection 2.1 (a)(141); (142) TTM, subsection 2.1 (a)(142); (143) TTM, subsection 2.1 (a)(143); (144) TTM, subsection 2.1 (a)(144); (145) TTM, subsection 2.1 (a)(145); (146) TTM, subsection 2.1 (a)(146); (147) TTM, subsection 2.1 (a)(147); (148) TTM, subsection 2.1 (a)(148); (149) TTM, subsection 2.1 (a)(149); (150) TTM, subsection 2.1 (a)(150); (151) TTM, subsection 2.1 (a)(151); (152) TTM, subsection 2.1 (a)(152); (153) TTM, subsection 2.1 (a)(153); (154) TTM, subsection 2.1 (a)(154); (155) TTM, subsection 2.1 (a)(155); (156) TTM, subsection 2.1 (a)(156); (157) TTM, subsection 2.1 (a)(157); (158) TTM, subsection 2.1 (a)(158); (159) TTM, subsection 2.1 (a)(159); (160) TTM, subsection 2.1 (a)(160); (161) TTM, subsection 2.1 (a)(161); (162) TTM, subsection 2.1 (a)(162); (163) TTM, subsection 2.1 (a)(163); (164) TTM, subsection 2.1 (a)(164); (165) TTM, subsection 2.1 (a)(165); (166) TTM, subsection 2.1 (a)(166); (167) TTM, subsection 2.1 (a)(167); (168) TTM, subsection 2.1 (a)(168); (169) TTM, subsection 2.1 (a)(169); (170) TTM, subsection 2.1 (a)(170); (171) TTM, subsection 2.1 (a)(171); (172) TTM, subsection 2.1 (a)(172); (173) TTM, subsection 2.1 (a)(173); (174) TTM, subsection 2.1 (a)(174); (175) TTM, subsection 2.1 (a)(175); (176) TTM, subsection 2.1 (a)(176); (177) TTM, subsection 2.1 (a)(177); (178) TTM, subsection 2.1 (a)(178); (179) TTM, subsection 2.1 (a)(179); (180) TTM, subsection 2.1 (a)(180); (181) TTM, subsection 2.1 (a)(181); (182) TTM, subsection 2.1 (a)(182); (183) TTM, subsection 2.1 (a)(183); (184) TTM, subsection 2.1 (a)(184); (185) TTM, subsection 2.1 (a)(185); (186) TTM, subsection 2.1 (a)(186); (187) TTM, subsection 2.1 (a)(187); (188) TTM, subsection 2.1 (a)(188); (189) TTM, subsection 2.1 (a)(189); (190) TTM, subsection 2.1 (a)(190); (191) TTM, subsection 2.1 (a)(191); (192) TTM, subsection 2.1 (a)(192); (193) TTM, subsection 2.1 (a)(193); (194) TTM, subsection 2.1 (a)(194); (195) TTM, subsection 2.1 (a)(195); (196) TTM, subsection 2.1 (a)(196); (197) TTM, subsection 2.1 (a)(197); (198) TTM, subsection 2.1 (a)(198); (199) TTM, subsection 2.1 (a)(199); (200) TTM, subsection 2.1 (a)(200); (201) TTM, subsection 2.1 (a)(201); (202) TTM, subsection 2.1 (a)(202); (203) TTM, subsection 2.1 (a)(203); (204) TTM, subsection 2.1 (a

Table 2-2 Palo Alto Tree Technical Manual

CONTRACTOR & ARBORIST INSPECTION SCHEDULE

Reference: the Palo Alto Tree Technical Manual is available at www.cityofpaloalto.org/environment

ALL CHECKED ITEMS APPLY TO THIS PROJECT:

1. ☒ **Inspection of Protective Tree Fencing.** For Public Trees, the Street Tree Verification Form shall be signed by the City Arborist. For Protected Trees, the project site arborist shall provide an initial Monthly Tree Activity Report form with a photograph verifying that he has conducted a field inspection of the trees and that the correct type of protective fencing is in place around the designated tree protection zone (TPZ) prior to issuance of a demolition, grading, or building permit. (See TTM, Verification of Tree Protection, Section 1.39).
2. ☒ **Pre-Construction Meeting.** Prior to commencement of construction, the applicant or contractor shall conduct a pre-construction meeting to discuss tree protection with the job site superintendent, grading operator, project site arborist, City Arborist, and, if a city maintained irrigation system is involved, the Parks Manager. (Council 650 496 696C).
3. ☒ **Inspection of Rough Grading or Trenching.** Contractor shall ensure the project site arborist performs an inspection during the course of rough grading or trenching adjacent to or within the TPZ to ensure trees will not be injured by compaction, cut or fill, damage and trenching, and if required, install aeration systems, soil wells, drains and special paving. The contractor shall provide the project arborist at least 24 hours advance notice of such activity.
4. ☒ **Monthly Tree Activity Report Inspections.** The project site arborist shall perform a minimum monthly activity inspection to monitor and advise on conditions, tree health and retention or, immediately if there are any revisions to the approved plans or protection measures. The Tree Technical Manual Monthly Tree Activity Report format shall be used and sent to the Planning Dept. landscape review staff no later than 14 days after issuance of building permit date. Fax to: (650) 329-3154. (See TTM, Monthly Tree Activity Inspection Report, Addendum 11 & version 1.17).
5. ☒ **Special activity within the Tree Protection Zone.** Work in the TPZ area (see also #7 below) requires the direct onsite supervision of the project arborist (see TTM, Trenching, Excavation & Equipment, Section 2.20 C).
6. ☐ **Landscape Architect Inspection.** For discretionary development projects, prior to temporary or final occupancy the applicant or contractor shall arrange for the Landscape Architect to perform an on site inspection of all plant stock, quality of the materials and planting (see TTM, Planting Quality, Section 5.20.1 A) and that the vegetation is functioning consistent with the approved construction plans. The Planning Dept. Landscape review staff shall be in receipt of written verification of Landscape Architect approval prior to scheduling the final inspection, unless otherwise approved.
7. ☐ **List Other (please describe as called out in the site Tree Preservation Report, Sheet T-1, T-2, etc.)**

Arborist Firm Data Here:

City of Palo Alto Tree Technical Manual

ADDENDUM 11

CPA/PA Certified Arborist FIRM
Customer: _____

Monthly Tree Activity Report- Construction Site

Inspection Date:	Site address:	Contractor- Main Site Contact Information	#1 Job site Superintendent Company Email Job site Office Cell Mail
Inspection #	Palo Alto, CA		
		Also present:	_____
Distribution:	1 City of Palo Alto	Attn: Dave Quisenberry	dave.quisenberry@cityofpaloalto.org 650.329.2449
	2 - Others		

Provide the requested minimum information with each report, verbiage as necessary. To be completed by project site arboret. Send monthly to city arborist at above address until project completion. Use additional sheet as needed.

- Assignment Activity (Demolition-grading-groves-trenching-foundation-list relevant vests)
 - Pre-construction meeting requirement with sub-contractors
 - Attempt to verify that tree protection measures are in place
 - Determine if field adjustments, watering or plan revisions may be needed.
- Field Observations (general site-wide and list by individual tree number)
 - Tree Protection Fences (TPF) are _____
 - Trenching has/will occur _____
- Action Items (list site-wide, by tree number and date to be satisfied) and Done Due
 - Tree Protection Fence (TPF) needs adjusting (tree # x, y)
 - Root zone buffer material (wood chips) can be installed next
 - Schedule sewer trench foundation dig with _____
- Photographs (use often)
- Tree Location Map (mandatorv 8.5 x 11 sheet)
- Recommendation: notes or monitor items for project staff/schedule
 - _____
- Past visits (list carry-over items satisfied/still outstanding)
 - _____

Respectfully submitted,

Project site arboret
 Communicate contact information (include email, cell#, and mailing).
 /s/ _____

Enter Date _____

CPA Monthly Tree Activity Report- Type site address here _____

Page #1 of 1

APPENDIX J

**PALO ALTO
STREET TREE PROTECTION INSTRUCTIONS
—SECTION 31—**

I-II-F General:

- A.** Tree protection has three primary functions, (1) to keep the bridge canopy and branching structure clear from contact by equipment, materials and activities; (2) to preserve trees and land conditions on an owner's undisturbed site and (3) to identify the Tree Protection Zone (TPZ) in which no work shall be conducted or permitted and activities are restricted, unless otherwise approved.
- B.** The Tree Protection Zone (TPZ) is a circular area around the base of the tree with a radius of two times its diameter or the trunk's lean to its feet, whichever is greater, overlaid by lines.

I-II-G References/Citations:

- A.** Detail 805 – Illustration of situations described below
- B.** **Tree Technical Manual (TTM) Form (<http://www.ci.paloalto.ca.gov/Information/Forms.aspx>)**
 1. Trimming Instructions form (<http://www.ci.paloalto.ca.gov/Information/Forms.aspx>)
 2. Surface Grading Permit (<http://www.ci.paloalto.ca.gov/Information/Forms.aspx>)
 3. Site Plan Requirements (<http://www.ci.paloalto.ca.gov/Information/Forms.aspx>)
 4. Tree Disclosure Statement (<http://www.ci.paloalto.ca.gov/Information/Forms.aspx>)
 5. Street Tree Verification (STV) Form (<http://www.ci.paloalto.ca.gov/Information/Forms.aspx>)
- C.** Street Tree Verification (STV) Form (<http://www.ci.paloalto.ca.gov/Information/Forms.aspx>)

I-II-A Evidences:

- A.** **Type I Free Protection:** The fence shall enclose the entire TPZ of the street to be protected throughout the life of the construction project. In some parking areas, if funding is limited or paving is imminent that will be discontinued, then the post may be supported by an appropriate grade level concrete ring, if approved by Public Works Department.
- B.** **Type II Free Protection:** For trees situated within a planting strip, open the planting strip and yard side of the TPZ shall be enclosed with the required chain link protective fencing in order to keep the sidewalk and street open for public use.
- C.** **Type III Tree Protection:** To be used only with approval in Public Works Department. Trees situated on a corner lot will be sidewalk planter pits, shall be wrapped with 2 inches of orange plastic fencing from the ground to the first branch and overlaid with 2-inch black wooden slats bound vertically (slats shall not be allowed to dig into the bark). During installation of the plastic fencing, caution shall be used to avoid damaging any bushes. Many leaks may also contain plastic debris as directed by the City Arborist.
- D.** **Size, type and area to be fenced.** All trees to be preserved shall be protected with six (6") foot high chain link fences. Fences are to be mounted on two-inch diameter galvanized iron posts, driven into the ground to a depth of at least 24-inches or deeper than 10-foot spacing. Fencing shall extend to the outer branching, unless specifically approved on the STV Form.
- E.** **"Warning" signs.** A warning sign shall be weather proof and prominently displayed on each fence at 20-foot intervals. The sign shall be minimum 8.5-inches x 11-inches and clearly state in bold face all letters: "WARNING - Tree Protection Zone - This space shall not be removed and is subject to fine according to PAMC Section 8.10110".
- F.** **Duration.** Tree fencing shall be covered before beginning grading or construction begins and remain in place until final completion of the project, except for work specifically authorized by the TPZ. Work on and disturbance to the TPZ requires approval by the project arboretor as City Arborists file the case work annual Street Tree Log.

I-II-B Encroachment

The violation within the public right of way require a Street Work Permit from Public Works.

- A.** All neighboring trees that overlapping the project site shall be protected from impact of any kind.
- B.** The applicant shall be responsible for the repair or replacement plus penalty of any publicly owned trees that are damaged during the course of construction, pursuant to Section 8.A.070 of the Palo Alto Municipal Code.
- C.** The following tree removal statement applies ("no tolerance for removal")
 - a. No removal of mature, legally established or designated trees is permitted within the TPZ.
 - b. The ground under and around the tree canopy shall not be altered.
 - c. Trees in or adjacent shall be irrigated, sustained and maintained as necessary to ensure survival.

END OF SECTION

City of Palo Alto 2003 Standard Documents and Specifications
Street Tree Verification Procedure, FWJ, Section 31

Revised 08/06

	City of Palo Alto Tree Department Public Works Operations PO Box 10229 Palo Alto, CA 94303 650/995-0953 FAX: 650/995-0700 treeprotection@CityOfPaloAlto.org	<h2 style="text-align: center;">Verification of Street Tree Protection</h2>
<p>Applicant Instructions: Complete upper portion of this form. Mail or FAX this form along with signed Tree Disclosure Statement to Public Works Dept. Public Works Tree Staff will inspect and notify applicant.</p>		
<p>APPLICATION RATE:</p>		
<p>ADDRESS/LOCATION OF STREET TREES TO BE PROTECTED:</p>		
<p>APPLICANT'S NAME:</p>		
<p>APPLICANT'S ADDRESS:</p>		
<p>APPLICANT'S TELEPHONE & FAX NUMBERS:</p>		
<p><i>This section to be filled out by City Tree Staff</i></p>		
<p>1. The Street Trees at the above address are adequately protected. The type of protection used is:</p>	<p>YES <input type="checkbox"/></p>	<p>NO <input type="checkbox"/></p> <p><i>if NO, go to #2 below</i></p>
<p>Inspected by:</p> <p>Date of Inspection:</p>		
<p>2. The Street Trees at the above address are NOT adequately protected. The following modifications are required:</p> <p>Indicate how the required modifications were communicated to the applicant:</p>	<div style="border: 1px solid black; height: 100px;"></div>	
<p>Subsequent Inspection</p>		
<p>Street trees at above address were found to be adequately protected:</p>	<p>YES <input type="checkbox"/></p>	<p>NO <input type="checkbox"/></p>
<p><i>* If NO, indicate in "Notes" below the disposition of case.</i></p>		
<p>Inspected by:</p>		
<p>Date of Inspection:</p>		
<p>Notes: List City street trees by species, size, condition and type of tree protection installed. Also note if pictures were taken. Use back of sheet if necessary.</p>		
<p>Return approved sheet to Applicant for demolition or building permit issuance.</p>		

---WARNING---

Tree Protection Zone

This fencing shall not be removed without City Arborist approval (650-496-5953)

Removal without permission is subject to a \$500 fine per day*

****Palo Alto Municipal Code Section 8.10.110***

City of Palo Alto Tree Protection Instructions are located at <http://www.city.palo-alto.ca.us/tree-technical-manual>

SPECIAL INSPECTIONS	PLANNING DEPARTMENT
TREE PROTECTION INSPECTIONS MANDATORY	
<p>PAMC 8.10.110 PROTECTED TREES: CONTRACTOR SHALL ENSURE PROJECT SITE ARBORIST IS PERFORMING REQUIRED TREE INSPECTION AND SITE MONITORING. PROVIDE WRITTEN MONTHLY TREE ACTIVITY REPORTS TO THE PLANNING DEPARTMENT LANDSCAPE REVIEW STAFF BEGINNING 14 DAYS AFTER BUILDING PERMIT ISSUANCE.</p>	
<p>BUILDING PERMIT DATE: _____</p>	
<p>DATE OF 1st TREE ACTIVITY REPORT: _____</p>	
<p>CITY STAFF: _____</p>	
<p>REPORTING DETAILS OF THE MONTHLY TREE ACTIVITY REPORT SHALL CONFORM TO SHEET T-1 FORM. VERIFY THAT ALL TREE PROTECTION MEASURES ARE IMPLEMENTED AND WILL INCLUDE ALL CONTRACTOR ACTIVITY, SCHEDULED OR UNSCHEDULED, WITHIN A TREE PROTECTION ROOT ZONE. NON-COMPLIANCE IS SUBJECT TO VIOLATION OF PAMC 8.10.110.B. REFERENCE: PALO ALTO TREE TECHNICAL MANUAL SECTION 2.00 AND ADDENDUM A.1.</p>	

Apply Tree Protection Report on sheet(s) T-2

Use additional "T" sheets as needed

City of Palo Alto

250 Hamilton Avenue, Palo Alto, CA 94301




Search:

Home > Planning & Community Environment

Advanced

Browse By Topic



Home

City Council / Board

Privately-owned Trees

About the Tree Ordinance

Tree x 10

Heritage Trees

Forms

Tree Technical Manual

FAQs

Contact Us

Resources

Tree Technical Manual

To purchase the Tree Technical Manual

June, 2001 First Edition

View this version:

- Table of Contents (PDF, 670K)
- Intent and Purpose (PDF, 1.05MB)
- Introduction - Use of Manual (PDF, 1.05MB)
- Section 1.0 - Definitions (PDF, 369K)
- Section 2.0 - Protection of Trees During Construction (PDF, 259KB)
- Section 3.0 - Removal, Replacement & Planting of Trees (PDF, 117KB)
- Section 4.0 - Hazardous Trees (PDF, 105KB)
- Section 5.0 - Tree Maintenance Guidelines (PDF, 110KB)
- Section 6.0 - Tree Reports (PDF, 844K)

View ALL sections:

- Tree Technical Manual - Full (PDF, 1.844K)

APPENDICES

- A. Palo Alto Municipal Code Chapter 8.10, Tree Preservation & Management Regulations
- B. Tree City - USA
- C. ISA Hazard Evaluation Form
- D. List of Inherent Failure Patterns for Selected Species (Reference source)
- E. ISA Tree Pruning Guidelines (PDF, 1.85MB)
- F. Tree Care Safety Standards, ANSI Z39.1-1994 (Reference source)
- G. Pruning Performance Standard, ANSI A300-1995 (Reference source) H.
- I. Tree Planting Details, Diagram 504 & 505
- I. Tree Disclosure Statement
- J. Palo Alto Standard Tree Protection Instructions

verizon

2705 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

Vinculums

575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500

ALLSTATES
ENGINEERING & SURVEYING

23675 BIRTCHER DRIVE
LAKE FOREST, CA 92630

[illegible]

SF PALO ALTO 203
PUBLIC R.O.W. ADJACENT TO:
519 WEBSTER STREET
PALO ALTO, 94301
LOCATION CODE: 566802

SHEET TITLE
PALO ALTO TREE
PROTECTION

SHEET NUMBER
L-1

POLLUTION PREVENTION — IT'S PART OF THE PLAN

Construction projects are required to implement year-round stormwater BMPs, as they apply to your project.

Runoff from streets and other paved areas is a major source of pollution to San Francisco Bay. Construction activities can directly affect the health of the Bay unless contractors and crews plan ahead to keep construction dirt, debris, and other pollutants out of storm drains and local creeks. Following these guidelines will ensure your compliance with City of Palo Alto Ordinance requirements.



MATERIALS & WASTE MANAGEMENT

Non-Hazardous Materials

- ☐ Berm and cover stockpiles of sand, dirt or other construction material with tarps when rain is forecast or when they are not in use.
- ☐ Use (but don't overuse) reclaimed water for dust control.
- ☐ Ensure dust control water doesn't leave site or discharge to storm drains.

Hazardous Materials

- ☐ Label all hazardous materials and hazardous wastes (such as pesticides, paints, thinners, solvents, fuel, oil, and antifreeze) in accordance with city, county, state and federal regulations.
- ☐ Store hazardous materials and wastes in water tight containers, store in appropriate secondary containment, and cover them at the end of every work day or during wet weather or when rain is forecast.
- ☐ Follow manufacturer's application instructions for hazardous materials and do not use more than necessary. Do not apply chemicals outdoors when rain is forecast within 24 hours.
- ☐ Arrange for appropriate disposal of all hazardous wastes.

Waste Management

- ☐ Cover and maintain dumpsters. Check frequently for leaks. Place dumpsters under roofs or cover with tarps or plastic sheeting secured around the outside of the dumpster. A plastic liner is recommended to prevent leaks. Never clean out a dumpster by hosing it down on the construction site.
- ☐ Place portable toilets away from storm drains. Make sure they are in good working order. Check frequently for leaks.
- ☐ Dispose of all wastes and demolition debris properly. Recycle materials and wastes that can be recycled, including solvents, water-based paints, vehicle fluids, broken asphalt and concrete, wood, and cleared vegetation.
- ☐ Dispose of liquid residues from paints, thinners, solvents, glues, and cleaning fluids as hazardous waste.
- ☐ Keep site clear of litter (e.g., lunch items, cigarette butts).
- ☐ Prevent litter from uncovered loads by covering loads that are being transported to and from site.

Construction Entrances and Perimeter

- ☐ Establish and maintain effective perimeter controls and stabilize all construction entrances and exits to sufficiently control erosion and sediment discharges from site and tracking off site.
- ☐ Sweep or vacuum any street tracking immediately and secure sediment source to prevent further tracking. Never hose down streets to clean up tracking.



EQUIPMENT MANAGEMENT & SPILL CONTROL

Maintenance and Parking

- ☐ Designate an area of the construction site, well away from streams or storm drain inlets and fitted with appropriate BMPs, for auto and equipment parking, and storage.
- ☐ Perform major maintenance, repair jobs, and vehicle and equipment washing off site.
- ☐ If refueling or vehicle maintenance must be done onsite, work in a bermed area away from storm drains and over a drip pan or drop cloths big enough to collect fluids. Recycle or dispose of fluids as hazardous waste.
- ☐ If vehicle or equipment cleaning must be done onsite, clean with water only in a bermed area that will not allow rinse water to run into gutters, streets, storm drains, or surface waters.
- ☐ Do not clean vehicle or equipment onsite using soaps, solvents, degreasers, or steam cleaning equipment, and do not use diesel oil to lubricate equipment or parts onsite.

Spill Prevention and Control

- ☐ Keep spill cleanup materials (e.g., rags, absorbents and cat litter) available at the construction site at all times.
- ☐ Maintain all vehicles and heavy equipment. Inspect frequently for and repair leaks. Use drip pans to catch leaks until repairs are made.
- ☐ Clean up leaks, drips and other spills immediately and dispose of cleanup materials properly.
- ☐ Use dry cleanup methods whenever possible (absorbent materials, cat litter and/or rags).
- ☐ Sweep up spilled dry materials immediately. Never attempt to "wash them away" with water, or bury them.
- ☐ Clean up spills on dirt areas by digging up and properly disposing of contaminated soil.
- ☐ Report any hazardous materials spills immediately! Call City of Palo Alto Communications, (650) 329-2413. If the spill poses a significant hazard to human health and safety, property or the environment, you must report it to the State Office of Emergency Services, (800) 852-7550 (24 hours).



EARTHMOVING

Grading and Earthwork

- ☐ Schedule grading and excavation work during dry weather.
- ☐ Stabilize all denuded areas, install and maintain temporary erosion controls (such as erosion control fabric or bonded fiber matrix) until vegetation is established.
- ☐ Remove existing vegetation only when absolutely necessary, plant temporary vegetation for erosion control on slopes or where construction is not immediately planned.
- ☐ Prevent sediment from migrating offsite and protect storm drain inlets, drainage courses and streams by installing and maintaining appropriate BMPs (e.g., silt fences, gravel bags, fiber rolls, temporary swales, etc.).
- ☐ Keep excavated soil on site and transfer it to dump trucks on site, not in the streets.

Contaminated Soils

- ☐ If any of the following conditions are observed, test for contamination and contact the Regional Water Quality Control Board:
 - Unusual soil conditions, discoloration, or odor.
 - Abandoned underground tanks.
 - Abandoned wells.
 - Buried barrels, debris, or trash.
- ☐ If the above conditions are observed, document any signs of potential contamination and clearly mark them so they are not disturbed by construction activities.

Landscaping

- ☐ Protect stockpiled landscaping materials from wind and rain by storing them under tarps all year-round.
- ☐ Stack bagged material on pallets and under cover.
- ☐ Discontinue application of any erodible landscape material within 2 days before a forecast rain event or during wet weather.



CONCRETE MANAGEMENT & DEWATERING

Concrete Management

- ☐ Store both dry and wet materials under cover, protected from rainfall and runoff and away from storm drains or waterways. Store materials off the ground, on pallets. Protect dry materials from wind.
- ☐ Wash down exposed aggregate concrete only when the wash water can (1) flow onto a dirt area; (2) drain onto a bermed surface from which it can be pumped and disposed of properly; or (3) block any storm drain inlets and vacuum washwater from the gutter. If possible, sweep first.
- ☐ Wash out concrete equipment/trucks offsite or in a designated washout area, where the water will flow into a temporary waste pit, and make sure wash water does not leach into the underlying soil. (See CASQA Construction BMP Handbook for properly designed concrete washouts.)

Dewatering

- ☐ Reuse water for dust control, irrigation or another on-site purpose to the greatest extent possible.
- ☐ Be sure to obtain a Permit for Construction in the Public Street from Public Works Engineering before discharging water to a street, gutter, or storm drain. Call the Regional Water Quality Control Plant (RWQCP) at (650) 329-2595 for an inspection prior to commencing discharge. Use filtration or diversion through a basin, tank, or sediment trap as required by the approved dewatering plan. Dewatering is not permitted from October to April.
- ☐ In areas of known contamination, testing is required prior to reuse or discharge of groundwater. Consult with the City inspector to determine what testing to do and to interpret results. Contaminated groundwater must be treated or hauled off-site for proper disposal.



PAVING/ASPHALT WORK

Paving

- ☐ Avoid paving and seal coating in wet weather or when rain is forecast, to prevent materials that have not cured from contacting stormwater runoff.
- ☐ Cover storm drain inlets and manholes when applying seal coat, slurry seal, fog seal, or similar materials.
- ☐ Collect and recycle or appropriately dispose of excess abrasive gravel or sand. Do NOT sweep or wash it into gutters.

Sawcutting & Asphalt/Concrete Removal

- ☐ Protect storm drain inlets during saw cutting.
- ☐ If saw cut slurry enters a catch basin, clean it up immediately.
- ☐ Shovel or vacuum saw cut slurry deposits and remove from the site. When making saw cuts, use as little water as possible. Sweep up, and properly dispose of all residues.



PAINTING & PAINT REMOVAL

Painting Cleanup and Removal

- ☐ Never clean brushes or rinse paint containers into a street, gutter, storm drain, or stream.
- ☐ For water-based paints, paint out brushes to the extent possible, and rinse into a drain that goes to the sanitary sewer. Never pour paint down a storm drain.
- ☐ For oil-based paints, paint out brushes to the extent possible and clean with thinner or solvent in a proper container. Filter and reuse thinners and solvents. Dispose of excess liquids as hazardous waste.
- ☐ Sweep up or collect paint chips and dust from non-hazardous dry stripping and sand blasting into plastic drop cloths and dispose of as trash.
- ☐ Chemical paint stripping residue and chips and dust from marine paints or paints containing lead, mercury, or tributyltin must be disposed of as hazardous waste. Lead based paint removal requires a state certified contractor.



STORM DRAIN POLLUTERS MAY BE LIABLE FOR FINES OF UP TO \$10,000 PER DAY!

250 Hamilton Avenue
Palo Alto, CA 94301
650.329.2211
cityofpaloalto.org



verizon

2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

Vinculums

575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500

ALLSTATES
ENGINEERING & SURVEYING
23675 BIRCHER DRIVE
LAKE FOREST, CA 92630

PROJECT ID:	TBD
DRAWN BY:	RF
CHECKED BY:	DW

2	09/10/2020	100% CD'S FOR SUBMITTAL	MG
1	06/11/2020	100% CD'S FOR SUBMITTAL	RF
0	05/22/2020	100% CD'S FOR APPROVAL	RF
B	05/04/2020	95% CD'S FOR REDLINE	RF
A	04/14/2020	90% CD'S FOR REDLINE	RF
REV	DATE	DESCRIPTION	



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 203
PUBLIC R.O.W. ADJACENT TO:
519 WEBSTER STREET
PALO ALTO, 94301
LOCATION CODE: 566802

SHEET TITLE
PALO ALTO POLLUTION
PREVENTION CHECKLIST


SHEET NUMBER
L-2

EROSION AND SEDIMENT CONTROL NOTES:


TEMPORARY EROSION/SEDIMENT CONTROL, PRIOR TO COMPLETION OF FINAL IMPROVEMENTS, SHALL BE PERFORMED BY THE CONTRACTOR OR QUALIFIED PERSON AS INDICATED BELOW:

- ALL REQUIREMENTS OF THE CITY "LAND DEVELOPMENT MANUAL, STORM WATER STANDARDS" MUST BE INCORPORATED INTO THE DESIGN AND CONSTRUCTION OF THE PROPOSED PUBLIC IMPROVEMENTS CONSISTENT WITH THE EROSION CONTROL PLAN AND/OR WATER POLLUTION CONTROL PLAN (WPCP), IF APPLICABLE.
- FOR STORM DRAIN INLETS, PROVIDE A GRAVEL BAG SILT BASIN IMMEDIATELY UPSTREAM OF INLET AS INDICATED ON DETAILS.
- THE CONTRACTOR OR QUALIFIED PERSON SHALL BE RESPONSIBLE FOR CLEANUP OF SILT AND MUD ON ADJACENT STREET(S) AND STORM DRAIN SYSTEM DUE TO CONSTRUCTION ACTIVITY.
- THE CONTRACTOR SHALL REMOVE SILT AND DEBRIS AFTER EACH MAJOR RAINFALL.
- EQUIPMENT AND WORKERS FOR EMERGENCY WORK SHALL BE MADE AVAILABLE AT ALL TIMES DURING THE RAINY SEASON.
- THE CONTRACTOR SHALL RESTORE ALL EROSION/SEDIMENT CONTROL DEVICES TO WORKING ORDER TO THE SATISFACTION OF THE CITY ENGINEER OR RESIDENT ENGINEER AFTER EACH RUN-OFF PRODUCING RAINFALL.
- THE CONTRACTOR SHALL INSTALL ADDITIONAL EROSION/SEDIMENT CONTROL MEASURES AS MAY THE CONTRACTOR SHALL INSTALL ADDITIONAL EROSION/SEDIMENT CONTROL MEASURES AS MAY BE REQUIRED BY THE RESIDENT ENGINEER DUE TO UNFORESEEN CIRCUMSTANCES, WHICH MAY ARISE.
- EROSION/SEDIMENT CONTROL MEASURES PROVIDED PER THE APPROVED IMPROVEMENT PLAN SHALL BE INCORPORATED HEREON. ALL EROSION/SEDIMENT CONTROL FOR INTERIM CONDITIONS SHALL BE DONE TO THE SATISFACTION OF THE RESIDENT ENGINEER.
- ALL REMOVABLE PROTECTIVE DEVICES SHOWN SHALL BE IN PLACE AT THE END OF EACH WORKING DAY WHEN RAIN IS IMMINENT.
- THE CONTRACTOR SHALL ARRANGE FOR WEEKLY MEETINGS DURING OCTOBER 1ST TO APRIL 30TH FOR PROJECT TEAM (GENERAL CONTRACTOR, QUALIFIED PERSON, EROSION CONTROL SUBCONTRACTOR IF ANY, ENGINEER OF WORK, OWNER/DEVELOPER AND THE RESIDENT ENGINEER) TO EVALUATE THE ADEQUACY OF THE EROSION/SEDIMENT CONTROL MEASURES AND OTHER RELATED CONSTRUCTION ACTIVITIES.

STORM DRAIN INLET PROTECTION



TYPICAL PROTECTION FOR INLET WITH OPPOSING FLOW DIRECTIONS



TYPICAL PROTECTION FOR INLET WITH SINGLE FLOW DIRECTION

NOTES:

- INTENDED FOR SHORT-TERM USE.
- USE TO INHIBIT NON-STORM WATER FLOW.
- ALLOW FOR PROPER MAINTENANCE AND CLEANUP.
- BAGS MUST BE REMOVED AFTER ADJACENT OPERATION IS COMPLETED.
- NOT APPLICABLE IN AREAS WITH HIGH SILTS AND CLAYS WITHOUT FILTER FABRIC.

NOTES:

- CONTRACTOR TO POTHOLE ALL UTILITY CROSSINGS.
- CONTRACTOR TO PLACE SANDBAGS AROUND ANY/ALL STORM DRAIN INLETS TO PREVENT CONTAMINATED WATER.
- SPOILS PILE WILL BE COVERED AND CONTAINED AND STREET WILL BE SWEEPED AND CLEANED AS NEEDED.
- CONTRACTOR TO REPAIR DAMAGED PUBLIC IMPROVEMENTS TO THE CONTRACTOR TO REPAIR DAMAGED PUBLIC IMPROVEMENTS TO THE SATISFACTION OF THE CITY ENGINEER.
- SIDEWALK TO BE REPLACED CURB & GUTTER TO BE PROTECTED IN PLACE. SIDEWALK TO BE REPLACED TO THE SATISFACTION OF THE CITY ENGINEER.
- THE CONTRACTOR SHALL RESTORE THE ROADWAY BACK TO ITS ORIGINAL CONDITION SATISFACTORY TO THE CITY ENGINEER INCLUDING, BUT NOT LIMITED TO PAVING, STRIPING, BIKE LANES, PAVEMENT LEGENDS, SIGNS, AND TRAFFIC LOOP DETECTORS.
- SIDEWALK SHALL BE RESTORED/REPLACED PER CITY STANDARD DRAWINGS.
- PEDESTRIAN RAMP WILL NOT BE DISTURBED. PEDESTRIAN RAMP WILL NOT BE DISTURBED.

GENERAL CONTRACTOR NOTES:

- STREET USE PERMIT SHALL BE OBTAINED BY CONTRACTOR PRIOR TO COMMENCING WORK.
- ALL WORK TO BE CONDUCTED IN THE RIGHT OF WAY.
- ALL DISTURBED LANDSCAPING SHALL BE REPLACED TO SIMILAR EXISTING CONDITION.
- ANY SIDEWALK CLOSURE SHALL BE COORDINATED WITH THE CITY AND PROPER SIGNING WILL BE PLACED.
- NO MATERIALS OR EQUIPMENT SHALL BE STORED ON PRIVATE PROPERTY OR BLOCK ACCESS TO PRIVATE PROPERTY.
- CLEANUP OF SITE WILL BE COMPLETED EACH EVENING AND THE SITE WILL BE RETURNED TO EXISTING CONDITIONS AT THE COMPLETION OF CONSTRUCTION AT EACH SITE.
- CONTRACTOR SHALL VERIFY ALL PLANS AND EXISTING DIMENSIONS AND CONDITIONS ON THE JOB SITE AND SHALL IMMEDIATELY NOTIFY THE ENGINEER IN WRITING OF ANY DISCREPANCIES BEFORE PROCEEDING WITH THE WORK OR RESPONSIBLE FOR SAME.

R.O.W. GROUND CONSTRUCTION NOTES:

- GROUND CONSTRUCTION TO REMOVE/CLEAN ALL DEBRIS, NAILS, STAPLES, GROUND CONSTRUCTION TO REMOVE/CLEAN ALL DEBRIS, NAILS, STAPLES, OR NON-USED VERTICALS OFF THE POLE.
- ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH MUNICIPAL, COUNTY, STATE, FEDERAL, G095 AND G0128 STANDARDS AND REGULATIONS.
- CALL USA 48 HOURS PRIOR TO EXCAVATING AT (800) 227-2600 OR 811.
- ALL LANDSCAPING TO BE RESTORED TO ORIGINAL CONDITION OR BETTER.
- ALL EQUIPMENT TO BE BONDED. ALL EQUIPMENT TO BE BONDED.
- METERING CABINET REQUIRES 36" CLEARANCE AT DOOR OPENING.
- CAULK CABINET BASE AT PAD.

CALIFORNIA STATE CODE COMPLIANCE:

ALL WORK AND MATERIALS SHALL BE PREFORMED AND INSTALLED IN ACCORDANCE WITH THE CURRENT EDITIONS OF THE FOLLOWING CODES AS ADOPTED BY THE LOCAL GOVERNING AUTHORITIES. NOTHING IN THESE PLANS IS TO BE CONSTRUCTED TO PERMIT WORK NOT CONFORMING TO THESE CODES:

- CALIFORNIA ADMINISTRATIVE CODE (INCLUDING TITLES 24 & 25) 2016
- 2016 CALIFORNIA BUILDING CODES WHICH ADOPTS THE 2015 IBC, 2015 IMC, 2015 IPC AND THE 2014 NEC, AND SHALL INCLUDE 2016 CBC, CFC, CMC, CEC, CPC, CGBSC.
- BUILDING OFFICIALS & CODE ADMINISTRATORS (BOCA) CURRENT NATIONAL CODES
- ANSI/EIA-222-G (2009 - 2ND EDITION)
- NFPA-101 - LIFE SAFETY CODE / CAL-05HA - TITLE 8 / FCR - TITLE 29
- LOCAL BUILDING CODE
- CITY/COUNTY ORDINANCES
- ACCESSIBILITY REQUIREMENTS:

** FACILITY IS UNMANNED AND NOT FOR HUMAN HABITATION. HANDICAPPED ACCESS REQUIREMENTS DO NOT APPLY IN ACCORDANCE WITH THE 2016 CALIFORNIA BUILDING CODE.

- FCC RF/EMF EXPOSURE/EMITTANCE COMPLIANCE:


**FCC NOTE: THIS WIRELESS COMMUNICATION FACILITY COMPLIES WITH FEDERAL STANDARDS FOR RADIO FREQUENCY IN ACCORDANCE WITH THE TELECOMMUNICATION ACT OF 1996 AND SUBSEQUENT AMENDMENTS AND ANY OTHER REQUIREMENTS IMPOSED BY STATE OR FEDERAL REGULATORY AGENCIES.

CITY OF PALO ALTO UTILITIES ENGINEERING NOTES:

- APPLICANT SHALL TAP ELECTRIC SERVICE TO THE SMALL CELL DISTRIBUTED ANTENNA SYSTEM FROM THE LOCATIONS JOINTLY IDENTIFIED DURING THE FIELD INVESTIGATION.
- SERVICE VOLTAGE TO ALL THE PROPOSED LOCATIONS MAY NOT BE THE SAME. APPLICANT SHALL DESIGN THEIR SYSTEM TO OPERATE AT THE AVAILABLE VOLTAGE IN THE VICINITY.
- IF BRAND NEW POLES NEED TO BE INSTALLED FOR APPLICANT'S SYSTEM THEN THE POLES MUST MATCH EXISTING POLES IN THE DOWN TOWN AREA.
- AFTER EXCAVATION IS COMPLETED ON THE PUBLIC RIGHT OF WAY, EXISTING STREETS INCLUDING SIDEWALKS/ CURB/ GUTTER OR ANY DECORATIVE PATHS MUST BE BROUGHT TO ITS ORIGINAL CONDITION AND MUST BE APPROVED BY PUBLIC WORKS ENGINEERING DEPARTMENT'S INSPECTOR. POTHOLING MUST BE DONE AND ALL THE UTILITIES MUST BE IDENTIFIED PRIOR TO COMMENCING EXCAVATION.
- EXCAVATION AND RESTORATION WORK MUST BE IN COMPLIANCE WITH PUBLIC WORKS ENGINEERING STANDARDS AND SPECIFICATIONS THAT ARE AVAILABLE ON THE FOLLOWING WEBSITE: <http://www.cityofpaloalto.org/news/displaynews.asp?NewsID=1834&TargetID=145>
- APPLICANTS SHALL BE RESPONSIBLE FOR MAINTAINING THEIR SYSTEM INCLUDING SUBSTRUCTURE. IN CASE OF KNOCK DOWNS, THE CITY WILL RE-INSTALL ITS STREET LIGHTING POLES BUT NOT APPLICANT'S EQUIPMENT ON OR OFF THE POLE.
- A FIELD MEETING IS RECOMMENDED WITH UTILITIES ENGINEERING PRIOR TO COMMENCING THE WORK.
- PLANS SHALL INCLUDE A NOTE: CONTRACTOR TREE INSPECTION REQUIREMENTS: MODIFIED TYPE III TRUNK WRAPPING SHALL BE VERIFIED BY URBAN FORESTRY PRIOR TO ANY WORK IN THE VICINITY. FOR EACH TREE SITE WRAPPED FOR PROTECTION WITHIN 15' OF ANY WORK ZONE OR CONCRETE FORM SECTION, A BILLABLE TREE INSPECTION BY URBAN FORESTRY (650-496-5953, 24-HOUR ADVANCE IS REQUIRED) SHALL BE COMPLETED PRIOR TO DEMOLITION, DRILLING, EXCAVATING, FORMING OR STREET LIGHT ACTIVITY. CONTRACTOR SHALL ARRANGE PAYMENTS AT THE DEVELOPMENT CENTER, 285 HAMILTON AVE, PALO ALTO, CA.
- THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE UTILITIES DEPARTMENT 650/329-2413 OR 650/496-6982 IF THE EXISTING WATER, WASTEWATER OR GAS MAINS ARE DISTURBED OR DAMAGED. A QUALIFIED CONTRACTOR MAY PERFORM REPAIRS ON CITY WATER AND WASTEWATER MAINS UNDER THE DIRECT SUPERVISION OF THE WGW UTILITIES INSPECTOR. FOR WATER REPAIRS ALL THE DISINFECTION REQUIREMENTS OF THE WGW UTILITY STANDARDS AND THESE CONDITIONS SHALL BE ADHERED TO. ALL REPAIRS TO THE CITY GAS SYSTEM MUST BE PERFORMED BY THE CITY OF PALO ALTO UTILITIES.
- NO WATER VALVES OR OTHER FACILITIES OWNED BY UTILITIES DEPARTMENT SHALL BE OPERATED FOR ANY PURPOSE BY THE APPLICANT'S CONTRACTOR. ALL REQUIRED OPERATION WILL ONLY BE PERFORMED BY AUTHORIZED UTILITIES DEPARTMENT PERSONNEL. WATER VALVES MAY BE OPERATED BY THE CONTRACTOR UNDER THE DIRECT SUPERVISION OF THE WGW UTILITIES INSPECTOR. THE APPLICANT'S CONTRACTOR SHALL NOTIFY THE UTILITIES DEPARTMENT NOT LESS THAN FORTY- EIGHT (48) HOURS IN ADVANCE OF THE TIME THAT SUCH OPERATION IS REQUIRED.

NORMAL LOCATION OF UNDERGROUND UTILITIES NOTES:

- LOCATION AND DEPTH OF EXISTING AND PROPOSED UTILITIES MUST BE PROVIDED BY THE SUBDIVIDER AND SHOWN ON ANY PLANS SUBMITTED TO THE DEPT. OF PUBLIC WORKS FOR APPROVAL.
- CHANGES MAY BE PERMITTED BY THE DEPT. OF PUBLIC WORKS IN CASES OF CONFLICTING FACILITIES.
- CONFLICTS BETWEEN UTILITY COMPANIES FACILITIES, EXISTING AND PROPOSED, MUST BE MUTUALLY RESOLVED BY THE UTILITY COMPANIES.
- FOR COMMERCIAL SIDEWALKS, THE FIRE HYDRANT SHALL BE PLACED WITHIN THE SIDEWALK 1'-6" BEHIND FACE OF CURB.
- MAXIMUM 2" DIAMETER GAS MAINS MAY BE PLACED IN JOINT UTILITIES TRENCH SUBJECT TO APPROVAL OF CITY ENGINEER (IN TRACTS).



Rev	By	Date	Conduit Location Detail Telecommunications	Approved by:
0	DWH	7/16/98		72158
1	MMN	7/20/04		01/10/18
Scale: NTS			City of Palo Alto Standard	Dwg No. 402

verizon

2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

Vinculums

575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500

ALLSTATES
ENGINEERING & SURVEYING
23675 BIRTCHE DRIVE
LAKE FOREST, CA 92630

PROJECT ID:	TBD
DRAWN BY:	RF
CHECKED BY:	DW

2	09/10/2020	100% CD'S FOR SUBMITTAL	MG	
1	06/11/2020	100% CD'S FOR SUBMITTAL	RF	
0	05/22/2020	100% CD'S FOR APPROVAL	RF	
B	05/04/2020	95% CD'S FOR REDLINE	RF	
A	04/14/2020	90% CD'S FOR REDLINE	RF	
REV	DATE	DESCRIPTION		



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 203
PUBLIC R.O.W. ADJACENT TO:
519 WEBSTER STREET
PALO ALTO, 94301
LOCATION CODE: 566802

SHEET TITLE
PALO ALTO EROSION
CONTROL AND CONDUIT
LOCATION DETAILS & NOTES

SHEET NUMBER
L-3



SITE ID:

PROJECT NAME:

POLE#:

LOCATION CODE:

ADJACENT APN:

SITE ADDRESS:

COUNTY:

SITE TYPE:

ROADWAY TYPE:

HISTORIC STATUS OR DISTRICT:

SF PALO ALTO 204

VZW PALO ALTO SMALL CELL

53

566800

120-05-098

ADJACENT TO 850 WEBSTER STREET

PALO ALTO, 94301

SANTA CLARA

STREET LIGHT POLE

COLLECTOR

verizon

2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

Vinculums

575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500

ALLSTATES
ENGINEERING & SURVEYING
23675 BIRTCHER DRIVE
LAKE FOREST, CA 92630

PROJECT ID: TBD
DRAWN BY: AM
CHECKED BY: DW

REV	DATE	DESCRIPTION	
2	09/10/2020	100% CD'S FOR SUBMITTAL	MG
1	06/11/2020	100% CD'S FOR SUBMITTAL	RF
0	05/22/2020	100% CD'S FOR APPROVAL	RF
B	05/06/2020	95% CD'S FOR REDLINE	RF
A	04/22/2020	90% CD'S FOR REDLINE	AM



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 204
PUBLIC R.O.W. ADJACENT TO:
ADJACENT TO
850 WEBSTER STREET
PALO ALTO, 94301
LOCATION CODE: 566800

SHEET TITLE

TITLE SHEET

SHEET NUMBER

T-1

PROJECT DESCRIPTION

VERIZON WIRELESS PROPOSES TO INSTALL A NEW WIRELESS COMMUNICATION SITE ON A NEW/REPLACEMENT STREET LIGHT POLE. THE SCOPE WILL CONSIST OF THE FOLLOWING:

- REMOVE (1) EXISTING STREET LIGHT/POLE #53 IN HOMER AVE. PUBLIC R.O.W.
- INSTALL (1) NEW 'DOWNTOWN' ROADWAY LIGHTING POLE W/ LED LAMP IN PLACE OF REMOVED LIGHT POLE #53, PER LIGHTING STYLE PLACEMENT GUIDE
- RE-CONNECT CPA STREET LIGHT POWER TO NEW/REPLACEMENT STREET LIGHT
- INSTALL (2) NEW ERICSSON SM-6701 RADIO/ANTENNAS ATOP NEW POLE
- INSTALL (1) NEW NEMA 6P AC DISCONNECT WITHIN NEW U.G. POWER HANDHOLE
- INSTALL (1) NEW 5/8"Ø x10'L. GROUND ROD WITHIN U.G. POWER HANDHOLE
- INSTALL NEW AC POWER CABLES FROM POC, TO DISCONNECT, TO RADIOS
- INSTALL NEW GROUND CABLES FROM DISCONNECT/RADIOS/POLE TO GROUND ROD
- INSTALL NEW FIBER CABLES FROM DEMARC TO RADIOS
- INSTALL NEW RF NOTICE AND EMERGENCY SHUT-DOWN SIGNAGE AS REQUIRED
- INSTALL NEW U.G. PATH FROM POWER POC TO NEW U.G. POWER HANDHOLE

ADMINISTRATIVE REQUIREMENTS


SUBCONTRACTOR SHALL VERIFY ALL PLANS, EXISTING DIMENSIONS & FIELD CONDITIONS ON THE JOB SITE & SHALL IMMEDIATELY NOTIFY THE ENGINEER IN WRITING OF ANY DISCREPANCIES BEFORE PROCEEDING WITH THE WORK OR BE RESPONSIBLE FOR SAME.

VICINITY MAP



SYMBOLS/ABBREVIATIONS LEGEND

ADD'L A.F.G. ANT. ASS'Y. AWG. BLDG. BTCW. CLR. CONC. CONN. CONST. CONT. DBL. D.F. DIA. DIM. EA. ELEV EMT. (E) F.G. FT.(') GA. HT. IN.(") LB.(#) L.F.	ADDITIONAL ABOVE FINISHED GRADE ANTENNA ASSEMBLY AMERICAN WIRE GAUGE BUILDING BARE TINNED COPPER WIRE CLEAR CONCRETE CONNECTION(OR) CONSTRUCTION CONTINUOUS CONTR. DOUGLAS FIR DIAMETER DIMENSION EACH ELEVATION EXISTING ELECTRICAL METALLIC TUBING EXISTING FINISH GRADE FOOT (FEET) GAUGE HEIGHT INCH(ES) POUND(S) LINEAR FEET (FOOT)	L. MAX. MFR. MIN. (N) NTS O.C. P.T. RAD.(R) REQ'D RGS. SCH. SIM. SQ. S.S. STD. TEMP. THK. TYP. U.G. U.L. U.N.O. V.I.F. W WD. W.P.	LONG(ITUDINAL) MAXIMUM MANUFACTURER MINIMUM NEW NOT TO SCALE ON CENTER PRESSURE TREATED RADIUS REQUIRED RIGID GALVANIZED STEEL SCHEDULE SIMILAR SQUARE STAINLESS STEEL STANDARD TEMPORARY THICK(NESS) TYPICAL UNDER GROUND UNDERWRITERS LABORATORY UNLESS NOTED OTHERWISE VERIFY IN FIELD WIDE (WIDTH) WITH WOOD WEATHERPROOF
--	---	--	---



CONCRETE (SURFACE)	CHAIN LINK FENCE
CONCRETE (CUT)	WOOD FENCE
EARTH	WROUGHT IRON FENCE
GRAVEL	OVERHEAD WIRES
PLYWOOD	POWER CONDUIT
STEEL	GROUND CONDUCTOR
EXISTING GRASS	PROPERTY LINE
ELEVATION DATUM	CENTERLINE

PROJECT TEAM

APPLICANT:
VERIZON WIRELESS
575 LENNON LANE SUITE 125
WALNUT CREEK, CA 94598
CONTACT: JEREMY STROUP
PHONE: (925) 202-8654
EMAIL: jstroup@vinculums.com

LEASING CONTACT:
VINCULUMS SERVICES
575 LENNON LANE SUITE 125
WALNUT CREEK, CA 94598
CONTACT: JEREMY STROUP
PHONE: (925) 202-8654
EMAIL: jstroup@vinculums.com

A&E PROJECT MANAGER:
ZALZALI & ASSOCIATES INC.
dba ALL STATES ENGINEERING
& SURVEYING
23675 BIRTCHER DRIVE
LAKE FOREST, CA 92630
PM: DEAN WALKER
PHONE: (714) 230-5714
EMAIL: dean@zalzali.com

CONSTRUCTION MANAGER:
VINCULUMS SERVICES
575 LENNON LANE SUITE 125
WALNUT CREEK, CA 94598
CONTACT: CURTIS GARDNER
PHONE: (510) 552-2944
EMAIL: cgardner@vinculums.com

ARBORIST CONTACT:
PROJECT ARBORIST
121 N 27TH STREET,
SAN JOSE, CA 95116
CONTACT: KATHERINE NAEGELE
PHONE: (408) 590-5976
EMAIL: katherine@andersonstreecare.com

SITE INFORMATION

LATITUDE: N 37° 26' 48.7" (37.446862)	JURISDICTION: CITY OF PALO ALTO
LONGITUDE: W 122° 9' 16.2" (-122.154493)	ASSESSORS PARCEL NUMBER: ADJACENT TO 850 WEBSTER
ELEVATION: +43' AMSL	PROPERTY LEGAL DESCRIPTION: N/A PUBLIC RIGHT OF WAY
ZONING: PC-8659	ADA COMPLIANCE: YES

DIG ALERT



DO NOT SCALE DRAWINGS

CONTRACTOR SHALL VERIFY ALL PLANS & (E) DIMENSIONS & CONDITIONS ON THE JOB SITE & SHALL IMMEDIATELY NOTIFY THE ENGINEER IN WRITING OF ANY DISCREPANCIES BEFORE PROCEEDING WITH THE WORK OR BE RESPONSIBLE FOR SAME IF USING 11"x17" PLOT, DRAWINGS WILL BE HALF SCALE.

CODE COMPLIANCE

ALL WORK AND MATERIALS SHALL BE PERFORMED AND INSTALLED IN ACCORDANCE WITH THE CURRENT EDITIONS OF THE FOLLOWING CODES AS ADOPTED BY THE LOCAL GOVERNING AUTHORITIES. NOTHING IN THESE PLANS IS TO BE CONSTRUCTED TO PERMIT WORK NOT CONFORMING TO THESE CODES.

2019 TITLE 24, CALIFORNIA CODE OF REGULATIONS

2019 CALIFORNIA BUILDING CODE

2019 CALIFORNIA ELECTRICAL CODE

2019 CALIFORNIA MECHANICAL CODE

2019 GREEN BUILDING CODE

2019 CALIFORNIA ENERGY CODE

*AS AMENDED BY CITY OF PALO ALTO AND MADE EFFECTIVE JANUARY 1ST, 2020 AS PER CURRENT CITY OF PALO ALTO MUNICIPAL CODE ORDINANCES GENERAL ORDER 95 (v.2018)



Vinculums **CA SJ Palo Alto 204** Looking Northeast from Webster Street
850 Webster Street View #1
Palo Alto, CA
9/3/20
Approved Imagination S10 914-0500



Vinculums **CA SJ Palo Alto 204** Looking South from Webster Street
850 Webster Street View #2
Palo Alto, CA
9/3/20
Approved Imagination S10 914-0500

verizon

2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

Vinculums

575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500

ALLSTATES
ENGINEERING & SURVEYING
23675 BIRCHER DRIVE
LAKE FOREST, CA 92630

PROJECT ID:	TBD
DRAWN BY:	AM
CHECKED BY:	DW

2	09/10/2020	100% CD'S FOR SUBMITTAL	MG
1	06/11/2020	100% CD'S FOR SUBMITTAL	RF
0	05/22/2020	100% CD'S FOR APPROVAL	RF
B	05/06/2020	95% CD'S FOR REDLINE	RF
A	04/22/2020	90% CD'S FOR REDLINE	AM
REV	DATE	DESCRIPTION	



IT IS A VIOLATION OF LAW FOR ANY PERSON,
UNLESS THEY ARE ACTING UNDER THE
DIRECTION OF A LICENSED PROFESSIONAL
ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 204
PUBLIC R.O.W. ADJACENT TO:
ADJACENT TO
850 WEBSTER STREET
PALO ALTO, 94301
LOCATION CODE: 566800

SHEET TITLE
PHOTOSIMS

SHEET NUMBER
T-2