



Vinculums **SF Palo Alto 061** Looking Northeast from Middlefield Road
Adjacent to 1221 Middlefield Road Palo Alto, CA **View #1**
9/3/20 Applied Imagination 510-514-0900



Vinculums **SF Palo Alto 061** Looking East from Middlefield Road
Adjacent to 1221 Middlefield Road Palo Alto, CA **View #2**
10/30/20 Applied Imagination 510-514-0900

verizon

2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

Vinculums

575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500

ALL STATES
ENGINEERING & SURVEYING
A ZALZALI & ASSOCIATES COMPANY

23675 BIRTCHE DRIVE
LAKE FOREST, CA 92630
PHONE: (949) 273-0996

PROJECT ID:	P-334882
DRAWN BY:	RF
CHECKED BY:	DW

3	11/20/2020	CITY COMMENTS	MG
2	08/31/2020	100% CD'S FOR SUBMITTAL	MG
1	06/11/2020	100% CD'S FOR SUBMITTAL	RF
0	05/22/2020	100% CD'S FOR APPROVAL	RF
B	05/04/2020	95% CD'S FOR REDLINE	RF
A	04/29/2020	90% CD'S FOR REDLINE	RF
REV	DATE	DESCRIPTION	



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 061
LIC R.O.W. ADJACENT TO:
1221 MIDDLEFIELD RD.
PALO ALTO, 94301
LOCATION CODE: 425208

SHEET TITLE
PHOTOSIMS

SHEET NUMBER
T-2

Verizon Wireless • Proposed Small Cell (No. 425208 "SF Palo Alto 061")
1221 Middlefield Road • Palo Alto, California

Statement of Hammett & Edison, Inc., Consulting Engineers

The firm of Hammett & Edison, Inc., Consulting Engineers, has been retained on behalf of Verizon Wireless, a personal wireless telecommunications carrier, to evaluate its small cell (No. 425208 "SF Palo Alto 061") proposed to be sited in Palo Alto, California, for compliance with appropriate guidelines limiting human exposure to radio frequency ("RF") electromagnetic fields.

Executive Summary

Verizon proposes to install three small antennas on the municipal light pole sited in the public right-of-way near 1221 Middlefield Road in Palo Alto. The proposed operation will comply with the FCC guidelines limiting public exposure to RF energy.

Prevailing Exposure Standards

The U.S. Congress requires that the Federal Communications Commission ("FCC") evaluate its actions for possible significant impact on the environment. A summary of the FCC's exposure limits is shown in Figure 1. These limits apply for continuous exposures and are intended to provide a prudent margin of safety for all persons, regardless of age, gender, size, or health. The most restrictive limit for exposures of unlimited duration at several wireless service bands are as follows:

Wireless Service Band	Transmit Frequency	"Uncontrolled" Public Limit	Occupational Limit (5 times Public)
Microwave (point-to-point)	1-80 GHz	1.0 mW/cm ²	5.0 mW/cm ²
Millimeter-wave	24-47	1.0	5.0
Part 15 (WiFi & other unlicensed)	2-6	1.0	5.0
CBRS (Citizens Broadband Radio)	3,550 MHz	1.0	5.0
BRS (Broadband Radio)	2,490	1.0	5.0
WCS (Wireless Communication)	2,305	1.0	5.0
AWS (Advanced Wireless)	2,110	1.0	5.0
PCS (Personal Communication)	1,930	1.0	5.0
Cellular	869	0.58	2.9
SMR (Specialized Mobile Radio)	854	0.57	2.85
700 MHz	716	0.48	2.4
600 MHz	617	0.41	2.05
[most restrictive frequency range]	30-300	0.20	1.0

General Facility Requirements

Small cells typically consist of two distinct parts: the electronic transceivers (also called "radios" or "channels") that are connected to the traditional wired telephone lines, and the passive antennas that send the wireless signals created by the radios out to be received by individual subscriber units. The radios are typically mounted on the support pole or placed in a cabinet at ground level, and they are

Verizon Wireless • Proposed Small Cell (No. 425208 "SF Palo Alto 061")
1221 Middlefield Road • Palo Alto, California

connected to the antennas by coaxial cables. Because of the short wavelength of the frequencies assigned by the FCC for wireless services, the antennas require line-of-sight paths for their signals to propagate well and so are installed at some height above ground. The antennas are designed to concentrate their energy toward the horizon, with very little energy wasted toward the sky or the ground. This means that it is generally not possible for exposure conditions to approach the maximum permissible exposure limits without being physically very near the antennas.

Computer Modeling Method

The FCC provides direction for determining compliance in its Office of Engineering and Technology Bulletin No. 65, "Evaluating Compliance with FCC-Specified Guidelines for Human Exposure to Radio Frequency Radiation," dated August 1997. Figure 2 describes the calculation methodologies, reflecting the facts that a directional antenna's radiation pattern is not fully formed at locations very close by (the "near-field" effect) and that at greater distances the power level from an energy source decreases with the square of the distance from it (the "inverse square law"). This methodology is an industry standard for evaluating RF exposure conditions and has been demonstrated through numerous field tests to be a conservative prediction of exposure levels.

Site and Facility Description

Based upon information provided by Verizon, including drawings by All States Engineering & Surveying, dated August 31, 2020, it is proposed to install three Ericsson Model 6701, 2-foot tall, directional panel antennas with integrated radios on top of a new light pole to replace the existing pole sited in the public right-of-way in front of the residence at 1221 Middlefield Road in Palo Alto. The antennas would employ no down tilt, would be mounted at an effective height of about 26½ feet above ground, and would be oriented toward 0°T, 120°T, and 240°T. The maximum effective radiated power proposed in any direction is 193 watts in the 28 GHz band. There are reported no other wireless telecommunications base stations at the site or nearby.

Study Results

For a person anywhere at ground, the maximum RF exposure level due to the proposed Verizon operation is calculated to be 0.0059 mW/cm², which is 0.59% of the applicable public exposure limit. The maximum calculated level at the second-story elevation of any nearby building* is 1.9% of the public exposure limit. It should be noted that these results include several "worst-case" assumptions and therefore are expected to overstate actual power density levels from the proposed operation.

* Including the nearest residence, located at 1221 Middlefield Road, at least 30 feet away based on the drawings.

Verizon Wireless • Proposed Small Cell (No. 425208 "SF Palo Alto 061")
1221 Middlefield Road • Palo Alto, California

Recommended Mitigation Measures

Due to their mounting locations and height, the antennas would not be accessible to unauthorized persons, and so no measures are necessary to comply with the FCC public exposure guidelines. To prevent occupational exposures in excess of the FCC guidelines, it is recommended that appropriate RF safety training be provided to all workers who have access within 8 feet outward from the antennas. No access within 2 feet directly in front of the antennas should be allowed while the antennas are in operation, unless other measures can be demonstrated to ensure that occupational protection requirements are met. It is recommended that explanatory signs* be posted at the antennas and/or on the pole below the antennas, readily visible from any angle of approach.

Conclusion

Based on the information and analysis above, it is the undersigned's professional opinion that operation of the small cell proposed by Verizon Wireless near 1221 Middlefield Road in Palo Alto, California, will comply with the prevailing standards for limiting public exposure to radio frequency energy and, therefore, will not for this reason cause a significant impact on the environment. The highest calculated level in publicly accessible areas is much less than the prevailing standards allow for exposures of unlimited duration. This finding is consistent with measurements of actual exposure conditions taken at other operating small cells. Training authorized personnel and posting explanatory signs are recommended to establish compliance with occupational exposure limits.

Authorship

The undersigned author of this statement is a qualified Professional Engineer, holding California Registration No. E-21306, which expires on September 30, 2021. This work has been carried out under his direction, and all statements are true and correct of his own knowledge except, where noted, when data has been supplied by others, which data he believes to be correct.



September 29, 2020


* Signs should comply with OET-65 color, symbol, and content recommendations. Contact information should be provided (e.g., a telephone number) to arrange for access to restricted areas. The selection of language(s) is not an engineering matter, and guidelines from the landlord, local zoning or health authority, or appropriate professionals may be required.

FCC Radio Frequency Protection Guide

The U.S. Congress required (1996 Telecom Act) the Federal Communications Commission ("FCC") to adopt a nationwide human exposure standard to ensure that its licensees do not, cumulatively, have a significant impact on the environment. The FCC adopted the limits from Report No. 86, "Biological Effects and Exposure Criteria for Radiofrequency Electromagnetic Fields," published in 1986 by the Congressionally chartered National Council on Radiation Protection and Measurements ("NCRP"). Separate limits apply for occupational and public exposure conditions, with the latter limits generally five times more restrictive. The more recent standard, developed by the Institute of Electrical and Electronics Engineers and approved as American National Standard ANSI/IEEE C95.1-2006, "Safety Levels with Respect to Human Exposure to Radio Frequency Electromagnetic Fields, 3 kHz to 300 GHz," includes similar limits. These limits apply for continuous exposures from all sources and are intended to provide a prudent margin of safety for all persons, regardless of age, gender, size, or health.

As shown in the table and chart below, separate limits apply for occupational and public exposure conditions, with the latter limits (in *italics* and/or dashed) up to five times more restrictive:

Frequency Applicable Range (MHz)	Electromagnetic Fields (f is frequency of emission in MHz)		
	Electric Field Strength (V/m)	Magnetic Field Strength (A/m)	Equivalent Far-Field Power Density (mW/cm ²)
0.3 - 1.34	614	1.63	100
1.34 - 3.0	614	1.63	100
3.0 - 30	1842/f	4.89/f	900/f ²
30 - 300	61.4	0.163	1.0
300 - 1,500	3.54/f	0.106/f	0.2
1,500 - 100,000	137	0.364	5.0



Higher levels are allowed for short periods of time, such that total exposure levels averaged over six or thirty minutes, for occupational or public settings, respectively, do not exceed the limits, and higher levels also are allowed for exposures to small areas, such that the spatially averaged levels do not exceed the limits. However, neither of these allowances is incorporated in the conservative calculation formulas in the FCC Office of Engineering and Technology Bulletin No. 65 (August 1997) for projecting field levels. Hammett & Edison has incorporated those formulas in a computer program capable of calculating, at thousands of locations on an arbitrary grid, the total expected power density from any number of individual radio frequency sources. The program allows for the inclusion of uneven terrain in the vicinity, as well as any number of nearby buildings of varying heights, to obtain more accurate projections.

RFR.CALC™ Calculation Methodology

Assessment by Calculation of Compliance with FCC Exposure Guidelines

The U.S. Congress required (1996 Telecom Act) the Federal Communications Commission ("FCC") to adopt a nationwide human exposure standard to ensure that its licensees do not, cumulatively, have a significant impact on the environment. The maximum permissible exposure limits adopted by the FCC (see Figure 1) apply for continuous exposures from all sources and are intended to provide a prudent margin of safety for all persons, regardless of age, gender, size, or health. Higher levels are allowed for short periods of time, such that total exposure levels averaged over six or thirty minutes, for occupational or public settings, respectively, do not exceed the limits.

Near Field.

Prediction methods have been developed for the near field zone of panel (directional) and whip (omnidirectional) antennas, typical at wireless telecommunications base stations, as well as dish (aperture) antennas, typically used for microwave links. The antenna patterns are not fully formed in the near field at these antennas, and the FCC Office of Engineering and Technology Bulletin No. 65 (August 1997) gives suitable formulas for calculating power density within such zones.

$$\text{For a panel or whip antenna, power density } S = \frac{180}{\theta_{HW}} \times \frac{0.1 \times P_{net}}{\pi \times D \times h}, \text{ in mW/cm}^2,$$

$$\text{and for an aperture antenna, maximum power density } S_{max} = \frac{0.1 \times 16 \times \eta \times P_{net}}{\pi \times h^2}, \text{ in mW/cm}^2,$$

where θ_{HW} = half-power beamwidth of antenna, in degrees,
 P_{net} = net power input to antenna, in watts,
 D = distance from antenna, in meters,
 h = aperture height of antenna, in meters, and
 η = aperture efficiency (unitless, typically 0.5-0.8).

The factor of 0.1 in the numerators converts to the desired units of power density.

Far Field.

OET-65 gives this formula for calculating power density in the far field of an individual RF source:

$$\text{power density } S = \frac{2.56 \times 1.64 \times 100 \times RFF^2 \times ERP}{4 \times \pi \times D^2}, \text{ in mW/cm}^2,$$

where ERP = total ERP (all polarizations), in kilowatts,
 RFF = three-dimensional relative field factor toward point of calculation, and
 D = distance from antenna effective height to point of calculation, in meters.

The factor of 2.56 accounts for the increase in power density due to ground reflection, assuming a reflection coefficient of 1.6 (1.6 x 1.6 = 2.56). The factor of 1.64 is the gain of a half-wave dipole relative to an isotropic radiator. The factor of 100 in the numerator converts to the desired units of power density. This formula is used in a computer program capable of calculating, at thousands of locations on an arbitrary grid, the total expected power density from any number of individual radio frequency sources. The program also allows for the inclusion of uneven terrain in the vicinity, as well as any number of nearby buildings of varying heights, to obtain more accurate projections.


Verizon Wireless • Proposed Small Cell (No. 425208 "SF Palo Alto 061")
1221 Middlefield Road • Palo Alto, California

Calculated RF Exposure Levels

at Elevation of Antennas (25 - 28 feet above ground)



Antennas at 26½ ft on 29 ft pole



The public limit extends about 8 feet from the antennas, not reaching any publicly accessible area.
The occupational limit extends about 2 feet from the antennas.

at Ground, at 10 feet Above Ground, and at Nearby Buildings



Legend:
■ less than FCC Public Limit
■ greater than FCC Public Limit
■ less than FCC Occupational Limit
■ greater than FCC Occupational Limit

Notes:
Calculations performed according to OET Bulletin No. 65, August 1997.
Base image from Google Maps.

NOTICE

RADIO FREQUENCY ANTENNAS
Verizon ANTENNAS on this pole
DO NOT APPROACH
within 8 feet of
24-29 feet above ground.
RF exposure there may exceed
FCC General Population Limits.
Contact Verizon at 1-800-254-0997.
Site No. 425208
sign on pole below antennas

(November 16, 2020) C11-H9X3.5
Supplemental Figure

verizon

2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

Vinculums

575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500

ALL STATES
ENGINEERING & SURVEYING
A ZALZALI & ASSOCIATES COMPANY

23675 BIRTCHE DRIVE
LAKE FOREST, CA 92630
PHONE: (949) 273-0996

PROJECT ID: P-334882

DRAWN BY: RF

CHECKED BY: DW

REV	DATE	DESCRIPTION	
3	11/20/2020	CITY COMMENTS	MG
2	08/31/2020	100% CD'S FOR SUBMITTAL	MG
1	06/11/2020	100% CD'S FOR SUBMITTAL	RF
0	05/22/2020	100% CD'S FOR APPROVAL	RF
B	05/04/2020	95% CD'S FOR REDLINE	RF
A	04/29/2020	90% CD'S FOR REDLINE	RF



IT IS A VIOLATION OF LAW FOR ANY PERSON,
UNLESS THEY ARE ACTING UNDER THE
DIRECTION OF A LICENSED PROFESSIONAL
ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 061


LIC R.O.W. ADJACENT TO:
1221 MIDDLEFIELD RD.
PALO ALTO, 94301
LOCATION CODE: 425208

SHEET TITLE

EME REPORT

SHEET NUMBER


T-3



2 POLE ELEVATION
1 inch = 5ft.

LEGEND

- | | | | |
|---------|--------------------|--------|-------------------------|
| □ | U.G. UTILITY VAULT | BLDG | TOP OF BUILDING |
| ⊕ | MANHOLE | MON | MONUMENT |
| ○ | UTILITY POLE | FL | FLOW LINE |
| ⊗ | SPOT ELEVATION | EOP | EDGE OF PAVEMENT |
| ⊗ | WATER VALVE | R.O.W. | RIGHT OF WAY |
| ⊙ | FOUND MONUMENT | R/W | RIGHT OF WAY |
| ⊕ | GEODETIC MARKER | SCO | SEWER CLEAN-OUT |
| — x — | CHAIN LINK FENCE | PS | PARKING STRIPE |
| — □ — | WOOD FENCE | SW | SIDEWALK |
| — O/H — | OVERHEAD LINE | VLT | U.G. UTILITY VAULT |
| — ○ — | METAL FENCE | OHE | OVERHEAD ELECTRICAL |
| — — — | GRADE BREAK | SVC | SERVICE |
| — — — | RIGHT OF WAY LINE | AC | ASPHALTIC CONCRETE |
| — — — | CENTER LINE | AP | ASPHALT PAVING |
| — — — | EASEMENT LINE | CONC | CONCRETE |
| — — — | MASONRY WALL | PED | PEDESTAL |
| ⊗ | WATER VALVE | OH | OVERHEAD |
| UP | UTILITY POLE | PUE | PUBLIC UTILITY EASEMENT |
| LP | LIGHT POLE | FC | FACE OF CURB |
| LUM | LUMINAIRE | BOL | BOLLARD |
| NG | NATURAL GRADE | TOP | TOP OF ITEM |
| | | BOT | BOTTOM OF ITEM |



1 POLE LOCATION
1 inch = 20ft.

TITLE REPORT

NOT APPLICABLE (RIGHT-OF-WAY)

LEGAL DESCRIPTION

NOT APPLICABLE (RIGHT-OF-WAY)

ASSESSOR'S PARCEL NO.

NOT APPLICABLE (RIGHT-OF-WAY)

UTILITY NOTE:

SURVEYOR DOES NOT GUARANTEE THAT ALL UTILITIES ARE SHOWN OR THEIR LOCATIONS ARE DEFINITE. IT IS THE RESPONSIBILITY OF THE CONTRACTOR AND DEVELOPER TO CONTACT BLUE STAKE AND ANY OTHER INVOLVED AGENCIES TO LOCATE ALL UTILITIES PRIOR TO CONSTRUCTION. REMOVAL, RELOCATION AND/ OR REPLACEMENT IS THE RESPONSIBILITY OF THE CONTRACTOR.

NOTES:

1. THIS IS NOT A BOUNDARY SURVEY. THIS IS A SPECIALIZED RIGHT OF WAY MAP. THE PROPERTY LINES AND EASEMENTS SHOWN HEREON ARE FROM RECORD INFORMATION AS NOTED HEREON. ALL STATES ENGINEERING & SURVEYING/ZALZALI & ASSOCIATES, INC. TRANSLATED THE TOPOGRAPHIC SURVEY TO RECORD INFORMATION USING MONUMENT(S)/LANDMARK(S) SHOWN HEREON. NO TITLE RESEARCH WAS PERFORMED BY ALL STATES ENGINEERING & SURVEYING/ZALZALI & ASSOCIATES, INC.

2. ANY CHANGES MADE TO THE INFORMATION ON THIS PLAN, WITHOUT THE WRITTEN CONSENT OF ALL STATES ENGINEERING & SURVEYING / ZALZALI & ASSOCIATES, INC. RELIEVES ALL STATES ENGINEERING & SURVEYING/ ZALZALI & ASSOCIATES, INC. OF ANY AND ALL LIABILITY.

3. THESE DRAWINGS & SPECIFICATIONS ARE THE PROPERTY & COPYRIGHT OF ALL STATES ENGINEERING & SURVEYING / ZALZALI & ASSOCIATES, INC. & SHALL NOT BE USED ON ANY OTHER WORK EXCEPT BY AGREEMENT WITH THE SURVEYOR. WRITTEN DIMENSIONS SHALL TAKE PREFERENCE OVER SCALED & SHALL BE VERIFIED ON THE JOB SITE. ANY DISCREPANCY SHALL BE BROUGHT TO THE NOTICE OF THE SURVEYOR PRIOR TO COMMENCEMENT OF ANY WORK.

4. THIS SITE IS PROPOSED TO BE DEVELOPED ON A STREET LIGHT POLE LOCATED WITHIN THE PUBLIC RIGHT OF WAY.

SURVEY DATE

08/16/2020

BASIS OF BEARING


BEARINGS SHOWN HEREON ARE BASED UPON U.S. STATE PLANE NAD83 COORDINATE SYSTEM. CALIFORNIA STATE PLANE COORDINATE ZONE THREE, DETERMINED BY GPS OBSERVATIONS.

BENCHMARK

RTCM-REF 3270
NORTHING: 1970498.865
EASTING: 6082238.002
+248.11' (A.M.S.L.)

REFERENCE MAPS

• 868 - RS - 41



VICINITY MAP

verizon

2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

Vinculums

575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500

ALLSTATES
ENGINEERING & SURVEYING
23675 BIRCHER DRIVE
LAKE FOREST, CA 92630

PROJECT NO: SF PALO ALTO 061

DRAWN BY: MG

CHECKED BY: BC/WZ/DW

O	08/27/2020	FINAL SURVEY	MA
A	08/27/2020	PRELIMINARY SURVEY	MG
REV	DATE	DESCRIPTION	



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 061
R.O.W. ADJACENT TO:
1221 MIDDLEFIELD RD
PALO ALTO, CA 94301
NEW BUILD-SMALL CELL

SHEET TITLE

SITE SURVEY

SHEET NUMBER

C-1

TREE NOTES:

1. THERE WILL BE NO TREE PRUNING WITHOUT THE SPECIFIC APPROVAL OF THE PALO ALTO URBAN FORESTRY DEPARTMENT ON ALL REGULATED TREES. ANY VIOLATION TO THIS POLICY WILL BE SUBJECT TO PENALTY. CONTACT THE PALO ALTO URBAN FORESTRY DEPARTMENT AT (650) 496-5953.
2. THIS CONSTRUCTION PROJECT TRIGGERS MANDATORY TREE PROTECTION MEASURES. SEE TREE PROTECTION PLAN & CONTACT THE PALO ALTO URBAN FORESTRY DEPARTMENT. AT (650) 496-5953 WITH ANY QUESTIONS.
3. EXCAVATION ACTIVITIES ASSOCIATED WITH THE PROPOSED SCOPE OF WORK SHALL OCCUR NO CLOSER THAN 10-FEET FROM THE EXISTING STREET TREE, OR AS APPROVED BY THE URBAN FORESTRY DIVISION CONTACT 650-496-5953. ANY CHANGES SHALL BE APPROVED BY THE SAME.
4. PROJECT ARBORIST:
KATHERINE NAEGELE
KATHERINE@ANDERSONTREECARE.COM
PHONE: (408) 590-5976
5. NO FEASIBLE GREEN SCREEN OPPORTUNITIES EXIST

NOTES:

1. METAL SURFACES REQUIRING PAINT TO BE PAINTED WITH A MUNSELL RAL5.5GY2.76/2.1 PAINT.
2. ANY CONSTRUCTION WITHIN THE CITY'S PUBLIC ROAD RIGHT-OF-WAY SHALL HAVE AN APPROVED PERMIT FOR CONSTRUCTION IN THE PUBLIC STREET PRIOR TO COMMENCEMENT OF THIS WORK

TREE TABLE


PALO ALTO TREE #	CITY TREE ID:	SPECIES:	COMMON NAME:	GROW SPACE:	TRUNK DIA. AT BREAST HT.:	DRIP LINE:	DISTANCE TO CONST.:	PROTECTION MEASURES REQUIRED:
PALO ALTO TREE #1	-	TILIA CORDATA	LITTLELEAF LINDEN	-	3.9"	3' 3"	-	-
PALO ALTO TREE #2	-	TILIA CORDATA	LITTLELEAF LINDEN	-	15.9"	13' 3"	-	TYPE 2

NEW TREE TABLE

TREE	CITY TREE ID:	SPECIES:	COMMON NAME:	COMMENTS:
PROPOSED TREE #1	TBD	SWAMP MYRTLE	TRISTANOPSIS LAURINA	REPLACEMENT FOR STREET TREE #1

NOTE:

ALL ITEMS AND DIMENSIONS SHOULD BE VERIFIED IN THE FIELD, PRIOR TO STARTING CONSTRUCTION.



SITE PLAN

24"x36" SCALE: 3/32" = 1'-0"
11"x17" SCALE: 3/64" = 1'-0"

verizon

2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

Vinculum

575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500

ALL STATES
ENGINEERING & SURVEYING
A ZALZALI & ASSOCIATES COMPANY

23675 BIRTCHE DRIVE
LAKE FOREST, CA 92630
PHONE: (949) 273-0996

PROJECT ID: P-334882

DRAWN BY: RF

CHECKED BY: DW

REV	DATE	DESCRIPTION	
3	11/20/2020	CITY COMMENTS	MG
2	08/31/2020	100% CD'S FOR SUBMITTAL	MG
1	06/11/2020	100% CD'S FOR SUBMITTAL	RF
0	05/22/2020	100% CD'S FOR APPROVAL	RF
B	05/04/2020	95% CD'S FOR REDLINE	RF
A	04/29/2020	90% CD'S FOR REDLINE	RF



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.


SF PALO ALTO 061
LIC R.O.W. ADJACENT TO:
1221 MIDDLEFIELD RD.
PALO ALTO, 94301
LOCATION CODE: 425208

SHEET TITLE

SITE PLAN

SHEET NUMBER

A-1



EXISTING UTILITY SITE PLAN

24"x36" SCALE: 3/32" = 1'-0"
11"x17" SCALE: 3/64" = 1'-0"



verizon
2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

Vinculum
575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500

ALL STATES
ENGINEERING & SURVEYING
A ZALZALI & ASSOCIATES COMPANY
23675 BIRCHER DRIVE
LAKE FOREST, CA 92630
PHONE: (949) 273-0996

PROJECT ID:	P-334882
DRAWN BY:	RF
CHECKED BY:	DW

REV	DATE	DESCRIPTION	
3	11/20/2020	CITY COMMENTS	MG
2	06/31/2020	100% CD'S FOR SUBMITTAL	MG
1	06/11/2020	100% CD'S FOR SUBMITTAL	RF
0	05/22/2020	100% CD'S FOR APPROVAL	RF
B	05/04/2020	95% CD'S FOR REDLINE	RF
A	04/29/2020	90% CD'S FOR REDLINE	RF

REGISTERED PROFESSIONAL ENGINEER
WESAM ZALZALI
71655
CIVIL
STATE OF CALIFORNIA

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 061
LIC R.O.W. ADJACENT TO:
1221 MIDDLEFIELD RD.
PALO ALTO, 94301
LOCATION CODE: 425208

SHEET TITLE
EXISTING UTILITY
SITE PLAN

SHEET NUMBER
A-1.1

Kingsley Ave

Middlefield Rd



THIS MAP IS PROVIDED FOR REFERENCE ONLY.
THE CITY OF PALO ALTO DOES NOT WARRANT
THE ACCURACY OF THIS MAP



THE CITY OF
Palo Alto




CPA WGW Utility Information
1221 Middlefield Rd
NODE 061
For Reference Use Only

Legend

- Assessment Parcel (AP)
- Building Roof Outline (BL)
- Address Label (AP)
- Curb Face (RF)
- Curb Edge (RF)
- Curb Edge, Rolled (RF)
- Pavement Edge (RF)
- Sidewalk Edge (RF)
- Road Centerline Small Text (TC)
- Easement Boundary Line (CG)
- Dimensions (AP)
- Easement Text (CG)
- Pipeline (SD)
- Catch Basin (SD)
- Manhole (SD)
- Pipe, Main (TB WT)
- Pipe, Service (TB WT)
- Crossing Casing (TB WT/NAD)
- Hydrant (TB WT)
- Valve (TB WT):
 - Fire Service
 - Hydrant Branch
 - Main
 - Service
 - Buried Alive
- Meter (TB WT/NAD)
- Meter, Service (TB WT/NAD)
- Wall (TB WT/NAD)
- Air Relief Valve (TB WT)
- Valve Blowoff (TB WT)
- Riser (TB GS)
- Pipe, Service (TB GS)
- Casing (TB GS/NAD)
- Fence (TB UF/NAD)
- Meter (TB GS):
 - Above Ground Service
 - Curb Service
 - Pipe, Main (TB GS)
- Valve (TB GS):
 - Main
 - Service
 - Dead End One Way
 - Emergency Shut Off Valve (ESV)
 - Buried Alive
- Pipe, Lateral (TB WW)
- Pipe, Main (TB WW)
- Crossing Casing (TB WW)
- Cleanout, Lateral (TB WW)
- Structure, Main (TB WW):
 - Manhole
 - Cleanout
 - Lamp Hole
 - Flushing Inlet
 - Pipe cap
 - Concrete plug
 - Non-structural node
- Point Tap (TB WW)
- Text (TB WW)

This map is a product of the
City of Palo Alto GIS



SITE LOCATION

objard, 2020-03-23 17:40:52
New Base Map Req (lcc-maps/Encompass/Admin/Personal/objard.mxd)

This document is a graphic representation only of best available sources.
The City of Palo Alto assumes no responsibility for any errors. ©1989 to 2016 City of Palo Alto

verizon

2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

Vinculum

575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500

ALL STATES
ENGINEERING & SURVEYING
A ZALZALI & ASSOCIATES COMPANY

23675 BIRCHER DRIVE
LAKE FOREST, CA 92630
PHONE: (949) 273-0996

PROJECT ID: P-334882

DRAWN BY: RF

CHECKED BY: DW

REV	DATE	DESCRIPTION	
3	11/20/2020	CITY COMMENTS	MG
2	06/31/2020	100% CD'S FOR SUBMITTAL	MG
1	06/11/2020	100% CD'S FOR SUBMITTAL	RF
0	05/22/2020	100% CD'S FOR APPROVAL	RF
B	05/04/2020	95% CD'S FOR REDLINE	RF
A	04/29/2020	90% CD'S FOR REDLINE	RF




IT IS A VIOLATION OF LAW FOR ANY PERSON,
UNLESS THEY ARE ACTING UNDER THE
DIRECTION OF A LICENSED PROFESSIONAL
ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 061
LIC R.O.W. ADJACENT TO:
1221 MIDDLEFIELD RD.
PALO ALTO, 94301
LOCATION CODE: 425208

SHEET TITLE
UTILITY PLAN
(FOR REFERENCE)

SHEET NUMBER
A-1.2



LOCATION MAP

verizon

2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

Vinculums

575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500

ALL STATES
ENGINEERING & SURVEYING
A ZALZALI & ASSOCIATES COMPANY

23675 BIRTCHE DRIVE
LAKE FOREST, CA 92630
PHONE: (949) 273-0996

PROJECT ID:	P-334882
DRAWN BY:	RF
CHECKED BY:	DW

3	11/20/2020	CITY COMMENTS	MG	
2	08/31/2020	100% CD'S FOR SUBMITTAL	MG	
1	06/11/2020	100% CD'S FOR SUBMITTAL	RF	
0	05/22/2020	100% CD'S FOR APPROVAL	RF	
B	05/04/2020	95% CD'S FOR REDLINE	RF	
A	04/29/2020	90% CD'S FOR REDLINE	RF	
REV	DATE	DESCRIPTION		

Nassim Zalzal

IT IS A VIOLATION OF LAW FOR ANY PERSON,
UNLESS THEY ARE ACTING UNDER THE
DIRECTION OF A LICENSED PROFESSIONAL
ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 061
LIC R.O.W. ADJACENT TO:
1221 MIDDLEFIELD RD.
PALO ALTO, 94301
LOCATION CODE: 425208

SHEET TITLE

LOCATION MAP

SHEET NUMBER

A-1.3

- ## ② NOTES


Sawcutting & Asphalt/Concrete Removal

- ☐ Protect storm drain inlets during saw cutting.
- ☐ If saw cut slurry enters a catch basin, clean it up immediately.
- ☐ Shovel or vacuum saw cut slurry deposits and remove from the site. When making saw cuts, use as little water as possible. Sweep up, and properly dispose of all residues.


VICINITY MAP

NOTES:



















1. APPLICANT SHOULD NOTE THE USE OF INNERDUCT IN ALL STREETLIGHTS
2. NOTE TO PREWIRE ALL STREETLIGHTS PRIOR TO INSTALLATION
3. WIRE SHOULD ENTER THE DISCONNECT AND THEN STREET LIGHT



① LIGHT POLE
1 inch = 2ft.



LEGEND

	U.G. UTILITY VAULT	BOL	BOLLARD	FL	FLOW LINE		WATER
	MANHOLE	TOP	TOP OF ITEM	EOP	EDGE OF PAVEMENT		SANITARY SEWER
	UTILITY POLE	BOT	BOTTOM OF ITEM	R.O.W.	RIGHT OF WAY		STORM DRAIN
	SPOT ELEVATION	BLDG	TOP OF BUILDING	AP	ASPHALT		GAS
	WATER VALVE	LP	LIGHT POLE	SW	SIDEWALK		COMMUNICATION
	FOUND MONUMENT	---	LIMITS OF PROPERTY	o/h	OVERHEAD LINE		ELECTRIC
	GEODETTIC MARKER	x	CHAIN LINK FENCE		METAL FENCE		UNKNOWN UTILITY
	MASONRY WALL	—	WOOD FENCE		GRADE BREAK		IRRIGATION

PROJECT SPECIFIC PERMIT INFORMATION		
DESCRIPTION	QTY	UNIT
PLACE (1) 4" SCH 40 CONDUIT	10	LF
PLACE (1) 2" SCH 40 CONDUIT	4	LF
REMOVE AND RESTORE SOIL	160	FT³



NOTES:

1. EXCAVATION RESTRICTIONS APPLY (TMM, SEC. 2.20 C & D). ANY APPROVED GRADING, DIGGING OR TRENCHING BENEATH A TREE CANOPY SHALL BE PERFORMED USING "AIR-SPADE" METHOD AS A PREFERENCE, WITH MANUAL HAND SHOVEL AS A BACKUP. FOR UTILITY TRENCHING, INCLUDING SEWER LINE, ROOTS EXPOSED WITH DIAMETER OF 1.5 INCHES AND GREATER SHALL REMAIN INTACT AND NOT BE DAMAGED.
2. SEE ATTACHED TREE PROTECTION PLAN FOR INSTRUCTIONS ON TREE PROTECTION.


NOTE:

ALL PROPOSED POWER RUNS TO
MAINTAIN A MIN. 2' CLR. ALL
AROUND AS REQUIRED BY CPAU

APN: 003-43-047
1221 MIDDLEFIELD RD

verizon[✓]

2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598



Vinculums

575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500



ALLSTATES
ENGINEERING & SURVEYING
23675 BIRCHER DRIVE
LAKE FOREST, CA 92630

PROJECT ID: P-334882

DRAWN BY: RF

CHECKED BY: DW

O	08/17/2020	FINAL BORING PLAN	SS
A	08/14/2020	PRELIMINARY BORING PLAN	SS
REV	DATE	DESCRIPTION	



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS
THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED
PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 061


LIC R.O.W. ADJACENT TO:
1221 MIDDLEFIELD RD.
PALO ALTO, 94301
LOCATION CODE: 425208

SHEET TITLE


BORING SITE PLAN

SHEET NUMBER


A-1.4




5 CITY STANDARD DWG 401
N.T.S.




4 CITY STANDARD DWG 403
N.T.S.



3 CITY STANDARD DWG 402
N.T.S.



2 CHRISTY N16 ELECTRICAL BOX
N.T.S.



1 IN DIRT - PRIVATE
N.T.S.

verizon

2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

Vinculums

575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500

ALLSTATES
ENGINEERING & SURVEYING
23675 BIRCHER DRIVE
LAKE FOREST, CA 92630

PROJECT ID: P-334882
DRAWN BY: RF
CHECKED BY: DW

REV	DATE	DESCRIPTION	SS
0	08/17/2020	FINAL BORING PLAN	SS
A	08/14/2020	PRELIMINARY BORING PLAN	SS



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS
THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED
PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 061
LIC R.O.W. ADJACENT TO:
1221 MIDDLEFIELD RD.
PALO ALTO, 94301
LOCATION CODE: 425208

SHEET TITLE
CITY STANDARDS
& DETAILS

SHEET NUMBER

A-1.5

- ▶ Grade fills over 6-inches or impervious overlay shall incorporate an approved permanent aeration system, permeable material or other approved mitigation.
- ▶ Grade cuts exceeding 4-inches shall incorporate retaining walls or an appropriate transition equivalent.

C. Trenching, Excavation and Equipment Use

Trenching, excavation or boring activity within the TPZ is restricted to the following activities, conditions and requirements if approved by the City Arborist. (See Restriction Zones for Excavation, Trenching or Boring Near Regulated Trees, Image 2.20-1 through 2.20-3). Mitigating measures shall include prior notification to and direct supervision by the project arborist.

1. Notification. Contractor shall notify the *project arborist* a minimum of 24 hours in advance of the activity in the TPZ.
2. Root Severance. Roots that are encountered shall be cut to sound wood and repaired (see *Root Injury, Section 2.25 A-1*). Roots 2-inches and greater must remain injury free.
3. Excavation. Any approved excavation, demolition or extraction of material shall be performed with equipment sitting outside the TPZ. Methods permitted are by hand digging, hydraulic or pneumatic air excavation technology. Avoid excavation within the TPZ during hot, dry weather.
 - ▶ If excavation or *trenching* for drainage, utilities, irrigation lines, etc., it is the duty of the contractor to tunnel under any roots 2-inches in diameter and greater.
 - ▶ Prior to excavation for foundation/footings/walls, grading or *trenching* within the TPZ, roots shall first be severed cleanly 1-foot outside the TPZ and to the depth of the future excavation. The trench must then be hand dug and roots pruned with a saw, sawzall, narrow trencher with sharp blades or other approved root pruning equipment.
4. Heavy Equipment. Use of backhoes, steel tread tractors or any heavy vehicles within the TPZ is prohibited unless approved by the *City Arborist*. If allowed, a protective *root buffer* (see *Root Buffer and Damage to Trees, Section 2.25.A-1*) is required. The protective buffer shall consist of a base course of tree chips spread over the root area to a minimum of 6-inch depth, layered by 3/4-inch quarry gravel to stabilize 3/4-inch plywood on top. This buffer within the TPZ shall be maintained throughout the entire construction process.
 - ▶ Structural design. If injurious activity or interference with roots greater than 2-inches will occur within the TPZ, plans shall specify a design of special foundation, footing, walls, concrete slab or pavement designs subject to *City Arborist* approval. Discontinuous foundations such as concrete pier and structural grade beam must maintain natural grade (not to exceed a 4-inch cut), to minimize root loss and allow the tree to use the existing soil.

notes:


Required Practices

- ▶ Basement excavations shall be designed outside the TPZ of all *protected* and *designated* trees (see *Excavation*, Section 2.20-3) and shall not be harmful to other mature or neighboring property trees.

D. Tunneling & Directional Drilling

If *trenching* or pipe installation has been approved within the TPZ, then the trench shall be either cut by hand, air-spade, hydraulic vac-on excavation or, by mechanically boring the tunnel under the roots with a horizontal directional drill and hydraulic or pneumatic air excavation technology. In all cases, install the utility pipe immediately, backfill with soil and soak within the same day. Installation of private utility improvements shall be tunnel bored beneath the tree and roots per *Trenching Tunneling & Distance Matrix* in Table 2-1.

TABLE 2-1.
Trenching & Tunneling Distance

TRENCHING DISTANCE	
	
When the Tree Diameter At 4.5 Ft Is:	Trenching will be Replaced with Boring at this Minimum Distance (10x tree dia.) from the Face of the Tree in any Direction:
6-9" Measured At 6'	6-9'
10-14" Measured At 54'	10-14'
15-19" Measured At 54'	15-19'
Over 19" Measured At 54'	20' +

Bore Pits Shall Be Located At A Minimum Distance As Specified By The Trenching Distance Table Above.

1. **Public Utilities**
Underground public utility improvements or repairs shall be performed in accordance with the *Utility Standards for Excavation, Trenching or Boring, Section 02200.309*; and per *Restriction Zones Near Regulated Trees (see Images 2.20-1 through 2.20-3)*.
2. **Street Trees**
Exclusions for *street trees* in the publicly owned right-of-way (ROW).
 - ▶ *Street Trees* that are in conflict with utility infrastructure where the conflict cannot be resolved may be removed if approved by Public Works Operations (e.g., a tree planted directly on top of a damaged sewer lateral.)

notes:

Required Practices



2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598



575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500



23675 BIRTCHER DRIVE
LAKE FOREST, CA 92631

PROJECT ID: P-334882

DRAWN BY:	RF
-----------	----

CHECKED BY: DW

O	08/17/2020	FINAL BORING PLAN	SS
A	08/14/2020	PRELIMINARY BORING PLAN	SS
REV	DATE	DESCRIPTION	



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS
THEY ARE ACTING UNDER THE DIRECTION OF A LICENSE
PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 061
LIC R.O.W. ADJACENT TO:
 1221 MIDDLEFIELD RD.
 PALO ALTO, 94301
 LOCATION CODE: 425208


SHEET TITLE
CITY STANDARDS
& DETAILS

SHEET NUMBER

A-1.6

NOTES:

1. METAL SURFACES REQUIRING PAINT TO BE PAINTED MUNSELL RAL5.5GY2.76/2.1
2. THE CONTRACTOR MAY BE REQUIRED TO SUBMIT A LOGISTICS PLAN TO THE PUBLIC WORKS DEPARTMENT PRIOR TO COMMENCING WORK THAT ADDRESSES ALL IMPACTS TO THE CITY'S RIGHT-OF-WAY, INCLUDING, BUT NOT LIMITED TO: PEDESTRIAN CONTROL, TRAFFIC CONTROL, TRUCK ROUTES, MATERIAL DELIVERIES, CONTRACTOR'S PARKING, CONCRETE POURS, CRANE LIFTS, WORK HOURS, NOISE CONTROL, DUST CONTROL, STORM WATER POLLUTION PREVENTION, CONTRACTOR'S CONTACT, NOTICING OF AFFECTED SURROUNDING PROPERTIES, AND SCHEDULE OF WORK. THE REQUIREMENT TO SUBMIT A LOGISTICS PLAN WILL BE DEPENDENT ON THE NUMBER OF APPLICATIONS PUBLIC WORKS ENGINEERING RECEIVES WITHIN CLOSE PROXIMITY TO HELP MITIGATE AND CONTROL THE IMPACT TO THE PUBLIC-RIGHT-OF-WAY. IF NECESSARY, PUBLIC WORKS MAY REQUIRE A LOGISTICS PLAN DURING CONSTRUCTION.
3. TREES MAY NOT BE PLANTED WITHIN 10 FEET OF EXISTING WATER, GAS OR WASTEWATER MAINS/SERVICES OR METERS; LESSER DISTANCES REQUIRE A PERMANENT IMPERMEABLE ROOT-BARRIER A MINIMUM OF 3' HORIZONTAL FROM WATER, GAS AND WASTEWATER SERVICES/MAINS/METERS.




ENLARGED SITE PLAN

24"x36" SCALE: 1" = 1'-0"
11"x17" SCALE: 1/2" = 1'-0"

2

ENLARGED SITE PLAN



TREE TABLE

PALO ALTO TREE #	CITY TREE ID:	SPECIES:	COMMON NAME:	GROW SPACE:	TRUNK DIA. AT BREAST HT.:	DRIP LINE:	DISTANCE TO CONST.:	PROTECTION MEASURES REQUIRED:
PALO ALTO TREE #1	-	TILIA CORDATA	LITTLELEAF LINDEN	-	3.9"	3' 3"	-	-
PALO ALTO TREE #2	-	TILIA CORDATA	LITTLELEAF LINDEN	-	15.9"	13' 3"	-	TYPE 2

NEW TREE TABLE

TREE	CITY TREE ID:	SPECIES:	COMMON NAME:	COMMENTS:
PROPOSED TREE #1	TBD	HETEROMELAS ARBUTIFOLIA OR MYRICA CALIFORNICA	TOYON OR PACIFIC WAX MYRTLE	REPLACEMENT FOR STREET TREE #1

NOTE:

ALL ITEMS AND DIMENSIONS SHOULD BE VERIFIED IN THE FIELD, PRIOR TO STARTING CONSTRUCTION.

verizon

2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

Vinculum

575 LENNON LANE #125
LAKE FOREST, CA 92630
OFFICE: (925) 482-8500

ALL STATES
ENGINEERING & SURVEYING
A ZALZALI & ASSOCIATES COMPANY

23675 BIRCHER DRIVE
LAKE FOREST, CA 92630
PHONE: (949) 273-0996

PROJECT ID: P-334882

DRAWN BY: RF

CHECKED BY: DW

REV	DATE	DESCRIPTION	
3	11/20/2020	CITY COMMENTS	MG
2	06/31/2020	100% CD'S FOR SUBMITTAL	MG
1	06/11/2020	100% CD'S FOR SUBMITTAL	RF
0	05/22/2020	100% CD'S FOR APPROVAL	RF
B	05/04/2020	95% CD'S FOR REDLINE	RF
A	04/29/2020	90% CD'S FOR REDLINE	RF



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 061
LIC R.O.W. ADJACENT TO:
1221 MIDDLEFIELD RD.
PALO ALTO, 94301
LOCATION CODE: 425208



SHEET TITLE
ENLARGED SITE PLAN

SHEET NUMBER

A-2

24"x36" SCALE: 1/2" = 1'-0"
11"x17" SCALE: 1/4" = 1'-0"

1



verizon

2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

Vinculum

575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500

ALL STATES
ENGINEERING & SURVEYING
A ZALZALI & ASSOCIATES COMPANY

23675 BIRCHER DRIVE
LAKE FOREST, CA 92630
PHONE: (949) 273-0996

PROJECT ID:	P-334882
DRAWN BY:	RF
CHECKED BY:	DW

REV	DATE	DESCRIPTION	MG
3	11/20/2020	CITY COMMENTS	MG
2	08/31/2020	100% CD'S FOR SUBMITTAL	MG
1	06/11/2020	100% CD'S FOR SUBMITTAL	RF
0	05/22/2020	100% CD'S FOR APPROVAL	RF
B	05/04/2020	95% CD'S FOR REDLINE	RF
A	04/29/2020	90% CD'S FOR REDLINE	RF


REGISTERED PROFESSIONAL ENGINEER
WISSAM ZALZALI
71655
STATE OF CALIFORNIA

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.


SF PALO ALTO 061
LIC R.O.W. ADJACENT TO:
1221 MIDDLEFIELD RD.
PALO ALTO, 94301
LOCATION CODE: 425208

SHEET TITLE
ELEVATIONS

SHEET NUMBER
A-3



2



1

verizon

2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

Vinculum

575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500

ALL STATES
ENGINEERING & SURVEYING
A ZALZALI & ASSOCIATES COMPANY

23675 BIRTCHE DRIVE
LAKE FOREST, CA 92630
PHONE: (949) 273-0996

PROJECT ID:	P-334882
DRAWN BY:	RF
CHECKED BY:	DW

3	11/20/2020	CITY COMMENTS		MG
2	06/31/2020	100% CD'S FOR SUBMITTAL		MG
1	06/11/2020	100% CD'S FOR SUBMITTAL		RF
0	05/22/2020	100% CD'S FOR APPROVAL		RF
B	05/04/2020	95% CD'S FOR REDLINE		RF
A	04/29/2020	90% CD'S FOR REDLINE		RF
REV	DATE	DESCRIPTION		

REGISTERED PROFESSIONAL ENGINEER
MISSAM ZALZALI
71655
CIVIL
STATE OF CALIFORNIA

IT IS A VIOLATION OF LAW FOR ANY PERSON,
UNLESS THEY ARE ACTING UNDER THE
DIRECTION OF A LICENSED PROFESSIONAL
ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 061
LIC R.O.W. ADJACENT TO:
1221 MIDDLEFIELD RD.
PALO ALTO, 94301
LOCATION CODE: 425208

SHEET TITLE
ELEVATIONS


SHEET NUMBER
A-3.1



ERICSSON 6701 POLE ATTACHMENT SHROUD
PART NO. 30311
(OR APPROVED EQUAL)

NOTES:


1. FULL SHROUD PAINTABLE TO MATCH COLOR OF EXISTING STRUCTURE.
2. COLOR-MATCHED 3M FILM TO BE APPLIED TO ANTENNA EMITTER FACE.
3. SHROUD DRY WEIGHT = 18 LBS.
4. TOTAL WEIGHT INCLUDING ANTENNA = 49LBS.



DETAIL A (SECTOR 1 RADIO HIDDEN FOR CLARITY)

BRACKET ID & OD
DEPENDENT ON POLE
DIMENSIONS

RADIO MOUNT RING BRACKET
ADJUSTMENT SLOTS (360°
AZIMUTH ADJUSTMENT)



DETAIL B

RADIOS FLUSH
WITH TOP OF POLE

Ø10.18

2x RADIO MOUNT
RING BRACKET

TAPERED & FLUTED
POLE RADIO SHROUD
MOUNTING CHANNEL

DETAIL A

Ø1.50 CABLE
ACCESS HOLE
(x3 AT 120°)

32.18

28.00

Ø1.50 CABLE
ACCESS HOLE
(x3 AT 120°)

11.69

13.90

POLE VENDOR TO
PROVIDE POLE MAX &
MIN OD AT EACH OF
THESE MOUNTING
HEIGHTS

(4x) 3/8" BOLTS WITH
CAPTIVE NUTS (TYP
BOTH RADIO MOUNT
RING BRACKETS)

SECTION C-C



PREFORMED LINE PRODUCTS

COYOTE TERMINAL CLOSURE (FIBER DEMARCATION UNIT)

- DIMENSIONS: 18.76"L x 9.70"W x 5.13"D
- WEIGHT: N/A


OR VERIZON APPROVED EQUAL



FIBER DEMARCATION UNIT

24"x36" SCALE: NTS
11"x17" SCALE: NTS

6




GROUND

AC POWER "IN"

AC POWER "OUT"

AC POWER DISCONNECT WIRE DIAGRAM

5



NOTE:
NEW PHENOLIC SIGN TO BE
ATTACHED TO DISCONNECT

SHUTDOWN SIGN ON DISCONNECT


24"x36" SCALE: NTS
11"x17" SCALE: NTS

4



RSCAC-1333-PH-240 AC POWER DISCONNECT
(OR APPROVED EQUAL)

- DIMENSIONS: 10.43"L x 8.59"W x 5.06"D
- WEIGHT: ±8 lbs (3.62 Kg)



RSCAC-1333-PH-240

NEMA 6P AC POWER DISCONNECT

24"x36" SCALE: NTS
11"x17" SCALE: NTS

3

CONTRACTOR NOTE:

- SITE ID WILL BE SWITCH #, SITE # AND SITE NAME.
- NODE NUMBER WILL BE MARKET#-NODE.B#-SMALL CELL NAME.



NOTE:

INSTALL EME NOTICE SIGN 3'
BELOW STREET MACRO UNITS.

GO95 RF SIGNAGE

24"x36" SCALE: NTS
11"x17" SCALE: NTS

2



- DIMENSION W/ PROTRUDING ITEMS INCL GPS ANT:
21.2"H x 8.1"W x 5.1"D
- TOTAL RADIO AREA (CU. IN.): 875.77 CU. IN.
- WEIGHT: ±31 lbs

RADIO AREA (CU. FT.)			
RADIO MODEL	TOTAL RADIO(S)	TOTAL RADIO AREA (CU. IN.)	TOTAL RADIO AREA (CU. FT.)
MACRO 6701	1	875.77 CU. IN.	0.50 CU. FT.

NEW GPS ATTACHED ON TOP OF
SM 6701 (PRE INSTALLED BY
MANUFACTURER) (1) TOTAL (MAX.
MEASUREMENTS WILL NOT EXCEED)




STREET MACRO 6701

24"x36" SCALE: NTS
11"x17" SCALE: NTS

1



2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598



575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500



23675 BIRTCHE DRIVE
LAKE FOREST, CA 92630
PHONE: (949) 273-0996

PROJECT ID: P-334882

DRAWN BY: RF

CHECKED BY: DW

REV	DATE	DESCRIPTION	
3	11/20/2020	CITY COMMENTS	MG
2	08/31/2020	100% CD'S FOR SUBMITTAL	MG
1	06/11/2020	100% CD'S FOR SUBMITTAL	RF
0	05/22/2020	100% CD'S FOR APPROVAL	RF
B	05/04/2020	95% CD'S FOR REDLINE	RF
A	04/29/2020	90% CD'S FOR REDLINE	RF



IT IS A VIOLATION OF LAW FOR ANY PERSON,
UNLESS THEY ARE ACTING UNDER THE
DIRECTION OF A LICENSED PROFESSIONAL
ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 061

LIC R.O.W. ADJACENT TO:
1221 MIDDLEFIELD RD.
PALO ALTO, 94301
LOCATION CODE: 425208

SHEET TITLE

DETAILS

SHEET NUMBER

D-1

SM6701 SHROUD & MOUNTING DETAILS

24"x36" SCALE: NTS
11"x17" SCALE: NTS

7

Verizon Wireless • Proposed Small Cells
Four Pole Locations • Palo Alto, California

Statement of Hammett & Edison, Inc., Consulting Engineers

The firm of Hammett & Edison, Inc., Consulting Engineers, has been retained on behalf of Verizon Wireless, a wireless telecommunications carrier, to evaluate the addition of small cells in its network in Palo Alto, California, for compliance with municipal limits on sound levels from the installations.

Executive Summary

Verizon proposes to install antennas and equipment on four light poles sited in the public right-of-way in Palo Alto. Noise from the proposed operations will comply with the City's pertinent noise limits.

Prevailing Standard

The City of Palo Alto adopted in April 2019 an amendment to Section 18.42.110 (Wireless Communication Facilities) of its Municipal Code, which sets limits at residential areas for Wireless Communication Facilities ("WCF") installed in public rights-of-way on wood utility poles and on streetlight poles. Noise at the nearest residential property line is limited to an increase of 5 dBA over existing ambient levels, if the ambient noise level would remain below 60 dBA L_{dn}, or to an increase of 3 dBA, otherwise. The composite "day-night" average L_{dn} incorporates a 10 dBA penalty during nighttime hours (10 pm to 7 am), to reflect typical residential conditions, where noise is more readily heard at night. By definition, sound from a continuous noise source will be 6.4 dBA higher when expressed in L_{dn}.

It is noted that the amended language also references Chapter 9.10 of the Code, which had set a more relaxed increase of 15 dBA for such WCF sitings, assessed at 25 feet from the pole. It is assumed for this study that the minimum reference ambient level is 40 dBA, as defined in Chapter 9.10.

A summary of noise assessment and calculation methodologies is shown in Figure 1.

General Facility Requirements

Wireless telecommunications facilities ("cell sites") typically consist of two distinct parts: the electronic base transceivers (also called "radios"), that are connected to traditional wired telephone lines, and the antennas, that send wireless signals created by the radios out to be received by individual subscriber units. The radios are typically located on or at the base of the pole and are connected to the antennas by cables. Some radios require fans to cool the electronics inside. Some radios are integrated with the antennas as a single unit.

Verizon Wireless • Proposed Small Cells
Four Pole Locations • Palo Alto, California

Site & Facility Description

According to information provided by Verizon, that carrier proposes to install up to three Ericsson Model 6701 antennas, with integrated radios, on top of the light pole at each of the four locations listed in Table 1.

Study Results

Ericsson reports that the maximum noise level from three Model 6701 units is 39.5 dBA,* at a reference distance of 5 feet. At the minimum ambient level of 40 dBA, in order for the increase above ambient to remain below 5 dBA, the equipment configuration described above would need to be sited at least 3½ feet from the nearest residential property line. If the measured ambient is found to be above 40 dBA, this distance, by definition, would decrease. All the proposed small cells in Table 1 meet this distance requirement.

Conclusion

Based on the information and analysis above, it is the undersigned's professional opinion that operation of these Verizon Wireless small cells in Palo Alto will, under the conditions noted above, comply with the municipal standards limiting acoustic noise emission levels.

Authorship

The undersigned author of this statement is a qualified Professional Engineer, holding California Registration Nos. E-13026 and M-20676, which expire on June 30, 2021. This work has been carried out under his direction, and all statements are true and correct of his own knowledge except, where noted, when data has been supplied by others, which data he believes to be correct.

William F. Hammett, P.E.
707/996-5200

September 1, 2020


Small Cell #	Approximate Address	Distance to Property Line
SF Palo Alto 061	1221 Middlefield Road	6 feet
SF Palo Alto 203	519 Webster Street	9
SF Palo Alto 204	850 Webster Street	9
SF Palo Alto 205	853 Middlefield Road	9

Table 1. Proposed Verizon small cells

* Adjusted value based on manufacturer data, to reflect record high temperature of 107°F in Palo Alto.

Noise Level Calculation Methodology

Most municipalities and other agencies specify noise limits in units of dBA, which is intended to mimic the reduced receptivity of the human ear to Sound Pressure ("L_p") at particularly low or high frequencies. This frequency-sensitive filter shape, shown in the graph to the right as defined in the International Electrotechnical Commission Standard No. 179, the American National Standards Institute Standard No. 5.1, and various other standards, is also incorporated into most calibrated field test equipment for measuring noise levels.



30 dBA	library
40 dBA	rural background
50 dBA	office space
60 dBA	conversation
70 dBA	car radio
80 dBA	traffic corner
90 dBA	lawnmower

The dBA units of measure are referenced to a pressure of 20 µPa (micropascals), which is the threshold of normal hearing. Although noise levels vary greatly by location and noise source, representative levels are shown in the box to the left.

Manufacturers of many types of equipment, such as air conditioners, generators, and telecommunications devices, often test their products in various configurations to determine the acoustical emissions at certain distances. This data, normally expressed in dBA at a known reference distance, can be used to determine the corresponding sound pressure level at any particular distance, such as at a nearby building or property line. The sound pressure drops as the square of the increase in distance, according to the formula:

$$L_T = L_K + 20 \log(D_K/D_T)$$

where L_T is the sound pressure level at distance D_T, and L_K is the known sound pressure level at distance D_K.

Individual sound pressure levels at a particular point from several different noise sources cannot be combined directly in units of dBA. Rather, the units need to be converted to scalar sound intensity units in order to be added together, then converted back to decibel units, according to the formula:

where L_T is the total sound pressure level and L₁, L₂, etc are individual sound pressure levels.



$$L_T = 10 \log(10^{L_1/10} + 10^{L_2/10} + \dots)$$

Certain equipment installations may include the placement of barriers and/or absorptive materials to reduce transmission of noise beyond the site. Noise Reduction Coefficients ("NRC") are published for many different materials, expressed as unitless power factors, with 0 being perfect reflection and 1 being perfect absorption. Unpainted concrete block, for instance, can have an NRC as high as 0.35. However, a barrier's effectiveness depends on its specific configuration, as well as the materials used and their surface treatment.

NOISE REPORT

24"x36" SCALE: NTS
11"x17" SCALE: NTS

2



24"x36" SCALE: NTS
11"x17" SCALE: NTS

3

FOUNDATION DETAIL

24"x36" SCALE: NTS
11"x17" SCALE: NTS

1

verizon

2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

Vinculum

575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500

ALL STATES
ENGINEERING & SURVEYING
A ZALZALI & ASSOCIATES COMPANY

23675 BIRTCHE DRIVE
LAKE FOREST, CA 92630
PHONE: (949) 273-0996

PROJECT ID:	P-334882
DRAWN BY:	RF
CHECKED BY:	DW

REV	DATE	DESCRIPTION	
3	11/20/2020	CITY COMMENTS	MG
2	08/31/2020	100% CD'S FOR SUBMITTAL	MG
1	06/11/2020	100% CD'S FOR SUBMITTAL	RF
0	05/22/2020	100% CD'S FOR APPROVAL	RF
B	05/04/2020	95% CD'S FOR REDLINE	RF
A	04/29/2020	90% CD'S FOR REDLINE	RF

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 061
LIC R.O.W. ADJACENT TO:
1221 MIDDLEFIELD RD.
PALO ALTO, 94301
LOCATION CODE: 425208

SHEET TITLE
NOISE STUDY,
FOUNDATION DETAILS,
POLE DRAWINGS

SHEET NUMBER

D-2

• **MAXCELL EDGE 2.00"**

- Designed for 2" conduit applications
- Solves cabling issues for conduits, allowing a range of cable sizes
- Enables overlay of cables in occupied conduits
- Reduces or eliminates number of conduits required in new construction
- Melting point of 419°F (almost twice that of HDPE)
- Halogen-free
- Resistant to ground chemicals and petroleum products
- Constructed of PET (Polyethylene Terephthalate) and Nylon 6
- Patented fabric design may reduce pulling tension by up to 20% over previous MaxCell versions
- Features pre-installed 1250LB Vis™ Glide Rope in each cell
- Pre-lubed for lower friction during MaxCell and cable installation*
- Manufactured in the U.S.A.

INSTALLATION TIPS:

- SKIVELS MUST BE USED WHEN PULLING MAXCELL
- CONTACT CUSTOMER SERVICE FOR INSTALLATION ASSISTANCE.



OLDCASTLE N16 UTILITY BOX


- EXCEEDS ASTM-D1643 STANDARDS FOR ENVIRONMENTAL STRESS CRACKING RESISTANCE

- ETCHED POLYPROPYLENE FACE
- FACE ANCHORED IN CONCRETE
- ULTRA-VIOLET INHIBITOR

A HIGH DENSITY REINFORCED CONCRETE BOX WITH NON-SETTING SHOULDERS POSITIONED TO MAINTAIN GRADE AND FACILITATE BACK FILLING. APPROXIMATE DIMENSIONS AND WEIGHT SHOWN.

NOTE: SPECIFICATION OF THIS VAULT MANUFACTURER AND MODEL ARE SUBJECT TO REPLACEMENT WITH APPROVED EQUIVALENT VAULT/LID

OLDCASTLE ORDER CODE	ITEM	APPROXIMATE SHIP'G. WEIGHT	DESCRIPTION
Ni6BOX	BOX	112 lbs.	Ni6 ELECTRICAL BOX (11-3/4"x22-1/4") - 20 PER PALLET
Ni6R	LID	32 lbs.	R-SERIES COMPOSITE LID WITH POLYPROPYLENE RING (ORDER N90 BOLT DOWN KIT SEPARATELY)
FLi6T	LID	13 lbs.	FIBRELYTE LID, NON-CONCRETE BOLT DOWN (ORDER N90 BOLT-DOWN KIT SEPARATELY)
Ni6J	LID	36 lbs.	CAST IRON LID BOLT DOWN (ORDER N90 BOLT-DOWN KIT SEPARATELY)
Bi6-6iD	COVER	28 lbs.	STEEL CHECKER PLATE COVER
Ni6-6iJ	COVER	28 lbs.	STEEL CHECKER PLATE COVER (ORDER N90 BOLT-DOWN KIT SEPARATELY)
Bi6Xi2	EXTENSION	113 lbs.	12" REINFORCED CONCRETE BOX EXTENSION - 20 PER PALLET
B30SL	SLAB	52 lbs.	REINFORCED CONCRETE SLAB (16"x28")



PANEL 'A'																		
SITE NAME: SF PALO ALTO 061					VOLTAGE: 120 V PHASE: 1 WIRE: 2 MAIN BREAKER: 60 AMP BUSS RATING: 60 AMP LOCATION: UG VAULT													
PANEL DESIGNATION: AC PANEL 'A'																		
CKT	LOAD DESCRIPTION	BREAKER AMPS	BREAKER POLES	BREAKER STATUS	SERVICE LOAD VA	USAGE FACTOR	PHASE A VA	PHASE B VA	PHASE A VA	PHASE B VA	USAGE FACTOR	SERVICE LOAD VA	BREAKER STATUS	BREAKER POLES	BREAKER AMPS	LOAD DESCRIPTION	CKT	
1	MAIN	60	2	ON			0	636	636	0	1.25	509	ON	1	20	ERICSSON SM-6701 #2	2	
3								0		636	1.25	509	ON	1	20	ERICSSON SM-6701 #3	4	
5	ERICSSON SM-6701 #1	20	1	ON	508.5	1.25	636		0							SPACE	6	
RAYCAP MODEL NO. RSCAC-1333-PH-240 (60A, 240V, NEMA-6P) CONTRACTOR SHALL LABEL PANEL WITH CARRIER I.D., SERVICE RATING, AND FEED SOURCE							PHASE A TOTAL VA					1271		NOTES: 1. ALL LOADS CALICED AS LCL/MCL LOADS (OK TO DESIGN TO 100% CAPACITY) 2. UNUSED BREAKER POSITIONS SHALL REMAIN COVERED W/ MFR. COVER 3. ALL EQUIPMENT/BREAKERS SHALL BEAR A LABEL FOR I.D. & RATING				
							PHASE B TOTAL VA					636						
							TOTAL KVA					1.91						
							TOTAL AMPS					7.95						

MAXCELL INTERDUCT

7



N16 U.G. UTILITY BOX

24"x36" SCALE: NTS
11"x17" SCALE: NTS

5

PANEL SCHEDULE


2



GROUND ROD

24"x36" SCALE: NTS
11"x17" SCALE: NTS

4



GROUND RISER DIAGRAM

6


SPLICE DTAILS

24"x36" SCALE: NTS
11"x17" SCALE: NTS

3

POWER SCHEMATIC

1



ELECTRICAL NOTE:

1. ALL WORK SHALL COMPLY TO THE CURRENT EDITION OF THE CALIFORNIA ELECTRICAL CODE, CALIFORNIA BUILDING CODE, NATIONAL ELECTRICAL CODE, ALL APPLICABLE REGULATIONS GOVERNING NON-JPA UTILITY POLES (G.O. 95), AND ALL APPLICABLE LOCAL CODES.
2. ALL WORK SHALL COMPLY WITH VERIZON CARRIER CONSTRUCTION STANDARDS FOR SMALL CELL INSTALLATION.
3. ALL ELECTRICAL WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS AND ALL APPLICABLE LOCAL CODES.
4. AC PANEL SHALL HAVE A 'MAIN' BREAKER AFFIXED TO BOTH POLES OF THE MAIN LUG BUSS AND FED THROUGH LOAD SIDE TO PROVIDE SINGLE SHUT-OFF SWITCH FOR ALL SMALL CELL POWER ON AC PANEL.
5. POWER, CONTROL AND EQUIPMENT GROUND WIRING IN TUBING OR CONDUIT. SHALL BE SINGLE CONDUCTOR (#14 AWG AND LARGER), 600V, OIL RESISTANT. THIN OR THIN-2, CLASS B STRANDED COPPER CABLE RATED FOR 90°C (WET AND DRY) OPERATION; LISTED OR LABELED FOR THE LOCATION AND RACEWAY SYSTEM USED.
6. REFER TO PANEL SCHEDULE (2/-) AND ONE-LINE DIAGRAM (1/-) FOR CIRCUIT ARRANGEMENT & WIRING CONNECTION.
7. SUBCONTRACTOR SHALL COORDINATE WITH UTILITY COMPANY BEFORE THE START OF CONSTRUCTION. POWER AND TELEPHONE CONDUIT SHALL BE PROVIDED AND INSTALLED PER UTILITY REQUIREMENTS.
8. SUBCONTRACTOR SHALL PROVIDE 20 AMP, SINGLE PHASE, 120/240 (OR 120/208) VAC, 60HZ SERVICE FOR VERIZON SITE.
9. ALL THE WIRES INSIDE THE POLE SHOULD RUN INTO 2" 3-CELL MAXCELL INNERDUCT.

verizon

2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

Vinculum

575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500

ALL STATES
ENGINEERING & SURVEYING
A ZALZALI & ASSOCIATES COMPANY

23675 BIRTCHE DRIVE
LAKE FOREST, CA 92630
PHONE: (949) 273-0996

PROJECT ID: P-334882

DRAWN BY: RF

CHECKED BY: DW

REV	DATE	DESCRIPTION	
3	11/20/2020	CITY COMMENTS	MG
2	08/31/2020	100% CD'S FOR SUBMITTAL	MG
1	06/11/2020	100% CD'S FOR SUBMITTAL	RF
0	05/22/2020	100% CD'S FOR APPROVAL	RF
B	05/04/2020	95% CD'S FOR REDLINE	RF
A	04/29/2020	90% CD'S FOR REDLINE	RF




IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 061
LIC R.O.W. ADJACENT TO:
1221 MIDDLEFIELD RD.
PALO ALTO, 94301
LOCATION CODE: 425208

SHEET TITLE
ELECTRICAL/GROUNDING
DIAGRAMS, NOTES, &
PANEL SCHEDULE

SHEET NUMBER

E-1



ADDITIONAL NOTES:
1.ASSIST RESIDENCE WITH IN/OUT ACCESS TO DRIVEWAYS ALONG THE CLOSURE WHEN SAFE TO DO SO.

- LEGEND:**
- CHANNELIZING DEVICE WITH K-RAIL/WATER FILLED BARRIERS
 - CLIP-ON SIGN
 - CHANNELIZING DEVICE
 - SIGN
 - WORK ZONE
 - DIRECTION OF TRAFFIC
 - TYPE 1 BARRICADE
 - TYPE 1 BARRICADE W/SIGN
 - TYPE 3 BARRICADE
 - TYPE 3 BARRICADE W/SIGN
 - TEMP RAISED MARKERS
 - ARROW BOARD MARKER
 - PEDESTRIAN BARRICADES
 - CERTIFIED FLAGGER
 - CRASH BARRELS
 - MESSAGE BOARD (PCMS)
 - FLASHING ARROWBOARD
 - CRASH ATTENUATORS
 - FLASHING BEACON/BARRICADE LIGHT

***POST TEMPORARY NO PARKING SIGN ON TYPE 1 BARRICADE 72 HRS IN ADVANCED.**

NOTE: Please contact B.A.T.S 72 hrs in advance in case if we are to install "TEMPORARY NO PARKING" signs.

- NOTES**
- Traffic control shall conform with the most current CAMUTCD part 6 and/or Caltrans Standards
 - One lane of traffic in each direction and all high volume turning lanes shall be maintained at all times on all streets at a minimum lane width of 10 feet.
 - Contractor shall notify local authorities once signs are posted.
 - All advanced warning signs shall be equipped with 2 (18" orange flags)
 - Certified Traffic Control Workers shall have Type II vests, work shoes, and hard hats.
 - Temporary no parking signs shall be placed a min of 72 hrs prior of work.
 - Driveways shall be monitored and maintained at all times during work hours.
 - Distance between sign and work area will be determined on speed limit.
 - Roadway shall not be opened until safe for public use. All open trenches must be plated or - backfilled prior to public usage.
 - All Devices shall be removed when no longer required.

MEANING OF LETTER CODES ON TYPICAL APPLICATION DIAGRAMS	ROAD TYPE			DISTANCE BETWEEN SIGNS		
		A	B	C		
	Urban (Low Speed) - 25 mph or less	100 ft	100 ft	100 ft		
	Urban (Low Speed) + 25 to 40 mph	250 ft	250 ft	250 ft		
	Urban (High Speed) + 40 mph	350 ft	350 ft	350 ft		
	Rural	500 ft	500 ft	500 ft		
	Expressway / Freeway	1,000 ft	1,500 ft	2,640 ft		

COMPASS:

SCALE:

NOT TO SCALE

PROJECT LOCATION:

1211 MIDDLEFIELD RD.,
PALO ALTO, CA

REQUEST BY:

YVONNE WASHINGTON
VINCULUMS
925-999-5523
YWASHINGTON@VINCULUMS.COM

DATE REQSTD: 4/24/20

DATE COMPLTD: 10/3/20

P0# SF PALO ALTO 061

PAGE# 1/1 (REVISION 2)

B.A.T.S. AFTER HOURS EMERGENCY 510-299-5666

44800 Industrial Drive Fremont, CA 94538
WWW.BATSTRAFFICSOLUTIONS.COM

B.A.T.S. TRAFFIC SOLUTIONS

Drawn By:
DREW PATEL
CSLB# 917034
Office: 510-657-2543
Fax: 510-657-2544



575 Lennon Lane #125
Walnut Creek, CA 94598
(925) 482-8500

VERIZON
PALO ALTO_061



23675 Birtcher Dr.
Lake Forest, CA
(949) 273-0996

All States Engineering & Surveying
Project No. 64 - CLUSTER-01PALO_ALTO_061

Structural Analysis Report

ROW Adjacent to 1221 Middlefield Rd. Palo Alto, 94301
Proposed 29'-0" AGL 'Downtown' Style Aluminum Light Pole & Foundation



Rev. #	Reason for Revision	Total # of Sheets	Prepared By	Checked By	Approved /Accepted	Date
2	CDs Revised	19	LeT	LeT	WZ	9/25/2020

	Quantity/Type /Shape	Strength (min.)	Dimensions	Thickness /Depth	Capacity Utilization
Pole Shaft:	Aluminum / 8-sided tapered	25 ksi*	5.73" ϕ at top 10.0" ϕ at bottom	0.219"	44.6 % PASS
Anchor Bolts	4	36 ksi	1" ϕ	-	44.0 % PASS
Base Plate	1	36 ksi	13.6" Cast Base	-	ADEQUATE
Foundation	Circular Caisson	3.25 ksi*	36" Dia.	7'-0"***	ADEQUATE

* Pole grade is 6063-T6 per provided specs.

** Required depth of caisson (Unrestrained at G/L) - This analysis was performed without a soil report, and minimum soil properties from IBC 18 were used. Required pole foundation embedment depth may change with a soil report from the proposed pole location.

Professional Engineering Firm
ARCHITECTURAL, CIVIL, STRUCTURAL, ELECTRICAL, GEOTECHNICAL, SURVEYING
www.allstatesengineering.com

Hazards by Location

Search Information

Address: 6011 Brown Ln., Bakersfield, CA 93308, USA
Coordinates: 36.3281277, -119.0741919
Elevation: 380 ft
Timezone: 2020-06-21T19:36:22-06:02
Hazard Type: Wind



ASCE 7-16		ASCE 7-10		ASCE 7-05	
MR1 10-Year	65 mph	MR1 10-Year	72 mph	ASCE 7-05 Wind Speed	80 mph
MR1 25-Year	71 mph	MR1 25-Year	79 mph		
MR1 50-Year	78 mph	MR1 50-Year	86 mph		
MR1 100-Year	81 mph	MR1 100-Year	91 mph		
Risk Category I	88 mph	Risk Category I	100 mph		
Risk Category II	94 mph	Risk Category II	110 mph		
Risk Category III	101 mph	Risk Category III-IV	115 mph		
Risk Category IV	105 mph				

The results indicated here DO NOT reflect any state or local amendments to the values or any definition lines made during the building code adoption process. Users should confirm any output obtained from this tool with the local Authority Having Jurisdiction before proceeding with design.

Disclaimer

Hazard loads are interpolated from data provided in ASCE 7 and rounded up to the nearest whole integer. For ASCE 7, winds and coastal areas outside the last contour should use the last wind speed contour of the coastal area - In some cases, this website will extrapolate past the last wind speed contour and therefore, provide a wind speed that is slightly higher. NOTE: For queries near wind-coastal areas region boundaries, the resulting determination is sensitive to rounding when any exact parameter or not it is concerned to be within a wind-coastal area region.

Manufacture terms, gages, codes, priorities, and special wind regions shall be examined for unusual wind conditions.

While the information presented on this website is believed to be correct, ATC and its operators and contributors assume no responsibility or liability for its accuracy. The material presented in the report should not be used or relied upon for any specific application without competent examination and verification of its accuracy, suitability and applicability by engineers or other licensed professionals. ATC does not intend that the use of this information replace the sound judgment of such competent professionals, having experience and knowledge in the field of practice, nor to substitute for the standard of care required of such professionals in interpreting and applying the results of the report provided by the website. Users of the information from this website assume all liability arising from such use. Use of the output of this website does not imply approval by the governing building code bodies responsible for building code approval and interpretation for the building site described by latitude/longitude location in the report.

Steel Decorated Pole
Palo Alto
PALO_ALTO_061



Project Description:

All States Engineering & Surveying (ASES) is pleased to submit this "Structural Analysis Report" to determine the structural integrity of the metal pole. The purpose of the analysis is to determine acceptability of the pole stress level. Based on our analysis we have determined the metal pole stress level for the structure and anchorage, under the following load case:

LC: Proposed Pole + Proposed Equipment
(Please see page 5 for details)

All modifications and equipment proposed in this report shall be installed in accordance with the attached drawings for the determined available structural capacity to be effective.


Structural Analysis Parameters:

This analysis has been performed in accordance with AASHTO 2013 guidelines.

- Wind Speed: 85 mph per AASHTO 2013
- Exposure Category: C
- Risk Category: II
- Topographical: 1
- Crest Height = 0
- Ice Thickness = 0 in
- Min. Soil Lateral Bearing = 100 psf/ft² = 200 psf/ft per CBC & IBC 1806.3.4
- Min. Soil Bearing = 1500 psf

We at All States Engineering & Surveying appreciate the opportunity of providing our continuing professional services to you. If you have any questions or need further assistance on this or any other projects, please give us a call.

Pole Wind & Seismic Analysis Based on AASHTO 2013



Hazards by Location

Search Information

Address: 1221 Middlefield Rd., Palo Alto, 94301
Coordinates: 37.446195, -122.147579
Elevation: 30 ft
Timezone: 2020-06-21T22:43:12-06:02
Hazard Type: Seismic
Reference Document: ASCE7-16
Risk Category: II
Site Class: D-Default



Basic Parameters

Item	Value	Description
S _g	1.582	MCE _g ground motion (period=0.2s)
S ₁	0.4	MCE ₁ ground motion (period=1.0s)
S _u	1.898	Site-modified spectral acceleration value
S _u	*null	Site-modified spectral acceleration value
S _{0.2}	1.269	Nominal seismic design value at 0.2s SA
S _{0.4}	*null	Nominal seismic design value at 1.0s SA

* See Section 11.4.4.8

Additional Information

Item	Value	Description
SDC	*null	Seismic design category
F _g	1.2	Site amplification factor at 0.2s
F ₁	*null	Site amplification factor at 1.0s
CR _g	0.826	Coefficient of risk (0.2s)
CR ₁	0.808	Coefficient of risk (1.0s)
PGA	0.65	MCE _g peak ground acceleration
F _{PGA}	1.2	Site amplification factor at PGA
PGA _u	0.78	Site modified peak ground acceleration
T _L	12	Long period transition period (s)
Se _{MT}	1.903	Probabilistic risk-targeted ground motion (0.2s)
Se _{MT1}	2.109	Factored uniform-based spectral acceleration (2% probability of exceedence in 50 years)
Se ₀	1.582	Factored deterministic acceleration value (0.2s)
S1RT	0.772	Probabilistic risk-targeted ground motion (1.0s)
S1MT1	0.861	Factored uniform-based spectral acceleration (2% probability of exceedence in 50 years)
S1D	0.6	Factored deterministic acceleration value (1.0s)
PGA _d	0.65	Factored deterministic acceleration value (PGA)

* See Section 11.4.4.8

The results indicated here DO NOT reflect any state or local amendments to the values or any definition lines made during the building code adoption process. Users should confirm any output obtained from this tool with the local Authority Having Jurisdiction before proceeding with design.

Pole Wind & Seismic Analysis Based on AASHTO 2013

Rad Center	Component Type	QUANTITY	MOUNT TYPE
27'-8"	(N) Ericsson SM6701 Antennas	3	Pole Mounted
17'-6"	Reserved 30" x 72" Banner	1	
8'-10"	(E) Street Sign	1	
-	(N) RF Signage	1	Inside Pole
-	(N) & (E) Conduit, Wire, & In-line Fuse	-	

WIND PRESSURE DERIVATION (AASHTO 2013)

Height of Pole	R = 25.0 ft	
Wind Speed	V = 85 mph	(AASHTO 2013)
Wind Exposure (B, C or D)	C	
Wind Directionality (Pole)	K _d = 0.95	(AASHTO 2013, Table 3.8.5-1)
Gust Effect Factor	G = 1.14	(AASHTO 2013, Sec. 3.8.6)
3-sec Gust Exponent	α = 0.90	(ASCE 7-16, Table 26.7-1)
Atmospheric Height	Z _a = 900 ft	(ASCE 7-16, Table 26.7-1)
Veil Pressure Coeff (Min)	K _z = 0.84	(ASCE 7-16, Table 29.10-1)
Velocity Pressure Coeff	K _z = 2.01/27.0 = 0.67	(AASHTO 2013, Equation 3.8-4-1)
Wind Force @ Pole top	F _w = 0.00258K _d GVP(C _e)A = 19.4 lbf/ft ²	(Wind Pressure Input For O-Calc Analysis)

Total Applied Shear	V _s = 1143 lbs	(From TNX Report)
Total Applied Moment	M _s = 17007 lb-ft	(From TNX Report)

CALCULATION OF WIND DRAG COEFFICIENTS (Cd) FROM AASHTO 2013, TABLE 3.8.7-1

Appurtenance	Height (in)	Width (in)	Depth (in)	d (in)	C _d Va	C _d
(N) Ericsson SM6701 Antennas	32.2	10.2	7.3	1.05	-	1.70
(E) Round Luminaire	2.9	88.0	-	0.24	20	0.50
(E) Round Pole	348	7.65	-	0.65	50	0.99

SEISMIC LOAD ANALYSIS (ASCE 7-16)

Total Pole Weight	W = P ₁ = 842 lbs	
Spectral Response (Short)	S _{RS} = 1.582	(Approximate W ₁ including Pole W ₁ (N) Components)
Spectral Response (1 sec)	S ₁ = 0.600	(ATC Hazards Design Maps Summary)
Importance Factor	I _s = 1.0	(ASCE 7-16, Section 15.4.1.1)
Response Factor	R = 1.5	(ASCE 7-16, Table 15.4-2)
Seismic Response Coeff	C _s = 0.044S _{RS} = 0.070	(ASCE 7-16, Section 15.4-1)
Seismic Response Coeff	C _s = 0.85/(R/I _s) = 0.320	(ASCE 7-16, Section 15.4-1)
Seismic Response Coeff	C _s = S _{RS} /(R/I _s) = 1.058	(ASCE 7-16, Section 15.4-2)
Lateral Seismic Force	V _s = MAX(C _s W) = 1.058 W	
Total Applied Shear	V _s = 877 lbs	
Total Applied Moment	M _s = V _s (2/3)h = 13091 lb-ft	

(Wind Loads Governing For Pole Shaft Capacity Check)

verizon
2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

Vinculums
575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500

ALL STATES
ENGINEERING & SURVEYING
A ZALZALI & ASSOCIATES COMPANY
23675 BIRTCHER DRIVE
LAKE FOREST, CA 92630
PHONE: (949) 273-0996

PROJECT ID: P-334882

DRAWN BY: RF

CHECKED BY: DW

REV	DATE	DESCRIPTION	
3	11/20/2020	CITY COMMENTS	MG
2	06/31/2020	100% CD'S FOR SUBMITTAL	MG
1	06/11/2020	100% CD'S FOR SUBMITTAL	RF
0	05/22/2020	100% CD'S FOR APPROVAL	RF
B	05/04/2020	95% CD'S FOR REDLINE	RF
A	04/29/2020	90% CD'S FOR REDLINE	RF



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.


SF PALO ALTO 061
LIC R.O.W. ADJACENT TO:
1221 MIDDLEFIELD RD.
PALO ALTO, 94301
LOCATION CODE: 425208

SHEET TITLE

CALCS

SHEET NUMBER

C-1



DESIGNED APPURTENANCE LOADING					
TYPE	ELEVATION	TYPE	ELEVATION		
Light Fixture	27.0	Light Fixture	27.0		
Sign	27.0	Sign	27.0		
Camera	27.0	Camera	27.0		
2" x 4" x 1/2" Light Fixture	27.0	2" x 4" x 1/2" Light Fixture	27.0		
MATERIAL STRENGTH					
GRADE	Fy	Fu	GRADE	Fy	Fu
A572-50	50	65	A572-50	50	65
TOWER DESIGN NOTES					
1. Tower is located in Santa Clara County, California.					
2. Tower designed for Exposure C to the ASHTO 2013 Standard.					
3. Tower designed for a 60 mph basic wind in accordance with the ASHTO 2013 Standard.					
4. Deflections are based upon a 60 mph wind.					
5. Tower Structure Class II.					
6. Topographic Category I with Crest Height of 6.0 ft.					
7. TOWER RATING: 44.6					

ALL STATES
ENGINEERING & SURVEYING
23675 BIRCHER DRIVE
LAKE FOREST, CA 92630
PHONE: (949) 273-0996
FAX: (949) 806-7222

PALO ALTO LIGHT POLE
S4 - Vinculum, V2W
ASHTO 2013
09/10/20
N12
S-1

Steel Decorated Pole
Palo Alto
PALO ALTO_061

Maximum Reactions						
Location	Condition	Gen. Load Comb.	Vertical lb	Horizontal, X lb	Horizontal, Z lb	
Pole	Max. Vert.	4	641.74	-568.52	568.52	
	Max. Hx	3	481.31	299.21	1103.22	
	Max. Hy	3	481.31	299.21	1103.22	
	Max. Mx	2	16141.04	299.21	1103.22	
	Max. My	2	16141.04	299.21	1103.22	
	Max. Tension	5	451.73	-1103.19	-299.19	
	Min. Vert.	7	481.31	-1103.19	-299.19	
	Min. Hx	6	641.74	-1103.22	-299.21	
	Min. Hy	6	641.74	-1103.22	-299.21	
	Min. Mx	7	-4423.78	-1103.19	-299.19	
	Min. My	7	-4423.78	-1103.19	-299.19	
	Min. Tension	1	0.06	-0.45	-0.43	

Tower Mast Reaction Summary						
Load Combination	Vertical lb	Shear, lb	Shear, lb	Overturning Moment, Mx lb-ft	Overturning Moment, My lb-ft	Torque lb-ft
Dead Only	534.78	0.45	0.43	-415.78	433.18	-0.06
1.2 Dead-1.6 Wind 0 deg - No Ice	641.74	-299.21	-1103.22	-16141.04	5357.16	-317.41
0.9 Dead-1.6 Wind 0 deg - No Ice	481.31	-299.21	-1103.22	-15948.28	5202.28	-319.18
1.2 Dead-1.6 Wind 45 deg - No Ice	641.74	568.52	-568.52	-8154.36	-7106.98	-449.18
0.9 Dead-1.6 Wind 45 deg - No Ice	481.31	568.50	-568.50	-7991.78	-7212.79	-451.73
1.2 Dead-1.6 Wind 90 deg - No Ice	641.74	1103.22	299.21	4310.87	-15094.41	-317.34
0.9 Dead-1.6 Wind 90 deg - No Ice	481.31	1103.19	299.19	4423.78	-15168.98	-319.16
Dead-Wind 0 deg - Service	534.78	-83.32	-307.27	-4766.74	1782.95	-88.98
Dead-Wind 45 deg - Service	534.79	158.35	-158.25	-2545.54	-1678.95	-125.77
Dead-Wind 90 deg - Service	534.79	307.23	83.36	915.01	-3897.06	-88.90

Compression Checks

Pole Design Data									
Section No.	Elevation ft	Size	L in	Le in	K1/r	A in ²	Pn lb	Phi* lb	Ratio Pn/Phi*
L1	29 - 0 (1)	TP10x5.73x0.219	29.00	29.00	97.7	7.1116	-639.51	12868.00	0.005

Steel Decorated Pole
Palo Alto
PALO ALTO_061

Tower Input Data

The tower is a monopole.
This tower is designed using the AASHTO 2013 standard.
The following design criteria apply:
Tower is located in Santa Clara County, California.
Basic wind speed of 85 mph.
Structure Class II.
Exposure Category C.
Topographic Category I.
Crest Height 0.00 ft.
Deflections calculated using a wind speed of 60 mph.

Tapered Pole Section Geometry

Section	Elevation ft	Section Length ft	Splice Length ft	Number of Sides	Top Diameter in	Bottom Diameter in	Wall Thickness in	Band Radius in	Pole Grade
L1	29.00-0.00	29.00		8	5.7300	10.0000	0.2190	0.8760	6061-T6 (25 ksi)

Tapered Pole Properties

Section	Tip Dia. in	Area in ²	I in ⁴	r in	C in	J in ⁴	I/C in ³	w lb/ft	w1 lb/ft
L1	6.0217	4.0069	16.0550	2.0060	3.0999	5.1791	32.8863	1.9529	1.4656
	10.6435	7.1116	89.7569	3.5603	5.4100	16.5909	183.8543	3.4661	3.2333

Tower Elevation ft	Chenest Area (per face) in ²	Chenest Thickness in	Chenest Grade	Adjust. Factor A1	Adjust. Factor A2	Weight Multi. Factor A3	Double-Angle Spacing Diagonals in	Double-Angle Spacing Horizontal in	Double-Angle Spacing Radial in
L1 29.00-0.00				1	1	1			

Feed Line/Linear Appurtenances - Entered As Area

Description	Face or Leg	Allow Area	Exclude From Calculation	Component Type	Placement	Total Number	CpAs ft ²	Weight plf
Existing Cable Inside Pole	C	No	Yes	CuAs (Out Of Face)	26.00 - 0.00	1	No Ice 0.06	0.15

Feed Line/Linear Appurtenances Section Areas

Tower Section	Tower Elevation ft	Face	As	Ar	CpAs In Face ft ²	CpAs Out Face ft ²	Weight lb
L1	29.00-0.00	A	0.000	0.000	0.000	0.000	0.00
		D	0.000	0.000	0.000	0.000	0.00
		C	0.000	0.000	0.000	1.638	3.90
		D	0.000	0.000	0.000	0.000	0.00

Steel Decorated Pole
Palo Alto
PALO ALTO_061

Pole Bending Design Data

Section No.	Elevation ft	Size	Mn lb-ft	Phi Mn lb-ft	Ratio Mn/Phi Mn	Mp lb-ft	Phi Mp lb-ft	Ratio Mp/Phi Mp
L1	29 - 0 (1)	TP10x5.73x0.219	17066.83	38573.92	0.441	0.00	38573.92	0.000

Pole Shear Design Data

Section No.	Elevation ft	Size	Actual Vn lb	Phi Vn lb	Ratio Vn/Phi Vn	Actual Tv lb	Phi Tv lb	Ratio Tv/Phi Tv
L1	29 - 0 (1)	TP10x5.73x0.219	1144.31	99206.40	0.012	317.35	80323.58	0.004

Pole Interaction Design Data

Section No.	Appurtenances	Phi Mn	Phi Mp	Phi Vn	Phi Tv	Ratio Mn/Phi Mn	Ratio Mp/Phi Mp	Ratio Vn/Phi Vn	Ratio Tv/Phi Tv
L1	PP-1111	41000	31441	0.000	0.012	0.004	0.446	1.000	44.2

Section Capacity Table

Section	Elevation ft	Component Type	Size	Critical Element	P lb	Phi P lb	Phi P/Phi Pn	Phi P/Phi Pn	Phi P/Phi Pn
L1	29 - 0	Pole	TP10x5.73x0.219	I	-639.51	12868.00	44.6	Pass	Pass
					Pole (L1) Summary				
					Base Plate				
					Rating = 44.6				

HILTI
Hilti PROFIS Engineering 3.0.64

www.hilti.com

Company: All State Eng. & Surveying
Address: 23675 Birchier Dr. Lake Forest, CA 92630
Phone / Fax: 949.273.0996 /
Design: Concrete - Sep 9, 2020 (1)
Fastening point:
Page: 9/25/2020
E-Mail:
Date:


Specifier's comments:

1 Input data

Anchor type and diameter: Heavy Hex Head ASTM F 1554 GR. 36 1
Item number: Not available
Effective embedment depth: he = 25.000 in
Material: ASTM F 1554
Proof: Design Method ACI 318-08 / CIP
Stand-off installation: without clamping (anchor); restraint level (anchor plate): 1.00; ee = 1.250 in.; t = 0.500 in.
Anchor plate: L x t = 13.000 in. x 13.000 in. x 0.500 in.; (Recommended plate thickness: not calculated)
Profile: Round HSS (AISC), HSS10K 168; (L x W x T) = 10.000 in. x 10.000 in. x 0.188 in.
Base material: cracked concrete, 3000, f'c = 3.000 ksi; f = 84.000 in.
Reinforcement: tension: condition A, shear: condition B, anchor reinforcement: tension edge reinforcement: > No. 4 bar with stirrups
Seismic loads (cat. C, D, E, or F): no

* - The anchor calculation is based on a rigid anchor plate assumption.

Geometry [in.] & Loading [lb, ft-lb]



Input data and results must be checked for conformity with the existing conditions and for plausibility!
PROFIS Engineering (c) 2000-2020 Hilti AG, Hilti-Software. Hilti is a registered trademark of Hilti AG, Schwanau.

verizon

2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

Vinculum

575 LENNON LANE #125
LAKE FOREST, CA 92630
OFFICE: (925) 482-8500

ALL STATES
ENGINEERING & SURVEYING
A ZALZALI & ASSOCIATES COMPANY

23675 BIRCHER DRIVE
LAKE FOREST, CA 92630
PHONE: (949) 273-0996

PROJECT ID: P-334882

DRAWN BY: RF

CHECKED BY: DW

REV	DATE	DESCRIPTION	
3	11/20/2020	CITY COMMENTS	MG
2	06/31/2020	100% CD'S FOR SUBMITTAL	MG
1	06/11/2020	100% CD'S FOR SUBMITTAL	RF
0	05/22/2020	100% CD'S FOR APPROVAL	RF
B	05/04/2020	95% CD'S FOR REDLINE	RF
A	04/29/2020	90% CD'S FOR REDLINE	RF



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 061

LIC R.O.W. ADJACENT TO:
1221 MIDDLEFIELD RD.
PALO ALTO, 94301
LOCATION CODE: 425208

SHEET TITLE

CALCS

SHEET NUMBER

C-2



Hilti PROFIS Engineering 3.0.64

www.hilti.com	All State Eng. & Surveying	Page:	2
Company:	23675 Birtcher Dr. Lake Forest, CA 92630	Specifier:	
Address:	9492730996	E-Mail:	
Phone / Fax:	Concrete - Sep 9, 2020 (1)	Date:	9/25/2020
Design:			
Fastening point:			

Case	Description	Forces (lb) / Moments (ft-lb)	Seismic	Max. Util. Anchor (%)
1	Combination 1	$N = 842; V = 0; V_x = 1.143;$ $M_x = 17,007.000; M_y = 0.000; M_z = 0.000;$	no	44



Hilti PROFIS Engineering 3.0.64

www.hilti.com	All State Eng. & Surveying	Page:	3
Company:	23675 Birtcher Dr. Lake Forest, CA 92630	Specifier:	
Address:	9492730996	E-Mail:	
Phone / Fax:	Concrete - Sep 9, 2020 (1)	Date:	9/25/2020
Design:			
Fastening point:			

2 Proof / Utilization (Governing Cases)

Loading	Proof	Load	Capacity	R_u / R_n (%)	Status
Tension	Pullout Strength	10,902	25,217	44 / -	OK
Shear	Steel failure (with lever arm)	286	842	- / 34	OK

Loading	R_u	R_n	ζ	Utilization $R_{u,v}$ (%)	Status
Combined tension and shear loads	0.432	0.339	5/3	42	OK

3 Warnings

- Please consider all details and hints/warnings given in the detailed report!

Fastening meets the design criteria!



Project Title: Light Pole Caisson Embedment Depth
Engineer: Zalzai & Associates, Inc.
Project ID: Palo Alto Light Pole
Project Descr:

Concrete Caisson

DESCRIPTION: Design Concrete Caisson

Code References

Calculations per ACI 318.14, IBC 2018, CBC 2018, ASCE 7-16;
Load Combinations Used: ASCE 7-16

General Information

f_c - Concrete 28 day strength	=	3,250 ksi
E_c	=	3,122.0 ksi
Density	=	150.0 pcf
f_y - Main Rebar	=	60.0 ksi
E_s - Main Rebar	=	29,000.0 ksi
Allow. Reinforcing Limits	=	0.250 %
Min. Reinf.	=	0.250 %
Max. Reinf.	=	8.0 %

Overall Caisson Height = 7.0 ft
End Fixity: Top Free, Bottom Fixed
Brace condition for deflection (buckling) along Caisson:
X-X (left) axis: Fully braced against buckling ABOUT Y-Y Axis
Y-Y (right) axis: Fully braced against buckling ABOUT X-X Axis

Caisson Dimensions: 36.0 in Diameter
Cross Section

Caisson Reinforcing



Applied Loads

Caisson self weight included: 7,422.0 lb * Dead Load Factor
AXIAL LOADS: Edge to Rebar Edge Cover = 3.0 in
Reaction from Pole: Axial Load at 7.0 ft above base, $D = 0.6420 \times$
BENDING LOADS: ...
Reaction from Pole: Lat. Point Load at 7.0 ft creating $M_{x-x} = 1,926 \text{ k-ft}$
Reaction from Pole: Moment about X-X axis at 7.0 ft, $M_x = 28.36 \text{ k-ft}$

DESIGN SUMMARY

Load Combination: +0.90D+1.60H
Location of rebar above base: 6.953 ft
Maximum Stress Ratio: $R_u / R_n = (P_u / A_g f_c) + (M_u / S_x f_y) + (M_y / S_y f_y) = 0.999 < 1$

$P_u = 7,258 \text{ k}$
 $M_{u-x} = 28,211 \text{ k-ft}$
 $M_{u-y} = 0.0 \text{ k-ft}$
 $\phi = 0.9$
 $\phi P_n = 65,887 \text{ k}$
 $\phi M_{n-x} = 350,890 \text{ k-ft}$
 $\phi M_{n-y} = 0.0 \text{ k-ft}$

$\mu = 0.0$
 μ at Angle = 0.0 deg
 μ at Angle = 28.211 k-ft
 ϕM_n at Angle = 350,522 k-ft
 P_n & M_n values located at P_u/M_u vector intersection with capacity curve

Caisson Capacities: ...
Prism: Nominal Max. Compressive Axial Capacity: 3,024.81 k
Prism: Nominal Min. Tension Axial Capacity: 3,720 k-ft
 ϕP_n max: Usable Compressive Axial Capacity: 1,799.75 k
 ϕP_n min: Usable Tension Axial Capacity:

Entered loads are factored per load combinations specified by user!

Maximum SERVICE Load Reactions: ...
Top along Y-Y: 0.0 k
Bottom along Y-Y: 0.0 k
Top along X-X: 0.0 k
Bottom along X-X: 1,142 k

Maximum SERVICE Load Deflections: ...
Along Y-Y: 0.0 in
Along X-X: 0.0 in
for load combination: W Only
for load combination: W Only

General Section Information: $\phi = 0.70$, $\beta = 0.850$, $\rho = 0.880$
 ρ : % Reinforcing: 0.3655 %
Reinforcing Area: 3.720 in²
Concrete Area: 1,017.88 in²



Hilti PROFIS Engineering 3.0.64

www.hilti.com	All State Eng. & Surveying	Page:	4
Company:	23675 Birtcher Dr. Lake Forest, CA 92630	Specifier:	
Address:	9492730996	E-Mail:	
Phone / Fax:	Concrete - Sep 9, 2020 (1)	Date:	9/25/2020
Design:			
Fastening point:			

4 Remarks; Your Cooperation Duties

- Any and all information and data contained in the Software concern solely the use of Hilti products and are based on the principles, formulas and security regulations in accordance with Hilti's technical directions and operating, mounting and assembly instructions, etc. that must be strictly complied with by the user. All figures contained therein are average figures, and therefore use-specific tests are to be conducted prior to using the relevant Hilti product. The results of the calculations carried out by means of the Software are based essentially on the data you put in. Therefore, you bear the sole responsibility for the absence of errors, the completeness and the relevance of the data to be put in by you. Moreover, you bear sole responsibility for having the results of the calculation checked and cleared by an expert, particularly with regard to compliance with applicable norms and permits, prior to using them for your specific facility. The Software serves only as an aid to interpret norms and permits without any guarantee as to the absence of errors, the correctness and the relevance of the results or suitability for a specific application.
- You must take all necessary and reasonable steps to prevent or limit damage caused by the Software. In particular, you must arrange for the regular backup of programs and data and, if applicable, carry out the updates of the Software offered by Hilti on a regular basis. If you do not use the AutoUpdate function of the Software, you must ensure that you are using the current and thus up-to-date version of the Software in each case by carrying out manual updates via the Hilti Website. Hilti will not be liable for consequences, such as the recovery of lost or damaged data or programs, arising from a culpable breach of duty by you.

Input data and results must be checked for conformity with the existing conditions and for plausibility!
PROFIS Engineering (C) 2000-2020 Hilti AG. Hilti is a registered trademark of Hilti AG, Schaan

4



Project Title: Light Pole Caisson Embedment Depth
Engineer: Zalzai & Associates, Inc.
Project ID: Palo Alto Light Pole
Project Descr:

Pole Footing Embedded in Soil

DESCRIPTION: Proposed Caisson embedment (soil values from IBC Table 1905.2 with linear bearing load increase from IBC 1806.3.4)

Code References

Calculations per IBC 2018 1807.3, CBC 2019, ASCE 7-16
Load Combinations Used: ASCE 7-16

General Information

Pole Footing Shape: Circular
Pole Footing Diameter: 36.0 in
Calculate Min. Depth for Allowable Pressures:
No Lateral Restraint at Ground Surface
Allow Passive: 200.0 pcf
Max Passive: 1,500.0 pcf

Controlling Values

Governing Load Combination: +0.9D+1.6H
Corner Load: 1,142 k
Moment: 17.0 k-ft

Pressure at 1/3 Depth:
Actual: 448.864 pcf
Allowable: 450.187 pcf

Minimum Required Depth: 6.875 ft

Footing Base Area: 7.069 ft²
Maximum Soil Pressure: 1,000.92 pcf


Applied Loads

Lateral Concentrated Load (k)	Lateral Distributed Loads (k/ft)	Vertical Load (k)
D: Dead Load		0.6420 k
L: Live Load		
S: Snow Load		
W: Wind Load	1.743 k/ft	
E: Earthquake		
H: Lateral Earth Load		
Load Distance above ground surface	14.889 ft	

Load Combination Results

Load Combination	Force @ Ground Surface (k)	Moment @ Ground Surface (k-ft)	Required Depth (ft)	Pressure at 1/3 Depth (pcf)	Soil Pressure Factor
+0.9D+1.6H	1,142	17,000	6.88	448.9	450.2

NOTE: THIS INFORMATION MAY NOT CONTAIN ALL DETAILS REQUIRED FOR CONSTRUCTION. APPROPRIATE MODIFICATION MAY BE REQUIRED TO ENSURE SUITABILITY OF THESE DRAWINGS FOR THE SPECIFIC APPLICATION. IT IS THE USER'S RESPONSIBILITY TO ENSURE INSTALLATION OF THE EQUIPMENT/SYSTEM IS IN ACCORDANCE WITH BUILDING/PROJECT SPECIFICATIONS, APPLICABLE CODES AND STANDARDS.



DO NOT SCALE DRAWINGS

ALL STATES
ENGINEERING & SURVEYING
23675 BIRTCHER DRIVE
LAKE FOREST, CA 92630

Vinculums
575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500



2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598



575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500



23675 BIRTCHER DRIVE
LAKE FOREST, CA 92630
PHONE: (949) 273-0996

PROJECT ID: P-334882

DRAWN BY: RF

CHECKED BY: DW

REV	DATE	DESCRIPTION	
3	11/20/2020	CITY COMMENTS	MG
2	06/31/2020	100% CD'S FOR SUBMITTAL	MG
1	06/11/2020	100% CD'S FOR SUBMITTAL	RF
0	05/22/2020	100% CD'S FOR APPROVAL	RF
B	05/04/2020	95% CD'S FOR REDLINE	RF
A	04/29/2020	90% CD'S FOR REDLINE	RF



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 061
LIC R.O.W. ADJACENT TO:
1221 MIDDLEFIELD RD.
PALO ALTO, 94301
LOCATION CODE: 425208

SHEET TITLE

CALCS

SHEET NUMBER

C-3

GENERAL CONSTRUCTION NOTES

1.

ALL WORK SHALL CONFORM TO THE REQUIREMENTS OF THE LOCAL BUILDING CODE, THE LATEST EDITION AND ALL OTHER APPLICABLE CODES AND ORDINANCES.
2.

CONTRACTOR SHALL CONSTRUCT SITE IN ACCORDANCE WITH THESE DRAWINGS AND CONSTRUCTION SPECIFICATIONS 80-TI196-1 REV H. THE SPECIFICATION IS THE RULING DOCUMENT AND ANY DISCREPANCIES BETWEEN THE SPECIFICATION AND THESE DRAWINGS SHOULD BE BROUGHT TO THE ATTENTION OF THE ENGINEER PRIOR TO PROCEEDING WITH CONSTRUCTION
3.

CONTRACTOR SHALL VISIT THE JOB SITE AND SHALL FAMILIARIZE HIMSELF WITH ALL CONDITIONS AFFECTING THE PROPOSED WORK (ROOF FRAMING, ELECTRICAL SERVICE, LOCAL PLANNING CODES, ETC.) AND SHALL MAKE PROVISIONS AS TO THE COST THEREOF. CONTRACTOR SHALL BE RESPONSIBLE FOR FAMILIARIZING HIMSELF WITH ALL CONTRACT DOCUMENTS, FIELD CONDITIONS AND DIMENSIONS AND CONFIRMING THAT THE WORK MAY BE ACCOMPLISHED AS SHOWN PRIOR TO PROCEEDING WITH CONSTRUCTION. ANY DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE ENGINEER PRIOR TO THE COMMENCEMENT OF WORK; NO COMPENSATION WILL BE AWARDED BASED ON CLAIM OF LACK OF KNOWLEDGE OF FIELD CONDITIONS
4.

PLANS ARE NOT TO BE SCALED. THESE PLANS ARE INTENDED TO BE A DIAGRAMMATIC OUTLINE ONLY UNLESS OTHERWISE NOTED. THE WORK SHALL INCLUDE FURNISHING MATERIALS, EQUIPMENT AND APPURTENANCES, AND LABOR NECESSARY TO EFFECT ALL INSTALLATIONS AS INDICATED ON THE DRAWINGS. OWNER PROVIDED MATERIALS WILL INCLUDE THE FOLLOWING, UNLESS NOTED OTHERWISE:
A) TRANSMITTER
B) RF FILTER
C) MFTS RACK
D) AUXILIARY EQUIPMENT IN MFTS RACK
E) PUMP ASSEMBLY
F) HEAT EXCHANGER
G) HOSE AND HOSE MANIFOLDS (ANY COPPER OR STEEL SECTIONS PROVIDE BY CONTRACTOR)
H) UHF ANTENNA AND MOUNTING BRACKETS, GPS ANTENNAS AND KU ANTENNAS
I) UHF COAX AND HANGERS
K) 480-208 # 208-400 ELECTRICAL TRANSFORMERS (RE: E-2 FOR SPECIALIZED TRANSFORMERS PROVIDED BY CONTRACTOR)
L) AUTOMATIC TRANSFER SWITCH AND GENERATOR
M) EQUIPMENT SHELTER (SHELTERS FURNISHED IN FACTORY W/ HVAC EQUIPMENT AND ELECTRICAL DISTRIBUTION PANEL)
N) INTEGRATED LOAD CENTER
5.

DIMENSIONS SHOWN ARE TO FINISH SURFACES UNLESS OTHERWISE NOTED. SPACING BETWEEN EQUIPMENT IS REQUIRED CLEARANCE. THEREFORE, IT IS CRITICAL TO FIELD VERIFY DIMENSIONS, SHOULD THERE BE ANY QUESTIONS REGARDING THE CONTRACT DOCUMENTS, EXISTING CONDITIONS AND/OR DESIGN INTENT, THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING THE WORK.
6.

DETAILS ARE INTENDED TO SHOW DESIGN INTENT. MODIFICATIONS MAY BE REQUIRED TO SUIT JOB DIMENSIONS OR CONDITIONS, AND SUCH MODIFICATIONS SHALL BE INCLUDED AS PART OF THE WORK.
7.

CONTRACTOR SHALL RECEIVE CLARIFICATION IN WRITING, AND SHALL RECEIVE IN WRITING AUTHORIZATION TO PROCEED BEFORE STARTING WORK ON ANY ITEMS NOT CLEARLY DEFINED OR IDENTIFIED BY THE CONTRACT DOCUMENTS.
8.

CONTRACTOR SHALL SUPERVISE AND DIRECT THE WORK USING THE BEST CONSTRUCTION SKILLS AND ATTENTION. CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES AND PROCEDURES AND FOR COORDINATING ALL PORTIONS OF THE WORK UNDER CONTRACT, UNLESS OTHERWISE NOTED.
9.

CONTRACTOR SHALL BE RESPONSIBLE FOR THE SAFETY OF THE WORK AREA, ADJACENT AREAS AND BUILDING OCCUPANTS THAT ARE LIKELY TO BE AFFECTED BY THE WORK UNDER THIS CONTRACT. WORK SHALL CONFORM TO ALL OSHA REQUIREMENTS.
10.

CONTRACTOR SHALL COORDINATE HIS WORK WITH THE SUPERINTENDENT OF BUILDINGS & GROUNDS AND SCHEDULE HIS ACTIVITIES AND WORKING HOURS IN ACCORDANCE WITH THE REQUIREMENTS.
11.

CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING HIS WORK WITH THE WORK OF OTHERS AS IT MAY RELATE TO RADIO EQUIPMENT, ANTENNAS AND ANY OTHER PORTIONS OF THE WORK.
12.

INSTALL ALL EQUIPMENT AND MATERIALS IN ACCORDANCE WITH MANUFACTURERS RECOMMENDATIONS UNLESS SPECIFICALLY OTHERWISE INDICATED OR WHERE LOCAL CODES OR REGULATIONS TAKE PRECEDENCE.
13.

MAKE NECESSARY PROVISIONS TO PROTECT EXISTING SURFACES, EQUIPMENT, IMPROVEMENTS, PIPING ETC. AND IMMEDIATELY REPAIR ANY DAMAGE THAT OCCURS DURING CONSTRUCTION.
14.

IN DRILLING HOLES INTO CONCRETE WHETHER FOR FASTENING OR ANCHORING PURPOSES, OR PENETRATIONS THROUGH THE FLOOR FOR CONDUIT RUNS, PIPE RUNS, ETC., MUST BE CLEARLY UNDERSTOOD THAT REINFORCING STEEL SHALL NOT BE DRILLED INTO, CUT OR DAMAGED UNDER ANY CIRCUMSTANCES (UNLESS NOTED OTHERWISE). LOCATIONS OF REINFORCING STEEL ARE NOT DEFINITELY KNOWN AND THEREFORE MUST BE SEARCHED FOR BY APPROPRIATE METHODS AND EQUIPMENT.
15.

REPAIR ALL EXISTING WALL SURFACES DAMAGED DURING CONSTRUCTION SUCH THAT THEY MATCH AND BLEND IN WITH ADJACENT SURFACES.
16.

SEAL PENETRATIONS THROUGH FIRE RATED AREAS WITH U.L. LISTED AND FIRE CODE APPROVED MATERIALS.
17.

KEEP CONTRACT AREA CLEAN, HAZARD FREE, AND DISPOSE OF ALL DIRT, DEBRIS, AND RUBBISH. EQUIPMENT NOT SPECIFIED AS REMAINING ON THE PROPERTY OF THE OWNER SHALL BE REMOVED. LEAVE PREMISES IN CLEAN CONDITION AND FREE FROM PAINT SPOTS, DUST, OR SMUDGES OF ANY NATURE. CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING ALL ITEMS UNTIL COMPLETION OF CONSTRUCTION.
18.

MINIMUM BEND RADIUS OF ANTENNA CABLES SHALL BE IN ACCORDANCE WITH CABLE MANUFACTURERS RECOMMENDATIONS.
19.

ALL EXISTING INACTIVE SEWER, WATER, GAS, ELECTRIC AND OTHER UTILITIES, WHICH INTERFERE WITH THE EXECUTION OF THE WORK, SHALL BE REMOVED AND/OR CAPPED, PLUGGED OR OTHERWISE DISCONTINUED AT POINTS WHICH WILL NOT INTERFERE WITH THE EXECUTION OF THE WORK, SUBJECT TO APPLICABLE REGULATORY AUTHORITIES
20.

CONTRACTOR SHALL MINIMIZE DISTURBANCE TO EXISTING SITE DURING CONSTRUCTION. EROSION CONTROL MEASURES, IF REQUIRED DURING CONSTRUCTION SHALL BE IN CONFORMANCE WITH JURISDICTIONAL OR STATE AND LOCAL GUIDELINES FOR EROSION AND SEDIMENT CONTROL AND COORDINATED WITH LOCAL REGULATORY AUTHORITIES.
21.

ALL CONSTRUCTION IS TO ADHERE TO VERIZON'S INTEGRATED CONSTRUCTION STANDARDS UNLESS CALIFORNIA CODE IS MORE STRINGENT.
22.

THE INTENT OF THE PLANS AND SPECIFICATIONS IS TO PERFORM THE CONSTRUCTION IN ACCORDANCE WITH THE CALIFORNIA BUILDING STANDARDS CODE, TITLES 19 AND 24, CALIFORNIA CODE OF REGULATIONS. SHOULD ANY CONDITIONS DEVELOP NOT COVERED BY THE APPROVED PLANS AND SPECIFICATIONS WHEREIN THE FINISHED WORK WILL NOT COMPLY WITH TITLE 24, CALIFORNIA CODE OF REGULATIONS, A CHANGE ORDER DETAILING AND SPECIFYING THE REQUIRED WORK SHALL BE SUBMITTED TO AND APPROVED BY THE JURISDICTION BEFORE PROCEEDING WITH THE WORK.

SITE WORK NOTES

1.

DO NOT EXCAVATE OR DISTURB BEYOND THE PROPERTY LINES OR LEASE LINES, UNLESS OTHERWISE NOTED.
2.

DO NOT SCALE BUILDING DIMENSIONS FROM DRAWING.
3.

SIZE, LOCATION AND TYPE OF ANY UNDERGROUND UTILITIES OR IMPROVEMENTS SHALL BE ACCURATELY NOTED AND PLACED ON AS-BUILT DRAWINGS BY GENERAL CONTRACTOR AND ISSUED TO ARCHITECT/ENGINEER AT COMPLETION OF PROJECT.
4.

ALL EXISTING UTILITIES, FACILITIES, CONDITIONS AND THEIR DIMENSIONS SHOWN ON PLANS HAVE BEEN PLOTTED FROM AVAILABLE RECORDS. THE ENGINEER AND OWNER ASSUME NO RESPONSIBILITY WHATSOEVER AS TO THE SUFFICIENCY OR ACCURACY OF THE INFORMATION SHOWN ON THE PLANS OR THE MANNER OF THEIR REMOVAL OR ADJUSTMENT. CONTRACTOR SHALL BE RESPONSIBLE FOR DETERMINING EXACT LOCATION OF ALL EXISTING UTILITIES AND FACILITIES PRIOR TO START OF CONSTRUCTION. CONTRACTOR SHALL ALSO OBTAIN FROM EACH UTILITY COMPANY DETAILED INFORMATION RELATIVE TO WORKING SCHEDULES AND METHODS OF REMOVING OR ADJUSTING EXISTING UTILITIES.
5.

CONTRACTOR SHALL VERIFY ALL EXISTING UTILITIES BOTH HORIZONTALLY AND VERTICALLY PRIOR TO START OF CONSTRUCTION. ANY DISCREPANCIES OR DOUBTS AS TO THE INTERPRETATION OF PLANS SHALL BE IMMEDIATELY REPORTED TO THE ARCHITECT/ENGINEER FOR RESOLUTION AND INSTRUCTION, AND NO FURTHER WORK SHALL BE PERFORMED UNTIL THE DISCREPANCY IS CHECKED AND CORRECTED BY THE ARCHITECT/ENGINEER. FAILURE TO SECURE SUCH INSTRUCTION MEANS CONTRACTOR WILL HAVE WORKED AT HIS/HER OWN RISK AND EXPENSE. CONTRACTOR SHALL CALL LOCAL DIGGER HOT LINE FOR UTILITY LOCATIONS 48 HOURS PRIOR TO START OF CONSTRUCTION.
6.

ALL NEW AND EXISTING UTILITY STRUCTURES ON SITE AND IN AREAS TO BE DISTURBED BY CONSTRUCTION SHALL BE ADJUSTED TO FINISH ELEVATIONS PRIOR TO FINAL INSPECTION OF WORK.
7.

GRADING OF THE SITE WORK AREA IS TO BE SMOOTH AND CONTINUOUS IN SLOPE AND IS TO FEATHER INTO EXISTING GRADES AT THE GRADING LIMITS.
8.

ALL TEMPORARY EXCAVATIONS FOR THE INSTALLATION OF FOUNDATIONS, UTILITIES, ETC., SHALL BE PROPERLY LAID BACK OR BRACED IN ACCORDANCE WITH CORRECT OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION (OSHA) REQUIREMENTS.
9.

STRUCTURAL FILLS SUPPORTING PAVEMENTS SHALL BE COMPACTED TO 95% OF MAXIMUM STANDARD PROCTOR DRY DENSITY.
10.

NEW GRADES NOT IN BUILDING AND DRIVENAY IMPROVEMENT AREA TO BE ACHIEVED BY FILLING WITH APPROVED CLEAN FILL AND COMPACTED TO 95% OF STANDARD PROCTOR DENSITY.
11.

ALL FILL SHALL BE PLACED IN UNIFORM LIFTS. THE LIFTS THICKNESS SHOULD NOT EXCEED THAT WHICH CAN BE PROPERLY COMPACTED THROUGHOUT ITS ENTIRE DEPTH WITH THE EQUIPMENT AVAILABLE.
12.

ANY FILLS PLACED ON EXISTING SLOPES THAT ARE STEEPER THAN 10 HORIZONTAL TO 1 VERTICAL SHALL BE PROPERLY BENCHED INTO THE EXISTING SLOPE AS DIRECTED BY A GEOTECHNICAL ENGINEER.
13.

CONTRACTOR SHALL CLEAN ENTIRE SITE AFTER CONSTRUCTION SUCH THAT NO PAPERS, TRASH, WEEDS, BRUSH OR ANY OTHER DEPOSITS WILL REMAIN. ALL MATERIALS COLLECTED DURING CLEANING OPERATIONS SHALL BE DISPOSED OF OFF-SITE BY THE GENERAL CONTRACTOR.
14.

ALL TREES AND SHRUBS WHICH ARE NOT IN DIRECT CONFLICT WITH THE IMPROVEMENTS SHALL BE PROTECTED BY THE GENERAL CONTRACTOR.
15.

ALL SITE WORK SHALL BE CAREFULLY COORDINATED BY GENERAL CONTRACTOR WITH LOCAL UTILITY COMPANY, TELEPHONE COMPANY, AND ANY OTHER UTILITY COMPANIES HAVING JURISDICTION OVER THIS LOCATION.

ENVIRONMENTAL NOTES

1.

ALL WORK PERFORMED SHALL BE DONE IN ACCORDANCE WITH ISSUED PERMITS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PAYMENT OF FINES AND PROPER CLEAN UP FOR AREAS IN VIOLATION.
2.

CONTRACTOR AND/OR DEVELOPER SHALL BE RESPONSIBLE FOR CONSTRUCTION AND MAINTENANCE OF EROSION AND SEDIMENTATION CONTROLS DURING CONSTRUCTION FOR PROTECTION OF ADJACENT PROPERTIES, ROADWAYS AND WATERWAYS AND SHALL BE MAINTAINED IN PLACE THROUGH FINAL JURISDICTIONAL INSPECTION & RELEASE OF SITE.
3.

CONTRACTOR SHALL INSTALL/CONSTRUCT ALL NECESSARY SEDIMENT/SILT CONTROL FENCING AND PROTECTIVE MEASURES WITHIN THE LIMITS OF SITE DISTURBANCE PRIOR TO CONSTRUCTION.
4.

NO SEDIMENT SHALL BE ALLOWED TO EXIT THE PROPERTY. THE CONTRACTOR IS RESPONSIBLE FOR TAKING ADEQUATE MEASURES FOR CONTROLLING EROSION. ADDITIONAL SEDIMENT CONTROL FENCING MAY BE REQUIRED IN ANY AREAS SUBJECT TO EROSION.
5.

THE CONTRACTOR IS RESPONSIBLE FOR MAINTAINING POSITIVE DRAINAGE ON THE SITE AT ALL TIMES WITH SILT AND EROSION CONTROL MEASURES MAINTAINED ON THE DOWNSTREAM SIDE OF SITE DRAINAGE. ANY DAMAGE TO ADJACENT PROPERTY AS A RESULT OF EROSION WILL BE CORRECTED AT THE CONTRACTORS EXPENSE.
6.

CONTRACTOR SHALL BE RESPONSIBLE FOR DAILY INSPECTIONS AND ANY REPAIRS OF ALL SEDIMENT CONTROL MEASURES INCLUDING SEDIMENT REMOVAL AS NECESSARY.
7.

CLEARING OF VEGETATION AND TREE REMOVAL SHALL BE ONLY AS PERMITTED AND BE HELD TO A MINIMUM. ONLY TREES NECESSARY FOR CONSTRUCTION OF THE FACILITIES SHALL BE REMOVED.
8.

SEEDING AND MULCHING AND/OR SODDING OF THE SITE WILL BE ACCOMPLISHED AS SOON AS POSSIBLE AFTER COMPLETION OF THE PROJECT FACILITIES AFFECTING LAND DISTURBANCE.
9.

CONTRACTOR SHALL PROVIDE ALL EROSION AND SEDIMENTATION CONTROL MEASURES AS REQUIRED BY LOCAL, COUNTY AND STATE CODES AND ORDINANCES TO PROTECT EMBANKMENTS FROM SOIL LOSS AND TO PREVENT ACCUMULATION OF SOIL AND SILT IN STREAMS AND DRAINAGE PATHS LEAVING THE CONSTRUCTION AREA. THIS MAY INCLUDE SUCH MEASURES AS SILT FENCES, STRAW BALE SEDIMENT BARRIERS, AND CHECK DAMS.
10.

RIP RAP OF SIZES INDICATED SHALL CONSIST OF CLEAN, HARD, SOUND, DURABLE, UNIFORM IN QUALITY STONE FREE OF ANY DETRIMENTAL QUANTITY OF SOFT, FRIABLE, THIN, ELONGATED OR LAMINATED PIECES, DISINTEGRATED MATERIAL, ORGANIC MATTER, OIL, ALKALI, OR OTHER DELETERIOUS SUBSTANCES

GENERAL NOTES

1.

THESE NOTES SHALL BE CONSIDERED A PART OF THE WRITTEN SPECIFICATIONS, CONTRACT AND CONSTRUCTION DOCUMENTS.
2.

THE WORK SHALL INCLUDE FURNISHING MATERIALS, EQUIPMENT, APPURTENANCES, AND LABOR NECESSARY TO COMPLETE ALL INSTALLATIONS AS INDICATED ON THESE PLANS AND IN THE CONTRACT DOCUMENTS.
3.

PRIOR TO THE SUBMISSION OF BIDS, THE CONTRACTOR(S) SHALL VISIT THE JOB SITE(S) AND BE RESPONSIBLE FOR ALL CONTRACT DOCUMENTS, FIELD CONDITIONS AND DIMENSIONS, AND CONFIRM THAT THE WORK MAY BE ACCOMPLISHED PER THE CONTRACT DOCUMENTS. ANY DISCREPANCIES ARE TO BE BROUGHT TO THE ATTENTION OF THE IMPLEMENTATION ENGINEER AND ARCHITECT/ENGINEER PRIOR TO BID SUBMITTAL
4.

THE CONTRACTOR SHALL RECEIVE WRITTEN AUTHORIZATION TO PROCEED ON ANY WORK NOT CLEARLY DEFINED OR IDENTIFIED IN THE CONTRACT AND CONSTRUCTION DOCUMENTS BEFORE STARTING ANY WORK.
5.

ALL WORK PERFORMED AND MATERIALS INSTALLED SHALL BE IN STRICT ACCORDANCE WITH ALL APPLICABLE CODES, REGULATIONS, AND ORDINANCES, INCLUDING APPLICABLE MUNICIPAL AND UTILITY COMPANY SPECIFICATIONS.
6.

THE CONTRACTOR SHALL INSTALL ALL EQUIPMENT AND MATERIALS IN ACCORDANCE WITH MANUFACTURER RECOMMENDATIONS. IF THESE RECOMMENDATIONS ARE IN CONFLICT WITH THE CONTRACT AND CONSTRUCTION DOCUMENTS AND/OR APPLICABLE CODES OR REGULATIONS, REVIEW AND RESOLVE THE CONFLICT WITH DIRECTION FROM THE IMPLEMENTATION ENGINEER AND ARCHITECT/ENGINEER PRIOR TO PROCEEDING.
7.

THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR ALL CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES AND FOR COORDINATION OF ALL PORTIONS OF THE WORK UNDER THE CONTRACT INCLUDING CONTACT AND COORDINATION WITH THE IMPLEMENTATION ENGINEER AND WITH THE AUTHORIZED REPRESENTATIVE OF ANY OUTSIDE POLE OR PROPERTY OWNER.
8.

THE CONTRACTOR SHALL MAKE NECESSARY PROVISIONS TO PROTECT EXISTING IMPROVEMENTS, INCLUDING BUT NOT LIMITED TO PAVING, CURBS, VEGETATION, GALVANIZED SURFACE OR OTHER EXISTING ELEMENTS AND UPON COMPLETION OF THE WORK, REPAIR ANY DAMAGE THAT OCCURRED DURING CONSTRUCTION TO THE SATISFACTION OF VERIZON.
9.

CONTRACTOR IS TO KEEP THE GENERAL AREA CLEAN, HAZARD FREE, AND DISPOSE OF ALL DIRT, DEBRIS, RUBBISH, AND REMOVE EQUIPMENT NOT SPECIFIED AS REMAINING ON THE PROPERTY. LEAVE PREMISES IN CLEAN CONDITION DAILY.
10.

PLANS ARE INTENDED TO BE DIAGRAMMATIC ONLY AND SHOULD NOT BE SCALED UNLESS OTHERWISE NOTED. RELY ONLY ON ANNOTATED DIMENSIONS AND REQUEST INFORMATION IF ADDITIONAL DIMENSIONS ARE REQUIRED.
11.

THE EXISTENCE AND LOCATION OF UTILITIES AND OTHER AGENCY'S FACILITIES WERE OBTAINED BY A SEARCH OF AVAILABLE RECORDS. OTHER FACILITIES MAY EXIST. CONTRACTOR SHALL VERIFY LOCATIONS PRIOR TO START OF CONSTRUCTION AND USE EXTREME CARE AND PROTECTIVE MEASURES TO PREVENT DAMAGE TO THESE FACILITIES. CONTRACTOR IS RESPONSIBLE FOR THE PROTECTION OF UTILITIES OR OTHER AGENCY'S FACILITIES WITHIN THE LIMITS OF THE WORK, WHETHER THEY ARE IDENTIFIED IN THE CONTRACT DOCUMENTS OR NOT.
12.

THE CONTRACTOR SHALL NOTIFY UNDERGROUND SERVICE ALERT (800) 227-2600, AT LEAST TWO WORKING DAYS PRIOR TO THE START OF ANY EXCAVATION.

DEFINITIONS

1.

"TYPICAL" OR "TYP" MEANS THAT THIS ITEM IS SUBSTANTIALLY THE SAME ACROSS SIMILAR CONDITIONS. "TYP." SHALL BE UNDERSTOOD TO MEAN "TYPICAL WHERE OCCURS" AND SHALL NOT BE CONSIDERED AS WITHOUT EXCEPTION OR CONSIDERATION OF SPECIFIC CONDITIONS.
2.

"SIMILAR" MEANS COMPARABLE TO CHARACTERISTICS FOR THE CONDITION NOTED. VERIFY DIMENSIONS AND ORIENTATION ON PLAN.
3.

"AS REQUIRED" MEANS AS REQUIRED BY REGULATORY REQUIREMENTS, BY REFERENCED STANDARDS, BY EXISTING CONDITIONS, BY GENERALLY ACCEPTED CONSTRUCTION PRACTICE, OR BY THE CONTRACT DOCUMENTS.
4.

"ALIGN" MEANS ACCURATELY LOCATE FINISH FACES OF MATERIALS IN THE SAME PLANE.
5.

THE TERM "VERIFY" OR "V.I.F." SHALL BE UNDERSTOOD TO MEAN "VERIFY IN FIELD WITH ENGINEER" AND REQUIRES THAT THE CONTRACTOR CONFIRM INTENTION REGARDING NOTED CONDITION AND PROCEED ONLY AFTER RECEIVING DIRECTION.
6.

WHERE THE WORDS "OR EQUAL" OR WORDS OF SIMILAR INTENT FOLLOW A MATERIAL SPECIFICATION, THEY SHALL BE UNDERSTOOD TO REQUIRE SIGNED APPROVAL OF ANY DEVIATION TO SAID SPECIFICATION PRIOR TO CONTRACTOR'S ORDERING OR INSTALLATION OF SUCH PROPOSED EQUAL PRODUCT.
7.

FURNISH: SUPPLY ONLY, OTHERS TO INSTALL.
INSTALL: INSTALL ITEMS FURNISHED BY OTHERS.
PROVIDE: FURNISH AND INSTALL.

811

USA North

Know what's below.
Call before you dig.

California and Nevada
Call Two Working Days Before You Dig!
811 / 800-227-2600

verizon

2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

Vinculum

575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500

ALL STATES

ENGINEERING & SURVEYING

A ZALZALI & ASSOCIATES COMPANY

23675 BIRTCHE DRIVE
LAKE FOREST, CA 92630
PHONE: (949) 273-0996

PROJECT ID:	P-334882
DRAWN BY:	RF
CHECKED BY:	DW

3	11/20/2020	CITY COMMENTS	MG	
2	08/31/2020	100% CD'S FOR SUBMITTAL	MG	
1	06/11/2020	100% CD'S FOR SUBMITTAL	RF	
0	05/22/2020	100% CD'S FOR APPROVAL	RF	
B	05/04/2020	95% CD'S FOR REDLINE	RF	
A	04/29/2020	90% CD'S FOR REDLINE	RF	
REV	DATE	DESCRIPTION		

REGISTERED PROFESSIONAL ENGINEER

WISSAM ZALZALI

71655

STATE OF CALIFORNIA

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 061

LIC R.O.W. ADJACENT TO:

1221 MIDDLEFIELD RD.

PALO ALTO, 94301

LOCATION CODE: 425208

SHEET TITLE

GENERAL NOTES

SHEET NUMBER

GN-1

ELECTRICAL NOTES

1. ELECTRICAL CONTRACTOR SHALL SUPPLY AND INSTALL ANY/ALL ELECTRICAL WORK INDICATED. ANY/ALL CONSTRUCTION SHALL BE IN ACCORDANCE W/DRAWINGS AND ANY/ALL APPLICABLE SPECIFICATIONS. IF ANY PROBLEMS ARE ENCOUNTERED BY COMPLYING WITH THESE REQUIREMENTS, CONTRACTOR SHALL NOTIFY 'CONSTRUCTION MANAGER' AS SOON AS POSSIBLE, AFTER THE DISCOVERY OF THE PROBLEMS, AND SHALL NOT PROCEED WITH THAT PORTION OF WORK, UNTIL THE 'CONSTRUCTION MANAGER' HAS DIRECTED THE CORRECTIVE ACTIONS TO BE TAKEN.
2. ELECTRICAL CONTRACTOR SHALL VISIT THE JOB SITE AND FAMILIARIZE HIMSELF WITH ANY/ALL CONDITIONS AFFECTING ELECTRICAL AND COMMUNICATION INSTALLATION AND MAKE PROVISIONS AS TO THE COST THEREOF. ALL EXISTING CONDITIONS OF ELECTRICAL EQUIP., LIGHT FIXTURES, ETC., THAT ARE PART OF THE FINAL SYSTEM, SHALL BE VERIFIED BY THE CONTRACTOR, PRIOR TO THE SUBMITTING OF HIS BID. FAILURE TO COMPLY WITH THIS PARAGRAPH WILL IN NO WAY RELIEVE CONTRACTOR OF PERFORMING ALL WORK NECESSARY FOR A COMPLETE AND WORKING SYSTEM.
3. ALL WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE LATEST EDITION OF THE NEC AND ALL CODES AND LOCAL ORDINANCES OF THE LOCAL POWER & TELEPHONE COMPANIES HAVING JURISDICTION AND SHALL INCLUDE BUT NOT BE LIMITED TO:
C - NATIONAL FIRE CODES
A. UL - UNDERWRITERS LABORATORIES
B. NEC - NATIONAL ELECTRICAL CODE
C. NEMA - NATIONAL ELECTRICAL MANUFACTURERS ASSOC.
D. OSHA - OCCUPATIONAL SAFETY AND HEALTH ACT
E. SBC - STANDARD BUILDING CODE
4. DO NOT SCALE ELECTRICAL DRAWINGS, REFER TO SITE PLANS AND ELEVATIONS FOR EXACT LOCATIONS OF ALL EQUIPMENT, AND CONFIRM WITH 'CONSTRUCTION MANAGER' ANY SIZES AND LOCATIONS WHEN NEEDED.
5. EXISTING SERVICES: CONTRACTOR SHALL NOT INTERRUPT EXISTING SERVICES WITHOUT WRITTEN PERMISSION OF THE OWNER.
6. CONTRACTOR SHALL PAY FOR ANY/ALL PERMITS, FEES, INSPECTIONS AND TESTING. CONTRACTOR IS TO OBTAIN PERMITS AND APPROVED SUBMITTALS PRIOR TO THE WORK BEGINNING OR ORDERING EQUIPMENT.
7. THE TERM "PROVIDE" USED IN CONSTRUCTION DOCUMENTS AND SPECIFICATIONS, INDICATES THAT THE CONTRACTOR SHALL FURNISH AND INSTALL.
8. CONTRACTOR SHALL CONFIRM WITH LOCAL UTILITY COMPANY ANY/ALL REQUIREMENTS SUCH AS THE: LUG SIZE RESTRICTIONS, CONDUIT ENTRY, SIZE OF TRANSFORMERS, SCHEDULED DOWNTIME FOR THE OWNERS' CONFIRMATION, ETC... ANY/ALL CONFLICTS SHALL BE BROUGHT TO THE ATTENTION OF THE CONSTRUCTION MANAGER, PRIOR TO BEGINNING ANY WORK.
9. MINIMUM WIRE SIZE SHALL BE #12 AWG, NOT INCLUDING CONTROL WIRING, UNLESS NOTED OTHERWISE. ALL CONDUCTORS SHALL BE COPPER WITH THIN INSULATION.
10. OUTLET BOXES SHALL BE PRESSED STEEL IN DRY LOCATIONS, CAST ALLOY WITH THREADED HUBS IN WET/DAMP LOCATIONS AND SPECIAL ENCLOSURES FOR OTHER CLASSIFIED AREAS.
11. IT IS NOT THE INTENT OF THESE PLANS TO SHOW EVERY MINOR DETAIL OF THE CONSTRUCTION. CONTRACTOR IS EXPECTED TO FURNISH AND INSTALL ALL ITEMS FOR A COMPLETE ELECTRICAL SYSTEM AND PROVIDE ALL REQUIREMENTS FOR THE EQUIPMENT TO BE PLACED IN PROPER WORKING ORDER.
12. ELECTRICAL SYSTEM SHALL BE AS COMPLETELY AND EFFECTIVELY GROUNDED, AS REQUIRED BY SPECIFICATIONS, SET FORTH BY VERIZON.
13. ALL WORK SHALL BE PERFORMED BY A LICENSED ELECTRICAL CONTRACTOR IN A FIRST CLASS, WORKMANLIKE MANNER. THE COMPLETED SYSTEM SHALL BE FULLY OPERATIVE AND SUBJECT TO REGULATORY INSPECTION AND APPROVAL BY CONSTRUCTION MANAGER.
14. ALL WORK SHALL BE COORDINATED WITH OTHER TRADES TO AVOID INTERFERENCE WITH THE PROGRESS OF CONSTRUCTION.
15. CONTRACTOR SHALL GUARANTEE ANY/ALL MATERIALS AND WORK FREE FROM DEFECTS FOR A PERIOD OF NOT LESS THAN ONE YEAR FROM DATE OF ACCEPTANCE.
16. THE CORRECTION OF ANY DEFECTS SHALL BE COMPLETED WITHOUT ANY ADDITIONAL CHARGE AND SHALL INCLUDE THE REPLACEMENT OR THE REPAIR OF ANY OTHER PHASE OF THE INSTALLATION, WHICH MAY HAVE BEEN DAMAGED THEREIN.
17. ADEQUATE AND REQUIRED LIABILITY INSURANCE SHALL BE PROVIDED FOR PROTECTION AGAINST PUBLIC LOSS AND ANY/ALL PROPERTY DAMAGE FOR THE DURATION OF WORK.
18. PROVIDE AND INSTALL CONDUIT, CONDUCTORS, PULL WIRES, BOXES, COVER PLATES AND DEVICES FOR ALL OUTLETS AS INDICATED.
19. DITCHING AND BACK FILL: CONTRACTOR SHALL PROVIDE FOR ALL UNDERGROUND INSTALLED CONDUIT AND/OR CABLES INCLUDING EXCAVATION AND BACKFILLING AND COMPACTION. REFER TO NOTES AND REQUIREMENTS 'EXCAVATION, AND BACKFILLING.
20. MATERIALS, PRODUCTS AND EQUIPMENT, INCLUDING ALL COMPONENTS THEREOF, SHALL BE NEW AND SHALL APPEAR ON THE LIST OF U.L. APPROVED ITEMS AND SHALL MEET OR EXCEED THE REQUIREMENTS OF THE NEC, NEMA AND IECE.
21. CONTRACTOR SHALL SUBMIT SHOP DRAWINGS OR MANUFACTURES CATALOG INFORMATION OF ANY/ALL LIGHTING FIXTURES, SWITCHES AND ALL OTHER ELECTRICAL ITEMS FOR APPROVAL BY THE CONSTRUCTION MANAGER PRIOR TO INSTALLATION.
22. ANY CUTTING OR PATCHING DEEMED NECESSARY FOR ELECTRICAL WORK IS THE ELECTRICAL CONTRACTORS RESPONSIBILITY AND SHALL BE INCLUDED IN THE COST FOR WORK AND PERFORMED TO THE SATISFACTION OF THE 'CONSTRUCTION MANAGER' UPON FINAL ACCEPTANCE.
23. THE ELECTRICAL CONTRACTOR SHALL LABEL ALL PANELS WITH ONLY TYPEWRITTEN DIRECTORIES. ALL ELECTRICAL WIRING SHALL BE THE RESPONSIBILITY OF THE ELECTRICAL CONTRACTOR.
24. DISCONNECT SWITCHES SHALL BE H.P. RATED HEAVY-DUTY, QUICK-MAKE AND QUICK-BREAK ENCLOSURES, AS REQUIRED BY EXPOSURE TYPE.
25. ALL CONNECTIONS SHALL BE MADE WITH A PROTECTIVE COATING OF AN ANTI-OXIDE COMPOUND SUCH AS "NO-OXIDE A" BY DEARBORNE CHEMICAL CO. COAT ALL WIRE SURFACES BEFORE CONNECTING. EXPOSED COPPER SURFACES, INCLUDING GROUND BARS, SHALL BE TREATED - NO SUBSTITUTIONS.
26. RACEWAYS: CONDUIT SHALL BE SCHEDULE 40 PVC MEETING OR EXCEEDING NEMA TC2 - 1990. CONTRACTOR SHALL PLUG AND CAP EACH END OF SPARE AND EMPTY CONDUITS AND PROVIDE TWO SEPARATE PULL STRINGS - 200 LBS TEST POLYETHYLENE CORD. ALL CONDUIT BENDS SHALL BE A MINIMUM OF 2 FT. RADIUS. RGS CONDUITS WHEN SPECIFIED, SHALL MEET UL-6 FOR GALVANIZED STEEL. ALL FITTINGS SHALL BE SUITABLE FOR USE WITH THREADED RIGID CONDUIT. COAT ALL THREADS WITH 'BRITE ZINC' OR 'GOLD GALV'.
27. SUPPORT OF ALL ELECTRICAL WORK SHALL BE AS REQUIRED BY NEC.

28. CONDUCTORS: CONTRACTOR SHALL USE 98% CONDUCTIVITY COPPER WITH TYPE THWN INSULATION, 800 VOLT, COLOR CODED. USE SOLID CONDUCTORS FOR WIRE UP TO AND INCLUDING NO. 8 AWG. USE STRANDED CONDUCTORS FOR WIRE ABOVE NO. 8 AWG.
29. CONNECTORS FOR POWER CONDUCTORS: CONTRACTOR SHALL USE PRESSURE TYPE INSULATED TWIST-ON CONNECTORS FOR NO. 10 AWG AND SMALLER. USE SOLDERLESS MECHANICAL TERMINAL LUGS FOR NO. 8 AWG AND LARGER.
30. SERVICE: 240/120V, SINGLE PHASE, 3 WIRE CONNECTION AVAILABLE FROM UTILITY COMPANY. OWNER OR OWNERS AGENT WILL APPLY FOR POWER.
31. TELEPHONE SERVICE: CONTRACTOR SHALL PROVIDE EMPTY CONDUITS WITH PULL STRINGS AS INDICATED ON DRAWINGS.
32. ELECTRICAL AND TELCO RACEWAYS TO BE BURIED A MINIMUM OF 2' DEPTH.
33. CONTRACTOR SHALL PLACE TWO LENGTHS OF WARNING TAPE AT A DEPTH OF 12" BELOW GROUND AND DIRECTLY ABOVE ELECTRICAL AND TELCO SERVICE CONDUITS. CAUTIONS TAPE TO READ "CAUTION BURIED ELECTRIC" OR "BURIED TELECOMM".
34. ALL BOLTS SHALL BE STAINLESS STEEL

GROUNDING NOTES

1. COMPRESSION CONNECTIONS (2), 2 AWG BARE TINNED SOLID COPPER CONDUCTORS TO GROUNDING BAR. ROUTE CONDUCTORS TO BURIED GROUNDING RING AND PROVIDE PARALLEL EXOTHERMIC WELD.
2. EC SHALL USE PERMANENT MARKER TO DRAW THE LINES BETWEEN EACH SECTION AND LABEL EACH SECTION ("P", "A", "N", "I") WITH 1" HIGH LETTERS.
3. ALL HARDWARE 18-8 STAINLESS STEEL, INCLUDING LOCK WASHERS, COAT ALL SURFACES WITH AN ANTI-OXIDANT COMPOUND BEFORE MATING. ALL HARDWARE SHALL BE STAINLESS STEEL 3/8 INCH DIAMETER OR LARGER.
4. FOR GROUND BOND TO STEEL ONLY: INSERT A CADMIUM FLAT WASHER BETWEEN LUG AND STEEL, COAT ALL SURFACES WITH AN ANTI-OXIDANT COMPOUND BEFORE MATING.
5. NUT & WASHER SHALL BE PLACED ON THE FRONT SIDE OF THE GROUNDING BAR AND BOLTED ON THE BACK SIDE.
6. NUMBER OF GROUNDING BARS MAY VARY DEPENDING ON THE TYPE OF TOWER, ANTENNA LOCATION, AND CONNECTION ORIENTATION. PROVIDE AS REQUIRED.
7. WHEN THE SCOPE OF WORK REQUIRES THE ADDITION OF A GROUNDING BAR TO AN EXISTING TOWER,THE SUBCONTRACTOR SHALL OBTAIN APPROVAL FROM THE TOWER OWNER PRIOR TO MOUNTING THE GROUNDING BAR TO THE TOWER.
8. ALL ELECTRICAL AND GROUNDING AT THE CELL SITE SHALL COMPLY WITH THE NATIONAL ELECTRICAL CODE (NEC), NATIONAL FIRE PROTECTION ASSOCIATION (NFPA) 780 (LATEST EDITION), AND MANUFACTURER.

ADDITIONAL NOTES:

9. ALL DETAILS ARE SHOWN IN GENERAL TERMS. ACTUAL GROUNDING INSTALLATION AND CONSTRUCTION MAY VARY DUE TO SITE SPECIFIC CONDITIONS.
10. GROUND ALL ANTENNA BASES, FRAMES, CABLE RUNS, AND OTHER METALLIC COMPONENTS USING #2 GROUND WIRES AND CONNECT TO SURFACE MOUNTED GROUND BUS BARS AS SHOWN. FOLLOW ANTENNA AND BTS MANUFACTURER'S PRACTICES FOR GROUNDING REQUIREMENTS. GROUND COAX SHIELD AT BOTH ENDS USING MANUFACTURERS PRACTICES. ALL UNDERGROUND WATER PIPES, METAL CONDUITS AND GROUNDS THAT ARE A PART OF THIS SYSTEM SHALL BE BONDED TOGETHER.
11. ALL GROUND CONNECTIONS SHALL BE #2 AWG U.N.O. ALL WIRES SHALL BE COPPER THIN/THIN. ALL GROUND WIRE SHALL BE SOLID TIN COATED OR STRANDED GREEN INSULATED WIRE.
12. CONTRACTOR TO VERIFY AND TEST GROUND TO SOURCE, 5 OHMS MAXIMUM. PROVIDE SUPPLEMENT GROUNDING RODS AS REQUIRED TO ACHIEVE SPECIFIED OHMS READING. GROUNDING AND OTHER OPTIONAL TESTING WILL BE WITNESSED BY THE VERIZON REPRESENTATIVE.
13. NOTIFY ARCHITECT/ENGINEER IF THERE ARE ANY DIFFICULTIES INSTALLING GROUNDING SYSTEM DUE TO SITE SOIL CONDITIONS.
14. BARE GROUNDING CONDUCTOR SHALL BE HARD DRAWN TINNED COPPER SIZES AS NOTED ON PLAN.
15. ALL HORIZONTALLY RUN GROUNDING CONDUCTORS SHALL BE INSTALLED MINIMUM 12" BELOW GRADE/FROST-LINE IN TRENCH, U.N.O., AND BACK FILL SHALL BE COMPACTED AS REQUIRED BY ARCHITECT.
16. ALL GROUND CONDUCTORS SHALL BE RUN AS STRAIGHT AND SHORT AS POSSIBLE, WITH A MINIMUM 12" BENDING RADIUS NOT LESS THAN 90 DEGREES.
17. ALL SUPPORT STRUCTURES, CABLE CHANNEL WAYS OR WIRE GUIDES SHALL BE BONDED TO GROUND SYSTEM AT A POINT NEAREST THE MAIN GROUNDING BUS "MGB" (OR DIRECTLY TO GROUND-RING).
18. ACCEPTABLE CONNECTIONS FOR GROUNDING SYSTEM SHALL BE:
a. BURNDY, HY-GRADE U.L. LISTED CONNECTORS FOR INDOOR USE OR AS APPROVED BY VERIZON PROJECT MANAGER.
b. CADWELD, EXOTHERMIC WELDS (WELDED CONNECTIONS).
c. TWO -(2) HOLE TINNED COPPER COMPRESSION (LONG BARREL) FITTINGS (BUS BAR CONNECTIONS).
19. ALL CRIMPED CONNECTIONS SHALL HAVE EMBOSSED MANUFACTURER'S DIEMARK VISIBLE AT THE CRIMP (RESULTING FROM USE OF PROPER CRIMPING DEVICES).
20. PRIOR TO ANY LUG-BUSSBAR CONNECTIONS, THE BUSSBAR SHALL BE CLEANED BY USE OF "SCOTCH-BRITE" OR PLAIN STEEL WOOL AS TO REMOVE ALL SURFACE OXIDATION AND CONTAMINANTS. A COATING OF "NO-OX-ID" SHALL BE APPLIED TO THE CONNECTION SURFACES.
21. ALL CONNECTION HARDWARE SHALL BE TYPE 316 SS (NOT ATTRACTED TO MAGNETS).
22. THE GROUND RING SHALL BE INSTALLED 24" MINIMUM BEYOND ANY BUILDING DRIP LINE.
23. ELECTRICAL SERVICE EQUIPMENT GROUNDING SHALL COMPLY WITH NEC, ARTICLE 250-82 AND SHALL BOND ALL EXISTING AND NEW GROUNDING ELECTRODES. NEW GROUNDING ELECTRODE SHALL INCLUDE BUT NOT LIMITED TO GROUND RODS, GROUND RING IF SERVICE IS WITHIN THE RADIO EQUIPMENT LOCATION, BUILDING STEEL IF APPLICABLE, COLD WATER CONNECTIONS MUST BE MADE ON THE STREET SIDE OF MAIN SHUT-OFF VALVE.

verizon

2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

Vinculum

575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500

ALL STATES
ENGINEERING & SURVEYING
A ZALZALI & ASSOCIATES COMPANY

23675 BIRTCHER DRIVE
LAKE FOREST, CA 92630
PHONE: (949) 273-0996

PROJECT ID: P-334882

DRAWN BY: RF

CHECKED BY: DW

3	11/20/2020	CITY COMMENTS	MG
2	08/31/2020	100% CD'S FOR SUBMITTAL	MG
1	06/11/2020	100% CD'S FOR SUBMITTAL	RF
0	05/22/2020	100% CD'S FOR APPROVAL	RF
B	05/04/2020	95% CD'S FOR REDLINE	RF
A	04/29/2020	90% CD'S FOR REDLINE	RF
REV	DATE	DESCRIPTION	



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 061

LIC R.O.W. ADJACENT TO:
1221 MIDDLEFIELD RD.
PALO ALTO, 94301
LOCATION CODE: 425208

SHEET TITLE

GENERAL NOTES

SHEET NUMBER

GN-2



11/24/2020

Jeremy Stroup
Real Estate Specialist III
Vinculums Services, LLC
10 Pasteur, Suite 100
Irvine, CA 92618
jstroup@vinculums.com
925-202-8654

Re: Tree Protection Measures at SF PALO ALTO 061 (1211 Middlefield Rd.)

Dear Jeremy,

Cellular equipment will be mounted on a new metal light pole, #121, adjacent to the above address, with a new handhole in the sidewalk adjacent to the pole, connected to the pole and to an existing handhole by conduit installed via trenching. The new light pole will be installed about four feet northwest of the existing pole. Nearly all excavation will be under the existing sidewalk, with a small amount in the unpaved park strip. I visually estimated distances between trees and project features onsite.

Two trees are present, as shown in the Tree Table, below. Both are street trees, and both lie within the project area. Tree #1 conflicts directly with the proposed light pole location and must be removed for the project to proceed as proposed. A small shrub is also present approximately where the proposed pole will be installed, and must be removed. A small amount of the proposed excavation lies within the dripline¹ of tree #2. Tree #2 requires Type II tree protection. Trenching must be performed by hand. If any live roots are encountered during excavation, the recommendations in section 2.25.1 apply:

1. Root injury: If trenches are cut and tree roots 2-inches or larger are encountered they must be cleanly cut back to a sound wood lateral root. The end of the root shall be covered with either a plastic bag and secured with tape or rubber band, or be coated with latex paint. All exposed root areas within the TPZ shall be backfilled or covered within one hour. Exposed roots may be kept from drying out by temporarily covering the roots and draping layered burlap or carpeting over the upper 3-feet of trench walls. The materials must be kept wet until backfilled to reduce evaporation from the trench walls.

Existing street tree foliage from tree #2 is within 35 feet of the WCF and provides interruption of direct views of the WCF from the southeast.

¹ The area within five feet of the tree's DBH, as specified in the City of Palo Alto Tree Technical Manual. Please note that this may be different from the edge of the canopy, also sometimes called the dripline.

Prepared by Anderson's Tree Care for Vinculums Services, LLC.


Page 1

At the direction of City of Palo Alto staff, one new 24" boxed tree shall be planted to replace tree #1, in the park strip northwest of the pole. I recommend planting the new tree slightly farther away from the pole than the current tree to facilitate possible future maintenance. This area currently contains agapanthus (*agapanthus* sp.) shrubs. The new tree will be within 10 feet of an existing water meter, so a permanent impermeable root barrier will be needed. I recommend placing this barrier as far as possible from the tree, 3 feet from the water meter.

I have been informed by my client that all trees planted near 5G equipment must reach a mature height of 20 feet or less. City staff has specified a drought-tolerant tree. Given these constraints, I recommend a swamp myrtle (*Tristanopsis laurina*).

Tree #	Species	Common Name	DBH ² (in.)	Dripline ² (ft. and in.)	Regulated Status
1	<i>Tilia cordata</i>	Littleleaf linden	3.9	3'3"	Street Tree
2	<i>Tilia cordata</i>	Littleleaf linden	15.9	13'3"	Street Tree
3	Swamp myrtle	<i>Tristanopsis laurina</i>	24" box	N/A	Replacement for Street Tree #1

Tree map (taken from plans provided to me, which reflect my previous recommendations; tree numbers mine)



² Diameter at breast height, a standard arboricultural measurement. Breast height is defined as 7.4 inches above a grade. ² Defined in the Palo Alto Tree Technical Manual as ten times the tree's DBH. Work within a tree's dripline must respect its impact.

Prepared by Anderson's Tree Care for Vinculums Services, LLC.

Page 2

Prepared by Anderson's Tree Care for Vinculums Services, LLC.

Page 3

Images of agapanthus, tree #1, shrub, and tree #2 (left to right)



ASSUMPTIONS AND LIMITING CONDITIONS

1. Any legal description provided to the consultant/appraiser is assumed to be correct. Any titles and ownerships to any property are assumed to be good and marketable. No responsibility is assumed for matters legal in character. Any and all property is appraised or evaluated as though free and clear, under responsible ownership and competent management.
2. It is assumed that any property is not in violation of any applicable codes, ordinances, statutes, or other government regulations.
3. Care has been taken to obtain all information from reliable sources. All data has been verified insofar as possible; however, the consultant/appraiser can neither guarantee nor be responsible for the accuracy of information provided by others.
4. The consultant/appraiser shall not be required to give testimony or to attend court by reason of this report unless subsequent contractual arrangements are made, including payment of an additional fee for such services as described in the fee schedule and contract of engagement.
5. Loss, alteration, or reproduction of any part of this report invalidates the entire report.
6. Possession of this report or a copy thereof does not imply right of publication or use for any purpose by any other than the person to whom it is addressed, without the prior expressed written or verbal consent of the consultant/appraiser.
7. Neither all nor any part of this report, nor any copy thereof, shall be conveyed by anyone, including the client, to the public through advertising, public relations, news, sales or other media, without the prior expressed written or verbal consent of the consultant/appraiser particularly as to value conclusions, identity of the consultant/appraiser, or any reference to any professional society or initialed designation conferred upon the consultant/appraiser as stated in his qualification.
8. This report and the values expressed herein represent the opinion of the consultant/appraiser, and the consultant/appraiser's fee is in no way contingent upon the reporting of a specified value, a stipulated result, the occurrence of a subsequent event, nor upon any finding to be reported.
9. Sketches, diagrams, graphs, and photographs in this report, being intended as visual aids, are not necessarily to scale and should not be construed as engineering or architectural reports or surveys.
10. Unless expressed otherwise: 1) information in this report covers only those items that were examined and reflects the condition of those items at the time of inspection; and 2) the inspection is limited to visual examination of accessible items without dissection, excavation, probing, or coring. There is no warranty or guarantee, expressed or implied, that problems or deficiencies of the plants or property in question may not arise in future.

Prepared by Anderson's Tree Care for Vinculums Services, LLC.

Page 4

Prepared by Anderson's Tree Care for Vinculums Services, LLC.

Page 5

Respectfully submitted,

Katherine Naegele

Katherine Naegele
Consulting Arborist
Anderson's Tree Care Specialists, Inc.
A TCIA Accredited Company
Master of Forestry, UC Berkeley
ISA Certified Arborist #WE-9658A
ISA Tree Risk Assessment Qualified
American Society of Consulting Arborists, Member
Office: 408 226-8733
Cell: 408 590-5976

www.andersonstreespecialists.com



Prepared by Anderson's Tree Care for Vinculums Services, LLC.

Page 6

verizon

2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

Vinculums

575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500

ALL STATES
ENGINEERING & SURVEYING
A ZALZALI & ASSOCIATES COMPANY

23675 BIRCHER DRIVE
LAKE FOREST, CA 92630
PHONE: (949) 273-0996

PROJECT ID: P-334882

DRAWN BY: RF

CHECKED BY: DW

REV	DATE	DESCRIPTION	
3	11/20/2020	CITY COMMENTS	MG
2	06/31/2020	100% CD'S FOR SUBMITTAL	MG
1	06/11/2020	100% CD'S FOR SUBMITTAL	RF
0	05/22/2020	100% CD'S FOR APPROVAL	RF
B	05/04/2020	95% CD'S FOR REDLINE	RF
A	04/29/2020	90% CD'S FOR REDLINE	RF



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 061

LIC R.O.W. ADJACENT TO:
1221 MIDDLEFIELD RD.
PALO ALTO, 94301
LOCATION CODE: 425208

SHEET TITLE
TREE PROTECTION REPORT

SHEET NUMBER
TPR-1

NOTE:
ANY CONSTRUCTION WITHIN THE CITY'S PUBLIC ROAD RIGHT-OF-WAY SHALL HAVE AN APPROVED PERMIT FOR CONSTRUCTION IN THE PUBLIC STREET PRIOR TO COMMENCEMENT OF THIS WORK

City of Palo Alto Tree Protection - It's Part of the Plan!

Make sure your crews and subs do the job right!

Fenced enclosures around trees are essential to protect them by keeping the foliage canopy and branching structure clear from contact by equipment, materials and activities, preserving roots and soil conditions in an intact and non-compacted state, and identifying the Tree Protection Zone (TPZ) in which no soil disturbance is permitted and activities are restricted, unless otherwise approved. **An approved tree protection report must be added to this sheet when project activity occurs within the TPZ of a regulated tree.** For detailed information on Palo Alto's regulated trees and protection during development, review the **City Tree Technical Manual (TTM)** found at www.cityofpaloalto.org/trees/.

For written specifications associated with illustrations below, see Public Works Specifications Section M. Detailed specifications are found in the Palo Alto Tree Technical Manual (TTM) (www.cityofpaloalto.org/trees/).

Tree Protection Zone (TPZ) shown in gray (radius of TPZ is equal to distance the diameter of the tree or its full arborize is present).

- Restricted activity area - see Tree Technical Manual (Sec 2.1.1.1)
- Restricted trenching area - see Tree Technical Manual Sec 2.20(C-D), any proposed trench or form work within TPZ of a protected tree requires approval from Public Works Operations. Call 650-496-5953.

Type I Tree Protection

Note: Unmanned Protected & Designated Trees. Issuance of a permit requires applicant's project arborist written verification Type I is included correctly according to the plans and Tree Preservation Report.

Type II Tree Protection

Note: Street Trees. Issuance of a permit requires Public Works Operations inspection and signed approval on the Street Tree Verification (STV) form provided.

Type III Tree Protection

Note: Street Trees. Issuance of a permit requires Public Works Operations inspection and signed approval on the Street Tree Verification (STV) form provided.

Tree fencing is required and shall be erected before demolition, grading or construction begins.

Date	By	Date	Approved by
01/01/01	J. J. (J. J.)	01/01/01	Dave Dockter
01/01/01	J. J. (J. J.)	01/01/01	J. J. (J. J.)
01/01/01	J. J. (J. J.)	01/01/01	J. J. (J. J.)

City of Palo Alto Standard

Tree Protection During Construction

Approved by: Dave Dockter

FEAL Date: 2006

Tree No.: 605

Table 2.1 Palo Alto Tree Technical Manual

CONTRACTOR & ARBORIST INSPECTION SCHEDULE

Reference: the Palo Alto Tree Technical Manual is available at www.cityofpaloalto.org/trees/

ALL CHECKED ITEMS APPLY TO THIS PROJECT:

- ☒ **Inspection of Protective Tree Fencing:** For Public Trees, the Street Tree Verification Form shall be signed by the City Arborist. For Protected Trees, the project site arborist shall provide an initial Monthly Tree Activity Report form with a photograph verifying that he has conducted a field inspection of the trees and that the correct type of protective fencing is in place around the designated tree protection zone (TPZ) prior to issuance of a demolition, grading, or building permit. (See TTM, Verification of Tree Protection, Section 1.19)
- ☒ **Pre-Construction Meeting:** Prior to commencement of construction, the applicant or contractor shall conduct a pre-construction meeting to discuss tree protection with the job site superintendent, grading operator, project site arborist, City Arborist, and, if a city maintained irrigation system is involved, the Parks Manager. (Contact 650-496-5953)
- ☒ **Inspection of Rough Grading or Trenching:** Contractor shall ensure the project site arborist perform an inspection during the course of rough grading or trenching adjacent to or within the TPZ to ensure trees will not be injured by compaction, cut or fill, drainage and trenching, and if required, inspect erosion systems, tree wells, drains and special paving. The contractor shall provide the project arborist at least 24 hours advance notice of such activity.
- ☒ **Monthly Tree Activity Report Inspections:** The project site arborist shall perform a minimum monthly activity inspection to monitor and advise on conditions, tree health and removal or, immediately if there are any violations to the approved plans or protection measures. The Tree Technical Manual Monthly Tree Activity Report form shall be read and sent to the Planning Dept. Inspections review staff no later than 14 days after issuance of building permit date. Fax to (805) 839-2134. (See TTM, Monthly Tree Activity Inspection Report, Addendum 11 & Section 1.17)
- ☒ **Special activity within the Tree Protection Zone:** Work in the TPZ area (see also #7 below) requires the direct creative supervision of the project arborist (see TTM, Trenching, Excavation & Equipment, Section 2.20 C).
- ☐ **Landscape Architect Inspection:** For discretionary development projects, prior to temporary or final occupancy the applicant or contractor shall arrange for the Landscape Architect to perform an on site inspection of all plant stock, quality of the materials and planting (see TTM, Planting Quality, Section 5.20.1 A) and that the irrigation is functioning consistent with the approved construction plans. The Planning Dept. Landscape review staff shall be in receipt of written verification of Landscape Architect approval prior to scheduling the final inspection, unless otherwise approved.
- ☐ **List Other:** (please describe in detail on in the site Tree Preservation Report, Sheet T-1, T-2, etc.)

City of Palo Alto Tree Technical Manual ADDENDUM 11

Arborist Exam Data Here

Monthly Tree Activity Report- Construction Site

Inspection Date:	Site address:	Contractor, Main Site Contact Information	#1 Job site superintendent
Inspection #	Palo Alto, CA	Also present:	Company: Palo Alto, CA
			Job site superintendent: Dave Dockter
			Cell: 650 320 2440
			Email: dave.dockter@cityofpaloalto.org

Distribution: 1 City of Palo Alto, 1 Others

Attn: Dave Dockter

Provide the requested information with each report, customize as necessary. To be completed by project site arborist. Send monthly to city arborist at above address until project completion. Use additional sheets as needed.

- Assignment Activity (Demolition/grading/trenching/foundation/lot relevant work):**
 - Pre-construction meeting requirement with sub-contractors
 - Inspect to verify that tree protection measures are in place
 - Determine if field adjustments, watering or plan revisions may be needed
- Field Observations (general site-wide and list by individual tree number):**
 - Tree Protection Fences (TPF) are:
 - Trenching has/will occur
- Action Items (list site-wide, by tree number and date to be satisfied) and Date Due:**
 - Tree Protection Fence (TPF) needs adjusting (tree # x, s, x)
 - Root zone buffer material (wood chips) can be installed next
 - Schedule sewer trench foundation dig work
- Photographs (see often)**
- Tree Location Map (mandatory 8.5 x 11 sheet)**
- Recommendations, notes or monitor items for project/staff/schedule**
- Post visits (list carry-over items satisfied/still outstanding)**

Respectfully submitted,

Project site arborist

Consultant contact information (include email, cell, and mailing):

CPA Monthly Tree Activity Report, Type site address here

PAGE #1 of 1

PALO ALTO

STREET TREE PROTECTION INSTRUCTIONS

SECTION 31

APPENDIX J

General

- Tree protection has three primary functions: 1) to keep the foliage canopy and branching structure clear from contact by equipment, materials and activities; 2) to preserve roots and soil conditions in an intact and non-compacted state; and 3) to identify the Tree Protection Zone (TPZ) in which no soil disturbance is permitted and activities are restricted, unless otherwise approved.
- The Tree Protection Zone (TPZ) is a circular area around the base of the tree with a radius of one times the diameter of the tree's trunk at 4.5 feet dbh, or 1.5 times dbh, whichever is greater.

Reference Documents

- Detail 605 - Illustration of situations described below.
- Tree Technical Manual (TTM) Form (see www.cityofpaloalto.org/trees/)
- Trenching Restriction Form (TRF), Section 2.20(C-D)
- Adoptive Reporting Protocol (TRP), Section 2.20(C-D)
- Site Plan Requirements (L15), www.cityofpaloalto.org/trees/
- Tree Blocking Statement (TBS), www.cityofpaloalto.org/trees/
- Street Tree Verification (STV) Form (see www.cityofpaloalto.org/trees/)

Enforcement

- Type I Tree Protection:** The tree shall include the entire TPZ of the tree to be protected throughout the project construction period. If necessary, trees shall be protected by a fence that will not be disturbed. Once the project is approved by an appropriate grade level concrete base, it approved by Public Works Operations.
- Type II Tree Protection:** For trees situated within a planting strip, only the planting strip and joint side of the TPZ shall be enclosed with the required clear plastic protective fencing in order to keep the sidewalk and street open for public use.
- Type III Tree Protection:** To be used only with approval of Public Works Operations. Trees situated in a tree well or sidewalk planter pit, shall be wrapped with 2-inches of orange plastic fencing from the ground to the first branch and overlaid with 2-inches of wooden slat board security fence shall not be allowed to dig into the back. During installation of the plastic fencing, caution shall be used to avoid damaging any reaches. Major limbs may also require plastic fencing as directed by the City Arborist.
- Site type and area to be fenced:** All trees to be protected shall be protected with six (6) foot high chain link fences. Fences are to be installed on two-inch diameter galvanized iron posts, driven into the ground to a depth of at least 2-feet at no more than 10-foot spacing. Fencing shall extend to the outer branching, unless specifically approved on the STV Form.
- Warning signs:** A warning sign shall be weather proof and prominently displayed on each fence at 20-foot intervals. The signs shall be minimum 8.5-inches x 11-inches and clearly state in half inch tall letters: "WARNING - Tree Protection Zone - This fence shall not be removed and is subject to a fine according to PAMC Section 8.10.110"
- Duration:** Tree fencing shall be erected before demolition, grading or construction begins and remain in place until final inspection of the project, except for work specifically allowed in the TPE. Work or soil disturbance in the TPZ requires approval by the project arborist or City Arborist in the case of work around Street Trees. Excavations within the public right of way require a Street Work Permit from Public Works.
- During construction**
 - All neighbor's trees that overhang the project site shall be protected from impact of any kind.
 - The applicant shall be responsible for the repair or replacement plus penalty of any publicly owned trees that are damaged during the course of construction, pursuant to Section 8.10.110 of the Palo Alto Municipal Code.
 - The following tree preservation measures apply to all trees in the project:
 - No removal of potential, repeat, or replacement shall be removed within the TPZ.
 - The ground under and around the tree canopy area shall not be altered.
 - Trees to be retained shall be irrigated, aerial and maintained as necessary to ensure survival.

END OF SECTION

City of Palo Alto 2004 Standard Drawings and Specifications

Street Tree Verification of Protection, PWT, Section 31

Revised 08/06

City of Palo Alto

Tree Department

Public Works Operations

550-496-5953 FAX: 650-852-9280

Verification of Street Tree Protection

Applicant Instructions: Complete upper portion of this form. Mail or FAX this form along with signed Tree Protection Statement to Public Works Dept. Public Works Tree Staff will inspect and notify applicant.

APPLICATION DATE:

ADDRESS/LOCATION OF STREET TREES TO BE PROTECTED:

APPLICANT'S NAME:

APPLICANT'S ADDRESS:

APPLICANT'S TELEPHONE & FAX NUMBERS:

This section to be filled out by City Tree Staff

1 The Street Trees at the above address(es) are adequately protected. The type of protection: NONE ☐ YES ☐ NO ☐ IF NO, go to #2 below

Inspected by:

Date of inspection:

2 The Street Trees at the above address(es) are NOT adequately protected. The following modifications are required:

Indicate how the required modifications were communicated to the applicant.

Subsequent inspection

Street trees at above address were found to be adequately protected: YES ☐ NO ☐ IF NO, indicate in "Notes" below the disposition of case.

Inspected by:

Date of inspection:

Notes: List City Street trees by species, size, condition and type of tree protection installed. Also note if pictures were taken. Use back of sheet if necessary.

Return approved sheet to Applicant for demolition or building permit issuance.

8/10/2004/Tree/Street/Tree/Tree/Tree

8/10/04

---WARNING---

Tree Protection Zone

This fencing shall not be removed without City Arborist approval (650-496-5953)

Removal without permission is subject to a \$500 fine per day*

***Palo Alto Municipal Code Section 8.10.110**

City of Palo Alto Tree Protection Instructions are located at <http://www.cityofpaloalto.org/trees/technicalmanual.html>

SPECIAL INSPECTIONS

TREE PROTECTION INSPECTIONS MANDATORY

PAMC 8.10 PROTECTED TREES. CONTRACTOR SHALL ENSURE PROJECT SITE ARBORIST IS PERFORMING REQUIRED TREE INSPECTION AND SITE MONITORING. PROVIDE WRITTEN MONTHLY TREE ACTIVITY REPORTS TO THE PLANNING DEPARTMENT LANDSCAPE REVIEW STAFF BEGINNING 14 DAYS AFTER BUILDING PERMIT ISSUANCE.

BUILDING PERMIT DATE:

DATE OF 1st TREE ACTIVITY REPORT:

CITY STAFF:

REPORTING DETAILS OF THE MONTHLY TREE ACTIVITY REPORT SHALL CONFORM TO SHEET T-1 FORM. VERIFY THAT ALL TREE PROTECTION MEASURES ARE IMPLEMENTED AND WILL INCLUDE ALL CONTRACTOR ACTIVITY, SCHEDULED OR UNSCHEDULED WITHIN A TREE PROTECTION ROOT ZONE. NON-COMPLIANCE IS SUBJECT TO VIOLATION OF PAMC 8.10.110. REFERENCE: PALO ALTO TREE TECHNICAL MANUAL, SECTION 2.20 AND ADDENDUM 11.

verizon

2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

Vinculums

575 LENNON LANE #125
LAKE FOREST, CA 92630
OFFICE: (925) 482-8500

ALL STATES
ENGINEERING & SURVEYING
A ZALZALI & ASSOCIATES COMPANY

23675 BIRCHER DRIVE
LAKE FOREST, CA 92630
PHONE: (949) 273-0996

PROJECT ID: P-334882

DRAWN BY: RF

CHECKED BY: DW

REV	DATE	DESCRIPTION	
3	11/20/2020	CITY COMMENTS	MG
2	06/31/2020	100% CD'S FOR SUBMITTAL	MG
1	06/11/2020	100% CD'S FOR SUBMITTAL	RF
0	05/22/2020	100% CD'S FOR APPROVAL	RF
B	05/04/2020	95% CD'S FOR REDLINE	RF
A	04/29/2020	90% CD'S FOR REDLINE	RF

REGISTERED PROFESSIONAL ENGINEER

WISAM ZALZALI

71655

STATE OF CALIFORNIA

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 061

LIC R.O.W. ADJACENT TO:

1221 MIDDLEFIELD RD.
PALO ALTO, 94301
LOCATION CODE: 425208

SHEET TITLE

PALO ALTO TREE PROTECTION

SHEET NUMBER

L-1

City of Palo Alto

250 Hamilton Avenue, Palo Alto, CA 94301

Search: Advanced Browse By Topic:

Home > Resources & Community Environment

Tree Technical Manual

To purchase the Tree Technical Manual

June, 2001 First Edition

View by section:

- Table of Contents (PDF, 67KB)
- Intent and Purpose (PDF, 1.05MB)
- Introduction - Use of Manual (PDF, 1.05MB)
- Section 1.0 - Definitions (PDF, 96KB)
- Section 2.0 - Protection of Trees During Construction (PDF, 259KB)
- Section 3.0 - Removal, Replacement & Planting of Trees (PDF, 117KB)
- Section 4.0 - Hazardous Trees (PDF, 105KB)
- Section 5.0 - Tree Maintenance Guidelines (PDF, 110KB)
- Section 6.0 - Tree Reports (PDF, 84KB)

View ALL sections:

- Tree Technical Manual - Full (PDF, 1.04MB)

APPENDICES

- Palo Alto Municipal Code Chapter 8.10, Tree Preservation & Management Regulations
- Tree City - USA
- ISA Hazard Evaluation Form
- List of Inherent Failure Patterns for Selected Species (Reference source)
- ISA Tree Pruning Guidelines (PDF, 1.05MB)
- Tree Care Safety Standards, ANSI Z133.1-1994 (Reference source)
- Pruning Performance Standards, ANSI A300-1995 (Reference source)
- Tree Planting Details, Diagram 504 & 505
- Tree Disclosure Statement
- Palo Alto Standard Tree Protection Instructions

Apply Tree Protection Report on sheet(s) T-2

Use additional "T" sheets as needed

POLLUTION PREVENTION — IT'S PART OF THE PLAN

Construction projects are required to implement year-round stormwater BMPs, as they apply to your project.

Runoff from streets and other paved areas is a major source of pollution to San Francisco Bay. Construction activities can directly affect the health of the Bay unless contractors and crews plan ahead to keep construction dirt, debris, and other pollutants out of storm drains and local creeks. Following these guidelines will ensure your compliance with City of Palo Alto Ordinance requirements.



MATERIALS & WASTE MANAGEMENT

Non-Hazardous Materials

- ☐ Berm and cover stockpiles of sand, dirt or other construction material with tarps when rain is forecast or when they are not in use.
- ☐ Use (but don't overuse) reclaimed water for dust control.
- ☐ Ensure dust control water doesn't leave site or discharge to storm drains.

Hazardous Materials

- ☐ Label all hazardous materials and hazardous wastes (such as pesticides, paints, thinners, solvents, fuel, oil, and antifreeze) in accordance with city, county, state and federal regulations.
- ☐ Store hazardous materials and wastes in water tight containers, store in appropriate secondary containment, and cover them at the end of every work day or during wet weather or when rain is forecast.
- ☐ Follow manufacturer's application instructions for hazardous materials and do not use more than necessary. Do not apply chemicals outdoors when rain is forecast within 24 hours.
- ☐ Arrange for appropriate disposal of all hazardous wastes.

Waste Management

- ☐ Cover and maintain dumpsters. Check frequently for leaks. Place dumpsters under roofs or cover with tarps or plastic sheeting secured around the outside of the dumpster. A plastic liner is recommended to prevent leaks. Never clean out a dumpster by hosing it down on the construction site.
- ☐ Place portable toilets away from storm drains. Make sure they are in good working order. Check frequently for leaks.
- ☐ Dispose of all wastes and demolition debris properly. Recycle materials and wastes that can be recycled, including solvents, water-based paints, vehicle fluids, broken asphalt and concrete, wood, and cleared vegetation.
- ☐ Dispose of liquid residues from paints, thinners, solvents, glues, and cleaning fluids as hazardous waste.
- ☐ Keep site clear of litter (e.g. lunch items, cigarette butts).
- ☐ Prevent litter from uncovered loads by covering loads that are being transported to and from site.

Construction Entrances and Perimeter

- ☐ Establish and maintain effective perimeter controls and stabilize all construction entrances and exits to sufficiently control erosion and sediment discharges from site and tracking off site.
- ☐ Sweep or vacuum any street tracking immediately and secure sediment source to prevent further tracking. Never hose down streets to clean up tracking.



EQUIPMENT MANAGEMENT & SPILL CONTROL

Maintenance and Parking

- ☐ Designate an area of the construction site, well away from streams or storm drain inlets and fitted with appropriate BMPs, for auto and equipment parking, and storage.
- ☐ Perform major maintenance, repair jobs, and vehicle and equipment washing off site.
- ☐ If refueling or vehicle maintenance must be done onsite, work in a bermed area away from storm drains and over a drip pan or drop cloths big enough to collect fluids. Recycle or dispose of fluids as hazardous waste.
- ☐ If vehicle or equipment cleaning must be done onsite, clean with water only in a bermed area that will not allow rinse water to run into gutters, streets, storm drains, or surface waters.
- ☐ Do not clean vehicle or equipment onsite using soaps, solvents, degreasers, or steam cleaning equipment, and do not use diesel oil to lubricate equipment or parts onsite.

Spill Prevention and Control

- ☐ Keep spill cleanup materials (e.g., rags, absorbents and cat litter) available at the construction site at all times.
- ☐ Maintain all vehicles and heavy equipment. Inspect frequently for and repair leaks. Use drip pans to catch leaks until repairs are made.
- ☐ Clean up leaks, drips and other spills immediately and dispose of cleanup materials properly.
- ☐ Use dry cleanup methods whenever possible (absorbent materials, cat litter and/or rags).
- ☐ Sweep up spilled dry materials immediately. Never attempt to "wash them away" with water, or bury them.
- ☐ Clean up spills on dirt areas by digging up and properly disposing of contaminated soil.
- ☐ Report any hazardous materials spills immediately! Call City of Palo Alto Communications, (650) 329-2413. If the spill poses a significant hazard to human health and safety, property or the environment, you must report it to the State Office of Emergency Services, (800) 852-7550 (24 hours).



EARTHMOVING

Grading and Earthwork

- ☐ Schedule grading and excavation work during dry weather.
- ☐ Stabilize all denuded areas, install and maintain temporary erosion controls (such as erosion control fabric or bonded fiber matrix) until vegetation is established.
- ☐ Remove existing vegetation only when absolutely necessary, plant temporary vegetation for erosion control on slopes or where construction is not immediately planned.
- ☐ Prevent sediment from migrating offsite and protect storm drain inlets, drainage courses and streams by installing and maintaining appropriate BMPs (e.g., silt fences, gravel bags, fiber rolls, temporary swales, etc.).
- ☐ Keep excavated soil on site and transfer it to dump trucks on site, not in the streets.

Contaminated Soils

- ☐ If any of the following conditions are observed, test for contamination and contact the Regional Water Quality Control Board:
 - Unusual soil conditions, discoloration, or odor.
 - Abandoned underground tanks.
 - Abandoned wells.
 - Buried barrels, debris, or trash.
- ☐ If the above conditions are observed, document any signs of potential contamination and clearly mark them so they are not disturbed by construction activities.

Landscaping

- ☐ Protect stockpiled landscaping materials from wind and rain by storing them under tarps all year-round.
- ☐ Stack bagged material on pallets and under cover.
- ☐ Discontinue application of any erodible landscape material within 2 days before a forecast rain event or during wet weather.



CONCRETE MANAGEMENT & DEWATERING

Concrete Management

- ☐ Store both dry and wet materials under cover, protected from rainfall and runoff and away from storm drains or waterways. Store materials off the ground, on pallets. Protect dry materials from wind.
- ☐ Wash down exposed aggregate concrete only when the wash water can (1) flow onto a dirt area; (2) drain onto a bermed surface from which it can be pumped and disposed of properly; or (3) block any storm drain inlets and vacuum washwater from the gutter. If possible, sweep first.
- ☐ Wash out concrete equipment/trucks offsite or in a designated washout area, where the water will flow into a temporary waste pit, and make sure wash water does not leach into the underlying soil. (See CASQA Construction BMP Handbook for properly designed concrete washouts.)

Dewatering

- ☐ Reuse water for dust control, irrigation or another on-site purpose to the greatest extent possible.
- ☐ Be sure to obtain a Permit for Construction in the Public Street from Public Works Engineering before discharging water to a street, gutter, or storm drain. Call the Regional Water Quality Control Plant (RWQCP) at (650) 329-2598 for an inspection prior to commencing discharge. Use filtration or diversion through a basin, tank, or sediment trap as required by the approved dewatering plan. Dewatering is not permitted from October to April.
- ☐ In areas of known contamination, testing is required prior to reuse or discharge of groundwater. Consult with the City inspector to determine what testing to do and to interpret results. Contaminated groundwater must be treated or hauled off-site for proper disposal.



PAVING/ASPHALT WORK

Paving

- ☐ Avoid paving and seal coating in wet weather or when rain is forecast, to prevent materials that have not cured from contacting stormwater runoff.
- ☐ Cover storm drain inlets and manholes when applying seal coat, slurry seal, fog seal, or similar materials.
- ☐ Collect and recycle or appropriately dispose of excess abrasive gravel or sand. Do NOT sweep or wash it into gutters.

Sawcutting & Asphalt/Concrete Removal

- ☐ Protect storm drain inlets during saw cutting.
- ☐ If saw cut slurry enters a catch basin, clean it up immediately.
- ☐ Shovel or vacuum saw cut slurry deposits and remove from the site. When making saw cuts, use as little water as possible. Sweep up, and properly dispose of all residues.



PAINTING & PAINT REMOVAL

Painting Cleanup and Removal

- ☐ Never clean brushes or rinse paint containers into a street, gutter, storm drain, or stream.
- ☐ For water-based paints, paint out brushes to the extent possible, and rinse into a drain that goes to the sanitary sewer. Never pour paint down a storm drain.
- ☐ For oil-based paints, paint out brushes to the extent possible and clean with thinner or solvent in a proper container. Filter and reuse thinners and solvents. Dispose of excess liquids as hazardous waste.
- ☐ Sweep up or collect paint chips and dust from non-hazardous dry stripping and sand blasting into plastic drop cloths and dispose of as trash.
- ☐ Chemical paint stripping residue and chips and dust from marine paints or paints containing lead, mercury, or tributyltin must be disposed of as hazardous waste. Lead based paint removal requires a state certified contractor.



STORM DRAIN POLLUTERS MAY BE LIABLE FOR FINES OF UP TO \$10,000 PER DAY!

250 Hamilton Avenue
Palo Alto, CA 94301
650.329.2211
cityofpaloalto.org



verizon

2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

Vinculum

575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500

ALL STATES
ENGINEERING & SURVEYING
A ZALZALI & ASSOCIATES COMPANY

23675 BIRTCHE DRIVE
LAKE FOREST, CA 92630
PHONE: (949) 273-0996

PROJECT ID: P-334882

DRAWN BY: RF

CHECKED BY: DW

REV	DATE	DESCRIPTION	
3	11/20/2020	CITY COMMENTS	MG
2	06/31/2020	100% CD'S FOR SUBMITTAL	MG
1	06/11/2020	100% CD'S FOR SUBMITTAL	RF
0	05/22/2020	100% CD'S FOR APPROVAL	RF
B	05/04/2020	95% CD'S FOR REDLINE	RF
A	04/29/2020	90% CD'S FOR REDLINE	RF



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 061
LIC R.O.W. ADJACENT TO:
1221 MIDDLEFIELD RD.
PALO ALTO, 94301
LOCATION CODE: 425208

SHEET TITLE
PALO ALTO POLLUTION
PREVENTION CHECKLIST


SHEET NUMBER
L-2

EROSION AND SEDIMENT CONTROL NOTES:


TEMPORARY EROSION/SEDIMENT CONTROL, PRIOR TO COMPLETION OF FINAL IMPROVEMENTS, SHALL BE PERFORMED BY THE CONTRACTOR OR QUALIFIED PERSON AS INDICATED BELOW:

- ALL REQUIREMENTS OF THE CITY "LAND DEVELOPMENT MANUAL, STORM WATER STANDARDS" MUST BE INCORPORATED INTO THE DESIGN AND CONSTRUCTION OF THE PROPOSED PUBLIC IMPROVEMENTS CONSISTENT WITH THE EROSION CONTROL PLAN AND/OR WATER POLLUTION CONTROL PLAN (WPCP), IF APPLICABLE.
- FOR STORM DRAIN INLETS, PROVIDE A GRAVEL BAG SILT BASIN IMMEDIATELY UPSTREAM OF INLET AS INDICATED ON DETAILS.
- THE CONTRACTOR OR QUALIFIED PERSON SHALL BE RESPONSIBLE FOR CLEANUP OF SILT AND MUD ON ADJACENT STREET(S) AND STORM DRAIN SYSTEM DUE TO CONSTRUCTION ACTIVITY.
- THE CONTRACTOR SHALL REMOVE SILT AND DEBRIS AFTER EACH MAJOR RAINFALL.
- EQUIPMENT AND WORKERS FOR EMERGENCY WORK SHALL BE MADE AVAILABLE AT ALL TIMES DURING THE RAINY SEASON.
- THE CONTRACTOR SHALL RESTORE ALL EROSION/SEDIMENT CONTROL DEVICES TO WORKING ORDER TO THE SATISFACTION OF THE CITY ENGINEER OR RESIDENT ENGINEER AFTER EACH RUN-OFF PRODUCING RAINFALL.
- THE CONTRACTOR SHALL INSTALL ADDITIONAL EROSION/SEDIMENT CONTROL MEASURES AS MAY THE CONTRACTOR SHALL INSTALL ADDITIONAL EROSION/SEDIMENT CONTROL MEASURES AS MAY BE REQUIRED BY THE RESIDENT ENGINEER DUE TO UNFORESEEN CIRCUMSTANCES, WHICH MAY ARISE.
- EROSION/SEDIMENT CONTROL MEASURES PROVIDED PER THE APPROVED IMPROVEMENT PLAN SHALL BE INCORPORATED HEREON. ALL EROSION/SEDIMENT CONTROL FOR INTERIM CONDITIONS SHALL BE DONE TO THE SATISFACTION OF THE RESIDENT ENGINEER.
- ALL REMOVABLE PROTECTIVE DEVICES SHOWN SHALL BE IN PLACE AT THE END OF EACH WORKING DAY WHEN RAIN IS IMMINENT.
- THE CONTRACTOR SHALL ARRANGE FOR WEEKLY MEETINGS DURING OCTOBER 1ST TO APRIL 30TH FOR PROJECT TEAM (GENERAL CONTRACTOR, QUALIFIED PERSON, EROSION CONTROL SUBCONTRACTOR IF ANY, ENGINEER OF WORK, OWNER/DEVELOPER AND THE RESIDENT ENGINEER) TO EVALUATE THE ADEQUACY OF THE EROSION/SEDIMENT CONTROL MEASURES AND OTHER RELATED CONSTRUCTION ACTIVITIES.

STORM DRAIN INLET PROTECTION



TYPICAL PROTECTION FOR INLET WITH OPPOSING FLOW DIRECTIONS



TYPICAL PROTECTION FOR INLET WITH SINGLE FLOW DIRECTION

NOTES:

- INTENDED FOR SHORT-TERM USE.
- USE TO INHIBIT NON-STORM WATER FLOW.
- ALLOW FOR PROPER MAINTENANCE AND CLEANUP.
- BAGS MUST BE REMOVED AFTER ADJACENT OPERATION IS COMPLETED.
- NOT APPLICABLE IN AREAS WITH HIGH SILTS AND CLAYS WITHOUT FILTER FABRIC.

NOTES:

- CONTRACTOR TO POTHOLE ALL UTILITY CROSSINGS.
- CONTRACTOR TO PLACE SANDBAGS AROUND ANY/ALL STORM DRAIN INLETS TO PREVENT CONTAMINATED WATER.
- SPOILS PILE WILL BE COVERED AND CONTAINED AND STREET WILL BE SWEEPED AND CLEANED AS NEEDED.
- CONTRACTOR TO REPAIR DAMAGED PUBLIC IMPROVEMENTS TO THE SATISFACTION OF THE CITY ENGINEER.
- SIDEWALK TO BE REPLACED CURB & GUTTER TO BE PROTECTED IN PLACE. SIDEWALK TO BE REPLACED TO THE SATISFACTION OF THE CITY ENGINEER.
- THE CONTRACTOR SHALL RESTORE THE ROADWAY BACK TO ITS ORIGINAL CONDITION SATISFACTORY TO THE CITY ENGINEER INCLUDING, BUT NOT LIMITED TO PAVING, STRIPING, BIKE LANES, PAVEMENT LEGENDS, SIGNS, AND TRAFFIC LOOP DETECTORS.
- SIDEWALK SHALL BE RESTORED/REPLACED PER CITY STANDARD DRAWINGS.
- PEDESTRIAN RAMP WILL NOT BE DISTURBED. PEDESTRIAN RAMP WILL NOT BE DISTURBED.

GENERAL CONTRACTOR NOTES:

- STREET USE PERMIT SHALL BE OBTAINED BY CONTRACTOR PRIOR TO COMMENCING WORK.
- ALL WORK TO BE CONDUCTED IN THE RIGHT OF WAY.
- ALL DISTURBED LANDSCAPING SHALL BE REPLACED TO SIMILAR EXISTING CONDITION.
- ANY SIDEWALK CLOSURE SHALL BE COORDINATED WITH THE CITY AND PROPER SIGNING WILL BE PLACED.
- NO MATERIALS OR EQUIPMENT SHALL BE STORED ON PRIVATE PROPERTY OR BLOCK ACCESS TO PRIVATE PROPERTY.
- CLEANUP OF SITE WILL BE COMPLETED EACH EVENING AND THE SITE WILL BE RETURNED TO EXISTING CONDITIONS AT THE COMPLETION OF CONSTRUCTION AT EACH SITE.

** CONTRACTOR SHALL VERIFY ALL PLANS AND EXISTING DIMENSIONS AND CONDITIONS ON THE JOB SITE AND SHALL IMMEDIATELY NOTIFY THE ENGINEER IN WRITING OF ANY DISCREPANCIES BEFORE PROCEEDING WITH THE WORK OR RESPONSIBLE FOR SAME.

R.O.W. GROUND CONSTRUCTION NOTES:

- GROUND CONSTRUCTION TO REMOVE/CLEAN ALL DEBRIS, NAILS, STAPLES, GROUND CONSTRUCTION TO REMOVE/CLEAN ALL DEBRIS, NAILS, STAPLES, OR NON-USED VERTICALS OFF THE POLE.
- ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH MUNICIPAL, COUNTY, STATE, FEDERAL, GO95 AND GO128 STANDARDS AND REGULATIONS.
- CALL USA 48 HOURS PRIOR TO EXCAVATING AT (800) 227-2600 OR 811.
- ALL LANDSCAPING TO BE RESTORED TO ORIGINAL CONDITION OR BETTER.
- ALL EQUIPMENT TO BE BONDED. ALL EQUIPMENT TO BE BONDED.
- METERING CABINET REQUIRES 36" CLEARANCE AT DOOR OPENING.
- CAULK CABINET BASE AT PAD.

CALIFORNIA STATE CODE COMPLIANCE:

ALL WORK AND MATERIALS SHALL BE PREFORMED AND INSTALLED IN ACCORDANCE WITH THE CURRENT EDITIONS OF THE FOLLOWING CODES AS ADOPTED BY THE LOCAL GOVERNING AUTHORITIES. NOTHING IN THESE PLANS IS TO BE CONSTRUCTED TO PERMIT WORK NOT CONFORMING TO THESE CODES:

- CALIFORNIA ADMINISTRATIVE CODE (INCLUDING TITLES 24 & 25) 2016
- 2016 CALIFORNIA BUILDING CODES WHICH ADOPTS THE 2015 IBC, 2015 IMC, 2015 IPC AND THE 2014 NEC, AND SHALL INCLUDE 2016 CBC, CFC, CMC, CEC, CPC, CGBSC.
- BUILDING OFFICIALS & CODE ADMINISTRATORS (BOCA) CURRENT NATIONAL CODES
- ANSI/EIA-222-G (2009 - 2ND EDITION)
- NFPA-101 - LIFE SAFETY CODE / CAL-OSHA - TITLE 8 / FCR - TITLE 29
- LOCAL BUILDING CODE
- CITY/COUNTY ORDINANCES
- ACCESSIBILITY REQUIREMENTS:

** FACILITY IS UNMANNED AND NOT FOR HUMAN HABITATION. HANDICAPPED ACCESS REQUIREMENTS DO NOT APPLY IN ACCORDANCE WITH THE 2016 CALIFORNIA BUILDING CODE.

- FCC RF/EMF EXPOSURE/EMIITANCE COMPLIANCE:


**FCC NOTE: THIS WIRELESS COMMUNICATION FACILITY COMPLIES WITH FEDERAL STANDARDS FOR RADIO FREQUENCY IN ACCORDANCE WITH THE TELECOMMUNICATION ACT OF 1996 AND SUBSEQUENT AMENDMENTS AND ANY OTHER REQUIREMENTS IMPOSED BY STATE OR FEDERAL REGULATORY AGENCIES.


CITY OF PALO ALTO UTILITIES ENGINEERING NOTES:

- APPLICANT SHALL TAP ELECTRIC SERVICE TO THE SMALL CELL DISTRIBUTED ANTENNA SYSTEM FROM THE LOCATIONS JOINTLY IDENTIFIED DURING THE FIELD INVESTIGATION.
- SERVICE VOLTAGE TO ALL THE PROPOSED LOCATIONS MAY NOT BE THE SAME. APPLICANT SHALL DESIGN THEIR SYSTEM TO OPERATE AT THE AVAILABLE VOLTAGE IN THE VICINITY.
- IF BRAND NEW POLES NEED TO BE INSTALLED FOR APPLICANT'S SYSTEM THEN THE POLES MUST MATCH EXISTING POLES IN THE DOWN TOWN AREA.
- AFTER EXCAVATION IS COMPLETED ON THE PUBLIC RIGHT OF WAY, EXISTING STREETS INCLUDING SIDEWALKS/ CURB/ GUTTER OR ANY DECORATIVE PATHS MUST BE BROUGHT TO ITS ORIGINAL CONDITION AND MUST BE APPROVED BY PUBLIC WORKS ENGINEERING DEPARTMENT'S INSPECTOR. POTHOLING MUST BE DONE AND ALL THE UTILITIES MUST BE IDENTIFIED PRIOR TO COMMENCING EXCAVATION.
- EXCAVATION AND RESTORATION WORK MUST BE IN COMPLIANCE WITH PUBLIC WORKS ENGINEERING STANDARDS AND SPECIFICATIONS THAT ARE AVAILABLE ON THE FOLLOWING WEBSITE:
http://www.cityofpaloalto.org/news/displaynews.asp?NewsID=1834&TargetID=145
- APPLICANTS SHALL BE RESPONSIBLE FOR MAINTAINING THEIR SYSTEM INCLUDING SUBSTRUCTURE. IN CASE OF KNOCK DOWNS, THE CITY WILL RE-INSTALL ITS STREET LIGHTING POLES BUT NOT APPLICANT'S EQUIPMENT ON OR OFF THE POLE.
- A FIELD MEETING IS RECOMMENDED WITH UTILITIES ENGINEERING PRIOR TO COMMENCING THE WORK.
- PLANS SHALL INCLUDE A NOTE: CONTRACTOR TREE INSPECTION REQUIREMENTS: MODIFIED TYPE III TRUNK WRAPPING SHALL BE VERIFIED BY URBAN FORESTRY PRIOR TO ANY WORK IN THE VICINITY. FOR EACH TREE SITE WRAPPED FOR PROTECTION WITHIN 15' OF ANY WORK ZONE OR CONCRETE FORM SECTION, A BILLABLE TREE INSPECTION BY URBAN FORESTRY (650-496-5963, 24-HOUR ADVANCE IS REQUIRED) SHALL BE COMPLETED PRIOR TO DEMOLITION, DRILLING, EXCAVATING, FORMING OR STREET LIGHT ACTIVITY. CONTRACTOR SHALL ARRANGE PAYMENTS AT THE DEVELOPMENT CENTER, 285 HAMILTON AVE, PALO ALTO, CA.
- THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE UTILITIES DEPARTMENT 650/329-2413 OR 650/496-6982 IF THE EXISTING WATER, WASTEWATER OR GAS MAINS ARE DISTURBED OR DAMAGED. A QUALIFIED CONTRACTOR MAY PERFORM REPAIRS ON CITY WATER AND WASTEWATER MAINS UNDER THE DIRECT SUPERVISION OF THE WGW UTILITIES INSPECTOR. FOR WATER REPAIRS ALL THE DISINFECTION REQUIREMENTS OF THE WGW UTILITY STANDARDS AND THESE CONDITIONS SHALL BE ADHERED TO. ALL REPAIRS TO THE CITY GAS SYSTEM MUST BE PERFORMED BY THE CITY OF PALO ALTO UTILITIES.
- NO WATER VALVES OR OTHER FACILITIES OWNED BY UTILITIES DEPARTMENT SHALL BE OPERATED FOR ANY PURPOSE BY THE APPLICANT'S CONTRACTOR. ALL REQUIRED OPERATION WILL ONLY BE PERFORMED BY AUTHORIZED UTILITIES DEPARTMENT PERSONNEL. WATER VALVES MAY BE OPERATED BY THE CONTRACTOR UNDER THE DIRECT SUPERVISION OF THE WGW UTILITIES INSPECTOR. THE APPLICANT'S CONTRACTOR SHALL NOTIFY THE UTILITIES DEPARTMENT NOT LESS THAN FORTY- EIGHT (48) HOURS IN ADVANCE OF THE TIME THAT SUCH OPERATION IS REQUIRED.

NORMAL LOCATION OF UNDERGROUND UTILITIES NOTES:

- LOCATION AND DEPTH OF EXISTING AND PROPOSED UTILITIES MUST BE PROVIDED BY THE SUBDIVIDER AND SHOWN ON ANY PLANS SUBMITTED TO THE DEPT. OF PUBLIC WORKS FOR APPROVAL.
- CHANGES MAY BE PERMITTED BY THE DEPT. OF PUBLIC WORKS IN CASES OF CONFLICTING FACILITIES.
- CONFLICTS BETWEEN UTILITY COMPANIES FACILITIES, EXISTING AND PROPOSED, MUST BE MUTUALLY RESOLVED BY THE UTILITY COMPANIES.
- FOR COMMERCIAL SIDEWALKS, THE FIRE HYDRANT SHALL BE PLACED WITHIN THE SIDEWALK 1'-6" BEHIND FACE OF CURB.
- MAXIMUM 2" DIAMETER GAS MAINS MAY BE PLACED IN JOINT UTILITIES TRENCH SUBJECT TO APPROVAL OF CITY ENGINEER (IN TRACTS).



Rev	By	Date	Conduit Location Detail Telecommunications	Approved by: 	
0	DWH	7/16/98		PE No.	72158
1	MMN	7/20/04		Date	01/10/18
Scale: NTS				Dwg No.	402
			City of Palo Alto Standard		

verizon

2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

Vinculum

575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500

ALL STATES
ENGINEERING & SURVEYING
A ZALZALI & ASSOCIATES COMPANY

23675 BIRTCHE DRIVE
LAKE FOREST, CA 92630
PHONE: (949) 273-0996

PROJECT ID: P-334882

DRAWN BY: RF

CHECKED BY: DW

3	11/20/2020	CITY COMMENTS	MG
2	08/31/2020	100% CD'S FOR SUBMITTAL	MG
1	06/11/2020	100% CD'S FOR SUBMITTAL	RF
0	05/22/2020	100% CD'S FOR APPROVAL	RF
B	05/04/2020	95% CD'S FOR REDLINE	RF
A	04/29/2020	90% CD'S FOR REDLINE	RF
REV	DATE	DESCRIPTION	



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 061
LIC R.O.W. ADJACENT TO:
1221 MIDDLEFIELD RD.
PALO ALTO, 94301
LOCATION CODE: 425208

SHEET TITLE
**PALO ALTO EROSION
CONTROL AND CONDUIT
LOCATION DETAILS & NOTES**

SHEET NUMBER

L-3



Vinculums CA SJ Palo Alto 204 Looking Northeast from Webster Street View #1
9/3/20 850 Webster Street Palo Alto, CA Applied Imagination 510 914-0500



Vinculums CA SJ Palo Alto 204 Looking South from Webster Street View #2
10/30/20 850 Webster Street Palo Alto, CA Applied Imagination 510 914-0500

verizon

2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

Vinculums

575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500

ALLSTATES
ENGINEERING & SURVEYING

23675 BIRCHER DRIVE
LAKE FOREST, CA 92630

PROJECT ID:	TBD
DRAWN BY:	AM
CHECKED BY:	DW

3	11/20/2020	CITY COMMENTS	MG
2	09/10/2020	100% CD'S FOR SUBMITTAL	MG
1	06/11/2020	100% CD'S FOR SUBMITTAL	RF
0	05/22/2020	100% CD'S FOR APPROVAL	RF
B	05/06/2020	95% CD'S FOR REDLINE	RF
A	04/22/2020	90% CD'S FOR REDLINE	AM
REV	DATE	DESCRIPTION	



IT IS A VIOLATION OF LAW FOR ANY PERSON,
UNLESS THEY ARE ACTING UNDER THE
DIRECTION OF A LICENSED PROFESSIONAL
ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 204
PUBLIC R.O.W. ADJACENT TO:
ADJACENT TO
850 WEBSTER STREET
PALO ALTO, 94301
LOCATION CODE: 566800

SHEET TITLE
PHOTOSIMS

SHEET NUMBER
T-2

Verizon Wireless • Proposed Small Cell (No. 566800 "SF Palo Alto 204")
850 Webster Street • Palo Alto, California

Statement of Hammett & Edison, Inc., Consulting Engineers

The firm of Hammett & Edison, Inc., Consulting Engineers, has been retained on behalf of Verizon Wireless, a personal wireless telecommunications carrier, to evaluate its small cell (No. 566800 "SF Palo Alto 204") proposed to be sited in Palo Alto, California, for compliance with appropriate guidelines limiting human exposure to radio frequency ("RF") electromagnetic fields.

Executive Summary

Verizon proposes to install two small antennas on the municipal light pole sited in the public right-of-way near 850 Webster Street in Palo Alto. The proposed operation will comply with the FCC guidelines limiting public exposure to RF energy.

Prevailing Exposure Standards

The U.S. Congress requires that the Federal Communications Commission ("FCC") evaluate its actions for possible significant impact on the environment. A summary of the FCC's exposure limits is shown in Figure 1. These limits apply for continuous exposures and are intended to provide a prudent margin of safety for all persons, regardless of age, gender, size, or health. The most restrictive limit for exposures of unlimited duration at several wireless service bands are as follows:

Wireless Service Band	Transmit Frequency	"Uncontrolled" Public Limit	Occupational Limit (5 times Public)
Microwave (point-to-point)	1-80 GHz	1.0 mW/cm ²	5.0 mW/cm ²
Millimeter-wave	24-47	1.0	5.0
Part 15 (WiFi & other unlicensed)	2-6	1.0	5.0
CBRS (Citizens Broadband Radio)	3,550 MHz	1.0	5.0
BRS (Broadband Radio)	2,490	1.0	5.0
WCS (Wireless Communication)	2,305	1.0	5.0
AWS (Advanced Wireless)	2,110	1.0	5.0
PCS (Personal Communication)	1,930	1.0	5.0
Cellular	869	0.58	2.9
SMR (Specialized Mobile Radio)	854	0.47	2.35
700 MHz	716	0.48	2.4
600 MHz	617	0.41	2.05
[most restrictive frequency-range]	30-300	0.20	1.0

Power line frequencies (60 Hz) are well below the applicable range of these standards, and there is considered to be no compounding effect from simultaneous exposure to power line and radio frequency fields.

Verizon Wireless • Proposed Small Cell (No. 566800 "SF Palo Alto 204")
850 Webster Street • Palo Alto, California

Authorship

The undersigned author of this statement is a qualified Professional Engineer, holding California Registration No. E-21306, which expires on September 30, 2021. This work has been carried out under his direction, and all statements are true and correct of his own knowledge except, where noted, when data has been supplied by others, which data he believes to be correct.



Neil J. Olij, P.E.
707/996-5200

September 29, 2020

Verizon Wireless • Proposed Small Cell (No. 566800 "SF Palo Alto 204")
850 Webster Street • Palo Alto, California

General Facility Requirements

Small cells typically consist of two distinct parts: the electronic transceivers (also called "radios" or "channels") that are connected to the traditional wired telephone lines, and the passive antennas that send the wireless signals created by the radios out to be received by individual subscriber units. The radios are typically mounted on the support pole or placed in a cabinet at ground level, and they are connected to the antennas by coaxial cables. Because of the short wavelength of the frequencies assigned by the FCC for wireless services, the antennas require line-of-sight paths for their signals to propagate well and so are installed at some height above ground. The antennas are designed to concentrate their energy toward the horizon, with very little energy wasted toward the sky or the ground. This means that it is generally not possible for exposure conditions to approach the maximum permissible exposure limits without being physically very near the antennas.

Computer Modeling Method

The FCC provides direction for determining compliance in its Office of Engineering and Technology Bulletin No. 65, "Evaluating Compliance with FCC-Specified Guidelines for Human Exposure to Radio Frequency Radiation," dated August 1997. Figure 2 describes the calculation methodologies, reflecting the facts that a directional antenna's radiation pattern is not fully formed at locations very close by (the "near-field" effect) and that at greater distances the power level from an energy source decreases with the square of the distance from it (the "inverse square law"). This methodology is an industry standard for evaluating RF exposure conditions and has been demonstrated through numerous field tests to be a conservative prediction of exposure levels.

Site and Facility Description


Based upon information provided by Verizon, including drawings by All States Engineering & Surveying, dated September 19, 2020, it is proposed to install two Ericsson Model 6701, 2-foot tall, directional panel antennas with integrated radios on top of a new light pole to replace the existing pole sited in the public right-of-way on the southeast side of Homer Avenue about 190 feet southwest of Webster Street, adjacent to the tall residential building at 850 Webster Street in Palo Alto. The antennas would employ no downtilt, would be mounted at an effective height of about 23 feet above ground, and would be oriented toward 0°T and 240°T. The maximum effective radiated power proposed in any direction is 193 watts in the 28 GHz band. There are reported no other wireless telecommunications base stations at the site or nearby.

FCC Radio Frequency Protection Guide

The U.S. Congress required (1996 Telecom Act) the Federal Communications Commission ("FCC") to adopt a nationwide human exposure standard to ensure that its licensees do not, cumulatively, have a significant impact on the environment. The FCC adopted the limits from Report No. 86, "Biological Effects and Exposure Criteria for Radiofrequency Electromagnetic Fields," published in 1986 by the Congressionally chartered National Council on Radiation Protection and Measurements ("NCRP"). Separate limits apply for occupational and public exposure conditions, with the latter limits generally five times more restrictive. The more recent standard, developed by the Institute of Electrical and Electronics Engineers and approved as American National Standard ANSI/IEEE C95.1-2006, "Safety Levels with Respect to Human Exposure to Radio Frequency Electromagnetic Fields, 3 kHz to 300 GHz," includes similar limits. These limits apply for continuous exposures from all sources and are intended to provide a prudent margin of safety for all persons, regardless of age, gender, size, or health.

As shown in the table and chart below, separate limits apply for occupational and public exposure conditions, with the latter limits (in *italics* and/or dashed) up to five times more restrictive:

Frequency Applicable Range (MHz)	Electromagnetic Fields (f is frequency of emission in MHz)		
	Electric Field Strength (V/m)	Magnetic Field Strength (A/m)	Equivalent Far-Field Power Density (mW/cm ²)
0.3 - 1.34	614	1.63	100
1.34 - 3.0	614	1.63	100
3.0 - 30	1842/f	4.89/f	900/f ²
30 - 300	61.4	0.163	1.0
300 - 1,500	3.54/√f	√f/106	f/1500
1,500 - 100,000	137	0.364	5.0



Higher levels are allowed for short periods of time, such that total exposure levels averaged over six or thirty minutes, for occupational or public settings, respectively, do not exceed the limits, and higher levels also are allowed for exposures to small areas, such that the spatially averaged levels do not exceed the limits. However, neither of these allowances is incorporated in the conservative calculation formulas in the FCC Office of Engineering and Technology Bulletin No. 65 (August 1997) for projecting field levels. Hammett & Edison has incorporated those formulas in a computer program capable of calculating, at thousands of locations on an arbitrary grid, the total expected power density from any number of individual radio frequency sources. The program allows for the inclusion of uneven terrain in the vicinity, as well as any number of nearby buildings of varying heights, to obtain more accurate projections.

Verizon Wireless • Proposed Small Cell (No. 566800 "SF Palo Alto 204")
850 Webster Street • Palo Alto, California

Study Results

For a person anywhere at ground, the maximum RF exposure level due to the proposed Verizon operation is calculated to be 0.0085 mW/cm², which is 0.85% of the applicable public exposure limit. The maximum calculated level at any nearby building² is 1.1% of the public exposure limit. It should be noted that these results include several "worst-case" assumptions and therefore are expected to overstate actual power density levels from the proposed operation.

Recommended Mitigation Measures

Due to their mounting locations and height, the antennas would not be accessible to unauthorized persons, and so no measures are necessary to comply with the FCC public exposure guidelines. To prevent occupational exposures in excess of the FCC guidelines, it is recommended that appropriate RF safety training be provided to all workers who have access within 8 feet outward from the antennas. No access within 2 feet directly in front of the antennas should be allowed while the antennas are in operation, unless other measures can be demonstrated to ensure that occupational protection requirements are met. It is recommended that explanatory signs³ be posted at the antennas and/or on the pole below the antennas, readily visible from any angle of approach.

Conclusion

Based on the information and analysis above, it is the undersigned's professional opinion that operation of the small cell proposed by Verizon Wireless near 850 Webster Street in Palo Alto, California, will comply with the prevailing standards for limiting public exposure to radio frequency energy and, therefore, will not for this reason cause a significant impact on the environment. The highest calculated level in publicly accessible areas is much less than the prevailing standards allow for exposures of unlimited duration. This finding is consistent with measurements of actual exposure conditions taken at other operating small cells. Training authorized personnel and posting explanatory signs are recommended to establish compliance with occupational exposure limits.

² Including the second- and third-floor balconies of the adjacent residential building, located at least 40 feet away based on the drawings.
³ Signs should comply with OET-65 color, symbol, and content recommendations. Contact information should be provided (e.g., a telephone number) to arrange for access to restricted areas. The selection of language(s) is not an engineering matter, and guidelines from the landlord, local zoning or health authority, or appropriate professionals may be required.

RFR.CALC™ Calculation Methodology

Assessment by Calculation of Compliance with FCC Exposure Guidelines

The U.S. Congress required (1996 Telecom Act) the Federal Communications Commission ("FCC") to adopt a nationwide human exposure standard to ensure that its licensees do not, cumulatively, have a significant impact on the environment. The maximum permissible exposure limits adopted by the FCC (see Figure 1) apply for continuous exposures from all sources and are intended to provide a prudent margin of safety for all persons, regardless of age, gender, size, or health. Higher levels are allowed for short periods of time, such that total exposure levels averaged over six or thirty minutes, for occupational or public settings, respectively, do not exceed the limits.

Near Field.

Prediction methods have been developed for the near field zone of panel (directional) and whip (omnidirectional) antennas, typical at wireless telecommunications base stations, as well as dish (aperture) antennas, typically used for microwave links. The antenna patterns are not fully formed in the near field at these antennas, and the FCC Office of Engineering and Technology Bulletin No. 65 (August 1997) gives suitable formulas for calculating power density within such zones.

$$\text{For a panel or whip antenna, power density } S = \frac{180}{\theta_{1/2}} \times \frac{0.1 \times P_{\text{net}}}{\pi \times D \times h}, \text{ in mW/cm}^2,$$

$$\text{and for an aperture antenna, maximum power density } S_{\text{max}} = \frac{0.1 \times 16 \times \eta \times P_{\text{net}}}{\pi \times h^2}, \text{ in mW/cm}^2,$$

where $\theta_{1/2}$ = half-power beamwidth of antenna, in degrees,

P_{net} = net power input to antenna, in watts,

D = distance from antenna, in meters,

h = aperture height of antenna, in meters, and

η = aperture efficiency (unitless, typically 0.5-0.8).

The factor of 0.1 in the numerators converts to the desired units of power density.

Far Field.

OET-65 gives this formula for calculating power density in the far field of an individual RF source:

$$\text{power density } S = \frac{2.56 \times 1.64 \times 100 \times \text{RFF}^2 \times \text{ERP}}{4 \times \pi \times D^2}, \text{ in mW/cm}^2,$$

where ERP = total ERP (all polarizations), in kilowatts,

RFF = three-dimensional relative field factor toward point of calculation, and

D = distance from antenna effective height to point of calculation, in meters.

The factor of 2.56 accounts for the increase in power density due to ground reflection, assuming a reflection coefficient of 1.6 (1.6 x 1.6 = 2.56). The factor of 1.64 is the gain of a half-wave dipole relative to an isotropic radiator. The factor of 100 in the numerator converts to the desired units of power density. This formula is used in a computer program capable of calculating, at thousands of locations on an arbitrary grid, the total expected power density from any number of individual radio frequency sources. The program also allows for the inclusion of uneven terrain in the vicinity, as well as any number of nearby buildings of varying heights, to obtain more accurate projections.

verizon

2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

Vinculum

575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500

ALLSTATES
ENGINEERING & SURVEYING
23675 BIRCHER DRIVE
LAKE FOREST, CA 92630

PROJECT ID: TBD
DRAWN BY: AM
CHECKED BY: DW

3	11/20/2020	CITY COMMENTS		MG
2	09/10/2020	100% CD'S FOR SUBMITTAL		MG
1	06/11/2020	100% CD'S FOR SUBMITTAL		RF
0	05/22/2020	100% CD'S FOR APPROVAL		RF
B	05/06/2020	95% CD'S FOR REDLINE		RF
A	04/22/2020	90% CD'S FOR REDLINE		AM
REV	DATE	DESCRIPTION		



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 204
PUBLIC R.O.W. ADJACENT TO:
ADJACENT TO
850 WEBSTER STREET
PALO ALTO, 94301
LOCATION CODE: 566800

SHEET TITLE

EME REPORT

SHEET NUMBER

T-3

verizon

2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

Vinculum

575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500

ALLSTATES
ENGINEERING & SURVEYING
23675 BIRCHER DRIVE
LAKE FOREST, CA 92630

PROJECT ID: TBD
DRAWN BY: AM
CHECKED BY: DW

3	11/20/2020	CITY COMMENTS	MG
2	09/10/2020	100% CD'S FOR SUBMITTAL	MG
1	06/11/2020	100% CD'S FOR SUBMITTAL	RF
0	05/22/2020	100% CD'S FOR APPROVAL	RF
B	05/06/2020	95% CD'S FOR REDLINE	RF
A	04/22/2020	90% CD'S FOR REDLINE	AM
REV	DATE	DESCRIPTION	



IT IS A VIOLATION OF LAW FOR ANY PERSON,
UNLESS THEY ARE ACTING UNDER THE
DIRECTION OF A LICENSED PROFESSIONAL
ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 204
PUBLIC R.O.W. ADJACENT TO:
ADJACENT TO
850 WEBSTER STREET
PALO ALTO, 94301
LOCATION CODE: 566800

SHEET TITLE

EME REPORT

SHEET NUMBER

T-4


Verizon Wireless - Proposed Small Cell (No. 566800 "SF Palo Alto 204")
850 Webster Street - Palo Alto, California

Calculated RF Exposure Levels

at Elevation of Antennas (21½ – 24½ feet above ground)



Antennas at 23 ft on 25 ft pole



The public limit extends about 8 feet from the antennas, not reaching any publicly accessible areas.
The occupational limit extends about 2 feet from the antennas.

at Ground, at 10 feet Above Ground, and at Nearby Buildings



No poles, trees, or roofs within 8 feet.

Legend:

- less than FCC Public Limit
- greater than FCC Public Limit
- less than FCC Occupational Limit
- greater than FCC Occupational Limit

Notes:

Calculations performed according to OET Bulletin No. 65, August 1997.


Base image from Google Maps.



Power line frequencies (60Hz) are well below the applicable range of the radio frequency exposure standards, and there is considered to be no compounding effect from simultaneous exposure to power lines and RF fields.

HAMMETT & EDISON, INC.
LUNSFORD ENGINEERS
SAN FRANCISCO ©2020


B32-Q2A7.5
Supplemental Figure




2 POLE ELEVATION
1 inch = 5ft.

LEGEND

- | | |
|--------------------|-----------------------------|
| U.G. UTILITY VAULT | BLDG TOP OF BUILDING |
| MANHOLE | MON MONUMENT |
| UTILITY POLE | FL FLOW LINE |
| SPOT ELEVATION | EOP EDGE OF PAVEMENT |
| WATER VALVE | R.O.W. RIGHT OF WAY |
| FOUND MONUMENT | R/W RIGHT OF WAY |
| GEODETIC MARKER | SCO SEWER CLEAN-OUT |
| CHAIN LINK FENCE | PS PARKING STRIPE |
| WOOD FENCE | SW SIDEWALK |
| O/H OVERHEAD LINE | VL U.G. UTILITY VAULT |
| METAL FENCE | OHE OVERHEAD ELECTRICAL |
| GRADE BREAK | SVC SERVICE |
| RIGHT OF WAY LINE | AC ASPHALTIC CONCRETE |
| CENTER LINE | AP ASPHALT PAVING |
| EASEMENT LINE | CONC CONCRETE |
| MASONRY WALL | PED PEDESTAL |
| WATER VALVE | OH OVERHEAD |
| UP UTILITY POLE | PUE PUBLIC UTILITY EASEMENT |
| LP LIGHT POLE | FC FACE OF CURB |
| LUM LUMINAIRE | BOL BOLLARD |
| NG NATURAL GRADE | TOP TOP OF ITEM |
| | BOT BOTTOM OF ITEM |



1 POLE LOCATION
1 inch = 20ft.



VICINITY MAP

TITLE REPORT

NOT APPLICABLE (RIGHT-OF-WAY)

LEGAL DESCRIPTION

NOT APPLICABLE (RIGHT-OF-WAY)

ASSESSOR'S PARCEL NO.

NOT APPLICABLE (RIGHT-OF-WAY)

UTILITY NOTE:

SURVEYOR DOES NOT GUARANTEE THAT ALL UTILITIES ARE SHOWN OR THEIR LOCATIONS ARE DEFINITE. IT IS THE RESPONSIBILITY OF THE CONTRACTOR AND DEVELOPER TO CONTACT BLUE STAKE AND ANY OTHER INVOLVED AGENCIES TO LOCATE ALL UTILITIES PRIOR TO CONSTRUCTION. REMOVAL, RELOCATION AND/ OR REPLACEMENT IS THE RESPONSIBILITY OF THE CONTRACTOR.

NOTES:

- THIS IS NOT A BOUNDARY SURVEY. THIS IS A SPECIALIZED RIGHT OF WAY MAP. THE PROPERTY LINES AND EASEMENTS SHOWN HEREON ARE FROM RECORD INFORMATION AS NOTED HEREON. ALL STATES ENGINEERING & SURVEYING/ZALZALI & ASSOCIATES, INC. TRANSLATED THE TOPOGRAPHIC SURVEY TO RECORD INFORMATION USING MONUMENT(S)/LANDMARK(S) SHOWN HEREON. NO TITLE RESEARCH WAS PERFORMED BY ALL STATES ENGINEERING & SURVEYING/ZALZALI & ASSOCIATES, INC.
- ANY CHANGES MADE TO THE INFORMATION ON THIS PLAN, WITHOUT THE WRITTEN CONSENT OF ALL STATES ENGINEERING & SURVEYING / ZALZALI & ASSOCIATES, INC. RELIEVES ALL STATES ENGINEERING & SURVEYING/ ZALZALI & ASSOCIATES, INC. OF ANY AND ALL LIABILITY.
- THESE DRAWINGS & SPECIFICATIONS ARE THE PROPERTY & COPYRIGHT OF ALL STATES ENGINEERING & SURVEYING / ZALZALI & ASSOCIATES, INC. & SHALL NOT BE USED ON ANY OTHER WORK EXCEPT BY AGREEMENT WITH THE SURVEYOR. WRITTEN DIMENSIONS SHALL TAKE PREFERENCE OVER SCALED & SHALL BE VERIFIED ON THE JOB SITE. ANY DISCREPANCY SHALL BE BROUGHT TO THE NOTICE OF THE SURVEYOR PRIOR TO COMMENCEMENT OF ANY WORK.
- THIS SITE IS PROPOSED TO BE DEVELOPED ON A STREET LIGHT POLE LOCATED WITHIN THE PUBLIC RIGHT OF WAY.

SURVEY DATE

08/16/2020

BASIS OF BEARING

BEARINGS SHOWN HEREON ARE BASED UPON U.S. STATE PLANE NAD83 COORDINATE SYSTEM. CALIFORNIA STATE PLANE COORDINATE ZONE THREE, DETERMINED BY GPS OBSERVATIONS.

BENCHMARK

RTCM-REF 3270
NORTHING: 1970498.865
EASTING: 6082238.002
+248.11' (A.M.S.L.)

REFERENCE MAPS

- 812-PM-8
- 120-APN MAP-5

verizon

2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

Vinculums

575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500

ALLSTATES
ENGINEERING & SURVEYING
23675 BIRTCHE DRIVE
LAKE FOREST, CA 92630

PROJECT NO: SF PALO ALTO 204
DRAWN BY: MG
CHECKED BY: BC/WZ/DW

REV	DATE	DESCRIPTION	
O	09/04/2020	FINAL SURVEY	DW
A	08/27/2020	PRELIMINARY SURVEY	MG



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 204
R.O.W. ADJACENT TO:
850 WEBSTER ST
PALO ALTO, CA 94301
NEW BUILD-SMALL CELL

SHEET TITLE

SITE SURVEY

SHEET NUMBER

C-1

TREE NOTES:

1. THERE WILL BE NO TREE PRUNING WITHOUT THE SPECIFIC APPROVAL OF THE PALO ALTO URBAN FORESTRY DEPARTMENT ON ALL REGULATED TREES. ANY VIOLATION TO THIS POLICY WILL BE SUBJECT TO PENALTY. CONTACT THE PALO ALTO URBAN FORESTRY DEPARTMENT AT (650) 496-5953.
2. THIS CONSTRUCTION PROJECT TRIGGERS MANDATORY TREE PROTECTION MEASURES. SEE TREE PROTECTION PLAN # CONTACT THE PALO ALTO URBAN FORESTRY DEPARTMENT. AT (650) 496-5953 WITH ANY QUESTIONS.
3. EXCAVATION ACTIVITIES ASSOCIATED WITH THE PROPOSED SCOPE OF WORK SHALL OCCUR NO CLOSER THAN 10-FEET FROM THE EXISTING STREET TREE, OR AS APPROVED BY THE URBAN FORESTRY DIVISION CONTACT 650-496-5953. ANY CHANGES SHALL BE APPROVED BY THE SAME.
4. PROJECT ARBORIST:
KATHERINE NAEGELE
KATHERINE@ANDERSONTREECARE.COM
PHONE: (408) 590-5976
5. NO FEASIBLE GREEN SCREEN OPPORTUNITIES EXIST
6. TREES #3-7 WILL REQUIRE MODIFIED TYPE II TREE PROTECTION AT THE EDGE OF THE SIDEWALK ONLY. TRENCHING MUST BE PERFORMED BY HAND.
7. IF ANY LIVE ROOTS ARE ENCOUNTERED DURING EXCAVATION, THE RECOMMENDATIONS IN SECTION 2.25.2 APPLY


NOTES:

1. METAL SURFACES REQUIRING PAINT SHALL BE PAINTED RAL 7022.
2. ANY CONSTRUCTION WITHIN THE CITY'S PUBLIC ROAD RIGHT-OF-WAY SHALL HAVE AN APPROVED PERMIT FOR CONSTRUCTION IN THE PUBLIC STREET PRIOR TO COMMENCEMENT OF THIS WORK

TREE TABLE

PALO ALTO TREE #	CITY TREE ID:	SPECIES:	COMMON NAME:	GROW SPACE:	TRUNK DIA. AT BREAST HT.:	DRIP LINE:	DISTANCE TO CONST.	PROTECTION MEASURES REQUIRED
PALO ALTO TREE #1	-	FRAXINUS SP.	ASH	-	5.2"	4'-4"	-	TYPE II FENCING
PALO ALTO TREE #2	-	FRAXINUS SP.	ASH	-	1.0"	0'-10"	-	NONE
PALO ALTO TREE #3	-	SEQUOIA SEMPERVIRENS	COAST REDWOOD	-	38.7"	32'-3"	-	MODIFIED TYPE II, SEE NOTE 6
PALO ALTO TREE #4	-	SEQUOIA SEMPERVIRENS	COAST REDWOOD	-	9.3"	7'-9"	-	MODIFIED TYPE II, SEE NOTE 6
PALO ALTO TREE #5	-	SEQUOIA SEMPERVIRENS	COAST REDWOOD	-	37.1"	30'-11"	-	MODIFIED TYPE II, SEE NOTE 6
PALO ALTO TREE #6	-	SEQUOIA SEMPERVIRENS	COAST REDWOOD	-	20.2"	16'-10"	-	MODIFIED TYPE II, SEE NOTE 6
PALO ALTO TREE #7	-	SEQUOIA SEMPERVIRENS	COAST REDWOOD	-	26.7"	22'-3"	-	MODIFIED TYPE II, SEE NOTE 6
PALO ALTO TREE #8	-	SEQUOIA SEMPERVIRENS	COAST REDWOOD	-	11.0"	9'-2"	-	NONE
PALO ALTO TREE #9	-	SEQUOIA SEMPERVIRENS	COAST REDWOOD	-	25.0"	20'-10"	-	NONE
PALO ALTO TREE #10	-	FRAXINUS SP.	ASH	-	1.0"	0'-10"	-	NONE
PALO ALTO TREE #11	-	TRISTANOPSIS LAURINA	SWAMP MYRTLE	-	24" BOX	N/A	-	REPLACEMENT FOR TREE #10

NOTE:
ALL ITEMS AND DIMENSIONS SHOULD BE VERIFIED IN THE FIELD, PRIOR TO STARTING CONSTRUCTION.



SITE PLAN

24"x36" SCALE: 3/32" = 1'-0"
11"x17" SCALE: 3/64" = 1'-0"

verizon

2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

Vinculum

575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500

ALLSTATES
ENGINEERING & SURVEYING
23675 BIRCHER DRIVE
LAKE FOREST, CA 92630

PROJECT ID: TBD
DRAWN BY: AM
CHECKED BY: DW

REV	DATE	DESCRIPTION	
3	11/20/2020	CITY COMMENTS	MG
2	09/10/2020	100% CD'S FOR SUBMITTAL	MG
1	06/11/2020	100% CD'S FOR SUBMITTAL	RF
0	05/22/2020	100% CD'S FOR APPROVAL	RF
B	05/06/2020	95% CD'S FOR REDLINE	RF
A	04/22/2020	90% CD'S FOR REDLINE	AM




IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 204
PUBLIC R.O.W. ADJACENT TO:
850 WEBSTER STREET
PALO ALTO, 94301
LOCATION CODE: 566800

SHEET TITLE
SITE PLAN

SHEET NUMBER
A-1



verizon
2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

Vinculum
575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500

ALLSTATES
ENGINEERING & SURVEYING
23675 BIRCHER DRIVE
LAKE FOREST, CA 92630

PROJECT ID:	TBD
DRAWN BY:	AM
CHECKED BY:	DW

REV	DATE	DESCRIPTION	
3	11/20/2020	CITY COMMENTS	MG
2	09/10/2020	100% CD'S FOR SUBMITTAL	MG
1	06/11/2020	100% CD'S FOR SUBMITTAL	RF
0	05/22/2020	100% CD'S FOR APPROVAL	RF
B	05/06/2020	95% CD'S FOR REDLINE	RF
A	04/22/2020	90% CD'S FOR REDLINE	AM


Nissam Zalzal

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 204
PUBLIC R.O.W. ADJACENT TO:
850 WEBSTER STREET
PALO ALTO, 94301
LOCATION CODE: 566800

SHEET TITLE
EXISTING UTILITY SITE PLAN

SHEET NUMBER
A-1.1



The City of Palo Alto

CPA WGW Utility Information
850 Webster St
NODE 204
For Reference Use Only

This map is a product of the
City of Palo Alto GIS

2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500

23675 BIRCHER DRIVE
LAKE FOREST, CA 92630

PROJECT ID:	TBD
DRAWN BY:	AM
CHECKED BY:	DW

REV	DATE	DESCRIPTION	
3	11/20/2020	CITY COMMENTS	MG
2	09/10/2020	100% CD'S FOR SUBMITTAL	MG
1	06/11/2020	100% CD'S FOR SUBMITTAL	RF
0	05/22/2020	100% CD'S FOR APPROVAL	RF
B	05/06/2020	95% CD'S FOR REDLINE	RF
A	04/22/2020	90% CD'S FOR REDLINE	AM

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.


SF PALO ALTO 204
PUBLIC R.O.W. ADJACENT TO:
850 WEBSTER STREET
PALO ALTO, 94301
LOCATION CODE: 566800

SHEET TITLE
UTILITY PLAN
(FOR REFERENCE)

SHEET NUMBER
A-1.2

sfpld_2020-03-24 10:53:59
New Base Map Req (loc-map)EncompassAdminPersonalAnd/or

This document is a graphic representation only of data provided by the City of Palo Alto. The City of Palo Alto assumes no responsibility for any errors. ©1989 to 2016 City of Palo Alto



LOCATION MAP

verizon

2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

Vinculum

575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500

ALLSTATES
ENGINEERING & SURVEYING

23675 BIRCHER DRIVE
LAKE FOREST, CA 92630

PROJECT ID:	TBD
DRAWN BY:	AM
CHECKED BY:	DW

3	11/20/2020	CITY COMMENTS		MG
2	09/10/2020	100% CD'S FOR SUBMITTAL		MG
1	06/11/2020	100% CD'S FOR SUBMITTAL		RF
0	05/22/2020	100% CD'S FOR APPROVAL		RF
B	05/06/2020	95% CD'S FOR REDLINE		RF
A	04/22/2020	90% CD'S FOR REDLINE		AM
REV	DATE	DESCRIPTION		

Nassim Zalzali

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 204
PUBLIC R.O.W. ADJACENT TO:
850 WEBSTER STREET
PALO ALTO, 94301
LOCATION CODE: 566800

SHEET TITLE

LOCATION MAP

SHEET NUMBER

A-1.3

- NOTES:**
1. APPLICANT SHOULD NOTE THE USE OF INNERDUCT IN ALL STREET LIGHTS
 2. NOTE TO PREWIRE ALL STREETLIGHTS PRIOR TO INSTALLATION
 3. WIRE SHOULD ENTER THE DISCONNECT AND THEN STREET LIGHT

NOTES:

WATER LINE

SANITATION SEWER

WEBSTER ST.

PROPOSED 8'X16' STAGING
AREA IN PARKING STALL(S)

EXISTING ELECTRICAL VAULT—

ELECTRICAL @
(2.5' BELOW GRADE)

PROPOSED LIGHT P

ELECTRICAL Ⓢ
(2.5' BELOW GRADE) -

NOTES:

1. EXCAVATION RESTRICTIONS APPLY (T.M. SEC. 2.20 C & D). ANY APPROVED GRADING, DIGGING OR TRENCHING BENEATH A TREE CANOPY SHALL BE PERFORMED USING 'AIR-SPADE' METHOD AS A PREFERENCE, WITH MANUAL HAND SHOVEL AS A BACKUP, FOR UTILITY TRENCHING, INCLUDING SEWER LINE. ROOTS EXPOSED WITH DIAMETER OF 1.5 INCHES AND GREATER SHALL REMAIN INTACT AND NOT BE DAMAGED.
2. SEE ATTACHED TREE PROTECTION PLAN FOR INSTRUCTIONS ON TREE PROTECTION.

NOTE:

ALL PROPOSED POWER RUNS TO
MAINTAIN A MIN. 2' CLR. ALL
AROUND AS REQUIRED BY CPAU

±5' HAND TRENCH (POWER)
1-2" SCH 40 POLE TO VAULT
±2.5' BELOW GRADE.
SEE NOTE

— PROPOSED N16 ELECTRICAL

SERVICE VAULT
PROPOSED FIRE VAULT


±3' TRENCH (POWER)
1-4" SCH 40 VAULT
±3.0' BELOW GRADE
/SEE NOTE

±13' TRENCH (POWER) 1-
SCH 40 TO VAULT ±3.0'
BELOW GRADE. SEE NOTE

PROPOSED TRENCHING , TYP.

APN: 120-05-098
850 WEBSTER ST.

- ☐ Protect storm drain inlets during saw cutting.
- ☐ If saw cut slurry enters a catch basin, clean it up immediately.
- ☐ Shovel or vacuum saw cut slurry deposits and remove from the site. When making saw cuts, use as little water as possible. Sweep up, and properly dispose of all residues.

VICINITY MAP





















① LIGHT POLE
1 inch = 2ft.



811 USA North
 Know what's below.
 Call before you dig.
 California and Nevada
 Call Two Working Days Before You Dig!
 811 / 800-227-2600



LEGEND

	U.G. UTILITY VAULT	BOL	BOLLARD	FL	FLOW LINE		WATER
	MANHOLE	TOP	TOP OF ITEM	EOP	EDGE OF PAVEMENT		SANITARY SEWER
	UTILITY POLE	BOT	BOTTOM OF ITEM	R.O.W.	RIGHT OF WAY		STORM DRAIN
	SPOT ELEVATION	BLDG	TOP OF BUILDING	AP	ASPHALT		GAS
	WATER VALVE	LP	LIGHT POLE	SW	SIDEWALK		COMMUNICATION
	FOUND MONUMENT	---	LIMITS OF PROPERTY		OVERHEAD LINE		ELECTRIC
	GEODETIC MARKER	- x -	CHAIN LINK FENCE		METAL FENCE		UNKNOWN UTILITY
	MASONRY WALL		WOOD FENCE		GRADE BREAK		IRRIGATION

PROJECT SPECIFIC PERMIT INFORMATION		
DESCRIPTION	QTY	UNIT
PLACE (1) 4" SCH 40 CONDUIT	10	LF
PLACE (1) 2" SCH 40 CONDUIT	5	LF
REMOVE AND RESTORE SOIL	120	FT ³

verizon ✓

2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

 Vinculums

575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500



ALLSTATES
ENGINEERING & SURVEYING
23675 BIRTCHE DRIVE
LAKE FOREST, CA 92630

PROJECT ID:	TBD
DRAWN BY:	AM
CHECKED BY:	DW

O	08/18/2020	FINAL BORING PLAN	SS
A	08/14/2020	PRELIMINARY BORING PLAN	SS
REV	DATE	DESCRIPTION	



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS
THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED
PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.


SF PALO ALTO 204
PUBLIC R.O.W. ADJACENT TO:
850 WEBSTER STREET
PALO ALTO, 94301
LOCATION CODE: 566800

SHEET TITLE


BORING SITE PLAN

SHEET NUMBER


A-1.4




5 CITY STANDARD DWG 401
N.T.S.




3 CITY STANDARD DWG 402
N.T.S.



4 CITY STANDARD DWG 403
N.T.S.



2 CHRISTY N16 ELECTRICAL BOX
N.T.S.



1 IN DIRT - PRIVATE
N.T.S.

verizon

2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

Vinculums

575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500

ALLSTATES
ENGINEERING & SURVEYING
23675 BIRCHER DRIVE
LAKE FOREST, CA 92630

PROJECT ID: TBD
DRAWN BY: AM
CHECKED BY: DW

REV	DATE	DESCRIPTION	
0	08/18/2020	FINAL BORING PLAN	SS
A	08/14/2020	PRELIMINARY BORING PLAN	SS



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS
THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED
PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 204
PUBLIC R.O.W. ADJACENT TO:
850 WEBSTER STREET
PALO ALTO, 94301
LOCATION CODE: 566800

SHEET TITLE
CITY STANDARDS
& DETAILS

SHEET NUMBER

A-1.5

- ▶ Grade fills over 6-inches or impervious overlay shall incorporate an approved permanent aeration system, permeable material or other approved mitigation.
- ▶ Grade cuts exceeding 4-inches shall incorporate retaining walls or an appropriate transition equivalent.

C. Trenching, Excavation and Equipment Use

Trenching, excavation or boring activity within the TPZ is restricted to the following activities, conditions and requirements if approved by the City Arborist. (See Restriction Zones for Excavation, Trenching or Boring Near Regulated Trees, Image 2.20-1 through 2.20-3). Mitigating measures shall include prior notification to and direct supervision by the project arborist.

1. Notification. Contractor shall notify the *project arborist* a minimum of 24 hours in advance of the activity in the TPZ.
2. Root Severance. Roots that are encountered shall be cut to sound wood and repaired (see *Root Injury, Section 2.25 A-1*). Roots 2-inches and greater must remain injury free.
3. Excavation. Any approved excavation, demolition or extraction of material shall be performed with equipment sitting outside the TPZ. Methods permitted are by hand digging, hydraulic or pneumatic air excavation technology. Avoid excavation within the TPZ during hot, dry weather.
 - ▶ If excavation or *trenching* for drainage, utilities, irrigation lines, etc., it is the duty of the contractor to tunnel under any roots 2-inches in diameter and greater.
 - ▶ Prior to excavation for foundation/footings/walls, grading or *trenching* within the TPZ, roots shall first be severed cleanly 1-foot outside the TPZ and to the depth of the future excavation. The trench must then be hand dug and roots pruned with a saw, sawzall, narrow trencher with sharp blades or other approved root pruning equipment.
4. Heavy Equipment. Use of backhoes, steel tread tractors or any heavy vehicles within the TPZ is prohibited unless approved by the *City Arborist*. If allowed, a protective *root buffer* (see *Root Buffer and Damage to Trees, Section 2.25.A-1*) is required. The protective buffer shall consist of a base course of tree chips spread over the root area to a minimum of 6-inch depth, layered by 3/4-inch quarry gravel to stabilize 3/4-inch plywood on top. This buffer within the TPZ shall be maintained throughout the entire construction process.
 - ▶ Structural design. If injurious activity or interference with roots greater than 2-inches will occur within the TPZ, plans shall specify a design of special foundation, footing, walls, concrete slab or pavement designs subject to *City Arborist* approval. Discontinuous foundations such as concrete pier and structural grade beam must maintain natural grade (not to exceed a 4-inch cut), to minimize root loss and allow the tree to use the existing soil.

notes:

Required Practices

- Basement excavations shall be designed outside the TPZ of all *protected* and *designated* trees (see *Excavation, Section 2.20-3*) and shall not be harmful to other mature or neighboring property trees.

D. Tunneling & Directional Drilling

If *trenching* or pipe installation has been approved within the TPZ, then the trench shall be either cut by hand, air-spade, hydraulic vac-on excavation or, by mechanically boring the tunnel under the roots with a horizontal directional drill and hydraulic or pneumatic air excavation technology. In all cases, install the utility pipe immediately, backfill with soil and soak within the same day. Installation of private utility improvements shall be tunnel bored beneath the tree and roots per *Trenching Tunneling & Distance Matrix* in Table 2-1.

TABLE 2-1
Trenching & Tunneling Distance

TRENCHING DISTANCE	
	
When the Tree Diameter At 4.5 Ft Is:	Trenching will be Replaced with Boring at this Minimum Distance (10x tree dia.) from the Face of the Tree in any Direction:
6'-9" Measured At 6"	6'-9"
10'-14" Measured At 54"	10'-14"
15'-19" Measured At 54"	15'-19"
Over 19" Measured At 54"	20' +

Bore Pits Shall Be Located At A Minimum Distance As Specified By The Trenching Distance Table Above.

1. **Public Utilities**
Underground public utility improvements or repairs shall be performed in accordance with the *Utility Standards for Excavation, Trenching or Boring, Section 02200.309*; and per *Restriction Zones Near Regulated Trees* (see *Images 2.20-1 through 2.20-3*).
2. **Street Trees**
Exclusions for *street trees* in the publicly owned right-of-way (ROW).
 - ▶ *Street Trees* that are in conflict with utility infrastructure where the conflict cannot be resolved may be removed if approved by Public Works Operations (e.g., a tree planted directly on top of a damaged sewer lateral.)

notes:

Required Practices



2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598



575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500



23675 BIRTCHE DRIVE
LAKE FOREST, CA 92631

PROJECT ID:	TB
DRAWN BY:	A
CHECKED BY:	D

O	08/18/2020	FINAL BORING PLAN	S
A	08/14/2020	PRELIMINARY BORING PLAN	S
REV	DATE	DESCRIPTION	



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS
THEY ARE ACTING UNDER THE DIRECTION OF A LICENSE
PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.


SF PALO ALTO 204
PUBLIC R.O.W. ADJACENT TO:
850 WEBSTER STREET
PALO ALTO, 94301
LOCATION CODE: 566800

SHEET TITLE
CITY STANDARDS
& DETAILS

SHEET NUMBER

A-1.6

- NOTES:
- METAL SURFACES REQUIRING PAINT TO BE PAINTED RAL 7022.
 - THE CONTRACTOR MAY BE REQUIRED TO SUBMIT A LOGISTICS PLAN TO THE PUBLIC WORKS DEPARTMENT PRIOR TO COMMENCING WORK THAT ADDRESSES ALL IMPACTS TO THE CITY'S RIGHT-OF-WAY, INCLUDING, BUT NOT LIMITED TO: PEDESTRIAN CONTROL, TRAFFIC CONTROL, TRUCK ROUTES, MATERIAL DELIVERIES, CONTRACTOR'S PARKING, CONCRETE POURS, CRANE LIFTS, WORK HOURS, NOISE CONTROL, DUST CONTROL, STORM WATER POLLUTION PREVENTION, CONTRACTOR'S CONTACT, NOTICING OF AFFECTED SURROUNDING PROPERTIES, AND SCHEDULE OF WORK. THE REQUIREMENT TO SUBMIT A LOGISTICS PLAN WILL BE DEPENDENT ON THE NUMBER OF APPLICATIONS PUBLIC WORKS ENGINEERING RECEIVES WITHIN CLOSE PROXIMITY TO HELP MITIGATE AND CONTROL THE IMPACT TO THE PUBLIC-RIGHT-OF-WAY. IF NECESSARY, PUBLIC WORKS MAY REQUIRE A LOGISTICS PLAN DURING CONSTRUCTION.
 - TREES MAY NOT BE PLANTED WITHIN 10 FEET OF EXISTING WATER, GAS OR WASTEWATER MAINS/SERVICES OR METERS; LESSER DISTANCES REQUIRE A PERMANENT IMPERMEABLE ROOT-BARRIER A MINIMUM OF 3' HORIZONTAL FROM WATER, GAS AND WASTEWATER SERVICES/MAINS/METERS.




ENLARGED SITE PLAN

24"x36" SCALE: 3/4" = 1'-0"
11"x17" SCALE: 3/8" = 1'-0"

2

ENLARGED SITE PLAN



verizon

2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

Vinculum

575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500

ALLSTATES
ENGINEERING & SURVEYING
23675 BIRCHER DRIVE
LAKE FOREST, CA 92630

PROJECT ID:	TBD
DRAWN BY:	AM
CHECKED BY:	DW

REV	DATE	DESCRIPTION	
3	11/20/2020	CITY COMMENTS	MG
2	09/10/2020	100% CD'S FOR SUBMITTAL	MG
1	06/11/2020	100% CD'S FOR SUBMITTAL	RF
0	05/22/2020	100% CD'S FOR APPROVAL	RF
B	05/06/2020	95% CD'S FOR REDLINE	RF
A	04/22/2020	90% CD'S FOR REDLINE	AM



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 204
PUBLIC R.O.W. ADJACENT TO:
850 WEBSTER STREET
PALO ALTO, 94301
LOCATION CODE: 566800



SHEET TITLE
ENLARGED SITE PLAN

SHEET NUMBER

A-2

24"x36" SCALE: 1/2" = 1'-0"
11"x17" SCALE: 1/4" = 1'-0"

1



- NOTES:
1. NEW LIGHT POLE TO BE PAINTED WITH RAL 7022 PAINT.
 2. NEW RADIOS AND HARDWARE TO BE PAINTED RAL 7022 OR WRAPPED AS ALLOWED BY THE MANUFACTURER.
 3. ALL CABLE/WIRE BETWEEN THE POLE ACCESS HOLE AND THE SHROUD GROMMET HOLE WILL RUN THROUGH 1.5" CONDUIT PAINTED/COLORED TO MATCH POLE COLOR.

TOTAL RADIO AREA (CU. FT.)		
RADIO MODEL	TOTAL RADIOS	TOTAL RADIO AREA (CU. FT.)
SM6701	2	±2.2

verizon

2785 MITCHELL DRIVE, SUITE 9
WALNUT CREEK, CA 94598

Vinculum

575 LENNON LANE #125
WALNUT CREEK, CA 94598
OFFICE: (925) 482-8500

ALLSTATES
ENGINEERING & SURVEYING

23675 BIRCHER DRIVE
LAKE FOREST, CA 92630

PROJECT ID:	TBD
DRAWN BY:	AM
CHECKED BY:	DW

REV	DATE	DESCRIPTION	
3	11/20/2020	CITY COMMENTS	MG
2	09/10/2020	100% CD'S FOR SUBMITTAL	MG
1	06/11/2020	100% CD'S FOR SUBMITTAL	RF
0	05/22/2020	100% CD'S FOR APPROVAL	RF
B	05/06/2020	95% CD'S FOR REDLINE	RF
A	04/22/2020	90% CD'S FOR REDLINE	AM

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SF PALO ALTO 204
PUBLIC R.O.W. ADJACENT TO:
850 WEBSTER STREET
PALO ALTO, 94301
LOCATION CODE: 566800

SHEET TITLE

ELEVATIONS

SHEET NUMBER

A-3

