

APPROVED PLANS
Plans Received 10-31-2018
17PLN-00280

PROJECT INFORMATION:
ZONING: CN

LOT AREA: 15,696 SF (PER SURVEY)

EXISTING:
COMMERCIAL: 5,554 SF
RESIDENTIAL: N/A
REPLACEMENT RETAIL: 5,231 SF

RESIDENTIAL DENSITY:
ALLOWED (20du/ac): 7.33 UNITS
PROPOSED: 7 UNITS

AFFORDABLE HOUSING PER PAMC:
REQUIRED (15%): 1.05 UNITS
PROPOSED: 1 MODERATE UNIT (14%) + .05 IN LIEU FEE

DENSITY BONUS INCENTIVES / CONCESSIONS:
10% MODERATE BMR: 1 CONCESSION PER PAMC 18.15.050 (c)
F.A.R. CONCESSION PER PAMC 18.15.50 (d) iv
BY RIGHT PARKING PER PAMC 18.15.050 (a)

LOT COVERAGE (SEE SHEET A006 FOR ANALYSIS)
ALLOWED (50%): 7,848 SF
PROPOSED: 7,797 SF

FLOOR AREA RATIO (SEE SHEET A005 FOR ANALYSIS)
ALLOWED:
COMMERCIAL (0.5:1): 7,848 SF
RESIDENTIAL (0.5:1 + BMR): 8,878 SF
PROPOSED:
COMMERCIAL: 7,848 SF
RESIDENTIAL: 8,877 SF


OPEN SPACE (SEE SHEET A007 FOR ANALYSIS)
REQUIRED (150 SF / UNIT): 1,050 SF
PROPOSED: 3,707 SF

SETBACKS
REQUIRED : FRONT = 0' TO 10'
SIDE = 0'
REAR = 0'
PROPOSED : FRONT = 4'-5" (12' SIDEWALKS)
SIDE - RIGHT = 3'- 8.5" - 4'- 0"
SIDE - LEFT = 0'- 6" - 2'- 3.5"
REAR = 52'-6"

PARKING (SEE SHEET A008 FOR ANALYSIS)
REQUIRED:
COMMERCIAL: 36 SPACES
RESIDENTIAL: 11 SPACES
TOTAL: 47 SPACES
PROPOSED:
SUB-GRADE GARAGE: 20 STD. SPACES
19 LIFT SPACES
AT GRADE GARAGES: 4 SPACES
AT GRADE UNCOVERED: 4 SPACES
TOTAL: 47 SPACES

BUILDING CODE SUMMARY
REFERENCE: 2016 CALIFORNIA BUILDING CODE / CALIFORNIA CODE OF REGULATIONS, TITLE 24, PART 2
OCCUPANCY: S2/ M / B / R2
TYPE OF CONSTRUCTION: IIB / VB
FIRE SPRINKLER SYSTEM: NFPA 13
NFPA 14 STANDPIPE
NFPA 24 UNDERGROUND
NFPA 72 FIRE ALARM
EMERGENCY RADIO TRANSPONDER
FIRE ALARMS:
FIRE SEPARATION (PER CRC 508.4):
OCCUPANCIES
S-2 / M
M / B
M / R-2
M / U
B / R-2
R-2 / R-2
REQUIRED SEPARATION
1 HOUR
NONE
1 HOUR
1 HOUR
1 HOUR
1 HOUR
OCCUPANT LOAD
RETAIL SPACE: 4,612 SQ. FT. / 60 GROSS 77 OCCUPANTS 2 EXITS
OFFICE SPACE: 2,319 SQ. FT. / 100 GROSS 24 OCCUPANTS 1 EXIT
GARAGE: 13,562 SQ. FT. / 200 GROSS 68 OCCUPANTS 2 EXITS
RESIDENTIAL: 8,878 SQ. FT. / 200 GROSS 44 OCCUPANTS
PLUMBING LOAD
RETAIL SPACE: 4,612 SQ. FT. / 200 23 OCCUPANTS
OFFICE SPACE: 2,319 SQ. FT. / 200 12 OCCUPANTS
TOTAL 35 OCCUPANTS
PLUMBING REQUIRED: PER C.P.C. 422.2 EXCEPTION 3
IN BUSINESS AND MERCANTILE OCCUPANCIES WITH A TOTAL OCCUPANT LOAD OF 50 OR LESS INCLUDING CUSTOMERS AND EMPLOYEES, ONE TOILET FACILITY, DESIGNED FOR USE BY NO MORE THAN ONE PERSON AT A TIME, SHALL BE PERMITTED FOR USE BY BOTH SEXES.

4115 EL CAMINO REAL



VICINITY MAP
N.T.S.

- SHEET INDEX:**
- A001 COVER SHEET
 - A002A CAL GREEN - TIER 2 PATH CHECKLIST NON RESIDENTIAL
 - A002B CAL GREEN - TIER 2 PATH CHECKLIST RESIDENTIAL
 - A003A EXISTING SITE PLAN
 - A003B EXISTING BUILDING PLAN
 - A004 SITE CONTEXT
 - A005 FLOOR AREA RATIO (F.A.R.)
 - A006 NEW SITE PLAN
 - A007 OPEN SPACE
 - A008 SUB-GRADE FLOOR PLAN
 - A009 FIRST FLOOR PLAN
 - A010 SECOND FLOOR PLAN
 - A011 THIRD FLOOR PLAN
 - A012 ROOF PLAN
 - A013 FRONT & RIGHT ELEVATIONS
 - A014 REAR & LEFT ELEVATIONS
 - A015 SECTIONS
 - A016 SECTIONS
 - A017 EL CAMINO REAL PERSPECTIVES
 - A018 EL CAMINO WAY PERSPECTIVES
 - A019 AXONOMETRIC VIEWS
 - L-1 GROUND FLOOR PRELIMINARY LANDSCAPE PLAN
 - L-2 3RD FLOOR PRELIMINARY LANDSCAPE PLAN
 - L-3 LANDSCAPE DESIGN IMAGES
 - C-1.0 TITLE SHEET
 - C-1.1 EXISTING CONDITION - TOPOGRAPHIC STUDY
 - C-2.0 DEMOLITION PLAN
 - C-3.0 PRELIMINARY GRADING AND UTILITY PLAN
 - SCP-1 IMPERVIOUS SURFACE EXHIBIT
 - SCP-2 STORMWATER CONTROL PLAN
 - SCP-3 STORMWATER CONTROL DETAILS
 - ER-1 EROSION CONTROL PLAN
 - ER-2 EROSION CONTROL DETAILS
 - SW-1 STORMWATER POLLUTION PREVENTION PLAN
 - T-1 SPECIAL TREE PROTECTION INSTRUCTION
 - T-2 SPECIAL TREE PROTECTION INSTRUCTION
 - S1 PRELIMINARY SHORING PLAN
 - PH-1 PHOTOMETRICS BASEMENT
 - PH-2 PHOTOMETRICS FIRST FLOOR

AREA CALCULATIONS

	AREA CALCULATION TABLE				
	BASEMENT FLOOR	1ST FLOOR	2ND FLOOR	3RD FLOOR	TOTAL
GARAGE (S-2)	13931				13931
RETAIL (M)		4612			4612
PRIVATE GARAGE (U)		991			991
OFFICE (B)			2319		2319
RESIDENTIAL (R-2)			3878	5000	8878
CIRCULATION		734	853	773	2360
TOTAL AREA PER FLOOR	13931	5603	7050	5773	30731

	MIXED OCCUPANCY AREA DETERMINATION (C.B.C. 506.2.4)									CALCULATED RATIO PER 506.2.4*	MAX. RATIO PER 506.2.4
	(M)		(U)		(B)		(R-2)				
1ST FLOOR	ACTUAL	$\frac{4612}{27000}$	+	$\frac{951}{16500}$	+		+		=	0.23	1
	ALLOWABLE										
2ND FLOOR	ACTUAL		+		+	$\frac{2319}{27000}$	+	$\frac{3878}{7000}$	=	0.64	1
	ALLOWABLE										
3RD FLOOR	ACTUAL		+		+		+	$\frac{5000}{7000}$	=	0.71	1
	ALLOWABLE										
TOTAL BUILDING RATIO										1.58	2.00

*FLOOR RATIO NOT TO EXCEED 1 PER C.B.C. 508.4.2

4115 El Camino Real
Palo Alto, CA

PALO ALTO, CA
ARB SUBMITTAL

OCTOBER 31, 2018

COVER SHEET
A001

3361 Walnut Blvd. Suite 120 Brentwood, CA 94513
925.634.7000
www.strausdesign.com



SDG Architects, Inc.

5.1 Planning and Design

	Code Section	Y	N	Plan Sheet, Spec or Attachment Reference	Compliance Path Verification							
					Plan Check	Inspection IPR # 112	Final Inspection IPR # 974	Part 1	Part 2	Part 3		
					CORR	INTAL	CORR	INTAL	CORR	INTAL	CORR	INTAL
Mandatory	Storm water pollution prevention	5.106.1.1	X	A002A								
Mandatory	Local storm water pollution prevention	PAMC 16.14.290 / 5.106.1.1	X	A002A								
Mandatory	Best management practices	5.106.1.2	X	A002A								
Mandatory	Bicycle parking	PAMC 16.54.060 / 5.106.4	X	A002A								
Mandatory	Short term bicycle parking	5.106.4.1	X	A002A								
Mandatory	(Bicycle) Parking stall markings	5.106.5.2.1	X	A002A								
Tier 2 Mand	Designated parking - 12% of Parking Capacity	AS.106.5.2.2	X	A002A								
Tier 2 Mand	Electric Vehicle (EV) charging for Non-Residential Structures (EVSE) [N]: New construction, Small provide Cordless Only, EVSE-Ready Outlet, or EVSE Installed for at least 25% of parking spaces, among which at least 5% (and no fewer than two) shall be EVSE installed.	PAMC 16.14.430 / AS.106.5.2.3	X	A002A								
Mandatory	Light pollution reduction	PAMC 16.14.295 / 5.106.6	X	A002A								
Mandatory	Grading and paving (except for additions and alterations not altering the drainage path)	5.106.10	X	A002A								
Tier 2 Mand	Cool roof for reduction of heat island effect: SHI of 82 ± 2.12 and SHI of 27 ± 2.12	AS.106.11.2	X	A002A								
Mandatory	Commonly connectivity	AS.103.11	X	A002A								
Electives	Brownfield or greyfield site redevelopment or infill area development	AS.103.2	X	A002A								
Electives	Reduce development footprint and optimize open space	AS.104.1	X	A002A								
Electives	Existing building structure (75%)	AS.105.1.1	X	A002A								
Electives	Existing non-structure elements (50%)	AS.105.1.2	X	A002A								
Electives	Salvage	AS.105.1.3	X	A002A								
Electives	Storm water runoff rate and quantity	AS.106.2.1	X	A002A								
Electives	Storm water runoff quality	AS.106.2.2	X	A002A								
Electives	Low impact development (LID)	AS.106.3	X	A002A								
Electives	Greyfield or infill site	AS.106.3.2	X	A002A								
Electives	Changing rooms	AS.106.4.3	X	A002A								
Electives	Parking capacity	AS.106.6	X	A002A								
Electives	Reduce parking capacity	AS.106.6.1	X	A002A								
Electives	Exterior wall shading: Fenestration-East and west walls	AS.106.7.1.1	X	A002A								
Electives	Exterior wall shading: Fenestration-South walls	AS.106.7.1.2	X	A002A								
Electives	Exterior wall shading:Opaque wall areas	AS.106.7.2	X	A002A								
Electives	Heat island effect: Hardscape alternatives and cool roof reduction	AS.106.11.1	X	A002A								
Electives	Heat island effect: Cool roof for reduction of heat island	AS.106.11.2	X	A002A								
Electives	Heat island effect: Solar reflectance	AS.106.11.2.1	X	A002A								
Electives	Heat island effect: Thermal emittance	AS.106.11.2.2	X	A002A								
Electives	Heat island effect: Solar reflectance index alternative	AS.106.11.2.3	X	A002A								


PAMC 16.17 Energy Reach Code

Mandatory or	Option 1: Performance approach specified within the 2016 California Energy Code shall be used to demonstrate that the TDV Energy of proposed non-residential construction is at least: Ten percent less than TDV Energy of the Standard Design if the proposed building does not include a photovoltaic system or includes a photovoltaic system smaller than 5kW	PAMC 16.17.050 Title 24, Part 6	X	T24								
Mandatory	Option 2: Performance approach specified within the 2016 California Energy Code shall be used to demonstrate that the TDV Energy of proposed non-residential construction is at least: Equal to the TDV Energy of the Standard Design if the proposed building includes a 5kW or greater photovoltaic system.	PAMC 16.17.050 Title 24, Part 6	X									
Mandatory	Energy Star portfolio manager- All new construction or renovation projects greater than \$100,000 in value	PAMC 16.14.380 / 5.410.4.6	X									
Mandatory	Performance Review- For projects over 10,000 SF	PAMC 16.14.390 / 5.410.4.7	X									

5.3 Water Efficiency and Conservation

Mandatory	New buildings or additions in excess of 50,000 square feet	5.303.1.1	X	A002A								
Mandatory	Excess consumption (Submeters for additions that consume over 1,000 gal/ day)	5.303.1.2	X	A002A								
Mandatory	Water Reduction- 20% savings over the "water use baseline" Table AS.303.2.3.1	AS.303.2.3.2	X	A002A								
Tier 2 Mand	Indoor Water Use: Water closets (shall not exceed 1.28 gallons per flush)	5.303.3.1	X	A002A								

Application: This plan sheet is for use by residential new construction projects of any size.




4115 El Camino Real
Palo Alto, CA
October 31, 2018

EXISTING SITE PLAN
A003A


3361 Walnut Blvd. Suite 120 Brentwood, CA 94513
925.634.7000
www.strausdesign.com



SDG Architects, Inc.



* SEE CIVIL SHEET EX-1 FOR
DIMENSIONED BUILDING



OCCUPANCY/AREAS FLOOR PLAN

- AREA INCLUDED IN F.A.R.
TO BE REPLACED
- AREA EXCLUDED IN F.A.R.
TO BE REPLACED

TOTAL F.A.R. TO BE REPLACED	
BUILDING AREA	4,738 SQ. FT.
PATIO AREA	816 SQ. FT.
TOTAL BUILDING	5,554 SQ. FT.
PUBLIC ACCESS AREA	114 SQ. FT.
PUBLIC ACCESS AREA	145 SQ. FT.
PUBLIC ACCESS AREA	64 SQ. FT.
TOTAL PUBLIC ACCESS AREA	323 SQ. FT.
TOTAL BUILDING	5,554 SQ. FT.
TOTAL PUBLIC ACCESS	323 SQ. FT.
REPLACEMENT RETAIL	5,231 SQ. FT.




VICINITY MAP
N.T.S.



4115 EL CAMINO REAL - EXISTING SITE




4073 EL CAMINO REAL



4111 EL CAMINO REAL



4113 EL CAMINO REAL



4119 EL CAMINO REAL




4131 EL CAMINO REAL




4115 El Camino Real
Palo Alto, CA
October 31, 2018

EL CAMINO REAL STREETSCAPE


SITE CONTEXT
A004



FIRST FLOOR



SECOND FLOOR





THIRD FLOOR

USE SF	CIRCULATION SF				TOTAL SF BY USE	MAX ALLOWABLE SF
	1ST FLOOR	2ND FLOOR	3RD FLOOR	TRASH ¹		
RESIDENTIAL	561	853	773	173	8,877	8,878
OFFICE	2,319	187	427	0	58	2,991
RETAIL	4,612	187	0	0	58	4,857
TOTALS	14,363	561	854	773	174	16,725

¹ INCLUDED IN CIRCULATION
BIKES NOT INCLUDED IN FAR = 210 SF
REPLACEMENT RETAIL (SEE SHEET A003B)


LEGEND	
RETAIL	
OFFICE	
RESIDENTIAL	
CIRCULATION	
F.A.R. ALLOWED	
COMMERCIAL: 0.5:1 0.5 x 15,696 SQ. FT.	
COMMERCIAL F.A.R. ALLOWED 7,848 SQ. FT.	
RESIDENTIAL: 0.5:1 + BMR 7,848 SQ. FT.	
BMR 1,030 SQ. FT.	
RESIDENTIAL F.A.R. ALLOWED 8,878 SQ. FT.	
REPLACEMENT RETAIL	
REQUIRED	
5231 (E) - 561 (CIRC.) = 4,670 SQ. FT.	
PROVIDED	
4612 + 58 (1/3 TRASH) = 4,670 SQ. FT.	
F.A.R. PROPOSED	
COMMERCIAL	
RETAIL 4,612 SQ. FT.	
OFFICE 2,319 SQ. FT.	
RETAIL CIRCULATION 187 SQ. FT.	
OFFICE CIRCULATION 614 SQ. FT.	
2/3 TRASH 116 SQ. FT.	
TOTAL COMMERCIAL F.A.R. 7,848 SQ. FT.	
RESIDENTIAL	
UNIT 1 731 SQ. FT.	
UNIT 2 728 SQ. FT.	
UNIT 3 763 SQ. FT.	
UNIT 4 (BMR) 1,030 SQ. FT.	
UNIT 5 1,030 SQ. FT.	
UNIT 6 1,550 SQ. FT.	
UNIT 7 1,600 SQ. FT.	
RESIDENTIAL CIRCULATION 1,387 SQ. FT.	
1/3 TRASH 58 SQ. FT.	
TOTAL RESIDENTIAL F.A.R. 8,877 SQ. FT.	






4115 El Camino Real
Palo Alto, CA
October 31, 2018

NEW SITE PLAN
A006




FIRST FLOOR

OPEN SPACE SQUARE FOOTAGES	
COMMON OPEN SPACE	
COMMON OPEN SPACE REQUIRED	
	150 SQ. FT. / UNIT
7 UNITS x 150 SQ. FT. =	1,050 SQ. FT.
COMMON OPEN SPACE PROVIDED	
GROUND LEVEL OPEN SPACE	3,127 SQ. FT.
3RD FLOOR DECK	580 SQ. FT.
TOTAL COMMON OPEN SPACE	3,707 SQ. FT.
PRIVATE OPEN SPACE	
PRIVATE OPEN SPACE PROVIDED	
OFFICE DECK	291 SQ. FT.
UNIT 1 DECK	153 SQ. FT.
UNIT 2 DECK	541 SQ. FT.
UNIT 3 DECK	361 SQ. FT.
UNIT 4 DECK	165 SQ. FT.
UNIT 5 DECK	121 SQ. FT.
UNIT 6 DECK	728 SQ. FT.
UNIT 7 DECK	539 SQ. FT.
TOTAL PRIVATE OPEN SPACE	2,899 SQ. FT.




SECOND FLOOR





THIRD FLOOR






ELECTRIC VEHICLE CALCULATIONS		PARKING CALCULATIONS	
REQUIRED ELECTRIC VEHICLE STATIONS		RETAIL	
EVSE: 25% x 36	9	RETAIL	4,612 SQ. FT.
EVCS: 5% x 9	1	RETAIL CIRCULATION	187 SQ. FT.
TOTAL REQUIRED EV STATIONS	9	TOTAL	4,799 SQ. FT.
EVSE = PRE-WIRED EVSE		1/200 SQ. FT. x 4,799 SQ. FT. =	24
EVCS = INSTALLED EVSE		REQUIRED RETAIL PARKING	24
ACCESSIBLE PARKING CALCULATIONS		OFFICE	
REQUIRED ACCESSIBLE PARKING		OFFICE	2,319 SQ. FT.
TOTAL NUMBER OF REQUIRED SPACES PER TABLE 11B-208.2		OFFICE CIRCULATION	613 SQ. FT.
VAN PARKING SPACE PER 11-B208.2.24		TOTAL	2,932 SQ. FT.
TOTAL REQUIRED ACCESSIBLE PARKING PROVIDED ACCESSIBLE PARKING		1/250 SQ. FT. x 2,932 SQ. FT. =	12
TOTAL REQUIRED ACCESSIBLE PARKING PROVIDED ACCESSIBLE PARKING		REQUIRED OFFICE PARKING	12
TOTAL REQUIRED ACCESSIBLE PARKING PROVIDED ACCESSIBLE PARKING		1 RESIDENTIAL	
TOTAL REQUIRED ACCESSIBLE PARKING PROVIDED ACCESSIBLE PARKING		PER P.A.M.C. 18.15 DENSITY BONUS	
TOTAL REQUIRED ACCESSIBLE PARKING PROVIDED ACCESSIBLE PARKING		1 BEDROOM = 1/SPACE x 3 UNITS	3
TOTAL REQUIRED ACCESSIBLE PARKING PROVIDED ACCESSIBLE PARKING		2 BEDROOM = 2/SPACE x 2 UNITS	4
TOTAL REQUIRED ACCESSIBLE PARKING PROVIDED ACCESSIBLE PARKING		3 BEDROOM = 2/SPACE x 2 UNITS	4
TOTAL REQUIRED ACCESSIBLE PARKING PROVIDED ACCESSIBLE PARKING		REQUIRED RESIDENTIAL PARKING	11
TOTAL REQUIRED ACCESSIBLE PARKING PROVIDED ACCESSIBLE PARKING		TOTAL REQUIRED PARKING	
TOTAL REQUIRED ACCESSIBLE PARKING PROVIDED ACCESSIBLE PARKING		REQUIRED RETAIL PARKING	24
TOTAL REQUIRED ACCESSIBLE PARKING PROVIDED ACCESSIBLE PARKING		REQUIRED OFFICE PARKING	12
TOTAL REQUIRED ACCESSIBLE PARKING PROVIDED ACCESSIBLE PARKING		REQUIRED RESIDENTIAL PARKING	11
TOTAL REQUIRED ACCESSIBLE PARKING PROVIDED ACCESSIBLE PARKING		TOTAL REQUIRED PARKING	47
TOTAL REQUIRED ACCESSIBLE PARKING PROVIDED ACCESSIBLE PARKING		PROVIDED PARKING	
TOTAL REQUIRED ACCESSIBLE PARKING PROVIDED ACCESSIBLE PARKING		SUB GRADE GARAGE	39
TOTAL REQUIRED ACCESSIBLE PARKING PROVIDED ACCESSIBLE PARKING		SURFACE PARKING	4
TOTAL REQUIRED ACCESSIBLE PARKING PROVIDED ACCESSIBLE PARKING		TOWN HOME GARAGES	4
TOTAL REQUIRED ACCESSIBLE PARKING PROVIDED ACCESSIBLE PARKING		TOTAL PROVIDED PARKING	47
TOTAL REQUIRED ACCESSIBLE PARKING PROVIDED ACCESSIBLE PARKING		BICYCLE PARKING CALCULATIONS	
TOTAL REQUIRED ACCESSIBLE PARKING PROVIDED ACCESSIBLE PARKING		REQUIRED COMMERCIAL BICYCLE PARKING	
TOTAL REQUIRED ACCESSIBLE PARKING PROVIDED ACCESSIBLE PARKING		RETAIL: 1/2000 SQ. FT. x 4,799 SQ. FT. (1 LONG TERM - 2 SHORT TERM)	3
TOTAL REQUIRED ACCESSIBLE PARKING PROVIDED ACCESSIBLE PARKING		OFFICE: 1/2500 SQ. FT. x 2,932 SQ. FT. (1 SHORT TERM)	1
TOTAL REQUIRED ACCESSIBLE PARKING PROVIDED ACCESSIBLE PARKING		REQUIRED COMMERCIAL PARKING	4
TOTAL REQUIRED ACCESSIBLE PARKING PROVIDED ACCESSIBLE PARKING		REQUIRED RESIDENTIAL BICYCLE PARKING	
TOTAL REQUIRED ACCESSIBLE PARKING PROVIDED ACCESSIBLE PARKING		1/UNIT = 1 x 7 UNITS + 1 GUEST (7 LONG TERM - 1 SHORT TERM)	8
TOTAL REQUIRED ACCESSIBLE PARKING PROVIDED ACCESSIBLE PARKING		REQUIRED RESIDENTIAL PARKING	8
TOTAL REQUIRED ACCESSIBLE PARKING PROVIDED ACCESSIBLE PARKING		REQUIRED BICYCLE PARKING	
TOTAL REQUIRED ACCESSIBLE PARKING PROVIDED ACCESSIBLE PARKING		REQUIRED COMMERCIAL PARKING	4
TOTAL REQUIRED ACCESSIBLE PARKING PROVIDED ACCESSIBLE PARKING		REQUIRED RESIDENTIAL PARKING	8
TOTAL REQUIRED ACCESSIBLE PARKING PROVIDED ACCESSIBLE PARKING		TOTAL REQUIRED BICYCLE PARKING (8 LONG TERM - 4 SHORT TERM)	12
TOTAL REQUIRED ACCESSIBLE PARKING PROVIDED ACCESSIBLE PARKING		PROVIDED BICYCLE PARKING	
TOTAL REQUIRED ACCESSIBLE PARKING PROVIDED ACCESSIBLE PARKING		BIKE LOCKERS	7
TOTAL REQUIRED ACCESSIBLE PARKING PROVIDED ACCESSIBLE PARKING		COMMERCIAL BIKE STORAGE	9
TOTAL REQUIRED ACCESSIBLE PARKING PROVIDED ACCESSIBLE PARKING		BIKE RACK	4
TOTAL REQUIRED ACCESSIBLE PARKING PROVIDED ACCESSIBLE PARKING		TOTAL PROVIDED BICYCLE PARKING (17 LONG TERM - 4 SHORT TERM)	20







4115 El Camino Real
Palo Alto, CA
October 31, 2018

FIRST FLOOR PLAN
A009



SECOND FLOOR PLAN
A010





4115 El Camino Real
Palo Alto, CA
October 31, 2018

THIRD FLOOR PLAN
A011


3361 Walnut Blvd. Suite 120 Brentwood, CA 94513
925.634.7000
www.straussdesign.com














SECTION A




SECTION B

SOIL CALCULATIONS






SECTION C



SECTION D





PREVIOUS STREET VIEW FROM EL CAMINO REAL



PROPOSED STREET VIEW FROM EL CAMINO REAL




PREVIOUS STREET VIEW FROM EL CAMINO REAL



PROPOSED STREET VIEW FROM EL CAMINO REAL






AXONOMETRIC A.



AXONOMETRIC B.

4115 El Camino Real
Palo Alto, CA
October 31, 2018

AXONOMETRIC VIEWS
A019





- PROGRAM AMENITY LEGEND**
- 1 EXISTING TREE TO REMAIN, TYPICAL
 - 2 12'-0" WIDE CONCRETE SIDEWALK, PER THE SOUTH EL CAMINO REAL DESIGN GUIDELINES. SEE CIVIL DRAWINGS.
 - 3 DRIVEWAY TO UNDERGROUND PARKING, PER CIVIL DRAWINGS
 - 4 DRIVEWAY, SEE CIVIL DRAWINGS
 - 5 RAISED METAL PLANTER WITH ACCENT PLANTING, TYPICAL
 - 6 PERVIOUS PAVING, TYPICAL
 - 7 NEW STREET TREE TO MATCH EXISTING SYCAMORE STREET TREES
 - 8 PARKING SPACES, SEE CIVIL DRAWINGS
 - 9 3' HT. HORIZONTAL WOOD FENCE ON TOP OF 36" HT. RETAINING WALL, TYPICAL. 6' HT. TOTAL
 - 10 BUILDING OVERHANG SHOWN DASHED, TYPICAL
 - 11 18" HT. RAISED LAWN AREA
 - 12 6' HT. WOOD GATE, ENTRY TO TENANT PRIVATE OPEN SPACE
 - 13 36" HT. RAISED FLOW-THROUGH PLANTER, TYPICAL.
 - 14 STEPS TO RAISED LAWN AREA, (3) TOTAL
 - 15 TREE GRATES AT STREET TREES PER 'EL CAMINO REAL' DESIGN GUIDELINES
 - 16 EXIT STAIR FROM BUILDING WITH PATHWAY
 - 17 BIKE RACKS, (4) BIKES
 - 18 LOUNGE SEATING AREA W/ OUTDOOR WALL TV
 - 19 OUTDOOR DINING TABLE
 - 20 TRASH RECEPTACLE, TYPICAL
 - 21 DECORATIVE PAVERS ON PEDESTAL
 - 22 ORNAMENTAL POTTERY WITH PLANTING, TYPICAL
 - 23 BENCH SEATING, TYPICAL
 - 24 MOVABLE CAFE TABLES AT ENTRY PLAZA
 - 25 WOOD PAVERS ON PEDESTAL ON 2nd & 3rd FLOOR
 - 26 30" HT. RAISED CORTEN STEEL PLANTER
 - 27 NOT USED
 - 28 WATER METERS AND BACKFLOW DEVICES ON-GRADE (SEE ARCH. DWGS. FOR PARKING GARAGE SECTION).
 - 29 ABOVE-GROUND TRANSFORMER ON-GRADE (SEE ARCH. DWGS. FOR PARKING GARAGE SECTION).
 - 30 GAS METERS AND WALL ENCLOSURE
 - 31 WOOD PAVERS ON PEDESTAL ON 2nd FLOOR PATIO BELOW
 - 32 3rd FLOOR ROOF DECK W/ PEDESTAL WOOD PAVERS, FURNITURE SEATING, AND RAISED PERIMETER ACCENT PLANTERS.
 - 33 BUILDING ELECTRICAL MAIN SWITCH GEAR PANEL
 - 34 SUNKEN FLOW-THROUGH PLANTER, SEE CIVIL DRAWINGS.



GROUND FLOOR
PRELIMINARY LANDSCAPE PLAN

NOT FOR CONSTRUCTION


4115 EL CAMINO REAL
PALO ALTO, CALIFORNIA



DATE: 10/31/18
JOB# 17007.01



**ENVIRONMENTAL
FORESIGHT, INC.**
Landscape Architecture
1700 N. Broadway, Suite 401
Walnut Creek, CA 94596
T (925) 945-0300 F (925) 945-6688
www.environmentalforesight.com



PLANT MATERIAL KEY					
KEY	BOTANICAL NAME	COMMON NAME	SIZE	SPACING	WUCOLS * (1)
TREES					
ARB MAR	Arbutus 'Marina'	Stranberry Tree	24" BOX-STD.	SEE PLANS	L
CER OCC	Ceris occidentalis	Western Redbud	24" BOX-STD.	SEE PLANS	L
SHRUBS, GROUNDCOVERS & GRASSES					
ASP ELA	Aspidistra elatior	Cast Iron Plant	5 GAL	24" O.C.	L
DIE IRI	Dietes iridioides	Fortnight Lily	5 GAL	36" O.C.	L
ERI KAR	Erigeron karvinskianus	Santa Barbara Daisy	1 GAL	36" O.C.	L
EVO SIL	Euonymus J. 'Silver King'	Upright Euonymus	15 GAL	30" O.C.	L
FES GLA	Festuca glauca	Blue Fescue	1 GAL	18" O.C.	L
HEU MAX	Heuchera maxima	Island Alum Root	1 GAL	18" O.C.	L
HEU MIR	Heuchera micrantha	Crevice Alumroot	1 GAL	24" O.C.	L
JUN PAT	Juncus patens	California Gray Rush	1 GAL	24" O.C.	L
MUH RIG	Muhlenbergia rigens	Deer Grass	5 GAL	48" O.C.	L
PHO RAI	Phormium h. 'Rainbow Warrior'	New Zealand Flax	15 GAL	POTS	L
POP MAK	Podocarpus m. 'Maki'	Shrubby Yew Pine	15 GAL	36" O.C.	M
RHA LIT	Rhamnus californica 'Little Sur Coffeeberry'	Coffeeberry	5 & 15 GAL	48" O.C.	L
RIB SPE	Ribes speciosum	Fuchsia-Flowering Gooseberry	15 GAL	SEE PLANS	L
RIB VIB	Ribes viburnifolium	Evergreen Currant	5 GAL	48" O.C.	L
WOO FIM	Woodwardia fimbriata	Giant Chain Fern	5 GAL	48" O.C.	M
VINES					
DIS BUC	Distictis buccinatoria	Blood-Red Trumpet Vine	15 GAL	SEE PLANS	M
FIC PUM	Ficus pumila	Creeping Fig	15 GAL	SEE PLANS	M

NOTES:
1. * - WUCOLS IV RATING IS AN INDUSTRY STANDARD FOR IRRIGATION WATER NEEDS OF LANDSCAPE PLANTINGS IN SPECIFIC CALIFORNIA REGIONS. THE MAJORITY OF PLANTS FOR THIS REGION ARE VERY LOW (VL) TO Medium (M) WATER REQUIREMENTS AND PLANTED IN SPECIFIC HYDROZONES. ABBREVIATIONS FOR WUCOLS WATER NEEDS ARE: VL - VERY LOW, L - LOW, M - MEDIUM, H - HIGH.
2. HIGHLIGHTED PLANT SPECIES ABOVE ARE CALIFORNIA NATIVES AS CLASSIFIED BY THE CALIFORNIA NATIVE PLANT SOCIETY AND THE SANTA CLARA VALLEY URBAN RUNOFF POLLUTION PREVENTION PROGRAM PLANT LISTS.

3rd FLOOR
PRELIMINARY LANDSCAPE PLAN
NOT FOR CONSTRUCTION

4115 EL CAMINO REAL
PALO ALTO, CALIFORNIA



DATE: 10/31/18
JOB# 17007.01



**ENVIRONMENTAL
FORESIGHT, INC.**
Landscape Architecture
1700 N. Broadway, Suite 401
Walnut Creek, CA 94596
T (925) 945-0300 F (925) 945-6688
www.environmentalforesight.com

L-2
2 of 3



TREE IMAGERY



SITE AMENITY IMAGERY



SHRUBS & GROUNDCOVER IMAGERY



LANDSCAPE DESIGN IMAGES

NOT FOR CONSTRUCTION

4115 EL CAMINO REAL
PALO ALTO, CALIFORNIA



DATE: 10/31/18
JOB# 17007.01



ENVIRONMENTAL
FORESIGHT, INC.
Landscape Architecture
1700 N. Broadway, Suite 401
Walnut Creek, CA 94596
T (925) 945-0000 F (925) 945-8888
www.environmentalforesight.com

L-3
3 of 3


4115 EL CAMINO REAL PALO ALTO, CA

LEGEND

EXISTING	PROPOSED	DESCRIPTION
---	---	BOUNDARY
---	---	PROPERTY LINE
---	---	RETAINING WALL
---	---	LANDSCAPE RETAINING WALL
---	---	RAINWATER TIGHTLINE
---	---	SUBDRAIN LINE
---	---	TIGHTLINE
---	---	STORM DRAIN LINE
---	---	SANITARY SEWER LINE
---	---	WATER LINE
---	---	GAS LINE
---	---	PRESSURE LINE
---	---	JOINT TRENCH
---	---	SET BACK LINE
---	---	CONCRETE VALLEY GUTTER
---	---	EARTHEN SWALE
---	---	CATCH BASIN
---	---	JUNCTION BOX
---	---	AREA DRAIN
---	---	CURB INLET
---	---	STORM DRAIN MANHOLE
---	---	FIRE HYDRANT
---	---	SANITARY SEWER MANHOLE
---	---	STREET SIGN
---	---	SPOT ELEVATION
---	---	FLOW DIRECTION
---	---	DEMOLISH/REMOVE
---	---	BENCHMARK
---	---	CONTOURS
---	---	TREE TO BE REMOVED

ABBREVIATIONS

AB	AGGREGATE BASE	LF	LINEAR FEET
AC	ASPHALT CONCRETE	MAX	MAXIMUM
ACC	ACCESSIBLE	MH	MANHOLE
AD	AREA DRAIN	MIN	MINIMUM
BC	BEGINNING OF CURVE	MON.	MONUMENT
B & D	BEARING & DISTANCE	(N)	NEW
BM	BENCHMARK	NO.	NUMBER
BW/FG	BOTTOM OF WALL/FINISH	NTS	NOT TO SCALE
GRADE		O.C.	ON CENTER
CB	CATCH BASIN	O/	OVER
C & G	CURB AND GUTTER	(PA)	PLANTING AREA
CL	CENTER LINE	PED	PEDESTRIAN
OPP	CORRUGATED PLASTIC PIPE (SMOOTH INTERIOR)	PIV	POST INDICATOR VALVE
CO	CLEANOUT	PSS	PUBLIC SERVICES EASEMENT
COTG	CLEANOUT TO GRADE	R	PROPERTY LINE
CONC	CONCRETE	PUE	PUBLIC UTILITY EASEMENT
CONST	CONSTRUCT or -TION	PVC	POLYVINYL CHLORIDE
CONC COR	CONCRETE CORNER	R	RADIUS
CY	CUBIC YARD	RCP	REINFORCED CONCRETE PIPE
D	DIAMETER	RIM	RIM ELEVATION
DI	DROP INLET	RW	RAINWATER
DIP	DUCTILE IRON PIPE	R/W	RIGHT OF WAY
EA	EACH	S	SLOPE
EC	END OF CURVE	S.A.D.	SEE ARCHITECTURAL DRAWINGS
EG	EXISTING GRADE	SAN	SANITARY
EL	ELEVATIONS	SD	STORM DRAIN
EP	EDGE OF PAVEMENT	SDMH	STORM DRAIN MANHOLE
EQ	EQUIPMENT	SHT	SHEET
EW	EACH WAY	S.L.D.	SEE LANDSCAPE DRAWINGS
(E)	EXISTING	SPEC	SPECIFICATION
FC	FACE OF CURB	SS	SANITARY SEWER
FF	FINISHED FLOOR	SSCO	SANITARY SEWER CLEANOUT
FG	FINISHED GRADE	SSMH	SANITARY SEWER MANHOLE
FH	FIRE HYDRANT	ST	STREET
FL	FLOW LINE	STA	STATION
FS	FINISHED SURFACE	STD	STANDARD
G	GAS	STRUCT	STRUCTURAL
GA	GAGE OR GAUGE	T	TELEPHONE
GB	GRADE BREAK	TC	TOP OF CURB
HDPE	HIGH DENSITY CORRUGATED POLYETHYLENE PIPE	TEMP	TEMPORARY
HORIZ	HORIZONTAL	TP	TOP OF PAVEMENT
HI PT	HIGH POINT	TW/FG	TOP OF WALL/FINISH GRADE
H&T	HUB & TACK	TYP	TYPICAL
ID	INSIDE DIAMETER	VC	VERTICAL CURVE
INV	INVERT ELEVATION	VCP	VITRIFIED CLAY PIPE
JB	JUNCTION BOX	VERT	VERTICAL
JT	JOINT TRENCH	W	WITH
JP	JOINT UTILITY POLE	W, WL	WATER LINE
L	LENGTH	WM	WATER METER
LDNG	LANDING	WWF	WELDED WIRE FABRIC



NOTES

ALL DISTANCES AND DIMENSIONS ARE IN FEET AND DECIMALS OF A FOOT.

UNDERGROUND UTILITY LOCATION IS BASED ON SURFACE EVIDENCE.

BUILDING FOOTPRINTS ARE SHOWN AT GROUND LEVEL.

FINISH FLOOR ELEVATIONS ARE TAKEN AT DOOR THRESHOLD (EXTERIOR).

BENCHMARK

CITY OF PALO ALTO BENCHMARK
BM068
BRASS DISK ON TOP AND CENTER OF THE NORTHEASTERLY HEADWALL AT EL CAMINO REAL AND BARRON CREEK. NEAR THE NORTH CORNER OF STREET INTERSECTION. CITY OF PALO ALTO
ELEVATION = 40.95'
(NAVD 88 DATUM)

EASEMENT NOTE

THERE ARE NO EASEMENTS LISTED IN THE COMMITMENT FOR TITLE INSURANCE ISSUED BY FIRST AMERICAN TITLE COMPANY, ORDER NO. NCS-760951-SM. DATED OCTOBER 23, 2015

SITE BENCHMARK

SURVEY CONTROL POINT
CUT CROSS IN CONCRETE
ELEVATION = 43.72'
(NAVD 88 DATUM)

FEMA NOTE:


THIS PROJECT IS LOCATED WITHIN FEMA FLOOD ZONE "X". ZONE "X" IS DESIGNATED AS: AREAS OF 0.2% ANNUAL CHANCE FLOOD; AREAS OF 1% ANNUAL CHANCE FLOOD WITH AVERAGE DEPTHS OF LESS THAN 1 FOOT OR WITH DRAINAGE AREAS LESS THAN 1 SQUARE MILE; AND AREAS PROTECTED BY LEVEES FROM 1% ANNUAL CHANCE FLOOD.

NO BASE FLOOD ELEVATION FOR SUBJECT SITE WAS SHOWN ON FLOOD INSURANCE RATE MAP (FIRM) NO. 06085C0017H, PANEL 17 OF 830 EFFECTIVE DATE MAY 18, 2009.

ESTIMATED EARTHWORK QUANTITIES

CUBIC YARDS	WITHIN BUILDING FOOTPRINT	OUTSIDE BUILDING FOOTPRINT	TOTAL CUBIC YARDS
CUT	8,500	0	8,500
FILL	0	0	0
EXPORT			8,500

NOTE:
GRADING QUANTITIES REPRESENT BANK YARDAGE. IT DOES NOT INCLUDE ANY SWELLING OR SHRINKAGE FACTORS AND IS INTENDED TO REPRESENT IN-SITU CONDITIONS. QUANTITIES DO NOT INCLUDE OVER-EXCAVATION, TRENCHING, STRUCTURAL FOUNDATIONS OR PIERS, OR POOL EXCAVATION (IF ANY). NOTE ADDITIONAL EARTHWORKS, SUCH AS KEYWAYS OR BENCHING MAY BE REQUIRED BY THE GEOTECHNICAL ENGINEER IN THE FIELD AT TIME OF CONSTRUCTION. CONTRACTOR TO VERIFY QUANTITIES.



OWNER'S INFORMATION

OWNER:
4115 ECR LLC
250 ROBERT LOUIS STEVENSON AVE.
ALAMEDA, CA

APN: 132-46-100

REFERENCES

- THIS GRADING AND DRAINAGE PLAN IS SUPPLEMENTAL TO:
1. TOPOGRAPHIC SURVEY BY LEA AND BRAZE ENGINEERING, ENTITLED: "TOPOGRAPHIC SURVEY" 4115 EL CAMINO REAL PALO ALTO, CA DATED: JANUARY 29, 2018
 2. SITE PLAN BY SDG ARCHITECT, INC. ENTITLED: "SITE PLAN" 4115 EL CAMINO REAL PALO ALTO, CA DATED: JANUARY 29, 2018
 3. LANDSCAPE PLAN BY ENVIRONMENTAL FORESIGHT INC. ENTITLED: "PRELIMINARY LANDSCAPE" 4115 EL CAMINO REAL PALO ALTO, CA DATED: JANUARY 31, 2018

THE CONTRACTOR SHALL REFER TO THE ABOVE NOTED SURVEY AND PLAN, AND SHALL VERIFY BOTH EXISTING AND PROPOSED ITEMS ACCORDING TO THEM.

SHEET INDEX

C-1.0	TITLE SHEET
C-1.1	EXISTING CONDITION - TOPOGRAPHIC SURVEY
C-2.0	DEMOLITION PLAN
C-3.0	PRELIMINARY GRADING & DRAINAGE PLAN
SCP-1	IMPERVIOUS AREA EXHIBIT
SCP-2	STORMWATER CONTROL PLAN
SCP-3	STORMWATER CONTROL DETAILS
ER-1	EROSION CONTROL PLAN
ER-2	EROSION CONTROL DETAILS
SW-1	STORMWATER POLLUTION PREVENTION PLAN



LEA & BRAZE ENGINEERING, INC.
CIVIL ENGINEERS • LAND SURVEYORS
SACRAMENTO REGION
307 DOUGLAS BLVD., # 300
SACRAMENTO, CA 95811
(916) 887-3388
(916) 887-3388
(916) 887-3388
WWW.LEABRAZE.COM

4115 EL CAMINO REAL
PALO ALTO, CALIFORNIA

TITLE SHEET

1	PLAN CHECK	TT
2	SITE REVISIONS	TT
3	SITE REVISIONS	TT
4	SITE REVISIONS	TT
5	SITE REVISIONS	TT
6	SITE REVISIONS	TT

REVISIONS BY

JOB NO: 2161066

DATE: 08-01-17

SCALE: AS SHOWN


DESIGN BY: PC/TT

DRAWN BY: TB/WA

SHEET NO:

C-1.0

01 OF 10 SHEETS




LEA & BRAZE ENGINEERING, INC.
CIVIL ENGINEERS • LAND SURVEYORS
SACRAMENTO REGION
3017 DOUGLAS BLVD., # 300
SACRAMENTO, CA 95834
(916) 887-3388
(916) 887-3398
(916) 887-3399
(916) 887-7383
WWW.LEABRAZE.COM



**4115 EL CAMINO REAL
PALO ALTO, CALIFORNIA**
SANTA CLARA COUNTY
APN: 132-46-100

**EXISTING CONDITION -
TOPOGRAPHIC SURVEY**

1	PLAN CHECK 11-22-17	TT
2	SITE REVISIONS 02-02-18	TT
3	SITE REVISIONS 04-20-18	TT
4	SITE REVISIONS 05-16-18	TT
5	SITE REVISIONS 10-05-18	TT
6	SITE REVISIONS 10-30-18	TT
REVISIONS		BY
JOB NO:		2161066
DATE:		08-01-17
SCALE:		AS NOTED
DESIGN BY:		PC/TT
DRAWN BY:		TB/WA
SHEET NO:		
C-1.1		
02 OF 10 SHEETS		



DEMOLITION LEGEND

-  (E) TREES HAVE PREVIOUSLY BEEN REMOVED UNDER SEPARATE PERMIT.
-  ALL ITEMS WITHIN LIMITS OF DEMOLITION TO BE REMOVED UNLESS OTHERWISE NOTED TO REMAIN ON PLANS. CONTRACTOR IS TO REMOVE ALL LAWN, IRRIGATION SYSTEMS, PAVEMENT, CONCRETE AND STRUCTURES UNLESS CALLED OUT TO REMAIN.

TREE PROTECTION NOTE:
FOR INFORMATION REGARDING TREE PROTECTION SEE
SHEET T-1 FOR NOTES AND DETAILS.

DEMOLITION NOTES:

1 EXISTING STORM DRAIN SYSTEM WITHIN THE LIMITS OF DEMOLITION TO BE REMOVED UNLESS OTHERWISE NOTED. CONTRACTOR TO TAKE CAUTION WHEN WORKING WITHIN AREA OF (E) STORM DRAIN. SEE GRADING AND DRAINAGE PLAN FOR NEW TIE-IN FOR STORM DRAIN SYSTEM.

- 2 (E) STORM DRAIN INLET REMAIN - PROTECT IN PLACE.
- 3 (E) SANITARY SEWER CLEANOUT TO REMAIN - PROTECT IN PLACE.
- 4 (E) SANITARY SEWER MANHOLE TO REMAIN - PROTECT IN PLACE.

PLAN CHECK 11-22-17	TT
SITE REVISIONS 02-02-18	TT
SITE REVISIONS 04-20-18	TT
SITE REVISIONS 05-16-18	TT
SITE REVISIONS 10-05-18	TT
SITE REVISIONS 10-30-18	TT
REVISIONS	BY

DB NO: 2161066

DATE: 08-01-17


SCALE: AS NOTED

DESIGN BY: PC/TT

RAWN BY: TB/WA

SHEET NO:

C-2.0



FLATWORK KEYNOTES TO
FINISHED GRADES AT BUILDING PERIMETER SHALL BE SLOPED AT A
MINIMUM OF 5% FOR THE FIRST 10' AWAY FROM THE BUILDING PER CBC
1804.3 OR TO AN APPROVED DRAINAGE SWALE OR STRUCTURE. GRADES
SHALL CONTINUE TO SLOPE TOWARDS POSITIVE DRAINAGE AND A POSITIVE
OUTFALL. MAINTAIN 8" CLEARANCE BETWEEN FINISH EARTHEN GRADE AND
BOTTOM OF MUD SILL AT ALL TIMES PER CBC 2304.11.2 UNLESS
STRUCTURAL DETAILING ALLOWS LESS. REFER TO STRUCTURAL PLANS FOR
FOUNDATION DESIGN AND DETAILS.

PROVIDE 2% (1% MIN.) SLOPE ACROSS FLAT WORK AND/OR PAVING PER
CBC 2304.11.2. SLOPE TOWARDS POSITIVE DRAINAGE AS SHOWN ON PLAN.

(N) CONCRETE DRIVEWAY. SEE DETAIL X SHEET X.

STORM DRAIN KEYNOTES TO
INSTALL (N) ON-SITE STORM DRAIN SYSTEM. USE MINIMUM 6" PVC (SDR
35) OR HDPE (ADS N-12 W/ SMOOTH INTERIOR WALLS). MAINTAIN 24"
MINIMUM COVER AND SLOPED AT 1% MINIMUM AT ALL TIMES UNLESS
OTHERWISE NOTED. PROVIDE CLEAN OUT TO GRADE. AT MAJOR CHANGES
IN DIRECTION, AVOID USING 90° BENDS AND INSTEAD USE (2) 45° BENDS
AND WYE CONNECTIONS.

UTILITIES KEYNOTES TO
INSTALL (N) SANITARY SEWER LATERALS. USE 6" HDPE (SDR-17) SLOPED
AT 2% MINIMUM. CONNECT TO (E) SEWER MAIN AS SHOWN. PROVIDE
CLEANOUT TO GRADE AT BUILDING AND BEHIND PROPERTY LINE AND AT
MAJOR CHANGES IN DIRECTION AS SHOWN. REUSE (E) LATERAL IF
POSSIBLE. CONNECT PER CITY STANDARDS.

CONNECT (N) FIRE PROTECTION SERVICE PER CITY STANDARDS.

CONNECT (N) WATER SERVICE PER CITY STANDARDS.

CONNECT (N) LANDSCAPE SERVICE PER CITY STANDARDS.

INSTALL (N) JOINT TRENCH FOR SERVICES INCLUDING GAS, ELECTRIC,
CATV & TELEPHONE FROM NEAREST POINT OF CONNECTION. DESIGN BY
OTHERS.

INSTALL (N) GAS SERVICE PER CITY STANDARDS. DESIGN BY OTHERS.

DEMOLITION KEYNOTES TO
DEMOLISH (E) IMPROVEMENTS AS NECESSARY TO ACCOMMODATE (N)
CONSTRUCTION. NO DEMOLITION SHALL COMMENCE WITHOUT REQUIRED
DEMOLITION PERMITS.

REMOVE (E) TREE. CONTRACTOR SHALL OBTAIN THE PROPER TREE
REMOVAL PERMITS AS REQUIRED.

PROVIDE TREE PROTECTION AROUND TREES TO REMAIN. SEE DETAIL X ON
SHEET C-X.



LEA & BRAZE ENGINEERING, INC.
CIVIL ENGINEERS • LAND SURVEYORS
BAY AREA REGION
2495 INDUSTRIAL PKWY WEST
SACRAMENTO, CA 95833
(916) 887-3338
(916) 887-3019
(916) 887-3338
WWW.LEABRAZE.COM

**4115 EL CAMINO REAL
PALO ALTO, CALIFORNIA**

**PRELIMINARY
GRADING AND
UTILITY PLAN**

1	PLAN CHECK	TT
2	SITE REVISIONS	TT
3	SITE REVISIONS	TT
4	SITE REVISIONS	TT
5	SITE REVISIONS	TT

REVISIONS BY

JOB NO: 2161066

DATE: 08-01-17

SCALE: AS SHOWN




DESIGN BY: PC/TT

DRAWN BY: TB/WA

SHEET NO:

C-3.0

04 OF 10 SHEETS



LEA & BRAZE ENGINEERING, INC.
CIVIL ENGINEERS • LAND SURVEYORS
2495 Industrial Parkway West
Hayward, California 94545
(510) 887-4086
Fax: (510) 887-3019
WWW.LEABRAZE.COM

PROJECT	4115 El Camino Real	DATE	October 30, 2018
JOB NO.	2161066	BY	T. THAO

SITE HYDROLOGY CALCULATION SUMMARY

Calculations based on a 10 year event with a 120 minute duration

Site Area (A)	A =	15,696 sqft.	0.360 acre
Rain Fall Intensity (I)	I =	0.56 in/hr	(From San Mateo County Rainfall Map)
Intensity Factor (F)	F =	0.80	(From San Mateo County Rainfall Map)
On-Site Run-Off Coefficient Tables (C)	(Impervious = 0.95, Pervious = 0.35)		

Existing:

Type of Surface	Area (ft ²)	C _{runoff}	Weight
Buildings	5,456	0.95	5,183
Impervious Driveway	0	0.95	0
Patios, Walkways & Pads	523	0.95	497
Uncovered Parking	9,672	0.95	9,188
Pervious Paving	0	0.35	0
Green Roof	0	0.35	0
Landscape / Treatment Planters	45	0.35	16
TOTAL	15,696		14,884
Total Site Pre-Construction Run-Off Coefficient = 0.95			

Proposed:

Type of Surface	Area (ft ²)	C _{runoff}	Weight
Buildings	7,969	0.95	7,571
Impervious Driveway	3,493	0.95	3,318
Patios, Walkways & Pads	2,025	0.95	1,924
Uncovered Parking	0	0.95	0
Pervious Paving	496	0.35	174
Green Roof	0	0.35	0
Landscape / Treatment Planters	1,713	0.35	600
TOTAL	15,696		13,536
Total Site Post-Construction Run-Off Coefficient = 0.87			

Run-Off (Q)
Q = CIAF

Pre-Construction: Q = 0.153 cfs

Post-Construction Without Retention: Q = 0.140 cfs

Change in Run-off
 $\Delta Q = Q_{POST} - Q_{PRE}$
 $\Delta Q = -0.013 \text{ c.f.s.} \quad -5.83 \text{ gal/min}$

PROPOSED PAVEMENT HATCH LEGEND

	BUILDING
	IMPERVIOUS CONCRETE
	IMPERVIOUS PAVER WALKWAY OVER STRUCTURAL SLAB
	PERVIOUS PAVER WALKWAY OVER NATIVE SOIL
	PLANTERS

TABLES AND CALCULATIONS:

TABLE 1:
ON-SITE PERVIOUS AND IMPERVIOUS SURFACE COMPARISON

	EXISTING CONDITIONS (SQ FT)	%	PROPOSED CONDITIONS (SQ FT)	%	DIFFERENCE (SQ. FT)	%
SITE (ACRES) = 0.36	15,696	100.0	15,696	100.0	0	0.0
BUILDING ROOF:	5,456	34.8	7,969	50.8	+2,513	+16.0
IMPERVIOUS DRIVEWAY:	0	0.0	3,493	22.3	+3,493	+22.3
SIDEWALKS, PATIOS, PATHS, ETC.:	523	3.3	2,025	12.9	+1,502	+9.6
IMPERVIOUS UN-COVERD PARKING:	9,672	61.6	0	0.0	-9,672	-61.6
PERVIOUS PAVERS:	0	0.0	496	3.2	+496	+3.2
GREEN ROOF:	0	0.0	0	0.0	+0	+0.0
LANDSCAPE:	45	0.3	1,713	10.9	+1,668	+10.6
TOTAL	15,696	100.0	15,696	100.0	0	0
IMPERVIOUS SURFACES:	15,651	99.7	13,487	85.9	-2,164	-13.8
PERVIOUS SURFACES:	45	0.3	2,209	14.1	+2,164	+13.8
TOTAL	15,696	100.0	15,696	100.0	0	0.0






LEA & BRAZE ENGINEERING, INC.
CIVIL ENGINEERS • LAND SURVEYORS
BAY AREA REGION
2495 Industrial Parkway West
Hayward, CA 94545
(510) 887-4086
(510) 887-3019
WWW.LEABRAZE.COM

4115 EL CAMINO REAL
PALO ALTO, CALIFORNIA
APN: 132-46-100
SANTA CLARA COUNTY

IMPERVIOUS SURFACE EXHIBIT

1	PLAN CHECK	TT
2	SITE REVISIONS	TT
3	SITE REVISIONS	TT
4	SITE REVISIONS	TT
5	SITE REVISIONS	TT
6	SITE REVISIONS	TT
REVISIONS		BY
JOB NO:		2161066
DATE:		08-01-17
SCALE:		AS SHOWN
DESIGN BY:		PC/TT
DRAWN BY:		TB/WA
SHEET NO:		

SCP-1
05 OF 10 SHEETS



****INTERCEPTOR TREE CREDIT:**

INTERCEPTOR TREE CREDIT FOR (E) STREET TREES ALONG EL CAMINO REAL FRONTAGE PER SCVURPPP C3 TECHNICAL GUIDANCE 4.5.1 AND 4.5.2

(E) TREE #2 (LONDON PLANE), 12" DBH, CANOPY SPREAD (962 SF)
(E) TREE #3 (GINKO), 13" DBH, CANOPY SPREAD (707 SF)

TOTAL INTERCEPTOR TREE CREDIT= 1,669 SF
TOTAL IMPERVIOUS AREA= 459 SF
EXCESS TREE CREDIT= 1,210 SF

TABLES AND CALCULATIONS:

**TABLE 1:
ON-SITE PERVIOUS AND IMPERVIOUS SURFACE COMPARISON**

	EXISTING CONDITIONS (SQ. FT.)	%	PROPOSED CONDITIONS (SQ. FT.)	%	DIFFERENCE (SQ. FT.)	%
SITE (ACRES) = 0.36	15,696	100.0	15,696	100.0	0	0.0
BUILDING ROOF:	5,456	34.8	7,969	50.8	+2,513	+16.0
IMPERVIOUS DRIVEWAY:	0	0.0	3,493	22.3	+3,493	+22.3
SIDEWALKS, PATIOS, PATHS, ETC.:	523	3.3	2,025	12.9	+1,502	+9.6
IMPERVIOUS UN-COVERED PARKING:	9,672	61.6	0	0.0	-9,672	-61.6
PERVIOUS PAVERS:	0	0.0	496	3.2	+496	+3.2
GREEN ROOF:	0	0.0	0	0.0	+0	+0.0
LANDSCAPE:	45	0.3	1,713	10.9	+1,668	+10.6
TOTAL	15,696	100.0	15,696	100.0	0	0
IMPERVIOUS SURFACES:	15,651	99.7	13,487	85.9	-2,164	-13.8
PERVIOUS SURFACES:	45	0.3	2,209	14.1	+2,164	+13.8
TOTAL	15,696	100.0	15,696	100.0	0	0.0

**TABLE 2:
TREATMENT AREA SIZING SUMMARY**

DRAINAGE MANAGEMENT AREA DESIGNATION	IMPERVIOUS AREA (SQ. FT.)	TREATMENT AREA REQUIRED (4% OF IMPERVIOUS AREA) (SQ. FT.)	TREATMENT AREA PROVIDED (SQ. FT.)	EXCESS TREATMENT AREA (SQ. FT.)
1	7,242	290	411	121
2	4,876	196	222	26
3	910	37	126	89
4	311	**EL CAMINO REAL SIDEWALK - DRAINS TO STREET - TREE CREDIT		
5	148	**EL CAMINO REAL DRIVEWAY - DRAINS TO STREET - TREE CREDIT		
SUBTOTAL	13,487			
6	496			
TOTAL	13,983	PERVIOUS PAVERS		

*PERVIOUS PAVERS COUNTED AS PERVIOUS AREA IN TABLE 1




LEA & BRAZE ENGINEERING, INC.
CIVIL ENGINEERS • LAND SURVEYORS
BAY AREA REGION
2495 INDUSTRIAL PKWY WEST
SACRAMENTO, CA 95833
(916) 887-3388
(916) 887-3019
WWW.LEABRAZE.COM
APN: 132-46-100
SANTA CLARA COUNTY

**4115 EL CAMINO REAL
PALO ALTO, CALIFORNIA**


**STORMWATER
CONTROL PLAN**

1	PLAN CHECK 11-22-17	TT
2	SITE REVISIONS 02-02-18	TT
3	SITE REVISIONS 04-20-18	TT
4	SITE REVISIONS 05-16-18	TT
5	SITE REVISIONS 10-05-18	TT
6	SITE REVISIONS 10-30-18	TT
REVISIONS		BY
JOB NO:		2161066
DATE:		08-01-17
SCALE:		AS SHOWN
DESIGN BY:		PC/TT
DRAWN BY:		TB/WA
SHEET NO:		

SCP-2





SUNKEN FLOW-THROUGH PLANTERS
FLOW-THROUGH TREATMENT PLANTERS 2 & 3
NTS



- NOTE:
1. CURB MAY EITHER BE EXTRUDED TO THE SHAPE SHOWN OR FORMED & POURED IN PLACE.
 2. PROVIDE EXPANSION JOINTS AT 15\" O.C.

PERMEABLE PAVER OVER NATIVE SOIL DETAIL
NTS



RAISED FLOW THROUGH PLANTERS
FLOW-THROUGH TREATMENT PLANTER 1
NTS



LEA & BRAZE ENGINEERING, INC.
CIVIL ENGINEERS • LAND SURVEYORS
BAY AREA REGION
2495 INDUSTRIAL PKWY WEST
EMERYVILLE, CA 94601
(415) 887-3386
(415) 887-3388
(510) 887-3019
WWW.LEABRAZE.COM

4115 EL CAMINO REAL
PALO ALTO, CALIFORNIA

SANTA CLARA COUNTY
APN: 132-46-100

STORMWATER
CONTROL DETAILS

1	PLAN CHECK 11-22-17	TT
2	SITE REVISIONS 02-02-18	TT
3	SITE REVISIONS 04-20-18	TT
4	SITE REVISIONS 05-16-18	TT
5	SITE REVISIONS 10-05-18	TT
6	SITE REVISIONS 10-30-18	TT

REVISIONS	BY
JOB NO:	2161066
DATE:	08-01-17
SCALE:	AS SHOWN
DESIGN BY:	PC/TT
DRAWN BY:	TB/WA
SHEET NO:	

SCP-3
07 OF 10 SHEETS

PURPOSE:

THE PURPOSE OF THIS PLAN IS TO STABILIZE THE SITE TO PREVENT EROSION OF GRADED AREAS AND TO PREVENT SEDIMENTATION FROM LEAVING THE CONSTRUCTION AREA AND AFFECTING NEIGHBORING SITES, NATURAL AREAS, PUBLIC FACILITIES OR ANY OTHER AREA THAT MIGHT BE AFFECTED BY SEDIMENTATION. ALL MEASURES SHOWN ON THIS PLAN SHOULD BE CONSIDERED THE MINIMUM REQUIREMENTS. SHOULD FIELD CONDITIONS DICTATE ADDITIONAL MEASURES, SUCH MEASURES SHALL BE PER CALIFORNIA REGIONAL WATER QUALITY CONTROL BOARD'S FIELD MANUAL FOR EROSION AND SEDIMENTATION CONTROL AND THE CALIFORNIA STORM WATER QUALITY ASSOCIATION BEST MANAGEMENT PRACTICES HANDBOOK FOR CONSTRUCTION. LEA & BRAZE ENGINEERING SHOULD BE NOTIFIED IMMEDIATELY SHOULD CONDITIONS CHANGE.








EROSION CONTROL NOTES:

1. IT SHALL BE THE OWNER'S/CONTRACTOR'S RESPONSIBILITY TO MAINTAIN CONTROL OF THE ENTIRE CONSTRUCTION OPERATION AND TO KEEP THE ENTIRE SITE IN COMPLIANCE WITH THIS EROSION CONTROL PLAN.
2. THE INTENTION OF THIS PLAN IS FOR INTERIM EROSION AND SEDIMENT CONTROL ONLY. ALL EROSION CONTROL MEASURES SHALL CONFORM TO CALIFORNIA REGIONAL WATER QUALITY CONTROL BOARD'S FIELD MANUAL FOR EROSION AND SEDIMENTATION CONTROL, THE CALIFORNIA STORM WATER QUALITY ASSOCIATION BEST MANAGEMENT PRACTICES HANDBOOK FOR CONSTRUCTION, AND THE LOCAL GOVERNING AGENCY FOR THIS PROJECT.
3. OWNER/CONTRACTOR SHALL BE RESPONSIBLE FOR MONITORING EROSION AND SEDIMENT CONTROL MEASURES PRIOR TO, DURING, AND AFTER STORM EVENTS. PERSON IN CHARGE OF MAINTAINING EROSION CONTROL MEASURES SHOULD WATCH LOCAL WEATHER REPORTS AND ACT APPROPRIATELY TO MAKE SURE ALL NECESSARY MEASURES ARE IN PLACE.
4. SANITARY FACILITIES SHALL BE MAINTAINED ON THE SITE AT ALL TIMES.
5. DURING THE RAINY SEASON, ALL PAVED AREAS SHALL BE KEPT CLEAR OF EARTH MATERIAL AND DEBRIS. THE SITE SHALL BE MAINTAINED SO AS TO MINIMIZE SEDIMENT-LADEN RUNOFF TO ANY STORM DRAINAGE SYSTEM, INCLUDING EXISTING DRAINAGE SWALES AND WATERCOURSES.
6. CONSTRUCTION OPERATIONS SHALL BE CARRIED OUT IN SUCH A MANNER THAT EROSION AND WATER POLLUTION WILL BE MINIMIZED. COMPLIANCE WITH FEDERAL, STATE AND LOCAL LAWS CONCERNING POLLUTION SHALL BE MAINTAINED AT ALL TIMES.
7. CONTRACTOR SHALL PROVIDE DUST CONTROL AS REQUIRED BY THE APPROPRIATE FEDERAL, STATE AND LOCAL AGENCY REQUIREMENTS.
8. ALL MATERIALS NECESSARY FOR THE APPROVED EROSION CONTROL MEASURES SHALL BE IN PLACE BY OCTOBER 15TH.
9. EROSION CONTROL SYSTEMS SHALL BE INSTALLED AND MAINTAINED THROUGHOUT THE RAINY SEASON, OR FROM OCTOBER 15TH THROUGH APRIL 15TH, WHICHEVER IS LONGER.
10. IN THE EVENT OF RAIN, ALL GRADING WORK IS TO CEASE IMMEDIATELY AND THE SITE IS TO BE SEALED IN ACCORDANCE WITH THE APPROVAL EROSION CONTROL MEASURES AND APPROVED EROSION CONTROL PLAN.
11. THE CONTRACTOR SHALL BE RESPONSIBLE FOR CHECKING AND REPAIRING EROSION CONTROL SYSTEMS AFTER EACH STORM.
12. ADDITIONAL EROSION CONTROL MEASURES MAY BE REQUIRED BY LOCAL JURISDICTION'S ENGINEERING DEPARTMENT OR BUILDING OFFICIALS.
13. MEASURES SHALL BE TAKEN TO COLLECT OR CLEAN ANY ACCUMULATION OR DEPOSIT OF DIRT, MUD, SAND, ROCKS, GRAVEL OR DEBRIS ON THE SURFACE OF ANY STREET, ALLEY OR PUBLIC PLACE OR IN ANY PUBLIC STORM DRAIN SYSTEMS. THE REMOVAL OF AFORESAID SHALL BE DONE BY STREET SWEEPING OR HAND SWEEPING. WATER SHALL NOT BE USED TO WASH SEDIMENTS INTO PUBLIC OR PRIVATE DRAINAGE FACILITIES.
14. EROSION CONTROL MEASURES SHALL BE ON-SITE FROM SEPTEMBER 15TH THRU APRIL 15TH.
15. ALL EROSION CONTROL MEASURES SHALL BE INSTALLED AND MAINTAINED THROUGHOUT THE RAINY SEASON OR FROM OCTOBER 15 THROUGH APRIL 15, WHICHEVER IS GREATER.
16. PLANS SHALL BE DESIGNED TO MEET C3 REQUIREMENTS OF THE MUNICIPAL STORMWATER REGIONAL PERMIT("MRP") NPDES PERMIT CAS 612008.
17. THE CONTRACTOR TO NPDES (NATIONAL POLLUTION DISCHARGE ELIMINATION SYSTEM) BEST MANAGEMENT PRACTICES (BMP) FOR SEDIMENTATION PREVENTION AND EROSION CONTROL TO PREVENT DELETERIOUS MATERIALS OR POLLUTANTS FROM ENTERING THE TOWN OR COUNTY STORM DRAIN SYSTEMS.
18. THE CONTRACTOR MUST INSTALL ALL EROSION AND SEDIMENT CONTROL MEASURES PRIOR TO THE INCEPTION OF ANY WORK ONSITE AND MAINTAIN THE MEASURES UNTIL THE COMPLETION OF ALL LANDSCAPING.
19. THE CONTRACTOR SHALL MAINTAIN ADJACENT STREETS IN A NEAT, CLEAN DUST FREE AND SANITARY CONDITION AT ALL TIMES AND TO THE SATISFACTION OF THE TOWN INSPECTOR. THE ADJACENT STREET SHALL AT ALL TIMES BE KEPT CLEAN OF DEBRIS, WITH DUST AND OTHER NUISANCE BEING CONTROLLED AT ALL TIMES. THE CONTRACTOR BE RESPONSIBLE FOR ANY CLEAN UP ON ADJACENT STREETS AFFECTED BY THE BY THEIR CONSTRUCTION, METHOD OF STREET CLEANING SHALL BE BY DRY SWEEPING OF ALL PAVED AREAS. NO STOCKPILING OF BUILDING MATERIALS WITHIN THE TOWN RIGHT-OF-WAY.
20. SEDIMENTS AND OTHER MATERIALS SHALL NOT BE TRACKED FROM THE SITE BY VEHICLE TRAFFIC. THE CONTRACTOR SHALL INSTALL A STABILIZED CONSTRUCTION ENTRANCE PRIOR TO THE INSPECTION OF ANY WORK ONSITE AND MAINTAIN IT FOR THE DURATION OF THE CONSTRUCTION PROCESS SO AS TO NOT INHIBIT SEDIMENTS FROM BEING DEPOSITED INTO THE PUBLIC RIGHT-OF-WAY UNTIL THE COMPLETION OF ALL LANDSCAPING.
21. THE CONTRACTOR SHALL PROTECT DOWN SLOPE DRAINAGE COURSES, STREAMS AND STORM DRAINS WITH ROCK FILLED SAND BAGS, TEMPORARY SWALES, SILT FENCES, AND EARTH PERMS IN CONJUNCTION OF ALL LANDSCAPING.
22. STOCKPILED MATERIALS SHALL BE COVERED WITH VISQUEEN OR A TARPULIN UNTIL THE MATERIAL IS REMOVED FROM THE SITE. ANY REMAINING BARE SOIL THAT EXISTS AFTER THE STOCKPILE HAS BEEN REMOVED SHALL BE COVERED UNTIL A NATURAL GROUND COVER IS ESTABLISHED OR IT IS SEEDED OR PLANTED TO PROVIDE GROUND COVER PRIOR TO THE FALL RAINY SEASON.
23. EXCESS OR WASTE CONCRETE MUST NOT BE WASHED INTO THE PUBLIC RIGHT-OF-WAY OR ANY OTHER DRAINAGE SYSTEM. PROVISIONS SHALL BE MADE TO RETAIN CONCRETE WASTES ON SITE UNTIL THEY CAN BE DISPOSED OF AS SOLID WASTE.
24. TRASH AND CONSTRUCTION RELATED SOLID WASTES MUST BE DEPOSITED INTO A COVERED RECEPTACLE TO PREVENT CONTAMINATION AND DISPERSAL BY WIND FUELS, OILS, SOLVENTS AND OTHER TOXIC MATERIALS MUST BE STORED IN ACCORDANCE WITH THEIR LISTING AND ARE NOT TO CONTAMINATE THE SOIL AND SURFACE WATERS. ALL APPROVED STORAGE CONTAINERS ARE TO BE PROTECTED FROM THE WEATHER. SPILLS MUST BE CLEANED UP IMMEDIATELY AND DISPOSED OF IN A PROPER MANNER. SPILLS MUST NOT BE WASHED INTO THE DRAINAGE SYSTEM.
25. DUST CONTROL SHALL BE DONE BY WATERING AND AS OFTEN AS REQUIRED BY THE TOWN INSPECTOR.
26. SILT FENCE(S) AND/OR FIBER ROLL(S) SHALL BE INSTALLED PRIOR TO SEPTEMBER 15TH AND SHALL REMAIN IN PLACE UNTIL THE LANDSCAPING GROUND COVER IS INSTALLED. CONTRACTOR SHALL CONTINUOUSLY MONITOR THESE MEASURES, FOLLOWING AND DURING ALL RAIN EVENTS, TO PUBLIC OWNED FACILITIES.



EROSION CONTROL MEASURES:

1. THE FACILITIES SHOWN ON THIS PLAN ARE DESIGNED TO CONTROL EROSION AND SEDIMENT DURING THE RAINY SEASON, OCTOBER 15TH TO APRIL 15. EROSION CONTROL FACILITIES SHALL BE IN PLACE PRIOR TO OCTOBER 15TH OF ANY YEAR. GRADING OPERATIONS DURING THE RAINY SEASON WHICH LEAVE DENUDED SLOPES SHALL BE PROTECTED WITH EROSION CONTROL MEASURES IMMEDIATELY FOLLOWING GRADING ON THE SLOPES.
2. SITE CONDITIONS AT TIME OF PLACEMENT OF EROSION CONTROL MEASURES WILL VARY. APPROPRIATE ACTION INCLUDING TEMPORARY SWALES, INLETS, HYDROSEEDING, STRAW BALES, ROCK SACKS, ETC. SHALL BE TAKEN TO PREVENT EROSION AND SEDIMENTATION FROM LEAVING SITE. EROSION CONTROL MEASURES SHALL BE ADJUSTED AS THE CONDITIONS CHANGE AND THE NEED OF CONSTRUCTION SHIFT.
3. CONSTRUCTION ENTRANCES SHALL BE INSTALLED PRIOR TO COMMENCEMENT OF GRADING. ALL CONSTRUCTION TRAFFIC ENTERING ONTO THE PAVED ROADS MUST CROSS THE STABILIZED CONSTRUCTION ENTRANCES. CONTRACTOR SHALL MAINTAIN STABILIZED ENTRANCE AT EACH VEHICLE ACCESS POINT TO EXISTING PAVED STREETS. ANY MUD OR DEBRIS TRACKED ONTO PUBLIC STREETS SHALL BE REMOVED DAILY AND AS REQUIRED BY THE GOVERNING AGENCY.
4. ALL EXPOSED SLOPES THAT ARE NOT VEGETATED SHALL BE HYDROSEEDING. IF HYDROSEEDING IS NOT USED OR IS NOT EFFECTIVE BY OCTOBER 15, THEN OTHER IMMEDIATE METHODS SHALL BE IMPLEMENTED, SUCH AS EROSION CONTROL BLANKETS, OR A THREE-STEP APPLICATION OF 1) SEED, MULCH, FERTILIZER 2) BLOWN STRAW 3) TACKIFIER AND MULCH. HYDROSEEDING SHALL BE IN ACCORDANCE WITH THE PROVISIONS OF SECTION 20" EROSION CONTROL AND HIGHWAY PLANTING" OF THE STANDARD SPECIFICATION OF THE STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION, AS LAST REVISED. REFER TO THE EROSION CONTROL SECTION OF THE GRADING SPECIFICATIONS THAT ARE A PART OF THIS PLAN SET FOR FURTHER INFORMATION.
5. INLET PROTECTION SHALL BE INSTALLED AT OPEN INLETS TO PREVENT SEDIMENT FROM ENTERING THE STORM DRAIN SYSTEM. INLETS NOT USED IN CONJUNCTION WITH EROSION CONTROL ARE TO BE BLOCKED TO PREVENT ENTRY OF SEDIMENT. MINIMUM INLET PROTECTION SHALL CONSIST OF A ROCK SACKS OR AS SHOWN ON THIS PLAN
6. THIS EROSION AND SEDIMENT CONTROL PLAN MAY NOT COVER ALL THE SITUATIONS THAT MAY ARISE DURING CONSTRUCTION DUE TO UNANTICIPATED FIELD CONDITIONS. VARIATIONS AND ADDITIONS MAY BE MADE TO THIS PLAN IN THE FIELD. A REPRESENTATIVE OF LEA & BRAZE ENGINEERING SHALL PERFORM A FIELD REVIEW AND MAKE RECOMMENDATIONS AS NEEDED. CONTRACTOR IS RESPONSIBLE TO NOTIFY LEA & BRAZE ENGINEERING AND THE GOVERNING AGENCY OF ANY CHANGES.
7. THE EROSION CONTROL MEASURES SHALL CONFORM TO THE LOCAL JURISDICTION'S STANDARDS AND THE APPROVAL OF THE LOCAL JURISDICTION'S ENGINEERING DEPARTMENT.
8. STRAW ROLLS SHALL BE PLACED AT THE TOE OF SLOPES AND ALONG THE DOWN SLOPE PERIMETER OF THE PROJECT. THEY SHALL BE PLACED AT 25 FOOT INTERVALS ON GRADED SLOPES. PLACEMENT SHALL RUN WITH THE CONTOURS AND ROLLS SHALL BE TIGHTLY END BUTTED. CONTRACTOR SHALL REFER TO MANUFACTURES SPECIFICATIONS FOR PLACEMENT AND INSTALLATION INSTRUCTIONS.

EROSION CONTROL LEGEND

	GRAVEL BAG		CONSTRUCTION ENTRANCE
	INLET PROTECTION		TREE PROTECTION
	STRAW ROLL		
	SILT FENCE		
	CONCRETE WASHOUT		

NOTE:
SEAL ALL OTHER INLETS NOT INTENDED TO ACCEPT STORM WATER AND DIRECT FLOWS TEMPORARILY TO FUNCTIONAL SEDIMENTATION BASIN INLETS. -TYP



LEA & BRAZE ENGINEERING, INC.
CIVIL ENGINEERS • LAND SURVEYORS
BAY AREA REGION
2495 INDUSTRIAL PKWY WEST
EMERYVILLE, CA 94641
(510) 887-3398
(510) 887-3019
WWW.LEABRAZE.COM

4115 EL CAMINO REAL
PALO ALTO, CALIFORNIA
SANTA CLARA COUNTY
APN: 132-46-100

EROSION CONTROL
PLAN

NO.	REVISIONS	BY
1	PLAN CHECK 11-22-17	TT
2	SITE REVISIONS 02-02-18	TT
3	SITE REVISIONS 04-20-18	TT
4	SITE REVISIONS 05-16-18	TT
5	SITE REVISIONS 10-05-18	TT
6	SITE REVISIONS 10-30-18	TT

JOB NO: 2161066
DATE: 08-01-17
SCALE: AS NOTED
DESIGN BY: PC/TT
DRAWN BY: TB/WA
SHEET NO:



LEA & BRAZE ENGINEERING, INC.

CIVIL ENGINEERS • LAND SURVEYORS

BAY AREA REGION	SACRAMENTO REGION
2495 INDUSTRIAL PKWY WEST	3017 DOUGLAS BLVD, # 300
HAYWARD, CALIFORNIA 94545	ROSELVILLE, CA 95861
(P) (510) 887-4086	(P) (916) 966-1338
(F) (510) 887-3019	(F) (916) 797-7363

4115 EL CAMINO REAL
PALO ALTO, CALIFORNIA

SANTA CLARA COUNTY

EROSION CONTROL DETAILS

1	PLAN CHECK 11-22-17	T
2	SITE REVISIONS 02-02-18	T
3	SITE REVISIONS 04-20-18	T
4	SITE REVISIONS 05-16-18	T
5	SITE REVISIONS 10-05-18	T
6	SITE REVISIONS 10-30-18	T

JOB NO: 2161066

DATE: 08-01-

SCALE: NTS


DESIGN BY: PC/TT

DRAWN BY: TB/WA


SHEET NO:

ER-2


09 OF 10 SHEETS




1 INLET PROTECTION
ER-2 NTS



2 STREET INLET PROTECTION



3
ER-2



4 CONSTRUCTION ENTRANCE
ER-2 NTS

NOTES:

STABILIZED CONSTRUCTION SITE
ACCESS SHALL BE CONSTRUCTED
OF 3" TO 4" WASHED, FRACTURED
STONE AGGREGATE.

MATERIAL SHALL BE PLACED TO A
MINIMUM THICKNESS OF 12".
LENGTH OF ENTRANCE SHALL BE A
MINIMUM OF 50'.

WIDTH SHALL BE A MIN. OF 15' OR
GREATER IF NECESSARY TO COVER
ALL VEHICULAR INGRESS AND
EGRESS. PROVIDE AMPLE TURNING
RADI.

THE ENTRANCE SHALL BE KEPT IN GOOD CONDITION BY OCCASIONAL TOP DRESSING WITH MATERIAL AS SPECIFIED IN ABOVE NOTE.

ACCESSES SHALL BE INSPECTED WEEKLY DURING PERIODS OF HEAVY USAGE, MONTHLY DURING NORMAL USAGE, AND AFTER EACH RAINFALL, WITH MAINTENANCE PROVIDED AS NECESSARY.

PERIODIC TOP DRESSING SHALL BE
DONE AS NEEDED.

REFERENCES:


1. CALIFORNIA REGIONAL WATER QUALITY CONTROL BOARD'S FIELD MANUAL FOR EROSION AND SEDIMENTATION CONTROL
2. CALIFORNIA STORM WATER QUALITY ASSOCIATION BEST MANAGEMENT PRACTICES HANDBOOK FOR CONSTRUCTION

PERIODIC MAINTENANCE:

1. MAINTENANCE IS TO BE PERFORMED AS FOLLOWS:

- A. DAMAGES CAUSED BY SOIL EROSION OR CONSTRUCTION SHALL BE REPAIRED AT THE END OF EACH WORKING DAY.
 - B. SWALES SHALL BE INSPECTED PERIODICALLY AND MAINTAINED AS NEEDED.
 - C. SEDIMENT TRAPS, BERMS, AND SWALES ARE TO BE INSPECTED AFTER EACH STORM AND REPAIRS MADE AS NEEDED.
 - D. SEDIMENT SHALL BE REMOVED AND SEDIMENT TRAP RESTORED TO ITS ORIGINAL DIMENSIONS WHEN SEDIMENT HAS ACCUMULATED TO A DEPTH OF 1' FOOT.
 - E. SEDIMENT REMOVED FROM TRAP SHALL BE DEPOSITED IN A SUITABLE AREA AND IN SUCH A MANNER THAT IT WILL NOT ERODE.
 - F. RILLS AND GULLIES MUST BE REPAIRED.
- GRAVEL BAG INLET PROTECTION SHALL BE CLEANED OUT WHENEVER SEDIMENT DEPTH IS ONE HALF THE HEIGHT OF ONE GRAVEL BAG.
- STRAW ROLLS SHALL BE PERIODICALLY CHECKED TO ASSURE PROPER FUNCTION AND CLEANED OUT WHENEVER THE SEDIMENT DEPTH REACHED HALF THE HEIGHT OF THE ROLL.


4. SILT FENCE SHALL BE PERIODICALLY CHECKED TO ASSURE PROPER FUNCTION AND CLEANED OUT WHENEVER THE SEDIMENT DEPTH REACHES ONE FOOT IN HEIGHT.
5. CONSTRUCTION ENTRANCE SHALL BE REGRAVELED AS NECESSARY FOLLOWING SILT/SOIL BUILDUP.
6. ANY OTHER EROSION CONTROL MEASURES SHOULD BE CHECKED AT REGULAR INTERVALS TO ASSURE PROPER FUNCTION.



NOTE:

1. STRAW ROLL INSTALLATION REQUIRES THE PLACEMENT AND SECURE STAKING OF THE ROLL IN A TRENCH, 3" TO 5" DEEP, DUG ON CONTOUR. RUNOFF MUST NOT BE ALLOWED TO RUN UNDER OR AROUND ROLL.
2. CONTRACTOR IS RESPONSIBLE FOR REGULAR MAINTENANCE AND INSPECTION. THE SILT SHALL BE CLEANED OUT WHEN IT REACHES HALF THE HEIGHT OF THE ROLL.


5 STRAW ROLLS FLAT LOT
ER-2 NTS



**NOTE:
REFER TO LANDSCAPE
ARCHITECTURAL PLANS
FOR ADDITIONAL TREE
PROTECTION INFORMATION.**

NOTE:
LOCAL JURISDICTION MIGHT HAVE
MORE STRINGENT REQUIREMENTS.
CONTRACTOR IS RESPONSIBLE FOR
COORDINATING W/ INSPECTOR TO
ENSURE PROPER PROCEDURES ARE
BEING FOLLOWED.

6 EXISTING TREE PROTECTION DETAIL
ER-2 NTS



NOTE:
PREMANUFACTURED SILT FENCE
PRODUCTS MAY BE USED IN
LIEU OF WIRE FENCE. INSTALL
PER MANUFACTURER'S
RECOMMENDATIONS AND
MAINTAIN KEYING OF FABRIC
PER THIS DETAIL.

NOTE:
IT IS ESSENTIAL THAT THE
WIRE/FABRIC BE FULLY
EMBEDDED INTO THE GROUND
SO RUN-OFF CANNOT FLOW
FREELY UNDER FENCE.

7 **SILT FENCE**
ER-2 NTS

POLLUTION PREVENTION — IT'S PART OF THE PLAN

Construction projects are required to implement year-round stormwater BMPs, as they apply to your project.

Runoff from streets and other paved areas is a major source of pollution to San Francisco Bay. Construction activities can directly affect the health of the Bay unless contractors and crews plan ahead to keep construction dirt, debris, and other pollutants out of storm drains and local creeks. Following these guidelines will ensure your compliance with City of Palo Alto Ordinance requirements.



MATERIALS & WASTE MANAGEMENT

Non-Hazardous Materials

- ☐ Berm and cover stockpiles of sand, dirt or other construction material with tarps when rain is forecast or when they are not in use.
- ☐ Use (but don't overuse) reclaimed water for dust control.
- ☐ Ensure dust control water doesn't leave site or discharge to storm drains.

Hazardous Materials

- ☐ Label all hazardous materials and hazardous wastes (such as pesticides, paints, thinners, solvents, fuel, oil, and antifreeze) in accordance with city, county, state and federal regulations.
- ☐ Store hazardous materials and wastes in water tight containers, store in appropriate secondary containment, and cover them at the end of every work day or during wet weather or when rain is forecast.
- ☐ Follow manufacturer's application instructions for hazardous materials and do not use more than necessary. Do not apply chemicals outdoors when rain is forecast within 24 hours.
- ☐ Arrange for appropriate disposal of all hazardous wastes.

Waste Management

- ☐ Cover and maintain dumpsters. Check frequently for leaks. Place dumpsters under roofs or cover with tarps or plastic sheeting secured around the outside of the dumpster. A plastic liner is recommended to prevent leaks. Never clean out a dumpster by hosing it down on the construction site.
- ☐ Place portable toilets away from storm drains. Make sure they are in good working order. Check frequently for leaks.
- ☐ Dispose of all wastes and demolition debris properly. Recycle materials and wastes that can be recycled, including solvents, water-based paints, vehicle fluids, broken asphalt and concrete, wood, and cleared vegetation.
- ☐ Dispose of liquid residues from paints, thinners, solvents, glues, and cleaning fluids as hazardous waste.
- ☐ Keep site clear of litter (e.g. lunch items, cigarette butts).
- ☐ Prevent litter from uncovered loads by covering loads that are being transported to and from site.

Construction Entrances and Perimeter

- ☐ Establish and maintain effective perimeter controls and stabilize all construction entrances and exits to sufficiently control erosion and sediment discharges from site and tracking off site.
- ☐ Sweep or vacuum any street tracking immediately and secure sediment source to prevent further tracking. Never hose down streets to clean up tracking.




EQUIPMENT MANAGEMENT & SPILL CONTROL

Maintenance and Parking

- ☐ Designate an area of the construction site, well away from streams or storm drain inlets and fitted with appropriate BMPs, for auto and equipment parking, and storage.
- ☐ Perform major maintenance, repair jobs, and vehicle and equipment washing off site.
- ☐ If refueling or vehicle maintenance must be done onsite, work in a bermed area away from storm drains and over a drip pan or drop cloths big enough to collect fluids. Recycle or dispose of fluids as hazardous waste.
- ☐ If vehicle or equipment cleaning must be done onsite, clean with water only in a bermed area that will not allow rinse water to run into gutters, streets, storm drains, or surface waters.
- ☐ Do not clean vehicle or equipment onsite using soaps, solvents, degreasers, or steam cleaning equipment, and do not use diesel oil to lubricate equipment or parts onsite.

Spill Prevention and Control

- ☐ Keep spill cleanup materials (e.g., rags, absorbents and cat litter) available at the construction site at all times.
- ☐ Maintain all vehicles and heavy equipment. Inspect frequently for and repair leaks. Use drip pans to catch leaks until repairs are made.
- ☐ Clean up leaks, drips and other spills immediately and dispose of cleanup materials properly.
- ☐ Use dry cleanup methods whenever possible (absorbent materials, cat litter and/or rags).
- ☐ Sweep up spilled dry materials immediately. Never attempt to "wash them away" with water, or bury them.
- ☐ Clean up spills on dirt areas by digging up and properly disposing of contaminated soil.
- ☐ Report any hazardous materials spills immediately! Call City of Palo Alto Communications, (650) 329-2413. If the spill poses a significant hazard to human health and safety, property or the environment, you must report it to the State Office of Emergency Services, (800) 852-7550 (24 hours).



EARTHMOVING

Grading and Earthwork

- ☐ Schedule grading and excavation work during dry weather.
- ☐ Stabilize all denuded areas, install and maintain temporary erosion controls (such as erosion control fabric or bonded fiber matrix) until vegetation is established.
- ☐ Remove existing vegetation only when absolutely necessary, plant temporary vegetation for erosion control on slopes or where construction is not immediately planned.
- ☐ Prevent sediment from migrating offsite and protect storm drain inlets, drainage courses and streams by installing and maintaining appropriate BMPs (e.g., silt fences, gravel bags, fiber rolls, temporary swales, etc.).
- ☐ Keep excavated soil on site and transfer it to dump trucks on site, not in the streets.

Contaminated Soils

- ☐ If any of the following conditions are observed, test for contamination and contact the Regional Water Quality Control Board:
 - Unusual soil conditions, discoloration, or odor.
 - Abandoned underground tanks.
 - Abandoned wells.
 - Buried barrels, debris, or trash.
- ☐ If the above conditions are observed, document any signs of potential contamination and clearly mark them so they are not disturbed by construction activities.

Landscaping

- ☐ Protect stockpiled landscaping materials from wind and rain by storing them under tarps all year-round.
- ☐ Stack bagged material on pallets and under cover.
- ☐ Discontinue application of any erodible landscape material within 2 days before a forecast rain event or during wet weather.



CONCRETE MANAGEMENT & DEWATERING

Concrete Management

- ☐ Store both dry and wet materials under cover, protected from rainfall and runoff and away from storm drains or waterways. Store materials off the ground, on pallets. Protect dry materials from wind.
- ☐ Wash down exposed aggregate concrete only when the wash water can (1) flow onto a dirt area; (2) drain onto a bermed surface from which it can be pumped and disposed of properly; or (3) block any storm drain inlets and vacuum washwater from the gutter. If possible, sweep first.
- ☐ Wash out concrete equipment/trucks offsite or in a designated washout area, where the water will flow into a temporary waste pit, and make sure wash water does not leach into the underlying soil. (See CASQA Construction BMP Handbook for properly designed concrete washouts.)

Dewatering

- ☐ Reuse water for dust control, irrigation or another on-site purpose to the greatest extent possible.
- ☐ Be sure to obtain a Permit for Construction in the Public Street from Public Works Engineering before discharging water to a street, gutter, or storm drain. Call the Regional Water Quality Control Plant (RWQCP) at (650) 329-2598 for an inspection prior to commencing discharge. Use filtration or diversion through a basin, tank, or sediment trap as required by the approved dewatering plan. Dewatering is not permitted from October to April.
- ☐ In areas of known contamination, testing is required prior to reuse or discharge of groundwater. Consult with the City inspector to determine what testing to do and to interpret results. Contaminated groundwater must be treated or hauled off-site for proper disposal.



PAVING/ASPHALT WORK

Paving

- ☐ Avoid paving and seal coating in wet weather or when rain is forecast, to prevent materials that have not cured from contacting stormwater runoff.
- ☐ Cover storm drain inlets and manholes when applying seal coat, slurry seal, fog seal, or similar materials.
- ☐ Collect and recycle or appropriately dispose of excess abrasive gravel or sand. Do NOT sweep or wash it into gutters.

Sawcutting & Asphalt/Concrete Removal


- ☐ Protect storm drain inlets during saw cutting.
- ☐ If saw cut slurry enters a catch basin, clean it up immediately.
- ☐ Shovel or vacuum saw cut slurry deposits and remove from the site. When making saw cuts, use as little water as possible. Sweep up, and properly dispose of all residues.



PAINTING & PAINT REMOVAL

Painting Cleanup and Removal

- ☐ Never clean brushes or rinse paint containers into a street, gutter, storm drain, or stream.
- ☐ For water-based paints, paint out brushes to the extent possible, and rinse into a drain that goes to the sanitary sewer. Never pour paint down a storm drain.
- ☐ For oil-based paints, paint out brushes to the extent possible and clean with thinner or solvent in a proper container. Filter and reuse thinners and solvents. Dispose of excess liquids as hazardous waste.
- ☐ Sweep up or collect paint chips and dust from non-hazardous dry stripping and sand blasting into plastic drop cloths and dispose of as trash.
- ☐ Chemical paint stripping residue and chips and dust from marine paints or paints containing lead, mercury, or tributyltin must be disposed of as hazardous waste. Lead based paint removal requires a state certified contractor.



STORM DRAIN POLLUTERS MAY BE LIABLE FOR FINES OF UP TO \$10,000 PER DAY!

250 Hamilton Avenue
Palo Alto, CA 94301
650.329.2211
cityofpaloalto.org



LEA & BRAZE ENGINEERING, INC.
CIVIL ENGINEERS • LAND SURVEYORS
BAY AREA REGION
2495 INDUSTRIAL PKWY WEST
SACRAMENTO, CA 95834
(916) 887-3388
(916) 887-3388
(510) 887-3019
WWW.LEABRAZE.COM

**4115 EL CAMINO REAL
PALO ALTO, CALIFORNIA**
SANTA CLARA COUNTY
APN: 132-46-100

STORMWATER POLLUTION PREVENTION PLAN

1	PLAN CHECK 11-22-17	TT
2	SITE REVISIONS 02-02-18	TT
3	SITE REVISIONS 04-20-18	TT
4	SITE REVISIONS 05-16-18	TT
5	SITE REVISIONS 10-05-18	TT
6	SITE REVISIONS 10-30-18	TT
REVISIONS		BY
JOB NO:		2161066
DATE:		08-01-17
SCALE:		NO SCALE
DESIGN BY:		PC/TT
DRAWN BY:		TB/WA
SHEET NO:		


SW-1
10 OF 10 SHEETS

City of Palo Alto
Tree Protection - It's Part of the Plan!

Make sure your crews and subs do the job right!

Fenced enclosures around trees are essential to protect them by keeping the foliage canopy and branching structure clear from contact by equipment, materials and activities, preserving roots and soil conditions in an intact and non-compacted state, and identifying the Tree Protection Zone (TPZ) in which no soil disturbance is permitted and activities are restricted, unless otherwise approved. **An approved tree protection report must be added to this sheet when project activity occurs within the TPZ of a regulated tree.**

For detailed information on Palo Alto's regulated trees and protection during development, review the **City Tree Technical Manual (TTM)** found at www.cityofpaloalto.org/trees/.



TREE DISCLOSURE STATEMENT

CITY OF PALO ALTO
 Planning Division, 250 Hamilton Avenue
 Palo Alto, CA 94301
 (650) 529-2441
<http://www.cityofpaloalto.org>

Palo Alto Municipal Code, Chapter 8.10.040, requires disclosure and protection of certain trees located on private and public property, and that they be shown on approved site plans. A completed disclosure statement must accompany all building permit applications that include exterior work, all demolition or grading permit applications, or other development activity.

PROPERTY ADDRESS: _____

Are there Regulated¹ trees on or adjacent to the property? **YES** **NO** (If no, proceed to Section 4)

[Sections 1-3 MUST be completed by the applicant. Please circle and/or check where applicable.]

1. Where are the trees? Check those that apply. **(Plans must be submitted showing over 4" diameter trees)**

☐ On the property
☐ On adjacent property overhanging the project site
☐ On the City planter strip or right-of-way easement within 30' of property line. (Street Trees)^{**}

^{**}Street trees¹ require special verification by a **licensed arborist**, per the attached instructions. Prior to receiving any permit, you must provide an authorized Street Tree Protection Verification form by calling Public Works Operations at 493-5953 or by completing of required type II, II or III fencing (see attached Detail 0605).

2. Are there any Protected¹ or Designated¹ Trees? **YES** (Check where applicable) **NO**

☐ Protected Tree (s)
☐ Designated Tree (s)
☐ On or overhanging the property

3. Is there activity or grading within the drip-line? (radius 10 times the trunk diameter) of these trees? **YES** **NO**

If Yes, a **Tree Preservation Report** must be prepared by an ISA certified arborist and submitted for staff review (see TTM², page 6.25). Attach this report to Sheet 1-1, Tree Protection, of Part of the Plan³, per Site Plan Requirements.

4. Are the Site Plan Requirements⁴ completed? **YES** **NO**

¹Protection of Regulated trees during development occurs the following: (1) Plans must show the measured trunk diameter (inch) canopy drip-line, (2) Plans must denote, as a bold dashed line, a fenced enclosure area out to the drip-line, per Sheet 1-1 and Detail 0605 - <http://www.cityofpaloalto.org/planning/permits.htm> (See also TTM, Section 2.15 for area to be fenced)

I, the undersigned, agree to the conditions of this disclosure. I understand that knowingly or negligently providing false or misleading information in response to this disclosure requirement constitutes a violation of the Palo Alto Municipal Code Section 8.10.040, which can lead to criminal and/or civil legal action.

Signature: _____ Print: _____ Date: _____
 (Prop, Owner or Agent)

FOR STAFF USE:

Protective Fencing
 Sections 5-6 must be completed by staff for the issuance of any development permit (demolition, grading or building permit).

5. Protected Trees. The specified tree fencing is in place. A written statement is attached verifying that protective fencing is correctly in place around protected and/or designated trees. **YES** **NO**
(N/A if there are no protected trees, check here ☐)

6. Street Trees. A signed Public Works Street Tree Protection Verification form is attached. **YES** **NO**
(N/A if there are no Street trees, check here ☐)

¹Regulated Trees are a street tree – over 6" caliper public property; 3" Protected tree – Open Life (Cottonwood, Valley Oak) which are 11.5" in diameter; 4" Large Redwoods which are 18" in diameter or larger; 5" non "regulated" 5" which are not public and private; and Heritage trees are trees designated by City Council; and c) Designated tree – commercial or non-residential property trees which are part of an approved landscape plan.

Palo Alto Tree Technical Manual (TTM) contains instructions for all registrations on this form, available at <http://www.cityofpaloalto.org/planning/community/tree-technicalmanual.html>

S:\Plan\Public\Info Tree Protection\Info Tree Disclosure Statement

Revised 11/06

City of Palo Alto

250 Hamilton Avenue, Palo Alto, CA 94301

[Home](#) > [Planning & Community Environment](#)

Home

[City-owned Trees](#)

[Privately-owned Trees](#)

[About the Tree Ordinance](#)

[TRE 8.10](#)

[Heritage Trees](#)

[Forms](#)

[Tree Technical Manual](#)

[FAQs](#)

[Contact Us](#)

[Resources](#)

Tree Technical Manual

To purchase the Tree Technical Manual

June, 2001 First Edition

View by section:

- [Table of Contents \(PDF, 67KB\)](#)
- [Intent and Purpose \(PDF, 1.65MB\)](#)
- [Introduction – Use of Manual \(PDF, 1.65MB\)](#)
- [Section 1.0 – Definitions \(PDF, 94KB\)](#)
- [Section 2.0 – Protection of Trees During Construction \(PDF, 256KB\)](#)
- [Section 3.0 – Removal, Replacement & Planting of Trees \(PDF, 117KB\)](#)
- [Section 4.0 – Hazardous Trees \(PDF, 105KB\)](#)
- [Section 5.0 – Tree Maintenance Guidelines \(PDF, 110KB\)](#)
- [Tree Reports \(PDF, 84KB\)](#)

View ALL sections:

- [Tree Technical Manual - Full \(PDF, 1.84MB\)](#)

APPENDICES

- A. Palo Alto Municipal Code Chapter 8.10, Tree Preservation & Management Regulations
- B. Tree City - USA
- C. ISA Hazard Evaluation Form
- D. List of Inherent Failure Patterns for Selected Species (Reference source)
- E. ISA Tree Pruning Guidelines (pdf - 1.83MB)
- F. Tree Care Safety Standards, ANSI Z39.1-1994 (Reference source)
- G. Pruning Performance Standards, ANSI A300-1995 (Reference source) H: Tree Planting Details, Diagram 504 & 505
- I. Tree Disclosure Statement
- J. Palo Alto Standard Tree Protection Instructions

For written specifications associated with illustrations below, see Public Works Specifications Section 21.01. Detailed specifications are found in the Palo Alto Tree Technical Manual (TTM3) (www.cityofpaloalto.org/tree3/).

Tree Protection Zone (TPZ) shown in gray (see [www.cityofpaloalto.org/tree3/](#) defines the function of the TPZ, which is in green).

- Restricted activity area – see Tree Technical Manual Sec 2.15(FP).
- Restricted treeing area – see Tree Technical Manual Sec 2.20(C), any proposed trench or form work within TPZ of a protected tree requires approval from Public Works Operations. Call 650.496.5933.

Type II Tree Protection

Type I Tree Protection

For all Ordinance Protected not Designated Street Trees, the TPZ shall be the same as the tree protection area (TPZ) as set forth in the TTM3 project information as displayed on the plan.

Note: Ordinance Protected & Designated Trees: Issuance of a permit requires applicant's project arborist written verification. Type I is installed according to the plans and Tree Preservation Report.

Note: Street Trees: Issuance of a permit requires Public Works Operations inspection and signed approval on the Street Tree Verification (STV) form provided.

Type III Tree Protection

(to be used only with approval of Public Works Operations)

Tree fencing is required and shall be erected before demolition, grading or construction begins.

Rev	By	Date	Approved by:
0	12/18/18	12/14/19	Dave Dockter
1	01/11/20	08/30/24	PE No. _____
2	01/11/20	08/19/26	Dwg No. _____

Tree Protection

During Construction

605

City of Palo Alto Standard

PALO ALTO STREET TREE PROTECTION INSTRUCTIONS (SECTION 3)

APPENDIX J

31-1 General

- a. **Tree protection has three primary functions:** 1) to keep tree foliage and canopy structure clear from contact by equipment, materials and activities; 2) to preserve roots and soil conditions in as intact and uncompromised state and 3) to identify the Tree Protection Zone (TPZ) in which no soil disturbance is permitted and activities are restricted, unless otherwise approved.
- b. **The Tree Protection Zone (TPZ):** a restricted area around the base of the tree with a radius of 1/3 times the diameter of the tree trunk at one foot, whichever is greater, determined by fencing.

31-2 Reference Documents

- a. **Detail 065** Illustrates of situations described below.
- b. **Tree Technical Manual (TTM) Forms** (<http://www.cityofpaloalto.org/development/perm/reqs>)
- c. **Tree Trimming Regulations (TTR)** (<http://www.cityofpaloalto.org/development/perm/reqs>)
- d. **Arborist Reporting Protocol (TRP)** (<http://www.cityofpaloalto.org/development/perm/reqs>)
- e. **Site Plan Requirements (TPR)** (<http://www.cityofpaloalto.org/development/perm/reqs>)
- f. **Tree Database Statement (TDS)** (<http://www.cityofpaloalto.org/development/perm/reqs>)
- g. **Street Tree Inventory (STI) Form** (<http://www.cityofpaloalto.org/development/perm/reqs>)

31-3 Erection

- a. **Tree Type I Tree Protection:** The faces shall enclose the Tree TPZ of the tree(s) to be protected throughout the life of the construction project. The faces shall be constructed of 2x4s (or larger) and be braced or coveyed so that they will not be demolished, then the posts may be supported by an appropriate grade level concrete base, if approved by Public Works Operations.
- b. **Tree II Tree Protection:** For trees situated within a planting strip, only the planting curb and yard side of the TPZ shall be enclosed with the required chain link protective fencing in order to keep the sidewalk and street open for public use.
- c. **Tree III Tree Protection:** To be used only with approval of Public Works Operations. Trees situated in a tree well or sidewalk planting pit, shall be protected with 2x4s of concrete facing driven from the ground to the first branch and overlaid with 2-inch black plastic. The plastic shall be secured with 1/2" x 4" black 1" x 4" aluminum clips into the bark. After final installation of the plastic facing, caution is to be used to avoid damaging any branches. Minor limbs may also require plastic facing as dictated by the City Arborist.
- d. **Sign, type and area to be marked:** All trees to be protected shall be marked with 10" x 10" high chain link fence liners. Fences are to be mounted on 10-inch diameter galvanized iron posts, driven into the ground to extend to a least 2 feet or to a more than 18 inches below ground. Fencing shall extend to the entire facing, unless specifically approved on the project.
- e. **Warning signs:** A warning sign shall be weather proof and prominently displayed on each face at 20-foot intervals. The sign shall be minimum 18" x 24" in size. It shall be white with black and red lettering. **WARNING - Tree Protection Zone** - This fence shall not be removed or subjected to a face according to PAMC Section 8.10.11(b).
- f. **Duration:** Tree fencing shall be erected before demolition, grading or construction begins and remain in place until final impact of the project, except: for work specifically allowed in the TPZ. Work on soil disturbance in the TPZ requires approval by the project arbors or City Arborist (in the case of work around Street Trees). Also requires notice the public right-of-way requires a Street Tree Permit from Public Works.


31-4 During construction


1. All neighbors' trees, other than the project site itself, shall be protected from impacts of any kind.
2. The applicant shall be responsible for the repair or replacement plus penalty of any publicly owned trees that are damaged during the course of construction, pursuant to Proposition 8.04.07 of the Palo Alto Municipal Code.
3. The following tree preservation measures apply to all trees to be retained:
 - a. No storage of material, spoil, vehicles or equipment shall be permitted within the TPZ.
 - b. The ground under and around the tree canopy area shall not be disturbed.
 - c. Trees to be retained shall be irrigated, aerated and mulched in accordance with necessary to ensure survival.

END OF SECTION

City of Palo Alto 2007 - Standard Drawings and Specifications
Street Tree Verification of Protection, PWF, Section 5A

Revised 08/06

Table 2-2 Palo Alto Tree Technical Manual	
CONTRACTOR & ARBORIST INSPECTION SCHEDULE	
	
Reference: the Palo Alto Tree Technical Manual is available at www.cityofpaloalto.org/www/citrans/	
ALL CHECKED ITEMS APPLY TO THIS PROJECT:	
1. <input checked="" type="checkbox"/>	Inspection of Protective Tree Fencing. For Public Trees, the Street Tree Verification Form shall be signed by the City Arborist. For Protected Trees, the project site arborist shall provide an initial Monthly Tree Activity Report form with a photograph verifying that he has conducted a field inspection of the trees and that the correct type of protective fencing is in place around the designated tree protection zone (TPZ) prior to issuance of a demolition, grading, or building permit. (See TTM, Verification of Tree Protection, Section 1.19).
2. <input checked="" type="checkbox"/>	Pre-Construction Meeting. Prior to commencement of construction, the applicant or contractor shall conduct a pre-construction meeting to discuss tree protection with the job site superintendent, grading operator, project arborist, City Arborist, and, if a city-managed irrigation system is involved, the Parks Manager. (Contract 650-486-6962).
3. <input checked="" type="checkbox"/>	Inspection of Rough Grading or Trenching. Contractor shall ensure the project site arborist performs an inspection during the course of rough grading or trenching adjacent to or within the TPZ to ensure trees will not be injured by compaction, cut, or fill, drainage and trenching, and if required, impact irrigation systems, tree wells, drains and special paving. The contractor shall provide the project arborist with not less than 24 hours advance notice of such activity.
4. <input checked="" type="checkbox"/>	Monthly Tree Activity Report Inspections. The project site arborist shall perform a maximum monthly tree activity inspection to monitor and advise on conditions, tree health and retention or, immediately if there are any variations to the approved plans or protection measures. The Tree Technical Manual Monthly Tree Activity Report form shall be used and sent to the Planning Department. Landscape review staff not later than 14 days after issuance of building permit date. Faxing 650-329-2154. (See TTM, Monthly Tree Activity Inspection Report, Addendum 11 (see also #2 below)).
5. <input checked="" type="checkbox"/>	Special advisory within the Tree Protection Zone. Work in the TPZ area (see also #2 below) requires the direct on-site supervision of the project arborist (see TTM, Trenching, Excavation & Equipment, Section 2.10 C).
6. <input type="checkbox"/>	Landscape Architect Inspection. For discretionary development projects, prior to temporary or final occupancy the applicant or contractor shall arrange for the Landscape Architect to perform an on site inspection of all plant stock, quality of the materials and planting (see TTM, Planting Quality, Section 5.00.1 A) and that the irrigation is functioning consistent with the approved construction plans. The Planning Dept. landscape review staff shall be in receipt of written verification of Landscape Architect approval prior to scheduling the final inspection, unless otherwise approved.
7. <input type="checkbox"/>	List Other (please describe as called out in the site Tree Preservation Report, Sheet T-1, T-2, etc.)
	*
	*

	City of Palo Alto Tree Department Public Works Operations PO Box 12250 Palo Alto, CA 94303 650-446-0963 FAX: 650-432-9286 treeprotection@cityofpaloalto.org	<h2 style="text-align: center;">Verification of Street Tree Protection</h2>
<i>Applicant Instructions: Complete upper portion of this form. Mail or FAX this form along with signed Tree Disclosure Statement to Public Works Dept. Public Works Tree Staff will inspect and notify applicant.</i>		
APPLICATION DATE:		
ADDRESS/LOCATION OF STREET TREES TO BE PROTECTED:		
APPLICANT'S NAME:		
APPLICANT'S ADDRESS:		
APPLICANT'S TELEPHONE & FAX NUMBERS:		
<i>This form to be filled out by City Tree Staff</i>		
1. The Street Trees at the above address(es) are adequately protected. The type of protection used is:	YES <input type="checkbox"/> NO* <input type="checkbox"/> * If NO, go to #2 below	
Inspected by:		
Date of Inspection:		
2. The Street Trees at the above address are NOT adequately protected. The following modifications are required: Indicate how the required modifications were communicated to the applicant:	<hr/> <hr/> <hr/> <hr/> <hr/> <hr/> <hr/> <hr/> <hr/> <hr/>	
Subsequent Inspection		
Street trees at above address were found to be adequately protected:	YES <input type="checkbox"/> NO* <input type="checkbox"/>	
* If NO, indicate in "Notes" below the disposition of case.		
Inspected by:		
Date of Inspection:		
Notes: List City street trees by species, size, condition and type of tree protection installed. Also note if pictures were taken. Use back of sheet if necessary.		
Return approved sheet to Applicant for demolition or building permit issuance. SPW\30PE\TreeDisc\BkTheProtect		

6/17/05

Arborist Firm Data Here

City of Palo Alto Tree Technical Manual

ADDENDUM 11

email:
RCA/USA Certified Arborist #10-600
Contract Cell #

Monthly Tree Activity Report- Construction Site

Inspection Date: _____	Site address: Palo Alto, CA	Contractor- Main Site Contact Information	#1: Job site superintendent Company: Email: Job site Office: Cell: Mail:
Inspection # _____		Also present:	* _____ * _____ * _____
Distribution:	1. City of Palo Alto 2. Others	Attn: Dave Dockter	dave.dockter@cityofpaloalto.org 650-329-2440

Provide the requested minimum information with each report, customize as necessary. To be completed by project site arborist. Send monthly to city arborist at above address until project completion. Use additional sheets as needed.

1. **Assignment Activity (Demolition/grading/sewer/trenching/foundation/list relevant visits)**
 - a. Pre construction meeting requirement with sub-contractor
 - b. Inspect to verify that tree protection measures are in place
 - c. Determine if field adjustments, watering or plan revisions may be needed
2. **Field Observations (general site-wide and visit by individual tree number)**
 - a. Tree Protection Fences (TPF) are ...
 - b. Trenching has/will occur ...
3. **Action Items (list site-wide, by tree number and date to be satisfied) and Date Due**
 - a. Tree Protection Fence (TPF) needs adjusting (tree # x, x, x)
 - b. Root zone buffer material (wood chips) can be installed next
 - c. Schedule sewer trench, foundation dig with ...
4. **Photographs (use often)**
5. **Tree Location Map (mandatory 8.5 x 11 sheet)**
6. **Recommendations, notes or monitor items for project staff/schedule**
 -
7. **Past visits (list carry-over items satisfied/visit outstanding)**
 -

Respectfully submitted,

Project site arborist

Consultant contact information (Include email, cell#, and mailing)

Cc:

<p align="center">---WARNING---</p> <p align="center">Tree Protection Zone</p> <p>This fencing shall not be removed without City Arborist approval (650-496-5953)</p> <p align="center">Removal without permission is subject to a \$500 fine per day*</p> <p align="center">*Palo Alto Municipal Code Section 8.10.110</p> <p>City of Palo Alto Tree Protection Instructions are located at http://www.city.palo-alto.ca.us/trees/technical_manual.html</p>	
<p>SPECIAL INSPECTIONS</p> <p>PAMC & 10 PROTECTED TREES, CONTRACTOR SHALL ENSURE PROJECT SITE ARBORIST IS PERFORMING REQUIRED TREE INSPECTION AND SITE MONITORING. PROVIDE WRITTEN MONTHLY TREE ACTIVITY REPORTS TO THE PLANNING DEPARTMENT LANDSCAPE REVIEW STAFF BEGINNING 14 DAYS AFTER BUILDING PERMIT ISSUANCE.</p> <p>BUILDING PERMIT DATE: _____</p> <p>DATE OF 1ST TREE ACTIVITY REPORT: _____</p> <p>CITY STAFF: _____</p>	<p>PLANNING DEPARTMENT</p> <p align="center">TREE PROTECTION INSPECTIONS MANDATORY</p> <p>REPORTING DETAILS OF THE MONTHLY TREE ACTIVITY REPORT SHALL CONFORM TO SHEET T-1 FORMAT. VERIFY THAT ALL TREE PROTECTION MEASURES ARE IMPLEMENTED AND WILL INCLUDE ALL CONTRACTOR ACTIVITY, SCHEDULED OR UNSCHEDULED, WITHIN A TREE PROTECTION ROOT ZONE. NON-COMPLIANCE IS SUBJECT TO VIOLATION OF PAMC & 10.080. REFERENCE: PALO ALTO TREE TECHNICAL MANUAL, SECTION 2.00 AND ADDENDUM 11.</p>

Apply Tree Protection Report on sheet(s) T-2

Use additional "T" sheets as needed

Project 4115 EL CAMINO REAL
Data PALO ALTO, CALIFORNIA



All other tree-related reports shall be added to the space provided on this sheet (adding as needed)
 Include this sheet(s) on Project Sheet Index or Legend Page.
 A copy of T-1 can be downloaded at
<http://www.cityofpaloalto.org/civica/filebank/blobdload.asp?BlobID=6460>

Special Tree Protection Instruction Sheet


City of Palo Alto



City of Palo Alto Tree Protection - It's Part of the Plan!

Make sure your crews and subs do the job right!

Fenced enclosures around trees are essential to protect them by keeping the foliage canopy and branching structure clear from contact by equipment, materials and activities, preserving roots and soil conditions in an intact and non-compacted state, and identifying the Tree Protection Zone (TPZ) in which no soil disturbance is permitted and activities are restricted, unless otherwise approved. **An approved tree protection report must be added to this sheet when project activity occurs within the TPZ of a regulated tree.**
For detailed information on Palo Alto's regulated trees and protection during development, review the **City Tree Technical Manual (TTM)** found at www.cityofpaloalto.org/trees/.



Project 4115 EL CAMINO REAL
PALO ALTO, CALIFORNIA
Data

T-2




All other tree-related reports shall be added to the space provided on this sheet (adding as needed).
Include this sheet(s) on Project Sheet Index or Legend Page.
A copy of T-1 can be downloaded at
<http://www.cityofpaloalto.org/civica/filebank/blobload.asp?BlobID=6460>

Special Tree Protection Instruction Sheet
City of Palo Alto



T-2

AMERICAN
DRILLING



FLATWORK KEYNOTES TO
FINISHED GRADES AT BUILDING PERIMETER SHALL BE SLOPED AT A MINIMUM OF 5% FOR THE FIRST 10' AWAY FROM THE BUILDING PER CBC 1804.3 OR TO AN APPROVED DRAINAGE SWALE OR STRUCTURE. GRADES SHALL CONTINUE TO SLOPE TOWARDS POSITIVE DRAINAGE AND A POSITIVE OUTFALL. MAINTAIN 8" CLEARANCE BETWEEN FINISH EARTHEN GRADE AND BOTTOM OF MUD SILL AT ALL TIMES PER CBC 2304.11.2 UNLESS STRUCTURAL DETAILING ALLOWS LESS. REFER TO STRUCTURAL PLANS FOR FOUNDATION DESIGN AND DETAILS.

PROVIDE 2% (1% MIN.) SLOPE ACROSS FLAT WORK AND/OR PAVING PER CBC 2304.11.2. SLOPE TOWARDS POSITIVE DRAINAGE AS SHOWN ON PLAN.

(N) CONCRETE DRIVEWAY. SEE DETAIL X SHEET X.

STORM DRAIN KEYNOTES TO
INSTALL (N) ON-SITE STORM DRAIN SYSTEM. USE MINIMUM 6" PVC (SDR 35) OR HDPE (ADS N-12 W/ SMOOTH INTERIOR WALLS). MAINTAIN 24" MINIMUM COVER AND SLOPED AT 1% MINIMUM AT ALL TIMES UNLESS OTHERWISE NOTED. PROVIDE CLEAN OUT TO GRADE AT MAJOR CHANGES IN DIRECTION. AVOID USING 90° BENDS AND INSTEAD USE (2) 45° BENDS AND WYE CONNECTIONS.

UTILITIES KEYNOTES TO
INSTALL (N) SANITARY SEWER LATERALS. USE 6" HDPE (SDR-17) SLOPED AT 2% MINIMUM. CONNECT TO (E) SEWER MAIN AS SHOWN. PROVIDE CLEANOUT TO GRADE AT BUILDING AND BEHIND PROPERTY LINE AND AT MAJOR CHANGES IN DIRECTION AS SHOWN. REUSE (E) LATERAL IF POSSIBLE. CONNECT PER CITY STANDARDS.

CONNECT (N) FIRE PROTECTION SERVICE PER CITY STANDARDS.

CONNECT (N) WATER SERVICE PER CITY STANDARDS.

CONNECT (N) LANDSCAPE SERVICE PER CITY STANDARDS.

INSTALL (N) JOINT TRENCH FOR SERVICES INCLUDING GAS, ELECTRIC, CATV & TELEPHONE FROM NEAREST POINT OF CONNECTION. DESIGN BY OTHERS.

INSTALL (N) GAS SERVICE PER CITY STANDARDS. DESIGN BY OTHERS.

DEMOLITION KEYNOTES TO
DEMOLISH (E) IMPROVEMENTS AS NECESSARY TO ACCOMMODATE (N) CONSTRUCTION. NO DEMOLITION SHALL COMMENCE WITHOUT REQUIRED DEMOLITION PERMITS.

REMOVE (E) TREE. CONTRACTOR SHALL OBTAIN THE PROPER TREE REMOVAL PERMITS AS REQUIRED.

PROVIDE TREE PROTECTION AROUND TREES TO REMAIN. SEE DETAIL X ON SHEET C-X.



LEA & BRAZE ENGINEERING, INC.
CIVIL ENGINEERS • LAND SURVEYORS
BAY AREA REGION
2485 INDUSTRIAL PKWY WEST
HAYWARD, CALIFORNIA 94545
(P) (510) 887-4086
(F) (510) 887-9777
WWW.LEABRAZE.COM

4115 EL CAMINO REAL
PALO ALTO, CALIFORNIA

APN: 132-46-100

SANTA CLARA COUNTY

PRELIMINARY
SHORING PLAN

NO.	REVISIONS	BY
1	PLAN CHECK 11-22-17	TT
2	SITE REVISIONS 02-02-18	TT
3	SITE REVISIONS 04-20-18	TT
4	SITE REVISIONS 05-15-18	TT
5	SITE REVISIONS 09-28-18	TT

JOB NO: 2161066
DATE: 08-01-17
SCALE: AS SHOWN
DESIGN BY: PC/TT
DRAWN BY: TB/WA
SHEET NO:


S1

04 OF 09 SHEETS

Note

Reflectances: 80/50/20 Standard
Luminaire Mounting Height: Indicated in the
Plan Drawing
Calculation Grid Height: 2'-6" Above Finished
Floor

Luminaire illuminance values provided in this
report, whether for normal, critical, or
emergency applications, are for product
application assistance only. These values were
developed in collaboration with, and are subject
to approval by, the design professional or record
(architect/engineer/LO), and are NOT intended
for construction. Because these values are
approximate and based on limited application
information provided to 16500, Inc. at the time
of calculation, 16500, Inc. does not warrant the
installed performance of the luminaire(s) will
match that shown in this report. Please verify all
data and conditions to assure the accuracy of
the report. 16500 shall neither be responsible
nor liable for design, approval, or results of
emergency lighting under any circumstances.




THIS LIGHTING APPLICATION REQUIRES SPECIFIC LIGHTING
CONTROL DEVICES OR SYSTEMS PER CALIFORNIA TITLE 24 PART 6.
Therefore, this proposal includes:

☐ SOLUTION: This proposal includes a complete lighting and control
system that is an alternative to that specified, or as a recommendation
based on the information provided, subject to your review and approval.

☐ SUPPLEMENT: This proposal includes lighting as requested/specified,
as well as a proposed lighting control system for your review and
approval.


☒ ALERT: This proposal includes only lighting as requested/specified,
and does not include a lighting control system. The lighting control
system is to be provided by the client, and the lighting control
quote/proposal is at your request.

Manual Switch(es)
Automatic time switch (astronomical)
Occupancy Sensor(s)
Photoeye(s) (daylight sensor(s))
Demand responsive / load shedding
Controlled Receptacle(s)
Motion Sensor(s) - Outdoor



Statistics				
Description	Symbol	Avg	Max	Min
Entrance 66ft Area (50fc Min in Day)	✖	3.2 fc	4.0 fc	1.5 fc
Parking 0'-0" AFG (1.0fc Min, 10:1 Max/Min)	+	2.4 fc	4.0 fc	1.2 fc
Parking Ramp (2fc Min, 10:1 Max/Min)	+	5.0 fc	6.5 fc	4.0 fc

Luminaire Schedule						
Symbol	Label	Image	Quantity	Manufacturer	Catalog Number	Description
	F1		12	Lithonia	DSXSC LED 200 700 30K T5R MVOLT	DSX SURFACE CANOPY FIXTURE WITH 2 LIGHT ENGINES, 700mA DRIVER, 3000K LEDs, T5R OPTIC.



THIS LIGHTING APPLICATION REQUIRES SPECIFIC LIGHTING CONTROL DEVICES OR SYSTEMS PER CALIFORNIA TITLE 24 PART 6.

Therefore, this proposal includes:

☐ **SOLUTION:** This proposal includes a complete lighting and control system either as an alternate to that specified, or as a recommendation based on the information provided, subject to your review and approval.

☐ **SUPPLEMENT:** This proposal includes lighting as requested/specified; as well as a proposed lighting control system for your review and approval.

☒ **ALERT:** This proposal includes only lighting as requested/specified. However, the application likely requires compatible lighting controls to meet the following criteria. We are happy to provide a lighting control quote/proposal at your request.

Manual Switch(es)

Automatic time switch (astronomical)

Occupancy Sensor(s)

Photobase(s) / daylight sensor(s)

Demand responsive / load shedding

Controlled Receptacle(s)

Motion Sensor(s) - Outdoor

Note


References: 30% for All Exterior Buildings and Surfaces, Objects

Luminaire Mounting Height: Indicated in the Plan Drawing

Calculation Grid Height: 0'-0" Above Finished Ground

Luminaire Illuminance values provided in this report, whether for normal, critical, or emergency applications, are for product application assistance only. These values were developed in collaboration with, and are subject to approval by, the design professional of record (architect/engineer/LC), and are NOT intended for construction. Because these values are approximate and based on limited application information provided to 16500, Inc. at the time of calculation, 16500, Inc. does not warrant the installed performance of the luminaire(s) will match that shown in this report. Please verify all data and conditions to assure the accuracy of the report. 16500 shall neither be responsible nor liable for design, approval, or results of emergency lighting under any circumstances.

Statistics		Symbol	Avg	Max	Min	Max/Min	Avg/Min
Description							
Level 1 - Ground All		+	3.1 fc	13.7 fc	0.1 fc	137.0:1	31.0:1
Level 1 - Outdoor Dining		✕	3.9 fc	12.4 fc	0.4 fc	31.0:1	9.8:1
Level 1 - Walkway N (0.2 -1fc Min)		✕	3.4 fc	13.7 fc	0.4 fc	34.3:1	8.5:1
Level 1 - Walkway S (0.2 -1fc Min)		✕	3.4 fc	9.4 fc	0.3 fc	31.3:1	11.3:1
Level 1 - Walkway W (0.2 -1fc Min)		✕	3.7 fc	13.3 fc	0.1 fc	133.0:1	37.0:1



Luminaire Schedule										
Symbol	Label	Quantity	Manufacturer	Catalog Number	Description	Lamp	Filename	Lumens Per Lamp	Light Loss Factor	Wattage
<div><div></div><div></div></div>	F2	1	LIGMAN	LI-30011-T2-W30	Light Linear PT 12 Surface 35W	2X12 LED 3000K 0.4218, 0.3943 3190K Ra83	LI-30011-T2-W30.IES	1561	0.85	41
										<div><div></div><div></div></div> <div>Max: 2641cd</div>
<div><div></div><div></div></div>	F2A	2	LIGMAN	LI-30011-T3-W30	Light Linear PT 12 Surface 35W	2X12 LED 3000K 0.4218, 0.3943 3190K Ra83	LI-30011-T3-W30.IES	1597	0.85	41
										<div><div></div><div></div></div> <div>Max: 1795cd</div>
<div><div></div><div></div></div>	F2B	3	LIGMAN	LI-30011-T4-W30	Light Linear PT 12 Surface 35W	2X12 LED 3000K 0.4218, 0.3943 3190K Ra83	LI-30011-T4-W30.IES	1604	0.85	41
										<div><div></div><div></div></div> <div>Max: 1750cd</div>
<div><div></div><div></div></div>	F3	5	LIGMAN	LI-21171-T2-W30	Light Linear PT 3 street and area lighting	2X12 LED 3000K 0.4218, 0.3943 3190K Ra83	LI-21171-T2-W30.IES	1772	0.85	55.7
<div><div></div><div></div></div>	F3A	2	LIGMAN	LI-21171-T4-W30	Light Linear PT 3 Single head 50W type IV	2X12 LED 3000K 0.4218, 0.3943 3190K Ra83	LI-21171-T4-W30.IES	1812	0.85	55.7