

Project Description

Project: The Melt - Stanford

Date: August 28, 2024

Project Scope

Existing restaurant to remodel exterior of restaurant with minor electrical and structural work. No interior work. No change in zoning is proposed under this application. The proposed scope will elevate patio space to align with current brand standards.

Exterior Materials – See sheet A05.02 for more information

- Wall finishes
 - New Tech Wood: Wooden finish plank voyager series- Spanish walnut
 - 3m: Opaque all season window film - matte black
 - Peppermill: Thin brick flats general shale
 - Kawneer: Storefront finish no. 29
 - Raynor: Garage Door Black factory finish
 - Mapes Panel - Black
- Paint
 - Sherwin Williams: SW6258 - Tricorn black, Satin finish
 - Sherwin Williams: SW7019 - Gauntlet Gray, Eggshell
 - Sherwin Williams: SW 7017 - Dorian Gray, Eggshell

Exterior signage – Under separate permit. See sheets A11-01 through A11-05 for more information.

- Primary
 - Location: Above entry way on existing facade
 - Open face channel letters painted PMS 1505C with orange minleon LED G30 bulbs.
- Secondary
 - Location: Above entry way
 - Front lit channel letters with white acrylic face and open face channel letters painted orange with Amber LED illumination.
- Blade Sign
 - Location: Facade
 - Blade sign with illuminated letters painted PMS 533C
- Circle Logo Vinyl
 - Location: Entry door sidelites
 - HP white and Kumquat Orange vinyl

Lighting - See sheet A03.01 for more information.

- New sconces added to the façade.
- String lights hung for ambiance throughout the patio.
- Street lights relocated from the sidewalk to the patio to allow a more e

Sincerely,

Aliana Ramos, Architect
Project Manager
aliana@globeateliê.com
+1.614.563.4883