



CITY OF PALO ALTO  
PALO ALTO HORIZONTAL LEVEE PILOT PROJECT  
FINAL DESIGN

PALO ALTO, CALIFORNIA  
NOVEMBER 1, 2023

INDEX OF SHEETS		
PAGE NO	DWG NO	SHEET TITLE
GENERAL		
1	G01	TITLE SHEET
2	G02	LEGEND, ABBREVIATIONS, AND NOTES
3	G03	BASIS OF DESIGN
4	G04	SITE OVERVIEW
5	G05	CONSTRUCTION PHASING
6	G06	ENVIRONMENTAL PROTECTION OVERVIEW
7	G07	ENVIRONMENTAL PROTECTION
8	G08	SPECIAL TREE PROTECTION INSTRUCTION
9	G09	POLLUTION PREVENTION
10	G10	EXISTING CONDITIONS AND DEMOLITION - EMBARCADERO ROAD
11	G11	EXISTING CONDITIONS AND DEMOLITION - PUMP STATION & OUTFALL BOX
12	G12	EXISTING CONDITIONS AND DEMOLITION - LEVEE AREA
CIVIL		
13	C01	GRADING PLAN
14	C02	TYPICAL GRADING SECTIONS
15	C03	HORIZONTAL LEVEE SECTIONS
16	C04	TYPICAL TREATMENT ZONE SECTIONS
17	C05	CIVIL DETAILS
18	C06	MATERIAL PLACEMENT PLAN
19	C07	GRADING SECTIONS 1
20	C08	GRADING SECTIONS 2
21	C09	GRADING SECTIONS 3
22	C10	GRADING SECTIONS 4
23	C11	SPUR TRAILS PLAN AND PROFILE
24	C12	STORM DRAIN PLAN
25	C13	STORM DRAIN PROFILES
26	C14	STORM DRAIN DETAILS
27	C15	PUBLIC ACCESS DETAILS
28	C16	SEDIMENT AND EROSION CONTROL PLAN
MECHANICAL		
29	M01	MECHANICAL NOTES AND SYMBOLS
30	M02	OVERALL PLAN AND KEY NOTES
31	M03	PUMPING PLAN AND SECTIONS
32	M04	RENZEL MARSH PUMP BYPASS UPGRADE (ADMIN BLDG)
33	M05	EFFLUENT PIPE PLAN AND PROFILE 1
34	M06	EFFLUENT PIPE PLAN AND PROFILE 2
35	M07	CONVEYANCE PIPE PLAN AND PROFILE 3
36	M08	HORIZONTAL LEVEE SUPPLY PIPE PLAN
37	M09	MECHANICAL DETAILS 1
ELECTRICAL AND INSTRUMENTATION		
38	E01	LEGEND AND SYMBOLS
39	E02	ONE LINE DIAGRAM
40	E03	OVERALL SITE PLAN
41	E04	UV ELECTRICAL ROOM PLAN
42	E05	RENZEL MARSH PUMP CONTROL DIAGRAM
43	P01	SYMBOLS AND LEGEND
44	P02	HORIZONTAL LEVEE FEED
LANDSCAPE		
45	L01	SEEDING PLAN
46	L01	PLANTING & SEEDING PLAN
47	L02	PLANTING & SEEDING SCHEDULES
48	L03	PLANTING DETAILS
48	L04	SEEDING PLAN & OTHERS
49	L05	SEDIMENT & EROSION CONTROL PLAN BY OTHERS



LOCATION MAP  
CITY OF PALO ALTO













VICINITY MAP






















NTS










<table><tr><td>DESIGNED</td><td>MRL</td></tr><tr><td>DRAWN</td><td>DPH/AGHC</td></tr><tr><td>CHECKED</td><td>MRL</td></tr></table>				DESIGNED	MRL	DRAWN	DPH/AGHC	CHECKED	MRL			 575 MARKET STREET SUITE 3700 SAN FRANCISCO, CA 94105 T 415.896.5900 WWW.ESASOC.COM				CITY OF PALO ALTO PALO ALTO HORIZONTAL LEVEE PILOT PROJECT		VERIFY SCALES BAR IS ONE INCH ON ORIGINAL DRAWING 0 1" IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY		DATE NOVEMBER 3, 2023 DRAWING NO. G01 SHEET NO. 1 OF 45															
DESIGNED	MRL																																		
DRAWN	DPH/AGHC																																		
CHECKED	MRL																																		
<table><tr><th>REV</th><th>DATE</th><th>BY</th><th>DESCRIPTION</th></tr><tr><td> </td><td> </td><td> </td><td> </td></tr><tr><td> </td><td> </td><td> </td><td> </td></tr><tr><td> </td><td> </td><td> </td><td> </td></tr><tr><td> </td><td> </td><td> </td><td> </td></tr></table>				REV	DATE	BY	DESCRIPTION																							TITLE SHEET					
REV	DATE	BY	DESCRIPTION																																

## GENERAL LEGEND

	EXISTING	PROPOSED
WORK LIMIT	N/A	— — — — —
GRADING LIMIT	N/A	-----
PROPERTY BOUNDARY	— — — — —	N/A
ALIGNMENT	— — — — —	=====
EDGE OF PAVEMENT	— — — — —	N/A
EDGE OF TRAIL	-----	N/A
BUILDING		N/A
SURVEY CONTROL POINT		N/A
VEGETATION		N/A
MARSH WETLAND	— — — — — WET — — — — —	N/A
TREE		N/A
TREE PROTECTION	N/A	
FIBER ROLL	N/A	
EROSION CONTROL FABRIC	N/A	
TEMPORARY ACOUSTIC BARRIER FENCE	N/A	— — — — — AB — — — — —
TEMPORARY ENVIRONMENTAL PROTECTION FENCE	N/A	— — — — — X — — — — —
IMMEDIATE VEGETATION REMOVAL AREA	N/A	
MAJOR CONTOUR	— — — — — 2.0 — — — — —	— — — — — 2.0 — — — — —
MINOR CONTOUR	— — — — — 0.5 — — — — —	— — — — — 0.5 — — — — —
GRADE BREAK	N/A	— — — — —
FLOWLINE	— — — — — . . . — — — — —	— — — — — . . . — — — — —
STAGING AREA	N/A	
LEVEE AREA	N/A	


ITEM	SYMBOL	DESCRIPTION
SUBGRADE (PROFILE AND SECTION)	N/A	
CUT MATERIAL (PROFILE AND SECTION)	N/A	
FILL MATERIAL (PROFILE AND SECTION)	N/A	
NATIVE MATERIAL	N/A	
NATIVE FINE MATERIAL	N/A	
NATIVE COARSE MATERIAL	N/A	
TREATMENT ZONE FINE MATERIAL	N/A	
TREATMENT ZONE COARSE MATERIAL	N/A	
SUBSURFACE TREATMENT MATERIAL	N/A	
LEEVE BERM MATERIAL	N/A	
SAND FILTER	N/A	
ROADWAY WORK AREA	N/A	
TRAIL SURFACE	N/A	
TREATMENT ZONE	N/A	
BIORETENTION SOIL	N/A	
EFFLUENT DISTRIBUTION BOX	N/A	
SIGN		
WOOD FENCE	N/A	
EXISTING GRADE (PROFILE AND SECTION)		N/A
DESIGN GRADE (PROFILE AND SECTION)	N/A	

## UTILITIES LEGEND

	EXISTING	PROPOSED
GAS LINE	—G—G—	N/A
OVERHEAD POWER LINE	—OH—OH—	N/A
OVERHEAD UTILITY POLE	○	N/A
UTILITY BOX	□	N/A
POTABLE WATER LINE	—W—W—	N/A
STORM DRAIN LINE	—SD—SD—	
STORM DRAIN INLET		N/A
CLEANOUT		N/A
TELECOM LINE	—T—T—	N/A
SANITARY SEWER LINE	—SS—SS—	N/A
UNDERGROUND POWER LINE	—E—E—	N/A
RECYCLED WATER LINE	—RW—	N/A
RECYCLED WATER BOX		N/A
RECYCLED WATER VALVE	○	N/A
RECYCLED WATER HYDRANT		N/A
HORIZONTAL LEEVE EFFLUENT SUPPLY LINE	N/A	—EFF—
INFILTRATOR UNITS	N/A	
PIEZOMETER	N/A	

## ABBREVIATIONS

AC	ASPHALTIC CONCRETE	JP	JOINT SERVICE POLE
ADMIN	ADMINISTRATION	(N)	NEW
BLDG	BUILDING	NIC	NOT IN CONTRACT
CONC	CONCRETE	PCC	PLAIN CEMENT CONCRETE
CLSM	CONTROLLED LOW-STRENGTH MATERIAL	OVHD / OH	OVERHEAD UTILITIES
		PIP	PROTECT IN PLACE
DBH	DIAMETER AT BREAST HEIGHT	RCP	REINFORCED CONCRETE PIPE
DG	DESIGN GRADE	RW	RECLAIMED WATER
D/S	DOWNSTREAM	RWQCP	REGIONAL WATER QUALITY CONTROL PLANT
(E)	EXISTING		
EG	EXISTING GRADE	CP	SURVEY CONTROL POINT
EL	ELEVATION	SD	STORM DRAIN
EFF	EFFLUENT	SS	SANITARY SEWER
F/L	FLOWLINE	TYP	TYPICAL
G	GAS	U/S	UPSTREAM
HDPE	HIGH-DENSITY POLYETHYLENE	W	WATER
INV	INVERT	WM	WATER METER



## GENERAL NOTES

## GENERAL

1. THESE NOTES HIGHLIGHT SOME OF THE KEY REQUIREMENTS FROM THE SPECIFICATIONS AND PROVIDE ADDITIONAL PROJECT INFORMATION. THE CONTRACTOR SHALL COMPLY WITH ALL REQUIREMENTS CONTAINED IN THE PLANS, SPECIFICATIONS, PERMITS, AND OTHER CONTRACT DOCUMENTS.

## PROTECTION OF FACILITIES

2. THE LOCATION OF EXISTING UTILITIES KNOWN TO THE OWNER ARE SHOWN IN THEIR APPROXIMATE LOCATION BASED ON INFORMATION AVAILABLE AT THE TIME THE DRAWINGS WERE PREPARED. THE ACTUAL LOCATION, SIZE, TYPE, AND NUMBER OF UTILITIES MAY DIFFER FROM THAT SHOWN, AND UTILITIES OR UNDERGROUND FACILITIES MAY BE PRESENT THAT ARE NOT SHOWN.
3. PROTECT ALL EXISTING UTILITIES WHETHER SHOWN OR NOT SHOWN ON THE DRAWINGS.
4. THE CONTRACTOR SHALL EXPOSE ALL UNDERGROUND FACILITIES THAT ARE TO BE CONNECTED TO OR THAT ARE IN THE PATH OF THE PROPOSED IMPROVEMENTS PRIOR TO THE COMMENCEMENT OF WORK IN THE VICINITY OF EACH UNDERGROUND UTILITY. CONTRACTOR SHALL NOTIFY THE OWNER IMMEDIATELY UPON DISCOVERY OF DISCREPANCIES BETWEEN EXISTING CONDITIONS IN THE FIELD AND INFORMATION SHOWN ON THESE PLANS. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO NOTIFY THE OWNER OF ANY DIFFERENCES IN LOCATIONS OF EXISTING UTILITIES SHOWN, OR ANY CONFLICTS WITH THE DESIGN THAT BECOME APPARENT DURING CONSTRUCTION, BEFORE CONTINUING WORK IN THAT AREA.
5. IF ANY DAMAGE TO EXISTING UTILITIES OCCURS, THE CONTRACTOR SHALL NOTIFY THE OWNER AND SHALL REPAIR THE DAMAGE AS DIRECTED BY THE OWNER AT NO ADDITIONAL COMPENSATION.
6. THE SITE INCLUDES OVERHEAD POWER LINES. EXERCISE CAUTION WHEN WORKING AROUND EXISTING ELECTRICAL LINES. COMPLY WITH ALL SAFETY REGULATIONS AND REQUIREMENTS.
7. THE CONTRACTOR SHALL CALL UNDERGROUND SERVICE ALERT (800-227-2600) FOR BURIED UTILITY INFORMATION AT LEAST 48 HOURS IN ADVANCE OF BEGINNING WORK.

8. RWQCP SHUTDOWNS SHALL BE COORDINATED WITH THE CITY PER SPECIFICATIONS SECTION 01 14 00 - WORK RESTRICTIONS.
9. THE CONTRACTOR SHALL PREPARE AND SUBMIT FAA FORM 7460-1, NOTICE OF PROPOSED CONSTRUCTION OR ALTERATION, TO THE FAA FOR ANY EQUIPMENT TALLER THAN 25 FEET. SEE SPECIFICATIONS SECTION 01 14 00 - WORK RESTRICTIONS.

## SITE ACCESS

10. THE FOLLOWING PROJECTS WILL BE OCCURRING WITHIN THE RWQCP AT THE SAME TIME AS THE PROJECT CONSTRUCTION: SECONDARY TREATMENT UPGRADES PROJECT AND LOCAL ADVANCED WATER PURIFICATION FACILITY. COORDINATE WITH THE RESIDENT ENGINEER ONE WEEK PRIOR TO ANY OVERLAPPING WORK WITH THE ABOVE DEFINED PROJECTS.
11. COORDINATE WITH THE RESIDENT ENGINEER FOR ACCESS TO RWQCP.
12. CONTRACTOR SHALL MAINTAIN MINIMUM ONE LANE OPEN ON EMBARCADERO ROAD AND HARBOR ROAD AT ALL TIMES DURING CONSTRUCTION.

## TOPOGRAPHIC DATA

13. ELEVATIONS ARE REFERENCED TO NORTH AMERICAN VERTICAL DATUM 1988 (NAVD 88). HORIZONTAL CONTROL IS CALIFORNIA STATE PLANE COORDINATE SYSTEM, ZONE 3, NORTH AMERICAN DATUM 1983 (NAD83, 2011), U.S. SURVEY FEET.
14. ALL ELEVATIONS AND HORIZONTAL COORDINATES ARE IN FEET. ALL DIMENSIONS ARE IN FEET UNLESS OTHERWISE NOTED.
15. THE AERIAL PHOTO IS BASED ON USGS EARTH EXPLORER DATABASE, PREPARED BY NORTHPOR GRUMMAN, DATED FEBRUARY 20 TO 24, 2015.
16. EXISTING TOPOGRAPHY IS SANTA CLARA COUNTY 2020 LIDAR, CAPTURED BY THE SANBORN MAP COMPANY, INC. IN APRIL 2020. SUPPLEMENTAL TOPOGRAPHIC DATA PROVIDED BY ESA (JUNE 2021).
17. ELEVATIONS ARE APPROXIMATE AND PROVIDED FOR GENERAL REFERENCE ONLY. THE ACCURACY OF THE ELEVATION CONTOURS IS LIMITED BY

DISTORTION DUE TO EXISTING VEGETATION.

18. EXISTING GRADES MAY HAVE CHANGED SINCE TIME OF SURVEY, FOR EXAMPLE DUE TO SUBSIDENCE AND CONSOLIDATION.
19. THE CONTRACTOR SHALL PERFORM PRE-CONSTRUCTION SURVEYS, SITE INVESTIGATIONS, ESTIMATE QUANTITIES AND INCLUDE SUFFICIENT CONTINGENCY IN ITS BID TO COVER TOPOGRAPHIC AND BATHYMETRIC VARIABILITY.

## ENVIRONMENTAL PROTECTION

20. REGULATORY PERMITS: OWNER HAS OBTAINED PERMITS FROM RESOURCE AGENCIES FOR THIS PROJECT. COMPLY WITH ALL PERMIT REQUIREMENTS FOR THE PROTECTION OF WATER QUALITY, WILDLIFE AND VEGETATION.
21. CONTRACTOR SHALL OBTAIN ALL OTHER PERMITS NOT PROVIDED BY OWNER.
22. COMPLY WITH ALL SCHEDULE RESTRICTIONS INCLUDED IN PROJECT PERMITS, INCLUDING REQUIREMENTS FOR THE PROTECTION OF NESTING BIRDS, PROTECTED FISH, AND OTHER WILDLIFE. SEE SHEET G06 AND SPECIFICATIONS SECTION 01 57 19 - TEMPORARY ENVIRONMENTAL CONTROLS AND PROJECT PERMITS FOR COMPLETE REQUIREMENTS.
23. CONTRACTOR SHALL PREPARE AND IMPLEMENT A STORMWATER POLLUTION PREVENTION PLAN (SWPPP) AS REQUIRED BY THE STATE WATER RESOURCES CONTROL BOARD. INCORPORATE SEDIMENT CONTROL AND EROSION CONTROL MEASURES TO PREVENT EROSION, SEDIMENT, AND HAZARDOUS MATERIALS RUNOFF FROM THE CONSTRUCTION SITE. SEE SHEET C16 AND SPECIFICATIONS SECTION 01 57 19 - TEMPORARY ENVIRONMENTAL CONTROLS FOR COMPLETE REQUIREMENTS.
24. ELIMINATE OR MINIMIZE NON-STORM DISCHARGE FROM THE CONSTRUCTION SITE TO THE BAY AND ALL OTHER WATER BODIES, INCLUDING GROUNDWATER.
25. STORE AND USE ALL MATERIALS THAT COULD CAUSE WATER POLLUTION (I.E. MOTOR OIL, FUELS, PAINTS, ETC.) IN A CONTAINED AREA THAT WILL NOT CAUSE ANY POLLUTION. REMOVE ALL DISCARDED MATERIAL AND ANY ACCIDENTAL SPILLS AND DISPOSE AT AN APPROVED DISPOSAL SITE.

26. CONSTRUCTION EQUIPMENT SHALL BE STORED, REFUELED, AND MAINTAINED IN DESIGNATED STAGING AREAS.
27. DUST FROM GRADING OPERATIONS SHALL BE CONTROLLED. AT MINIMUM, WATER ACTIVE WORK AREAS TO PREVENT VISIBLE DUST FROM LEAVING THE SITE.

## EARTHWORK AND WATER MANAGEMENT

29. THE PROJECT INVOLVES EXCAVATION, TRANSPORT, AND PLACEMENT OF MATERIAL BELOW GROUNDWATER LEVELS AND/OR WITHIN TIDAL WATERS.
30. ACCESS WITH CONVENTIONAL EQUIPMENT INCLUDING WHEELED SCRAPERS MAY BE DIFFICULT OR IMPOSSIBLE, PARTICULARLY IN AREAS EXCAVATED BELOW EXISTING GROUND SURFACE. PORTIONS OF THE WORK MAY REQUIRE USE OF LOW GROUND PRESSURE EQUIPMENT AND/OR USE OF CRANE MATS. THE CONTRACTOR SHALL DEVELOP EARTHWORK PLANS AND UTILIZE EQUIPMENT APPROPRIATE FOR SOFT, DIFFICULT CONDITIONS.
31. CONTRACTOR IS RESPONSIBLE FOR ESTIMATING ALL EARTHWORK QUANTITIES. APPROXIMATE EARTHWORK QUANTITIES ARE PROVIDED FOR CONTRACTOR'S REFERENCE ONLY. [
32. THE CONTRACTOR IS RESPONSIBLE FOR ALL WATER MANAGEMENT THROUGHOUT CONSTRUCTION, INCLUDING ISOLATING WORK FROM TIDAL WATERS. DEWATER AS REQUIRED FOR LEVEE SUBGRADE CONSTRUCTION AND OTHERWISE DEEMED NECESSARY TO SAFELY AND EFFICIENTLY PERFORM AND CONTROL THE WORK. SEE SHEET G05 FOR CONSTRUCTION PHASING.

				DESIGNED MRL				 <b>ESA</b> 575 MARKET STREET SUITE 3700 SAN FRANCISCO, CA 94105 T 415.896.5900 WWW.ESASSOC.COM	 CITY OF <b>PALO ALTO</b>	CITY OF PALO ALTO PALO ALTO HORIZONTAL LEVEE PILOT PROJECT	VERIFY SCALES BAR IS ONE INCH ON ORIGINAL DRAWING 0  1" IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY	DATE NOVEMBER 3, 2023 DRAWING NO. G02 SHEET NO. 2 OF 45			
				DRAWN DPH/AGHC											
				CHECKED MRL											
REV	DATE	BY	DESCRIPTION												LEGEND, ABBREVIATIONS, AND NOTES

## DESIGN NOTES

## OVERALL DESIGN OBJECTIVES

1. IMPROVE HABITAT ALONG THE PERIMETER OF HARBOR MARSH
2. ADAPT TO SEA LEVEL RISE BY PROVIDING A TRANSITIONAL SLOPE THAT PROVIDES TRANSGRESSION SPACE FOR UP TO THREE FEET OF SEA LEVEL RISE
3. REDUCE FLOOD RISK BY INTEGRATING A HORIZONTAL LEVEE ON THE OUTBOARD SIDE OF A TRADITIONAL FLOOD CONTROL LEVEE PROVIDING WIND-WAVE ATTENUATION AND VEGETATIVE EROSION PROTECTION FOR THE FLOOD CONTROL LEVEE CORE.
4. PROVIDE POLISHING TREATMENT TO DISCHARGED TREATED WASTEWATER.
5. MAINTAIN PUBLIC ACCESS TO THE EXISTING TRAIL SYSTEM.

### HORIZONTAL LEVEE EFFLUENT PIPELINE

1. DESIGN FLOW
  - a. MAXIMUM FLOW = 59,500 GPD
  - b. MINIMUM FLOW = 5,000 GPD
2. FUTURE FLOW
  - a. MAXIMUM FULL BUILD OUT FLOW = 249,500 GPD

### HORIZONTAL LEVEE FLOW OPERATION

1. CONTROL SCHEDULE:

SETPPOINT	VALUE	UNIT
FLOW	100	GPM
VALVE MINIMUM OPEN	10	%
VALVE MAXIMUM OPEN	100	%

- ## 2. DAILY RUNTIME SCHEDULE

MONTH	MIN DAILY FLOW	MIN DAILY VALVE OPEN*	EST MAX DAILY FLOW	EST MAX DAILY VALVE OPEN*	EST MAX DAILY FLOW INTERVAL
	GPD	HOURS	GPD	HOURS	(EVERY X DAYS)
OCTOBER	6,700	1.1	7,900	1.3	6
NOVEMBER	5,000	0.8	29,700	5	5
DECEMBER	8,400	1.4	51,600	8.6	4
JANUARY	11,700	2	56,400	9.4	3
FEBRUARY	15,000	2.5	59,800	10	3
MARCH	16,700	2.8	52,200	8.7	4
APRIL	16,700	2.8	32,100	5.4	5
MAY	15,000	2.5	19,700	3.3	6
JUNE	13,400	2.2	14,900	2.5	7
JULY	11,700	2	11,700	2	7
AUGUST	10,000	1.7	11,600	1.9	7
SEPTEMBER	8,400	1.4	9,900	1.7	7

\*ASSUMES VALVE OPENS TO 100 GPM


3. CONTROL AT HORIZONTAL LEVEE TREATMENT ZONE
  - a. FLOWS TO EACH ZONE ADJUSTED MANUALLY AT A MONTHLY BASIS
  - b. NUMBER OF ZONES = 4

RENZEL MARSH PUMP

1. MAXIMUM FLOW = 3 MGD
2. TYPICAL OPERATION FLOW = 1.0 TO 1.5 MGD
3. PUMP OPERATION CHARACTERISTICS

PARAMETER	VALUE
Primary Point at Full Speed (gpm @ TDH)	1,200 @ 19.3 ft
NPSHa at Primary Point	36 feet
Maximum Capacity at Full Speed (gpm @ TDH)	1,600 @ 8 ft
Minimum Capacity at Full Speed (gpm @ TDH)	200 @ 42 ft
Secondary Point at Reduced Speed (gpm @ TDH @ rpm)	650 gpm @ 12.5 ft @ 1,150 rpm
NPSHa at Secondary Point	30 feet
Minimum Shutoff Head	55 ft
Maximum Synchronous Speed	1,800 rpm
Pump Drive Type	Adjustable Speed
Minimum Operating Speed	1,100 rpm
Motor Horsepower	10 HP
Required minimum efficiency at Primary Point	54% (Wire-to-Water Efficiency)
Minimum Solids sphere passage	3 inches
Minimum Size Suction x Discharge (inches)	6 x 6
Discharge pressure gauge range	0 to 30 psig

				DESIGNED MRL					 575 MARKET STREET SUITE 3700 SAN FRANCISCO, CA 94105 T 415.896.5900 WWW.EASSOC.COM	 CITY OF <b>PALO ALTO</b>	CITY OF PALO ALTO PALO ALTO HORIZONTAL LEVEE PILOT PROJECT		VERIFY SCALES	DATE NOVEMBER 3, 2023
				DRAWN DPH/AGHC							BAR IS ONE INCH ON ORIGINAL DRAWING	DRAWING NO.		
				CHECKED MRL							0  1"	G03		
											IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY	SHEET NO. 3 OF 45		
REV	DATE	BY	DESCRIPTION								BASIS OF DESIGN			



CONTROL POINT				
POINT	ELEVATION	NORTHING	EASTING	DESCRIPTION
HT1271	7.30	1991435.38	6093694.31	NGS HT1271 BENCHMARK


NOTES

1. THIS PROJECT WILL ROUTE TREATED EFFLUENT FROM THE PALO ALTO RWQCP TO THE PROPOSED HORIZONTAL LEVEE. SEE MECHANICAL PLANS.
2. THE (E) RENZEL MARSH PUMP IN THE ADMINISTRATION BUILDING BASEMENT SHALL BE DEMOLISHED AND REPLACED BY A (N) RENZEL MARSH PUMP INSTALLED IN THE EFFLUENT JUNCTION BOX NEXT TO THE CHLORINE CONTACT TANK. SEE MECHANICAL PLANS. MAINTAIN THE (E) RENZEL MARSH PUMP UNTIL THE (N) RENZEL MARSH PUMP IS FULLY OPERATIONAL.
3. THE HORIZONTAL LEVEE WILL INCORPORATE A SUBSURFACE TREATMENT ZONE THAT DISCHARGES POLISHED EFFLUENT TO THE ECOTONE HABITAT SLOPE. SEE CIVIL PLANS.
4. CONTRACTOR TO MAINTAIN ACCESS FOR VEHICLE TRAFFIC ALONG LANDFILL ACCESS ROAD. CONFIRM LOCATION, EXTENT AND ANY USE LIMITATIONS WITH THE RESIDENT ENGINEER PRIOR TO MOBILIZATION.

SITE OVERVIEW


PLAN

SCALE: 1" = 60'



DESIGNED MRL				575 MARKET STREET SUITE 3700 SAN FRANCISCO, CA 94105 T 415.896.5900 WWW.ESASOC.COM		CITY OF PALO ALTO PALO ALTO HORIZONTAL LEVEE PILOT PROJECT	VERIFY SCALES BAR IS ONE INCH ON ORIGINAL DRAWING 0 1" IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY	DATE NOVEMBER 3, 2023 DRAWING NO. G04 SHEET NO. 4 OF 45							
DRAWN DPH/AGHC															
CHECKED MRL															
MRL															
REV	DATE	BY	DESCRIPTION		SITE OVERVIEW										
1															
2															
3															
4															
5															
6															
7															
8															
9															
10															
11															
12															
13															





<div>DESIGNED MRL</div> <div>DRAWN DPH/AGHC</div> <div>CHECKED MRL</div>				<div>REGISTERED PROFESSIONAL ENGINEER</div> <div>MARK R. LINDLEY</div> <div>C 66701</div> <div>EXP. 9/30/22</div> <div>CIVIL</div> <div>STATE OF CALIFORNIA</div>	<div>ESA</div> <div>575 MARKET STREET</div> <div>SUITE 3700</div> <div>SAN FRANCISCO, CA 94105</div> <div>T 415.896.5900</div> <div>WWW.ESASOC.COM</div>	<div>CITY OF PALO ALTO</div> <div>CONSTRUCTION PHASING</div>	<div>VERIFY SCALES</div> <div>BAR IS ONE INCH ON ORIGINAL DRAWING</div> <div>0 1" IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY</div>	<div>DATE</div> <div>NOVEMBER 3, 2023</div> <div>DRAWING NO.</div> <div>G05</div> <div>SHEET NO.</div> <div>5 OF 45</div>
REV	DATE	BY	DESCRIPTION					
1								
2								
3								
4								
5								
6								
7								
8								
9								
10								
11								
12								
13								



1. THIS SHEET OUTLINES SOME BUT NOT ALL THE REGULATORY PERMIT REQUIREMENTS. SEE PROJECT SPECIFICATIONS AND PERMITS.
2. SEE SHEET G05 FOR ADDITIONAL CONSTRUCTION PHASING RESTRICTIONS
3. WORK ALLOWED BETWEEN FEBRUARY 1 TO AUGUST 31:
  - A. ROADWAY WORK WITH TEMPORARY ACOUSTIC BARRIER FENCE INSTALLED ALONG HARBOR ROAD AS SHOWN.
  - B. RWQCP PLANT AREA WORK WITH TEMPORARY ACOUSTIC BARRIER FENCE INSTALLED ALONG HARBOR ROAD AS SHOWN.
  - C. ESTABLISHMENT AND USE OF STAGING AREA WITH TEMPORARY ACOUSTIC BARRIER FENCE INSTALLED ALONG EXISTING TRAIL BERM AND TEMPORARY ENVIRONMENTAL PROTECTION FENCE INSTALLED ALONG PERIMETER OF STAGING AREA AS SHOWN.
  - D. LEVEE AREA VEGETATION REMOVAL UP TO LANDWARD SIDE OF EXISTING TRAIL BERM WITH TEMPORARY ACOUSTIC BARRIER FENCE INSTALLED ALONG EXISTING TRAIL BERM AS SHOWN. SEE VEGETATION REMOVAL RESTRICTIONS BELOW.






4. WORK ALLOWED BETWEEN SEPTEMBER 1 AND JANUARY 31:
  - A. NO TEMPORARY ACOUSTIC BARRIER FENCE REQUIRED FOR ANY PROJECT WORK.
  - B. ROADWAY WORK.
  - C. RWQCP PLANT AREA WORK.
  - D. ESTABLISHMENT AND USE OF STAGING AREA.
  - E. LEVEE AREA VEGETATION REMOVAL. SEE VEGETATION REMOVAL RESTRICTIONS BELOW.
  - F. LEVEE AREA EARTHWORK WITH TEMPORARY ENVIRONMENTAL PROTECTION FENCE INSTALLED ALONG PROJECT BOUNDARIES AS SHOWN.
5. IN WATER WORK LIMITED TO SEPTEMBER 1 TO NOVEMBER 30. IN WATER WORK REQUIRES INSTALLATION OF TURBIDITY CURTAIN. SEE PROJECT SPECIFICATIONS AND PERMITS.
6. VEGETATION REMOVAL:

- A. STAKE LIMITS FOR REVIEW AND APPROVAL BY RESIDENT ENGINEER.
- B. VEGETATION REMOVAL WILL START AT THE WESTERN EDGE OF THE WORK AREA AT HARBOR ROAD AND PROGRESS TOWARD THE TIDAL MARSH
- C. ALL VEGETATION TALL AND/OR SPARSE ENOUGH TO BE EASILY INSPECTED BY THE OWNER'S BIOLOGICAL MONITOR WILL BE TRIMMED DOWN TO A HEIGHT NO LESS THAN 2-INCHES AT WHICH ADDITIONAL INSPECTION CAN BE CONDUCTED, IF NECESSARY
- D. IN RUDERAL GRASSLANDS, MOTORIZED PUSH MOWERS AND/OR STRING TRIMMERS MAY BE USED FOR VEGETATION REMOVAL.
- E. IN SMHM VEGETATION REMOVAL AREAS, NON-MOTORIZED HAND TOOLS (E.G., RAKES AND GRASS WHIPS) MAY BE USED.
- F. ONCE THE OWNER'S BIOLOGICAL MONITOR IS CONFIDENT THAT ALL SMHM ARE ABSENT FROM OR HAVE MOVED OUT OF THE VEGETATION IN THE IMMEDIATE VEGETATION REMOVAL AREA, THE VEGETATION WILL BE CUT DOWN TO GROUND LEVEL WITH THE EQUIPMENT SPECIFIED FOR EACH HABITAT TYPE, SO THAT NO COVER SUITABLE FOR USE BY MICE REMAINS IN THE PROJECT FOOTPRINT.
- G. ALL CUT VEGETATION WILL BE REMOVED DAILY FROM VEGETATION REMOVAL AREAS TO PREVENT IT FROM BEING USED AS REFUGIA BY SMHM.

— STAGING AREA, TYP

PLAN

SCALE: 1" = 30'

TEMPORARY ACOUSTIC BARRIER FENCE	
TEMPORARY ENVIRONMENTAL PROTECTION FENCE	
SMHM VEGETATION REMOVAL AREA	
EXISTING TRAIL	
STAGING AREA	

— END ACOUSTIC BARRIER

PROTECT (E) 32-INCH DBH  
EUCALYPTUS USING TYPE 1  
TREE PROTECTION, SHT G08

— (E) RENZEL MARSH  
INTAKE STRUCTURE

— STAGING AREA, TYP

## DAL ANNEL

HARBOR MARSH

— (E) RENZEL MARSH

PROTECT (E) 32-INCH DBH  
EUCALYPTUS USING TYPE 1  
TREE PROTECTION, SHT G08

ESA

575 MARKET STREET  
SUITE 3700  
SAN FRANCISCO, CA 94105  
T 415.896.5900  
WWW.ESASSOC.COM

CITY OF  
**PALO ALTO**

CITY OF PALO ALTO  
PALO ALTO HORIZONTAL LEVEE PILOT PROJECT

## ENVIRONMENTAL PROTECTION OVERVIEW

VERIFY SCALES	
---------------	--

BAR IS ONE INCH ON

ORIGINAL DRAWING

IF NOT ONE INCH ON  
THIS SHEET, ADJUST  
SCALE ACCORDINGLY

DATE \_\_\_\_\_

NOVEMBER 3,  
DRAWING NO.

C06


G06

SHEET NO.

DESIGNED	MRL
DRAWN	DPH/AGHC
CHECKED	MRL



REV	DATE	BY	DESCRIPTION
-----	------	----	-------------



FILENAME: 007 ENVIRONMENTAL PROTECTION 11-03-23 04:19pm Drawn: XREFS: X-TBLK-PaloAlto-Border X-PAL-DTL-CIVIL K<<-

REV	DATE	BY	DESCRIPTION

DESIGNED MRL
DRAWN DPH/AGHC
CHECKED MRL



575 MARKET STREET  
SUITE 3700  
SAN FRANCISCO, CA 94105  
T 415.896.5900  
WWW.ESASSOC.COM



CITY OF PALO ALTO  
PALO ALTO HORIZONTAL LEVEE PILOT PROJECT

ENVIRONMENTAL PROTECTION

VERIFY SCALES  
BAR IS ONE INCH ON ORIGINAL DRAWING  
0 1" IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY

DATE  
NOVEMBER 3, 2023  
DRAWING NO.  
G07  
SHEET NO.  
7 OF 45



# City of Palo Alto Tree Protection - It's Part of the Plan!

Make sure your crews and subs do the job right!

Fenced enclosures around trees are essential to protect them by keeping the foliage canopy and branching structure clear from contact by equipment, materials and activities, preserving roots and soil conditions in an intact and non-compacted state, and identifying the Tree Protection Zone (TPZ) in which no soil disturbance is permitted and activities are restricted, unless otherwise approved. **An approved tree protection report must be added to this sheet when project activity occurs within the TPZ of a regulated tree.**

For detailed information on Palo Alto's regulated trees and protection during development, review the **City Tree Technical Manual (TTM)** found at [www.cityofpaloalto.org/trees/](http://www.cityofpaloalto.org/trees/).

## NOTE

- SEE SPECIFICATIONS SECTION 01 56 39 - TEMPORARY TREE PROTECTION FOR COMPLETE REQUIREMENTS ON TREE PROTECTION.

TREE DISCLOSURE STATEMENT		CITY OF PALO ALTO Planning Division, 250 Hamilton Avenue Palo Alto, CA 94301 (650) 329-2441 <a href="http://www.cityofpaloalto.org">http://www.cityofpaloalto.org</a>
Palo Alto Municipal Code, Chapter 8.10.040, requires disclosure and protection of certain trees located on private and public property, and that they be shown on approved site plans. A completed disclosure statement must accompany all building permit applications that include exterior work, all demolition or grading permit applications, or other development activity.		
PROPERTY ADDRESS: 2375 Embarcadero Road, Palo Alto, CA		
Are there Regulated trees on or adjacent to the property? <input checked="" type="checkbox"/> YES <input type="checkbox"/> NO (if no, proceed to Section 4)		
[Sections 1-4 MUST be completed by the applicant. Please circle and/or check where applicable.]		
1. Where are the trees? Check those that apply. (Plans must be submitted showing over 4" diameter trees) <input checked="" type="checkbox"/> On the property <input type="checkbox"/> On adjacent property overhanging the project site <input type="checkbox"/> In the City planter site or right-of-way easement within 30' of property line (Street Trees)*		
*Street trees require special protection by a fenced enclosure, per the attached instructions. Prior to receiving your permit, you must provide an enclosed Street Tree Protection Verification Form by calling Public Works Operations at 650-5953 for inspection of required type I, II or III fencing (see attached Detail 6005).		
2. Are there any Protected or Designated Trees? <input type="checkbox"/> YES (Check where applicable) <input checked="" type="checkbox"/> NO		
<input type="checkbox"/> Protected Tree (s) <input type="checkbox"/> Designated Tree (s) On or overhanging the property		
3. Is there activity or grading within the dieline? (radius 10 times the trunk diameter) of these trees? <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO If Yes, a Tree Preservation Report must be prepared by an ISA certified arborist and submitted for staff review (see TTM, Section 6.25, attach this report to Street Tree Protection, as Part of the Plan** per Site Plan Requirements).		
4. Are the Site Plan Requirements** completed? <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO		
**Protection of Regulated trees during development requires the following: (1) Plans must show the measured trunk diameter and canopy dieline; (2) Plans must show, as a bold double line, a fenced enclosure access to the dieline, per Sheet T-1 and Detail 6005 - <a href="http://www.cityofpaloalto.org/links/links.htm">http://www.cityofpaloalto.org/links/links.htm</a> (See also TTM, Section 2.15 for area to be fenced)		
I, the undersigned, agree to the conditions of this disclosure. I understand that knowingly or negligently providing false or misleading information in response to this disclosure requirement constitutes a violation of the Palo Alto Municipal Code Section 8.10.040, which can lead to criminal and/or civil legal action.		
Signature: _____	Print: _____	Date: _____
FOR STAFF USE.		
Protective Fencing Sections 5-6 must be completed by staff for the issuance of any development permit (demolition, grading or building permit).		
5. Protected Trees. The specified tree fencing is in place. A written statement is attached verifying that protective fencing is correctly in place around protected and/or designated trees. <input type="checkbox"/> YES <input type="checkbox"/> NO (N/A if there are no protected trees, check here <input type="checkbox"/> )		
6. Street Trees. A signed Public Works Street Tree Protection Verification form is attached. <input type="checkbox"/> YES <input type="checkbox"/> NO (N/A if there are no street trees, check here <input type="checkbox"/> )		
Regulated Trees - a) Street trees - trees on public property; b) Protected trees - Coast Live Oaks or Valley Oaks which are 11.5" in diameter or larger, Coast Redwoods which are 10" in diameter or larger, when measured 4' above natural grade; and Heritage trees are trees designated by City Council; and c) Designated trees - commercial or non-commercial property trees, which are not of an approved landscape plan.		
Palo Alto Tree Technical Manual (TTM) contains instructions for all requirements on this form, available at: <a href="http://www.cityofpaloalto.org/planning-community/trees-technical-manual.html">http://www.cityofpaloalto.org/planning-community/trees-technical-manual.html</a>		
S:\Plan\Prod\Arborist\Tree Protection Info\Tree Disclosure Statement		Revised 06/06

Far written specifications associated with illustrations below, see Public Works Specifications Section 31 Detailed specifications are found in the Palo Alto Tree Technical Manual (TTM) ( <a href="http://www.cityofpaloalto.org/trees/">www.cityofpaloalto.org/trees/</a> )	
<b>Tree Protection Zone (TPZ)</b> shown in gray (radius of TPZ equals 10 times the diameter of the tree or 10-foot, whichever is greater). • Rooted activity area - see Tree Technical Manual Sec 2.14(d) • Rooted activity area - see Tree Technical Manual Sec 2.14(c) (D), any proposed trench or form work within a TPZ of a protected tree requires approval from Public Works Operations. Call 650-496-5953.	
<b>Type I Tree Protection</b> For all Ordinance Protected and Designated trees, a minimum 4-foot high fence must be erected around the tree to the specified project extent as indicated on the plan. Note: Ordinance Protected & Designated Trees. Issuance of a permit requires applicant's project arborist verification. Type I is installed correctly according to the Plans and Tree Preservation Report.	<b>Type II Tree Protection</b> For all Ordinance Protected and Designated trees, a minimum 4-foot high fence must be erected around the tree to the specified project extent as indicated on the plan. Note: Street Trees. Issuance of a permit requires Public Works Operations inspection and signed approval on the Street Tree Verification (STV) form provided.
<b>Type III Tree Protection</b> For all Ordinance Protected and Designated trees, a minimum 4-foot high fence must be erected around the tree to the specified project extent as indicated on the plan. Note: Street Trees. Issuance of a permit requires Public Works Operations inspection and signed approval on the Street Tree Verification (STV) form provided.	<b>Tree Protection During Construction</b> City of Palo Alto Standard Scale: NTS

PALO ALTO STREET TREE PROTECTION INSTRUCTIONS -SECTION 31-	
31-1 General	a. Tree protection has three primary functions: 1) to keep the foliage canopy and branching structure clear from contact by equipment, materials and activities; 2) to preserve roots and soil conditions in an intact and non-compacted state; and 3) to identify the Tree Protection Zone (TPZ) in which no soil disturbance is permitted and activities are restricted, unless otherwise approved.
31-2 Reference Documents	a. Detail 605 - Illustration of dieline described below. b. Tree Technical Manual (TTM) Form (2/2003) at <a href="http://www.cityofpaloalto.org/trees/">www.cityofpaloalto.org/trees/</a> c. Submittal Review Process (TTL, Section 6.03) d. Site Plan Requirements (TTL, Section 6.15) e. Tree Disclosure Statement (TTL, Section 6.25) f. Street Tree Verification (STV) Form ( <a href="http://www.cityofpaloalto.org/trees/">http://www.cityofpaloalto.org/trees/</a> )
31-3 Execution	a. <b>Type I Tree Protection:</b> The fence shall enclose the entire TPZ of the tree(s) to be protected throughout the life of the construction project. In some parking areas, if fencing is located on parking or concrete that will not be demolished, then the posts may be supported by an appropriate grade level concrete base, as approved by Public Works Operations. b. <b>Type II Tree Protection:</b> For trees situated within a planting strip, only the planting strip and yard side of the TPZ shall be enclosed with the required chain link protective fencing to enter to keep the sidewalk and street open for public use. c. <b>Type III Tree Protection:</b> To be used only with approval of Public Works Operations. Trees situated in a tree well or otherwise planted pit, shall be wrapped with 2-inch x 4-inch energy plastic fencing from the ground to the first branch and overlaid with 2-inch thick wooden strips board security (chain link shall not be allowed to dig into the back). During installation of the plastic fencing, caution shall be used to avoid damaging any trenches. Where trees may also require plastic fencing is directed by the City Arborist. d. <b>Site, type and area to be fenced:</b> All trees to be protected shall be protected with 48" foot high chain link fence. Fence is to be maintained on two-foot diameter galvanized steel posts, driven into the ground to a depth of at least 2-feet or to more than 10-foot spacing. Fencing shall extend to the outer boundary, unless specifically approved by the STV Form. e. <b>Warning signs:</b> A warning sign shall be weather proof and prominently displayed on each fence at 20-foot intervals. The sign shall be minimum 45 inches x 11 inches and clearly state in half inch tall letters "WARNING - Tree Protection Zone - This fence shall not be removed and is subject to a fine according to PAMC Section 8.10.107". f. <b>Duration:</b> Tree fencing shall be erected before demolition, grading or construction begins and remain in place until final inspection of the project, except for work specifically allowed in the TPZ. Work or soil disturbance in the TPZ requires approval by the project arborist or City Arborist in the case of work around Street Trees. Excavations within the public right of way require a Street Work Permit from Public Works. g. <b>During construction</b> 1. All neighbor trees from encroaching the project site shall be protected from impact of any kind. 2. The applicant shall be responsible for the repair or replacement (at penalty of any publicly owned trees that are damaged during the course of construction, pursuant to Section 8.10.076 of the Palo Alto Municipal Code). 3. The following tree preservation measures apply to all trees to be retained: a. No storage of material, equipment, vehicles or equipment shall be permitted within the TPZ. b. The ground under and around the tree shall not be compacted. c. Trees to be retained shall be irrigated, weeded and maintained as necessary to ensure survival.
END OF SECTION City of Palo Alto 2004 Standard Drawings and Specifications Street Tree Verification of Protection, PWE, Section 31 Revised 06/06	

Table 2-2 Palo Alto Tree Technical Manual CONTRACTOR & ARBORIST INSPECTION SCHEDULE	
Reference: the Palo Alto Tree Technical Manual is available at <a href="http://www.cityofpaloalto.org/trees/">www.cityofpaloalto.org/trees/</a>	
ALL CHECKED ITEMS APPLY TO THIS PROJECT:	
1. <input checked="" type="checkbox"/> <b>Inspection of Protective Tree Fencing:</b> For Public Trees, the Street Tree Verification Form shall be signed by the City Arborist. For Protected Trees, the project site arborist shall provide an initial Monthly Tree Activity Report form with a photograph verifying that he has conducted a field inspection of the trees and that the correct type of protective fencing is in place around the designated tree protection zone (TPZ) prior to issuance of a demolition, grading, or building permit. (See TTM, Verification of Tree Protection, Section 1.39).	
2. <input checked="" type="checkbox"/> <b>Pre-Construction Meeting:</b> Prior to commencement of construction, the applicant or contractor shall conduct a pre-construction meeting to discuss tree protection with the job site superintendent, grading operator, project site arborist, City Arborist, and, if a city maintained irrigation system is involved, the Parks Manager (Contact 650-496-6963).	
3. <input checked="" type="checkbox"/> <b>Inspection of Rough Grading or Trenching:</b> Contractor shall ensure the project site arborist performs an inspection during the course of rough grading or trenching adjacent to or within the TPZ to ensure trees will not be impacted by compaction, cut or fill, drainage and trenching, and if required, impact mitigation systems, new wells, drains and special paving. The contractor shall provide the project arborist at least 24 hours advance notice of each activity.	
4. <input checked="" type="checkbox"/> <b>Monthly Tree Activity Report Inspections:</b> The project site arborist shall perform a minimum monthly activity inspection to monitor and advise on conditions, tree health and retention or, immediately if there are any revisions to the approved plans or protection measures. The Tree Technical Manual Monthly Tree Activity Report form shall be used and sent to the Planning Dept. Landscape review staff no later than 14 days after issuance of building permit. Fax to (650) 329-2154. (See TTM, Monthly Tree Activity Inspection Report, Addendum 11 & section 1.17).	
5. <input checked="" type="checkbox"/> <b>Special activity within the Tree Protection Zone:</b> Work in the TPZ area (see also #7 below) requires the direct onsite supervision of the project arborist (see TTM, Trenching, Excavation & Equipment, Section 2.20 C).	
6. <input type="checkbox"/> <b>Landscape Architect Inspection:</b> For discretionary development projects, prior to temporary or final occupancy the applicant or contractor shall arrange for the Landscape Architect to perform an on site inspection of all plant stock, quality of the materials and planting (see TTM, Planting Quality, Section 3.20.1 A) and that the irrigation is functioning consistent with the approved construction plans. The Planning Dept. Landscape review staff shall be in receipt of written verification of Landscape Architect approval prior to scheduling the final inspection, unless otherwise approved.	
7. <input type="checkbox"/> <b>Lin Other:</b> (please describe as called out in the site Tree Preservation Report, Sheet T-1, T-2, etc.)	

City of Palo Alto Tree Department Public Works Operations PO Box 9220 Palo Alto, CA 94303 (650) 496-5953 FAX: (650) 496-5953 <a href="mailto:treeprotection@cityofpaloalto.org">treeprotection@cityofpaloalto.org</a>	
<b>Verification of Street Tree Protection</b>	
Applicant Instructions: Complete upper portion of this form. Mail or FAX this form along with signed Tree Disclosure Statement to Public Works Dept. Public Works Tree Staff will inspect and notify applicant.	
APPLICATION DATE: _____	
ADDRESS/LOCATION OF STREET TREES TO BE PROTECTED: _____	
APPLICANT'S NAME: _____	
APPLICANT'S ADDRESS: _____	
APPLICANT'S TELEPHONE & FAX NUMBERS: _____	
This section to be filled out by City Tree Staff	
1. The Street Trees at the above address(es) are adequately protected. The type of protection used is: _____	YES <input type="checkbox"/> NO <input type="checkbox"/> * If NO, go to #2 below
Inspected by: _____	
Date of inspection: _____	
2. The Street Trees at the above address(es) are adequately protected. The following modifications are required: _____	
Indicate how the required modifications were communicated to the applicant: _____	
Subsequent inspection: _____	YES <input type="checkbox"/> NO <input type="checkbox"/> * If NO, indicate in "Notes" below the disposition of case.
Inspected by: _____	
Date of inspection: _____	
Notes: List City street trees by species, site, condition and type of tree protection installed. Also note if pictures were taken. Use back of sheet if necessary.	
Return approved sheet to Applicant for demolition or building permit issuance. <a href="mailto:treeprotection@cityofpaloalto.org">treeprotection@cityofpaloalto.org</a>	

City of Palo Alto Tree Technical Manual ADDENDUM 11 Arborist Firm Data Here	
Monthly Tree Activity Report- Construction Site	
Inspection Date: _____	Site address: _____
Inspection # _____	Contractor Main Site Contact Information: _____
	#1 Job site superintendent: _____
	Company: _____
	Email: _____
	Job site Office: _____
	Call: _____
	Mail: _____
	Also present: _____
	Attn: Dave Dockter
	<a href="mailto:dave.dockter@cityofpaloalto.org">dave.dockter@cityofpaloalto.org</a>
	650-329-2440
Distribution:	1. City of Palo Alto 2. Others: _____
Provide the requested minimum information with each report, enclosure as necessary. To be completed by project site arborist. Send monthly to city arborist at above address until project completion. Use additional sheets if needed.	
1. Assignment Activity (Demolition/grading/trenching/foundation list relevant visits) a. Pre-construction meeting requirement with sub-contractors b. Inspect to verify that tree protection measures are in place c. Determine if field adjustments, watering or plan revisions may be needed	
2. Field Observations (general site-wide and list by individual tree number) a. Tree Protection Fences (TPF) are ... b. Trenching has/will occur ...	
3. Action Items (list site-wide, by tree number and date to be satisfied) and Date Due a. Tree Protection Fence (TPF) needs adjusting (tree #, s, s) b. Root zone buffer material (wood chips) can be installed next c. Schedule sewer trench, foundation dig with ...	
4. Photographs (use often)	
5. Tree Location Map (mandatory 8.5 x 11 sheet)	
6. Recommendations, notes or monitor items for project/staff/schedule	
7. Past visits (list carry-over items satisfied/still outstanding)	
Respectfully submitted,	
Project site arborist	
Consultant contact information (include email, cell#, and mailing)	
Cc: _____	
Enter Date	CFA Monthly Tree Activity Report: Type site address here
	Page #1 of 1

---WARNING---	
<b>Tree Protection Zone</b>	
This fencing shall not be removed without City Arborist approval (650-496-5953)	
Removal without permission is subject to a \$500 fine per day*	
*Palo Alto Municipal Code Section 8.10.110	
City of Palo Alto Tree Protection Instructions are located at <a href="http://www.cityofpaloalto.org/trees/technical-manual.html">http://www.cityofpaloalto.org/trees/technical-manual.html</a>	

SPECIAL INSPECTIONS	
TREE PROTECTION INSPECTIONS MANDATORY	
PAMC 8.10 PROTECTED TREES. CONTRACTOR SHALL ENSURE PROJECT SITE ARBORIST IS PERFORMING REQUIRED TREE INSPECTION AND SITE MONITORING. PROVIDE WRITTEN MONTHLY TREE ACTIVITY REPORTS TO THE PLANNING DEPARTMENT LANDSCAPE REVIEW STAFF BEGINNING 14 DAYS AFTER BUILDING PERMIT ISSUANCE.	
BUILDING PERMIT DATE: _____	
DATE OF 1 <sup>ST</sup> TREE ACTIVITY REPORT: _____	
CITY STAFF: _____	
REPORTING DETAILS OF THE MONTHLY TREE ACTIVITY REPORT SHALL CONFORM TO SHEET T-1 FORMAT. VERIFY THAT ALL TREE PROTECTION MEASURES ARE IMPLEMENTED AND WILL INCLUDE ALL CONTRACTOR ACTIVITY, SCHEDULED OR UNSCHEDULED, WITHIN A TREE PROTECTION ROOT ZONE. NON-COMPLIANCE IS SUBJECT TO VIOLATION OF PAMC 8.10.066. REFERENCE: PALO ALTO TREE TECHNICAL MANUAL, SECTION 2.09 AND ADDENDUM 11.	

Apply Tree Protection Report on sheet(s) T-2

Use additional "T" sheets as needed

# T-1



All other tree-related reports shall be added to the space provided on this sheet (adding as needed). Include this sheet(s) on Project Sheet Index or Legend Page. A copy of T-1 can be downloaded at <http://www.cityofpaloalto.org/civica/filebank/blobload.asp?BlobID=6460>

## Special Tree Protection Instruction Sheet

### City of Palo Alto




# T-1

DESIGNED MRL		DRAWN DPH/AGHC		CHECKED MRL		REV		DATE		BY		DESCRIPTION	
1		2		3		4		5		6		7	
8		9		10		11		12		13		14	
15		16		17		18		19		20		21	
22		23		24		25		26		27		28	
29		30		31		32		33		34		35	
36		37		38		39		40		41		42	
43		44		45		46		47		48		49	
50		51		52		53		54		55		56	
57		58		59		60		61		62		63	
64		65		66		67		68		69		70	
71		72		73		74		75		76		77	
78		79		80		81		82		83		84	
85		86		87		88		89		90		91	
92		93		94		95		96		97		98	
99		100		101		102		103		104		105	
106		107		108		109		110		111		112	
113		114		115		116		117		118		119	
120		121		122		123		124		125		126	
127		128		129		130		131		132		133	
134		135		136		137		138		139		140	
141		142		143		144		145		146		147	
148		149		150		151		152		153		154	
155		156		157		158		159		160		161	
162		163		164		165		166		167		168	
169		170		171		172		173		174		175	
176		177		178		179		180		181		182	
183		184		185		186		187		188		189	
190		191		192		193		194		195		196	
197		198		199		200		201		202		203	
204		205		206		207		208		209		210	
211		212		213		214		215		216		217	
218		219		220		221		222		223		224	
225		226		227		228		229		230		231	
232		233		234		235		236		237		238	
239		240		241		242		243		244		245	
246		247		248		249		250		251		252	
253		254		255		256		257		258		259	
260		261		262		263		264		265		266	
267		268		269		270		271		272		273	
274		275		276		277		278		279		280	
281		282		283		284		285		286		287	
288		289		290		291		292		293		294	
295		296		297		298		299		300		301	
302		303		304		305		306		307		308	
309		310		311		312		313		314		315	
316		317		318		319		320		321		322	
323		324		325		326		327		328		329	
330		331		332		333		334		335		336	
337		338		339		340		341		342		343	
344		345		346		347		348		349		350	
351		352		353		354		355		356		357	
358		359		360		361		362		363		364	
365		366		367		368		369		370		371	
372		373		374		375		376		377		378	
379		380		381		382		383		384		385	
386		387		388		389		390		391		392	
393		394		395		396		397		398		399	
400		401		402		403		404		405		406	
407		408		409		410		411		412		413	
414		415		416		417		418		419		420	
421		422		423		424		425		426		427	
428		429		430		431		432		433		434	
435		436		437		438		439		440		441	
442		443		444		445		446		447		448	
449		450		451		452		453		454		455	
456		457		458		459		460		461		462	
463		464		465		466		467		468		469	
470													




Construction projects are required to implement year-round stormwater BMPs, as they apply to your project.

- ☐ Establish and maintain effective perimeter controls and stabilize all construction entrances and exits to sufficiently control erosion and sediment discharges from site and tracking off site.
- ☐ Sweep or vacuum any street tracking immediately and secure sediment source to prevent further tracking. Never hose down streets to clean up tracking.



- ☐ Keep spill cleanup materials (e.g., rags, absorbents and cat litter) available at the construction site at all times.
- ☐ Maintain all vehicles and heavy equipment. Inspect frequently for and repair leaks. Use drip pans to catch leaks until repairs are made.
- ☐ Clean up leaks, drips and other spills immediately and dispose of cleanup materials properly.
- ☐ Use dry cleanup methods whenever possible (absorbent materials, cat litter and/or rags).
- ☐ Sweep up spilled dry materials immediately. Never attempt to "wash them away" with water, or bury them.
- ☐ Clean up spills on dirt areas by digging up and properly disposing of contaminated soil.
- ☐ Report any hazardous materials spills immediately! Call City of Palo Alto Communications, **(650) 329-2413**. If the spill poses a significant hazard to human health and safety, property or the environment, you must report it to the State Office of Emergency Services, **(800) 852-7550 (24 hours)**.



- ❑ Schedule grading and excavation work during dry weather.
- ❑ Stabilize all denuded areas, install and maintain temporary erosion controls (such as erosion control fabric or bonded fiber matrix) until vegetation is established.
- ❑ Remove existing vegetation only when absolutely necessary; plant temporary vegetation for erosion control on slopes or where construction is not immediately planned.
- ❑ Prevent sediment from migrating offsite and protect storm drain inlets, drainage courses and streams by installing and maintaining appropriate BMPs (e.g., silt fences, gravel bags, fiber rolls, temporary swales, etc.).
- ❑ Keep excavated soil on site and transfer it to dump trucks on site, not in the streets.

☐ If any of the following conditions are observed, test for contamination and contact the Regional Water Quality Control Board:

- Unusual soil conditions, discoloration, or odor.
- Abandoned underground tanks.
- Abandoned wells.
- Buried barrels, debris, or trash.


☐ If the above conditions are observed, document any signs of potential contamination and clearly mark them so they are not disturbed by construction activities.

- ☐ Protect stockpiled landscaping materials from wind and rain by storing them under tarps all year-round.
- ☐ Stack bagged material on pallets and under cover.
- ☐ Discontinue application of any erodible landscape material within 2 days before a forecast rain event or during wet weather.



- ❑ Store both dry and wet materials under cover, protected from rainfall and runoff and away from storm drains or waterways. Store materials off the ground, on pallets. Protect dry materials from wind.
- ❑ Wash down exposed aggregate concrete only when the wash water can (1) flow onto a dirt area; (2) drain onto a bermed surface from which it can be pumped and disposed of properly; or (3) block any storm drain inlets and vacuum washwater from the gutter. If possible, sweep first.
- ❑ Wash out concrete equipment/trucks offsite or in a designated washout area, where the water will flow into a temporary waste pit, and make sure wash water does not leach into the underlying soil. (See CASQA Construction BMP Handbook for properly designed concrete washouts.)

- ❑ Reuse water for dust control, irrigation or another on-site purpose to the greatest extent possible.
- ❑ Be sure to obtain a Permit for Construction in the Public Street from Public Works Engineering before discharging water to a street, gutter, or storm drain. Call the Regional Water Quality Control Plant (RWQCP) at **(650) 329-2598** for an inspection prior to commencing discharge. Use filtration or diversion through a basin, tank, or sediment trap as required by the approved dewatering plan. Dewatering is not permitted from October to April.
- ❑ In areas of known contamination, testing is required prior to reuse or discharge of groundwater. Consult with the City inspector to determine what testing to do and to interpret results. Contaminated groundwater must be treated or hauled off-site for proper disposal.




- ☐ Avoid paving and seal coating in wet weather or when rain is forecast, to prevent materials that have not cured from contacting stormwater runoff.
- ☐ Cover storm drain inlets and manholes when applying seal coat, slurry seal, fog seal, or similar materials.
- ☐ Collect and recycle or appropriately dispose of excess abrasive gravel or sand. Do NOT sweep or wash it into gutters.

- ☐ Protect storm drain inlets during saw cutting.
- ☐ If saw cut slurry enters a catch basin, clean it up immediately.
- ☐ Shovel or vacuum saw cut slurry deposits and remove from the site. When making saw cuts, use as little water as possible. Sweep up, and properly dispose of all residues.



- ☐ Never clean brushes or rinse paint containers into a street, gutter, storm drain, or stream.
- ☐ For water-based paints, paint out brushes to the extent possible, and rinse into a drain that goes to the sanitary sewer. Never pour paint down a storm drain.
- ☐ For oil-based paints, paint out brushes to the extent possible and clean with thinner or solvent in a proper container. Filter and reuse thinners and solvents. Dispose of excess liquids as hazardous waste.
- ☐ Sweep up or collect paint chips and dust from non-hazardous dry stripping and sand blasting into plastic drop cloths and dispose of as trash.
- ☐ Chemical paint stripping residue and chips and dust from marine paints or paints containing lead, mercury, or tributyltin must be disposed of as hazardous waste. Lead based paint removal requires a state certified contractor.



250 Hamilton Avenue  
Palo Alto, CA 94301  
650.329.2211  
cityofpaloalto.org




S				DESIGNED MRL					 575 MARKET STREET SUITE 3700 SAN FRANCISCO, CA 94105 T 415.896.5900 WWW.ESASSOC.COM	 CITY OF <b>PALO ALTO</b>	CITY OF PALO ALTO PALO ALTO HORIZONTAL LEVEE PILOT PROJECT	VERIFY SCALES BAR IS ONE INCH ON ORIGINAL DRAWING 0  1" IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY	DATE NOVEMBER 3, 2023 DRAWING NO. G09 SHEET NO. 9 OF 45	G
				DRAWN DPH/AGHC										
				CHECKED MRL										
	REV	DATE	BY	DESCRIPTION							POLLUTION PREVENTION			










- NOTES**
1. THE CONTRACTOR SHALL IDENTIFY, LOCATE, AND PROTECT ALL EXISTING UTILITIES WITHIN THE LIMITS OF WORK, INCLUDING ONSITE AND OFFSITE ACCESS ROUTES.
  2. THE LOCATION OF EXISTING UTILITIES AND UNDERGROUND FACILITIES KNOWN TO THE CITY ARE SHOWN IN THEIR APPROXIMATE LOCATION BASED ON INFORMATION AVAILABLE AT THE TIME THE DRAWINGS WERE PREPARED. THE ACTUAL LOCATION, SIZE, TYPE AND NUMBER OF UTILITIES AND UNDERGROUND FACILITIES MAY DIFFER FROM THAT SHOWN, AND UTILITIES OR UNDERGROUND FACILITIES MAY BE PRESENT THAT ARE NOT SHOWN.
  3. OBTAIN BEST AVAILABLE CURRENT INFORMATION ON LOCATION, IDENTIFICATION AND MARKING OF EXISTING UTILITIES, PIPING AND CONDUITS AND OTHER UNDERGROUND FACILITIES BEFORE BEGINNING ANY EXCAVATION. CALL UNDERGROUND SERVICE ALERT FOR INFORMATION AT LEAST 48 HOURS IN ADVANCE OF BEGINNING WORK.
  4. CONTRACTOR SHALL DISPOSE OF ALL TRASH AND DEMOLITION DEBRIS AT APPROPRIATE LOCATION, SEE SPECIFICATIONS.
  5. PROTECT (E) OVERHEAD POWER LINES. CONTRACTOR SHALL EXERCISE CAUTION WHEN WORKING AROUND AND TRAVERSING UNDER THE OVERHEAD POWER LINES.
  6. REMOVE (E) ABANDONED W4 LINE FROM WITHIN THE LIMITS OF WORK. CAP (E) LINE AT END OF REMAINING LINE AS APPROVED BY THE RESIDENT ENGINEER.
  7. CONTRACTOR SHALL CCTV CONDITION OF EXISTING PIPE PRE- AND POST-CONSTRUCTION TO VERIFY THE CONDITION DOES NOT DETERIORATE DUE TO PROPOSED CONSTRUCTION AND NEW MATERIAL LOADS. SEE SPECIFICATIONS.
  8. CONTRACTOR SHALL MANAGE STORM DRAIN FLOWS DURING EARTHWORK UNTIL (N) STORMWATER SWALE AND (N) CULVERTS ARE INSTALLED AND OPERATIONAL. MAINTAIN PUMP AND PIPING AS NEEDED TO CONTROL WATER DURING WORK.

**EXISTING CONDITIONS AND DEMOLITION - LEVEE AREA**  
PLAN  
SCALE: 1" = 20'




<div>DESIGNED MRL DRAWN DPH/AGHC CHECKED MRL</div>				<div>REGISTERED PROFESSIONAL ENGINEER MARK R. LINDLEY C 66701 EXP. 9/30/22 CIVIL STATE OF CALIFORNIA</div>	<div>ESA 575 MARKET STREET SUITE 3700 SAN FRANCISCO, CA 94105 T 415.896.5900 WWW.ESASOC.COM</div>		<div>CITY OF PALO ALTO</div>	<div>CITY OF PALO ALTO PALO ALTO HORIZONTAL LEVEE PILOT PROJECT</div>		<div>VERIFY SCALES BAR IS ONE INCH ON ORIGINAL DRAWING 0 1" IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY</div>		<div>DATE NOVEMBER 3, 2023 DRAWING NO. G12 SHEET NO. 12 OF 45</div>
REV	DATE	BY	DESCRIPTION									
1												
2												
3												
4												
5												
6												
7												
8												
9												
10												
11												
12												
13												

FILENAME: G12 EXISTING CONDITIONS AND DEMOLITION - LEVEE AREA 11-03-23 04:20pm D:\work\X-PA\Building\Topo\X-PA\Project Limits\X-PA\_Permit\X-TBLR-PaloAlto-Border\X-PA\_ESA\_Survey\X-PA\_Building\_Schedule\X-PA\_Building\_Schedule\_KC-11-03-23 04:20pm

Last Saved By: oto 4-12-18 02:36pm






## GRADING PLAN

## PLAN

SCALE: 1" = 20'



## NOTES

1. GRADING SECTIONS SHOWN ON SHEETS C07 TO C10.

07			
REV	DATE	BY	DESCRIPTION

DESIGNED
MRL
DRAWN
DPH/AGHC
CHECKED
MRL



575 MARKET STREET  
SUITE 3700  
SAN FRANCISCO, CA 94105  
T 415.896.5900  
WWW.ESASSOC.COM



CITY OF  
**PALO ALTO**

CITY OF PALO ALTO  
PALO ALTO HORIZONTAL LEVEE PILOT PROJECT

## GRADING PLAN

VERIFY SCALES	
1. <i>Depression</i>	10
2. <i>Anxiety</i>	10
3. <i>Stress</i>	10
4. <i>Self-esteem</i>	10
5. <i>Life satisfaction</i>	10
6. <i>Resilience</i>	10
7. <i>Optimism</i>	10
8. <i>Gratitude</i>	10
9. <i>Emotional stability</i>	10
10. <i>Interpersonal skills</i>	10
11. <i>Problem-solving skills</i>	10
12. <i>Emotional regulation</i>	10
13. <i>Self-awareness</i>	10
14. <i>Empathy</i>	10
15. <i>Communication skills</i>	10
16. <i>Conflict resolution</i>	10
17. <i>Decision-making skills</i>	10
18. <i>Time management</i>	10
19. <i>Organization skills</i>	10
20. <i>Goal setting</i>	10
21. <i>Stress management</i>	10
22. <i>Emotional intelligence</i>	10
23. <i>Self-motivation</i>	10
24. <i>Resilience</i>	10
25. <i>Optimism</i>	10
26. <i>Gratitude</i>	10
27. <i>Emotional stability</i>	10
28. <i>Interpersonal skills</i>	10
29. <i>Problem-solving skills</i>	10
30. <i>Emotional regulation</i>	10
31. <i>Self-awareness</i>	10
32. <i>Empathy</i>	10
33. <i>Communication skills</i>	10
34. <i>Conflict resolution</i>	10
35. <i>Decision-making skills</i>	10
36. <i>Time management</i>	10
37. <i>Organization skills</i>	10
38. <i>Goal setting</i>	10
39. <i>Stress management</i>	10
40. <i>Emotional intelligence</i>	10
41. <i>Self-motivation</i>	10
42. <i>Resilience</i>	10
43. <i>Optimism</i>	10
44. <i>Gratitude</i>	10
45. <i>Emotional stability</i>	10
46. <i>Interpersonal skills</i>	10
47. <i>Problem-solving skills</i>	10
48. <i>Emotional regulation</i>	10
49. <i>Self-awareness</i>	10
50. <i>Empathy</i>	10
51. <i>Communication skills</i>	10
52. <i>Conflict resolution</i>	10
53. <i>Decision-making skills</i>	10
54. <i>Time management</i>	10
55. <i>Organization skills</i>	10
56. <i>Goal setting</i>	10
57. <i>Stress management</i>	10
58. <i>Emotional intelligence</i>	10
59. <i>Self-motivation</i>	10
60. <i>Resilience</i>	10
61. <i>Optimism</i>	10
62. <i>Gratitude</i>	10
63. <i>Emotional stability</i>	10
64. <i>Interpersonal skills</i>	10
65. <i>Problem-solving skills</i>	10
66. <i>Emotional regulation</i>	10
67. <i>Self-awareness</i>	10
68. <i>Empathy</i>	10
69. <i>Communication skills</i>	10
70. <i>Conflict resolution</i>	10
71. <i>Decision-making skills</i>	10
72. <i>Time management</i>	10
73. <i>Organization skills</i>	10
74. <i>Goal setting</i>	10
75. <i>Stress management</i>	10
76. <i>Emotional intelligence</i>	10
77. <i>Self-motivation</i>	10
78. <i>Resilience</i>	10
79. <i>Optimism</i>	10
80. <i>Gratitude</i>	10
81. <i>Emotional stability</i>	10
82. <i>Interpersonal skills</i>	10
83. <i>Problem-solving skills</i>	10
84. <i>Emotional regulation</i>	10
85. <i>Self-awareness</i>	10
86. <i>Empathy</i>	10
87. <i>Communication skills</i>	10
88. <i>Conflict resolution</i>	10
89. <i>Decision-making skills</i>	10
90. <i>Time management</i>	10
91. <i>Organization skills</i>	10
92. <i>Goal setting</i>	10
93. <i>Stress management</i>	10
94. <i>Emotional intelligence</i>	10
95. <i>Self-motivation</i>	10
96. <i>Resilience</i>	10
97. <i>Optimism</i>	10
98. <i>Gratitude</i>	10
99. <i>Emotional stability</i>	10
100. <i>Interpersonal skills</i>	10

BAR IS ONE INCH ON

DATE \_\_\_\_\_


NOVEMBER 3, 2021

DRAWING NO.

C01


SHEET NO.

Last Saved By: otc 4-12-18 02:38pm



**A** TYPICAL SECTION - RIDGES/HIGH & WIDE  
SECTION

SCALE: 1" = 10' H  
1" = 5' V




**B** TYPICAL SECTION - SWALES  
SECTION

SCALE: 1" = 10' H  
1" = 5' V

**NOTES**


1. SEGREGATE LEVEE, FINE AND COARSE MATERIAL ENCOUNTERED DURING EXCAVATION OF SITE TO SUBGRADE. DURING FILL OPERATIONS, PRIORITIZE PLACEMENT OF LEVEE MATERIAL FOR LEVEE CORE, AND PLACE COARSE MATERIAL ON THE RIDGES AND FINE MATERIALS IN THE SWALES. TRANSITION FROM COARSE MATERIAL TO FINE MATERIAL BETWEEN RIDGES AND SWALES.
2. SUBSURFACE TREATMENT MATERIAL COMPRISED OF A BLEND OF PERMEABLE MATERIAL AND COMPOSTED WOOD CHIPS.
3. SAND FILTER COMPRISED OF A BLEND OF SAND AND WOOD FINES.
4. TREATMENT AREA COARSE AND FINE MATERIAL INCLUDES A BLEND OF NATIVE MATERIAL WITH SAND AND COMPOSTED WOOD FINES.
5. ALL ELEVATIONS ARE ON NORTH AMERICAN VERTICAL DATUM 1988 (NAVD88).




				DESIGNED MRL				 <div>575 MARKET STREET SUITE 3700 SAN FRANCISCO, CA 94105 T 415.896.5900 WWW.ESASSOC.COM</div>		CITY OF PALO ALTO PALO ALTO HORIZONTAL LEVEE PILOT PROJECT		VERIFY SCALES	DATE NOVEMBER 3, 2023
				DRAWN DPH/AGHC						BAR IS ONE INCH ON ORIGINAL DRAWING	DRAWING NO.		
				CHECKED MRL						0  1"	C02		
										IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY	SHEET NO. 14 OF 45		
REV	DATE	BY	DESCRIPTION							TYPICAL GRADING SECTIONS			

FILENAME: C:\G:\C02 GRADING SECTIONS 4\_11-03-23 04:21pm D:\work\X-PA-Profile\X-TALK-PaloAlto-Border\X-C-02






**INFILTRATOR**  
SECTION SCALE: 1" = 20' H  
1" = 5' V






D TREATMENT ZONE  
 C01 SECTION SCALE: 1" = 20' H  
 1" = 5' V



ECOTONE HABITAT SLOPE  
SECTION SCALE: 1" = 20' H  
1" = 5' V



## NOTES

1. SECTIONS ON THIS SHT ARE CENTERED ON B1-LINE (N) BERM TRAIL STA 3+36 SECTION.
2. SEE SHT C04 FOR TREATMENT ZONE LAYER DETAILS.
3. SEE SHT C06 FOR MATERIAL PLACEMENT PLAN VIEW DETAILS.
4. IN THE INFILTRATOR CHAMBER AREA: ALONG RIDGES PLACE 4-INCH TREATMENT AREA COARSE MATERIAL SOIL CAP ABOVE SAND FILTER AND ALONG SWALES, PLACE 4-INCH TREATMENT AREA FINE MATERIAL SOIL CAP ABOVE SAND FILTER.
5. IN THE TREATMENT ZONE: ALONG RIDGES, PLACE 1.5-FT TREATMENT AREA COARSE MATERIAL ABOVE SAND FILTER AND ALONG SWALES, PLACE 1.5-FT TREATMENT AREA FINE MATERIAL ABOVE SAND FILTER.
6. ALONG THE HABITAT SLOPES, PLACE COARSE AND FINE NATIVE MATERIAL AT RIDGES AND SWALES; TRANSITION FROM COARSE TO FINE MATERIAL BETWEEN THE RIDGES AND SLOPES.

G			
	REV	DATE	BY DESCRIPTION

DESIGNED
MRL
DRAWN
DPH/AGHC
CHECKED
MRL



575 MARKET STREET  
SUITE 3700  
SAN FRANCISCO, CA 94105  
T 415.896.5900  
WWW.ESASSOC.COM



CITY OF PALO ALTO  
PALO ALTO HORIZONTAL LEVEE PILOT PROJECT

## HORIZONTAL LEVEE SECTIONS

VERIFY SCALES	
---------------	--


NO

BAR IS ONE INCH ON  
ORIGINAL DRAWING


0 1"



IF NOT ONE INCH ON  
THIS SHEET, ADJUST



FILENAME: C:\00 GRADING SECTIONS 4\_11-03-23 04:22pm D:\0001\X-PA-Profile\X-TBLK-PaloAlto-Border 1-1-23



DESIGNED MRL
DRAWN DPH/AGHC
CHECKED MRL




CITY OF  
**PALO ALTO**

## CIVIL DETAILS

DATE  
NOVEMBER 3, 2023

DRAWING NO.  
C05

SHEET NO.  
17 OF 45



MATERIAL LEGEND

NATIVE MATERIAL	
NATIVE FINE MATERIAL	
NATIVE COARSE MATERIAL	
TREATMENT ZONE FINE MATERIAL	
TREATMENT ZONE COARSE MATERIAL	
SUBSURFACE TREATMENT MATERIAL	
BERM MATERIAL	
BIOTREATMENT SOIL	


NOTES

- BOUNDARY OF FINE AND COARSE GRAINED NATIVE MATERIAL IS APPROXIMATE. THE CONTRACTOR SHALL PRIORITIZE THE COARSEST NATIVE MATERIAL FOR PLACEMENT IN THE HIGHEST RIDGE ZONES AND THE FINEST NATIVE MATERIAL FOR PLACEMENT IN THE LOWEST PORTIONS OF THE SWALES.
- IN BETWEEN RIDGES AND SWALES, MATERIAL SHALL BE GENERALLY CLASSIFIED AS COARSE TRANSITIONING TO FINE TO FILL OUT THE REMAINING HIGHER TO LOWER GRADES ALONG THE ECOTONE.
- ESTIMATED VOLUMES ARE BASED ON BANK CUBIC YARDS, AS CALCULATED AS THE DIFFERENCE OF EXISTING AND DESIGN GRADES (INCLUDING SUBGRADES).
- CONTRACTOR RESPONSIBLE FOR ESTIMATING ACTUAL VOLUMES AND SHALL ACCOUNT FOR VOLUME ADJUSTMENTS (SHRINKAGE, DRYING, BULKING, LOSSES, ETC.)

MATERIAL PLACEMENT PLAN

PLAN  
MATERIAL PLACEMENT

SCALE: 1" = 20'



EXCAVATION	MATERIAL TYPE	QUANTITY	UNIT
STRIP TOP 3-INCHES WITHIN GRADING FOOTPRINT	DISPOSAL	420	BCY
TOP 4 TO 12-INCHES LANDWARD SIDE OF LEVEE	NATIVE MATERIAL	930	BCY
ALL OTHER EXCAVATION	BERM MATERIAL	1620	BCY

FILL PLACEMENT LOCATION	MATERIAL TYPE	QUANTITY	UNIT	PRIMARY COMPONENTS													
				BERM MATERIAL		NATIVE MATERIAL		PERMEABLE MATERIAL		SAND		WOOD CHIPS		COMPOSTED WOOD FINES		BIOTREATMENT SOIL	
				% VOL	BCY	% VOL	BCY	% VOL	BCY	% VOL	BCY	% VOL	BCY	% VOL	BCY	% VOL	BCY
LEVEE BERM	BERM MATERIAL (ON-SITE)	1,130	BCY	100	1,130				-		-		-		-		-
	BERM MATERIAL (IMPORTED)	550	BCY	100	550												
SPUR TRAIL	NATIVE MATERIAL	440	BCY		-	100	440										
HABITAT SLOPE	FINE NATIVE MATERIAL	110	BCY		-	70	77		-	30	33		-		-		-
	COARSE NATIVE MATERIAL	150	BCY		-	40	60		-	60	90		-		-		-
TREATMENT ZONE	TREATMENT AREA FINE MATERIAL	70	BCY		-	60	42			30	21			10	7		
	TREATMENT AREA COARSE MATERIAL	320	BCY		-	30	96		-	60	192		-	10	32		-
	SAND FILTER	150	BCY		-		-		-	70	105		-	30	45		-
	SUBSURFACE TREATMENT MATERIAL	410	BCY		-		-	70	287		-	30	123		-		-
STORMWATER SWALE	BIOTREATMENT SOIL	44	BCY		-		-		-		-		-		-	100	44
TOTAL		3,374			1,680		715		287		441		123		84		44

REV	DATE	BY	DESCRIPTION

DESIGNED MRL
DRAWN DPH/AGHC
CHECKED MRL



575 MARKET STREET  
SUITE 3700  
SAN FRANCISCO, CA 94105  
T 415.896.5900  
WWW.ESASOC.COM




CITY OF PALO ALTO  
PALO ALTO HORIZONTAL LEVEE PILOT PROJECT


MATERIAL PLACEMENT PLAN

VERIFY SCALES  
BAR IS ONE INCH ON ORIGINAL DRAWING  
0 1" IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY


DATE  
NOVEMBER 3, 2023  
DRAWING NO.  
C06  
SHEET NO.  
18 OF 45



TRANSITION AT BERM STA 1+43  
GRADING SECTION SCALE: 1" = 10' H  
1" = 10' V




RIDGE AT BERM STA 1+86  
GRADING SECTION SCALE: 1" = 10' H  
1" = 10' V



TRANSITION AT BERM STA 2+26  
GRADING SECTION SCALE: 1" = 10' H  
1" = 10' V

NOTES  
1. GRADING SECTIONS SHOWN IN PLAN VIEW ON SHEET C01.



REV	DATE	BY	DESCRIPTION

DESIGNED  
MRL  
DRAWN  
DPH/AGHC  
CHECKED  
MRL



575 MARKET STREET  
SUITE 3700  
SAN FRANCISCO, CA 94105  
T 415.896.5900  
WWW.ESASSOC.COM



CITY OF PALO ALTO  
PALO ALTO HORIZONTAL LEVEE PILOT PROJECT


GRADING SECTIONS 1

VERIFY SCALES  
BAR IS ONE INCH ON  
ORIGINAL DRAWING  
0 1" IF NOT ONE INCH ON  
THIS SHEET, ADJUST  
SCALES ACCORDINGLY

DATE  
NOVEMBER 3, 2023  
DRAWING NO.  
C07  
SHEET NO.  
19 OF 45

FILENAME C:\01 GRADING SECTIONS 4\_11-03-23 04:23pm D:\0001\X-PALM\Palto-Hor-Border 11-03-23 04:23pm





DESIGNED MRL						575 MARKET STREET SUITE 3700 SAN FRANCISCO, CA 94105 T 415.896.5900 WWW.ESASSOC.COM		CITY OF PALO ALTO PALO ALTO HORIZONTAL LEVEE PILOT PROJECT				VERIFY SCALES BAR IS ONE INCH ON ORIGINAL DRAWING 0 1" IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY	DATE NOVEMBER 3, 2023 DRAWING NO. C08 SHEET NO. 20 OF 45
DRAWN DPH/AGHC								GRADING SECTIONS 2					
CHECKED MRL													
REV	DATE	BY	DESCRIPTION										
1													
2													
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													

Last Saved By: oto 4-12-18 02:36pm















DESIGNED	MRL
DRAWN	DPH/AGHC
CHECKED	MRL



CITY OF  
**PALO ALTO**


**VERIFY SCALES**

BAR IS ONE INCH ON  
ORIGINAL DRAWING


0  1"

IF NOT ONE INCH ON  
THIS SHEET, ADJUST  
SCALES ACCORDINGLY


DATE NOVEMBER 3, 2023
DRAWING NO. C13
SHEET NO. 25 OF 45




1 END SECTION  
C01 PLAN SCALE: 1" = 1'




1A END SECTION  
SECTION SCALE: 1" = 1'




1C END SECTION CONNECTION  
DETAIL SCALE: 1" = 6"



1B END SECTION  
SECTION SCALE: 1" = 1'



2 FLAP GATE & PIPE SUPPORTS  
C01 PLAN SCALE: 1" = 1'



2A FLAP GATE & PIPE SUPPORTS  
SECTION SCALE: 1" = 1'

#### NOTES

- STORM DRAIN OUTFALL WITH FLAP GATE SHALL BE SUPPORTED BY PIPE SUPPORTS. PILES AND PIPE SUPPORT MEMBERS SHALL BE 8-INCH DIA STEEL PIPE PILE OR 6X6-INCH H-PILE. STEEL SHALL BE EPOXY COATED, SEE SPECS OR OWNER-APPROVED EQUAL.
- SUPPORT PILES SHALL BE DRIVEN TO REFUSAL OR 8 FEET MIN BELOW FINISHED GRADE
- APPROXIMATE DIMENSIONS OF END SECTION SHOWN. CONTRACTOR SHALL VERIFY WITH MANUFACTURER PRIOR TO INSTALLATION.

FILENAME: C14 STORM DRAIN DETAILS 11-03-23 04:24pm D:\oreff\X-TBLK-PaloAlto-Border\X\_PA\_Design\_Linkwork\K<<--

REV	DATE	BY	DESCRIPTION

DESIGNED  
MRL  
DRAWN  
DPH/AGHC  
CHECKED  
MRL



575 MARKET STREET  
SUITE 3700  
SAN FRANCISCO, CA 94105  
T 415.896.5900  
WWW.ESASSOC.COM




CITY OF PALO ALTO  
PALO ALTO HORIZONTAL LEVEE PILOT PROJECT

STORM DRAIN DETAILS

VERIFY SCALES  
BAR IS ONE INCH ON  
ORIGINAL DRAWING  
0 1"  
IF NOT ONE INCH ON  
THIS SHEET, ADJUST  
SCALES ACCORDINGLY

DATE  
NOVEMBER 3, 2023  
DRAWING NO.  
C14  
SHEET NO.  
26 OF 45



REV	DATE	BY	DESCRIPTION

DESIGNED  
MRL

DRAWN  
DPH/AGHC

CHECKED  
MRL



575 MARKET STREET  
SUITE 3700  
SAN FRANCISCO, CA 94105  
T 415.896.5900  
WWW.ESASOC.COM



CITY OF PALO ALTO  
PALO ALTO HORIZONTAL LEVEE PILOT PROJECT

PUBLIC ACCESS DETAILS


VERIFY SCALES  
BAR IS ONE INCH ON ORIGINAL DRAWING  
0 1" IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY

DATE  
NOVEMBER 3, 2023

DRAWING NO.  
C15

SHEET NO.  
27 OF 45

1. ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS, THE PROJECT SWPPP, AND THE PROJECT PERMITS.
2. THE FOLLOWING BMPs AS OUTLINED IN, BUT NOT LIMITED TO, THE CONSTRUCTION BEST MANAGEMENT PRACTICE HANDBOOK, CALIFORNIA STORMWATER QUALITY ASSOCIATION (CASQA), 2009, OR THE LATEST REVISED EDITION, MAY APPLY DURING THE CONSTRUCTION OF THIS PROJECT (ADDITIONAL MEASURES MAY BE REQUIRED IF DEEMED APPROPRIATE BY CITY INSPECTORS):
  - a. SILT FENCE (SE-1);
  - b. FIBER ROLLS (BIODEGRADABLE COIR; SE-5);
  - c. STREET SWEEPING (SE-7);
  - d. STORM DRAIN INLET PROTECTION (SE-10);
  - e. STABILIZED CONSTRUCTION ENTRANCE/EXIT (TC-1);
  - f. STAGING AREA (NS-1, NS-8, NS-9, NS-10, NS-14, WM-01, WM-02, WM-04, WM-09, AND WM-10);
  - g. TEMPORARY STOCKPILE AREA (WM-03);
  - h. INTERIM HYDROSEEDING (EC-4);
  - i. DEWATERING OPERATION (NS-2);
  - j. CLEAR WATER DIVERSION (NS-5);
  - k. DEMOLITION REMOVAL ADJACENT TO WATER (NS-15).
3. THE BMPs SHOWN ON THIS PLAN ARE SUBJECT TO CHANGE. IF ADDITIONAL EROSION CONTROL MEASURES ARE NEEDED TO PROTECT THE SITE AND NEARBY AREAS, SUCH MEASURES SHALL BE INSTALLED AT THE DISCRETION OF THE RESIDENT ENGINEER AND NOTIFY THE DESIGN ENGINEER.
4. CONTRACTOR SHALL BE RESPONSIBLE FOR MONITORING EROSION AND SEDIMENT MEASURES PRIOR TO, DURING, AND AFTER STORM EVENTS.
5. CONTRACTOR SHALL UPDATE THE PLANS TO REFLECT CHANGING SITE CONDITIONS. PLAN UPDATES SHALL BE BASED UPON GENERAL SURVEY DATA. EROSION CONTROL EFFECTIVENESS SHALL ALSO BE MONITORING AND THE PLANS UPGRADED AS REQUIRED TO PREVENT SIGNIFICANT QUANTITIES OF SEDIMENT FROM ENTERING THE BAY AND OTHER WATERS.
6. CHANGES TO THIS SEDIMENT AND EROSION CONTROL PLAN SHALL BE MADE TO MEET FIELD CONDITIONS ONLY WITH THE APPROVAL OF OR AT THE DIRECTION OF THE RESIDENT ENGINEER.
7. LIMITS OF DISTURBED AREAS ARE APPROXIMATE ONLY. EROSION CONTROL MEASURES MUST BE MAINTAINED UNTIL DISTURBED AREAS ARE STABILIZED.
8. CONSTRUCTION BMPs WILL REMAIN IN PLACE AND BE MAINTAINED OR REPLACED AS NECESSARY UNTIL THE PERMANENT SITE IMPROVEMENTS AND STORMWATER TREATMENT FACILITIES ARE IN PLACE. IF CONSTRUCTION IS NOT COMPLETE BY THE START OF THE WET SEASON (OCTOBER 15 THROUGH APRIL 15, OR PRIOR TO A RAINFALL EVENT PREDICTED PRIOR TO OCTOBER 15), A WINTERIZATION PROGRAM WILL BE IMPLEMENTED TO MINIMIZE THE POTENTIAL FOR EROSION AND SEDIMENTATION. AS APPROXIMATE TO THE SITE AND STATUS OF CONSTRUCTION, WINTERIZATION REQUIREMENTS SHALL INCLUDE INSPECTING/MAINTAINING/CLEANING ALL SOIL EROSION AND SEDIMENTATION CONTROLS PRIOR TO, DURING, AND IMMEDIATELY AFTER EACH STORM EVENT; STABILIZATION DISTURBED SOILS THROUGH TEMPORARY OR PERMANENT SEEDING, MULCHING, MATTING, TARPING OR OTHER PHYSICAL MEANS; ROCKING UNPAVED VEHICLE ACCESS TO LIMIT DISPERSION OF MULCH ONTO PUBLIC RIGHT-OF-WAY; AND COVERING/TARPING STORED CONSTRUCTION MATERIALS, FUELS, AND OTHER



11. CONSTRUCTION ENTRANCES SHALL BE INSTALLED PRIOR TO THE COMMENCEMENT OF GRADING IN THE LEVEE AREA. CONSTRUCTION TRAFFIC ENTERING ONTO THE PAVED ROADS MUST CROSS THE STABILIZED CONSTRUCTION ENTRANCE WAYS.
12. INLET PROTECTION SHALL BE INSTALLED AT OPEN INLETS PREVENT SEDIMENT FROM ENTERING THE STORM DRAIN SYSTEM. INLETS NOT USED IN CONJUNCTION WITH EROSION CONTROL ARE TO BE BLOCKED TO PREVENT ENTRY OF SEDIMENT.
13. PRIOR TO EARTH-MOVING ACTIVITIES IN THE LEVEE AREA, CONTRACTOR SHALL INSTALL AND MAINTAIN A TEMPORARY CAP ON CULVERT TO PREVENT TIDAL FLOW INTO WORK AREA. CAP SHOULD BE MAINTAINED UNTIL EXISTING TRAIL BERM IS LOWERED.

DESIGNED	MRL
DRAWN	DPH/AGHC
CHECKED	MRL



575 MARKET STREET  
SUITE 3700  
SAN FRANCISCO, CA 94105  
T 415.896.5900  
WWW.ESASSOC.COM

CITY OF  
**PALO ALTO**

## SEDIMENT AND EROSION CONTROL PLAN


THIS SHEET, ADJUST  
SCALES ACCORDINGLY

SHEET NO.

YARD PIPING LEGEND			YARD PIPING LEGEND (CONT'D)			GENERAL CIVIL NOTES																																																																								
<p>NOTES:</p> <p>SYMBOLGY SHOWN IS FOR SINGLE LINE PIPING. DOUBLE LINE PIPING SYMBOLS ARE SIMILAR.</p> <p>VALVES</p> <p>GATE VALVE</p> <p>GLOBE VALVE</p> <p>BALL VALVE</p> <p>CHECK VALVE</p> <p>BUTTERFLY VALVE</p> <p>DIAPHRAGM VALVE</p> <p>PRESSURE RELIEF VALVE</p> <p>PLUG VALVE</p> <p>NEEDLE VALVE</p> <p>PRESSURE REDUCING VALVE</p> <p>AIR RELIEF / VACUUM VALVE</p> <p>A = AIR RELIEF</p> <p>V = VACUUM</p> <p>PRESSURE REGULATING VALVE</p>			<p>MISCELLANEOUS</p> <p>VARIABLE AREA METER</p> <p>ROTAMETER</p> <p>UNION</p> <p>WYE-STRAINER</p> <p>LINE SIZE CHANGE (CONCENTRIC REDUCER)</p> <p>FLEXIBLE HOSE OR TUBING</p> <p>FLEXIBLE PIPING CONNECTION</p> <p>LINE SIZE CHANGE (CONCENTRIC REDUCER)</p> <p>LINE SIZE CHANGE (ECCENTRIC REDUCER)</p> <p>LINE TURNING DOWN</p> <p>LINE TURNING UP</p> <p>BLIND FLANGE</p> <p>PIPE JOINT (SEE SPECS FOR REQUIREMENTS)</p> <p>SLEEVE TYPE COUPLING</p> <p>FLANGED COUPLING ADAPTER (FCA)</p> <p>FLEXIBLE CONNECTION</p> <p>HARNESSED MECHANICAL COUPLING</p> <p>PRESSURE GAGE (W/COCK)</p> <p>TRAP</p> <p>QUICK DISCONNECT</p> <p>CAM &amp; GROOVE COUPLING</p> <p>CAP or PLUG</p> <p>INTERIOR CLEANOUT</p> <p>HOSE VALVE, HOSE BIBB OR FLUSHING CONNECTION</p> <p>HOSE RACK</p> <p>FLOOR DRAIN</p> <p>PIPE IN SECTION</p> <p>BELL UP (PLAN)</p> <p>BELL UP (SECTION OR SCHEMATIC)</p>			<p>GENERAL NOTES</p> <p>1. TYPES, LOCATIONS, SIZES, AND DEPTHS OF EXISTING UNDERGROUND UTILITIES AND FACILITIES AS SHOWN ON THESE IMPROVEMENT PLANS WERE OBTAINED FROM SOURCES OF VARYING RELIABILITY. A REASONABLE EFFORT HAS BEEN MADE TO LOCATE AND DELINEATE ALL KNOWN UNDERGROUND FACILITIES. OWNER AND ENGINEER ASSUME NO RESPONSIBILITY FOR COMPLETENESS OR ACCURACY OF DELINEATION OF SUCH UNDERGROUND FACILITIES. NOR FOR EXISTENCE OF OTHER BURIED OBJECTS OR FACILITIES WHICH ARE ENCOUNTERED BUT WHICH ARE NOT SHOWN ON THESE PLANS. CONTRACTOR SHALL EXPOSE ALL UNDERGROUND FACILITIES THAT ARE TO BE CONNECTED TO FOR VERIFICATION OF LOCATION AND ELEVATION.</p> <p>2. LOCATION SHOWN FOR ALL PIPING BETWEEN NEW AND EXISTING FACILITIES IS APPROXIMATE AND DEPENDS ON LOCATION OF EXISTING PIPING AND OTHER IMPROVEMENTS. CONTRACTOR IS REQUIRED TO FOLLOW ALIGNMENT SHOWN AS CLOSELY AS POSSIBLE AFTER DETERMINING EXACT LOCATION OF EXISTING FACILITIES.</p> <p>3. COORDINATE ALL PIPING WITH SITE ELECTRICAL WORK IN EXISTING PLANT. DO NOT START PIPING UNTIL ELECTRICAL CONDUITS AND DUCT BANKS ARE LOCATED.</p> <p>4. SMALL DIAMETER (LESS THAN 4") WATER AND OTHER MISCELLANEOUS PIPING EXISTS THROUGHOUT SITE AREA. CONTRACTOR IS REQUIRED TO REPAIR PIPING DAMAGED BY CONSTRUCTION AND/OR REALIGN PIPING AS REQUIRED TO CONSTRUCT IMPROVEMENTS UNDER THIS CONTRACT.</p> <p>5. ALL PAVING, LANDSCAPING, PIPING, AND OTHER EXISTING FACILITIES NOT DESIGNATED FOR REMOVAL/DEMOLITION DURING CONSTRUCTION OF NEW FACILITIES TO BE PROTECTED IN PLACE OR REPLACED IN KIND.</p> <p>6. SELECT MECHANICAL EQUIPMENT TO MINIMIZE DAMAGE TO EXISTING PAVEMENT AT PROJECT SITE AND AT ALL ROADS USED TO MOVE MATERIAL AND EQUIPMENT TO AND FROM PROJECT. REPLACE ALL DAMAGED ASPHALT CONCRETE PAVEMENT IN ACCORDANCE WITH CONTRACT DOCUMENTS.</p> <p>7. COMPLY WITH ALL STATE AND COUNTY LAWS AND ORDINANCES RELATING TO SAFETY AND CHARACTER OF WORK, EQUIPMENT AND LABOR. THIS SHALL INCLUDE, BUT NOT LIMITED TO, SHORING OF TRENCHES, VENTILATION OF CONFINED SPACES, CONFORMANCE TO TRAFFIC CONTROL REQUIREMENTS, INCLUDING PROVISION AND MAINTENANCE OF BARRICADES AND PREPARATION AND IMPLEMENTATION OF TRAFFIC CONTROL PLANS AS REQUIRED.</p> <p>8. ARRANGE FOR ALL REQUIRED INSPECTION. PRESENCE OR ABSENCE OF AN INSPECTOR WILL NOT RELIEVE CONTRACTOR OF FULL RESPONSIBILITY FOR PROPER PERFORMANCE OF WORK.</p> <p>9. WORK TO BE RESTRICTED TO LIMITS OF OWNERS PROPERTY, TEMPORARY CONSTRUCTION EASEMENTS, PERMANENT EASEMENTS, AND RIGHTS-OF-WAYS.</p> <p>10. CONTRACTOR SHALL VERIFY ALL CONTROLLING FIELD DIMENSIONS BEFORE ORDERING OR FABRICATING MATERIAL.</p> <p>11. WHEN EXCAVATION IS REQUIRED AROUND EXISTING UTILITIES THOSE UTILITIES SHALL BE SUPPORTED USING STEEL BEAMS OR OTHER SUITABLE SUPPORTS.</p> <p>12. PIPE SLOPES SHOWN ON PIPING PROFILES ARE APPROXIMATE. PIPES SHALL BE CONSTRUCTED TO INVERT ELEVATIONS SHOWN ON THESE DRAWINGS.</p>																																																																								
<table><tr><td>DESIGNED</td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td>DRAWN</td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td>CHECKED</td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td>REV</td><td>DATE</td><td>BY</td><td colspan="10">DESCRIPTION</td></tr></table>			DESIGNED													DRAWN													CHECKED													REV	DATE	BY	DESCRIPTION																									CITY OF PALO ALTO PALO ALTO HORIZONTAL LEVEE PILOT PROJECT			VERIFY SCALES BAR IS ONE INCH ON ORIGINAL DRAWING 0 1" IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY			DATE NOVEMBER 3, 2023 DRAWING NO. M01 SHEET NO. 29 OF 45		
DESIGNED																																																																														
DRAWN																																																																														
CHECKED																																																																														
REV	DATE	BY	DESCRIPTION																																																																											









NOTES:

1. POT HOLE EXISTING PIPE AT LOCATION OF NEW HDPE FITTING. CONFIRM DEPTH OF CONNECTION AND DETERMINE PRECISE BEND ANGLE OF FITTING PRIOR TO SUBMITTAL OF HDPE SHOP DRAWINGS.



SECTION B  
1/4"=1'-0"



NOTE:

1. CUT (E) BOTTOM RAIL TO ACCOMMODATE PIPE. LEAVE 2" LONG MAX STUB. SEAL STUB END WITH WELDED 1/4" CAP PL. GRIND WELDS AND EDGES SMOOTH. REPAIR WITH COLD GALVANIZING SPRAY.

2. CUT 10" LONG MAX SECTION OUT OF (E) TOEBOARD TO ACCOMMODATE PIPE SUPPORT INSTALLATION. GRIND ENDS SMOOTH AND REPAIR WITH COLD GALVANIZING SPRAY. CLOSE GAP WITH 12" LONG SECTION OF MATCHING, HOT DIP GALVANIZED TOEBOARD, FASTENED AT EA END W/ (1)-HDG 1/2" Ø BOLT, CENTERED ON 1" OVERLAP.

3. GRIND WELDS SMOOTH AND REPAIR WITH COLD GALVANIZING SPRAY.

SECTION C  
NOT TO SCALE


REV	DATE	BY	DESCRIPTION
1			
2			
3			
4			
5			
6			
7			
8			
9			
10			
11			
12			
13			

DESIGNED T. HOFFMAN
DRAWN S. LARI
CHECKED T. KONONICKAS

CITY OF PALO ALTO  
PALO ALTO HORIZONTAL LEVEE PILOT PROJECT

**PUMPING PLAN AND SECTIONS**

VERIFY SCALES BAR IS ONE INCH ON ORIGINAL DRAWING 0 1" IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY	DATE NOVEMBER 3, 2023 DRAWING NO. M03 SHEET NO. 31 OF 45
---	---



- NOTES:
1. PIPING AND EQUIPMENT THAT IS REMOVED AND WHICH IS NOT SHOWN TO BE RELOCATED OR SALVAGED SHALL BE DISPOSED OF BY THE CONTRACTOR.
  2. CONTRACTOR SHALL ASSUME (E) SUPPORTS TO BE DEMOLISHED ARE SIMILAR TO THE SUPPORTS REPLACING THEM.
  3. ALL NEW PIPING ON THIS SHEET SHALL BE 12"Ø WELDED STEEL.

FILENAME: W4 9-08-23 01:12pm SLAR XREFS: X-TBLK-PadAuto-Border K<<-

REV	DATE	BY	DESCRIPTION

DESIGNED T. HOFFMAN
DRAWN S. LARI
CHECKED T. KONTONICKAS





CITY OF PALO ALTO  
PALO ALTO HORIZONTAL LEVEE PILOT PROJECT  
I

RENZEL MARSH PUMP  
BYPASS UPGRADE (ADMIN BLDG)

VERIFY SCALES  
BAR IS ONE INCH ON ORIGINAL DRAWING  
0 1"  
IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY

DATE  
NOVEMBER 3, 2023  
DRAWING NO.  
M04  
SHEET NO.  
32 OF 45

FILENAME: M05\_11-03-23\_12:21pm BELERT | XREFS: X-TBLK-PaloAlto-Border\_1 | X\_Pa\_existing\_Sectures\_1 | X\_Pa\_Boundary | X\_Pa\_ESA\_Survey | X\_Pa\_Grading\_Limits | X\_Pa\_Parcel | X\_Pa\_Project\_Limits | X\_Pa\_Existing\_Topo | Utilities | Basecamp | Mapplan | PaloAlto\_Landfill\_2015\_Plan | Mapplan\_08February2015 |




EFFLUENT PIPE

PLAN

SCALE: 1" = 20'

NOTES:

1. PROVIDE 12" MINIMUM CLEAR BETWEEN PIPE CROSSINGS.
2. EXISTING PIPING SHOWN IN APPROXIMATE LOCATION. CONTRACTOR TO VERIFY PIPING SIZE, LOCATION, AND DEPTH.



EFFLUENT PIPE

PROFILE

SCALE: 1" = 20'

REV	DATE	BY	DESCRIPTION

DESIGNED  
T. HOFFMAN  
DRAWN  
S. LARI  
CHECKED  
T. KONTONICKAS




CITY OF PALO ALTO  
PALO ALTO HORIZONTAL LEVEE PILOT PROJECT

EFFLUENT PIPE PLAN AND PROFILE 1

VERIFY SCALES  
BAR IS ONE INCH ON ORIGINAL DRAWING  
0 1"  
IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY

DATE  
NOVEMBER 3, 2023  
DRAWING NO.  
M05  
SHEET NO.  
33 OF 45


FILENAME: M06 9-08-23 12:27pm SLARI XREFS: X-TBLK-PaloAlto-Border\_1 X-Prop-additions-features\_1 X-PA-Boundary X-PA-ESA-Survey X-PA-Project-Limits X-PA-Profile X-PA-Existing-Topo EB\_USGS-2020(1) Utilities Basecamp Altmap PaloAlto-Landfill 2015 PLAN Altmap\_08February2015 K--



EFFLUENT PIPE  
PLAN

SCALE: 1" = 20'

- NOTES:
1. PROVIDE 12" MINIMUM CLEAR BETWEEN PIPE CROSSINGS.



EFFLUENT PIPE  
PROFILE

SCALE: 1" = 20'

REV	DATE	BY	DESCRIPTION

DESIGNED  
T. HOFFMAN  
DRAWN  
S. LARI  
CHECKED  
T. KONTONICKAS





CITY OF PALO ALTO  
PALO ALTO HORIZONTAL LEVEE PILOT PROJECT

EFFLUENT PIPE PLAN AND PROFILE 2


VERIFY SCALES  
BAR IS ONE INCH ON ORIGINAL DRAWING  
0 1"  
IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY

DATE  
NOVEMBER 3, 2023  
DRAWING NO.  
M06  
SHEET NO.  
34 OF 45

FILENAME: M07 9-08-23 12:28pm SLARI XREFS: X-TBLK-PaloAlto-Border\_1 X-rc-utilities-features\_1 X-PA-Boundary X-PA\_LSA\_Survey X-PA\_Existing\_Topo EB\_USGS-2020(1) Utilities Basemap Alameda PaloAlto\_Landfill\_2015\_PLAN Alameda\_08February2015 K--



EFFLUENT PIPE  
PLAN  
SCALE: 1" = 20'



EFFLUENT PIPE  
PROFILE  
SCALE: 1" = 20'

REV	DATE	BY	DESCRIPTION

DESIGNED  
T. HOFFMAN  
DRAWN  
S. LARI  
CHECKED  
T. KONTONICKAS



CITY OF PALO ALTO  
PALO ALTO HORIZONTAL LEVEE PILOT PROJECT


CONVEYANCE PIPE PLAN AND PROFILE 3

VERIFY SCALES  
BAR IS ONE INCH ON ORIGINAL DRAWING  
0 1"  
IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY

DATE  
NOVEMBER 3, 2023  
DRAWING NO.  
M07  
SHEET NO.  
35 OF 45



FILENAME: M08\_11-03-23\_12:45pm BELERT | XREFS: X-TRK-PaloAlto-Border\_1 | X-PA\_Boundary | X-PA\_ESA\_Survey | X-PA\_Project\_Limits | X-PA\_Parade | X-PA\_Design\_Topo | X-PA\_Design\_Linework | Utilities | Basecamp | Alignment | PaloAlto\_Landfill | 2023



- NOTES**
1. REFER TO CIVIL PLANS FOR GRADING OF LEVEE.
  2. PROVIDE CONSISTENT SLOPE BETWEEN IDENTIFIED INVERT ELEVATIONS WITHOUT LOCAL HIGH OR LOW POINTS.
  3. BEDDING AND BACKFILL MATERIAL FOR SINGLE AND DUAL PIPE TRENCH WITHIN LEVEE TO BE CLSM, STA 0+50 TO STA 4+48 THIS SHEET.

HORIZONTAL LEVEE EFFLUENT PIPE  
PLAN  
SCALE: 1" = 20'


REV	DATE	BY	DESCRIPTION

DESIGNED  
T. HOFFMAN  
DRAWN  
S. LARI  
CHECKED  
T. KONTONICKAS




CITY OF PALO ALTO  
PALO ALTO HORIZONTAL LEVEE PILOT PROJECT  
  
HORIZONTAL LEVEE SUPPLY PIPE PLAN

VERIFY SCALES BAR IS ONE INCH ON ORIGINAL DRAWING 0 1" IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY	DATE NOVEMBER 3, 2023 DRAWING NO. M08 SHEET NO. 36 OF 45
---	---




**TRENCH DETAIL**  
NOT TO SCALE




**Trenches  
Limits of Restoration**

City of Palo Alto Standard




**PLAN**




**SECTION**


**DISTRIBUTION BOX**  
3/4" = 1'-0"



**SECTION FLOW METER ASSEMBLY**  
1/2" = 1'-0"



**PIPE TRANSITION**  
NOT TO SCALE



**NOTES:**





































































1. UP TO 8"Ø PIPES ONLY
2. ALL SUPPORT MATERIALS TO BE SST

**SURFACE MOUNT MODULAR STRUT**  
NOT TO SCALE




CITY OF PALO ALTO  
PALO ALTO HORIZONTAL LEVEE PILOT PROJECT  
**MECHANICAL DETAILS 1**

VERIFY SCALES	DATE
BAR IS ONE INCH ON ORIGINAL DRAWING	NOVEMBER 3, 2023
0 1"	DRAWING NO.
IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY	M09
	SHEET NO.
	37 OF 45

	1	2	3	4	5	6	7	8	9	10	11	12	13		
	ONE LINE DIAGRAMS			CONTROL DIAGRAMS			PLAN DRAWINGS			PLAN DRAWINGS (CONTINUED)			GENERAL NOTES:		
A	<div><div></div><div>BUS CONNECTION OR CONNECTED WIRES</div></div> <div><div></div><div>TRANSFORMER</div></div> <div><div></div><div>AMPS DISCONNECT</div></div> <div><div></div><div>AMPS CIRCUIT BREAKER</div></div> <div><div></div><div>MCP n XX COMBINATION MOTOR STARTER MCP AND THERMAL OVERLOAD SIZED BY MANUFACTURER BASED ON SUBMITTED AND APPROVED MOTOR</div></div> <div><div></div><div>n NEMA SIZE</div></div> <div><div></div><div>XX TYPE: BLANK FULL VOLTAGE, NON-REVERSING FVR FULL VOLTAGE, REVERSING 2S2W FULL VOLTAGE, 2 SPEED, 2 WINDING</div></div> <div><div></div><div>INSTRUMENT OR DEVICE</div></div> <div><div></div><div>SURGE PROTECTION DEVICE</div></div> <div><div></div><div>XX TYPE: VFD VARIABLE FREQUENCY DRIVE RVSS REDUCED VOLTAGE SOLID STATE</div></div> <div><div></div><div>MOTOR LOAD n MOTOR HORSEPOWER</div></div> <div><div></div><div>n KW, KVA KW OR KVA RATED EQUIPMENT n LOAD VALUE IN KW OR KVA</div></div> <div><div></div><div>ENCLOSURE OR COMMON SUPPORT FOR COLLECTED EQUIPMENT (SKID, BACKBOARD, ETC.)</div></div> <div><div></div><div>KIRK KEY INTERLOCK</div></div>			<div><div></div><div>MOTOR CONTACTOR COIL</div></div> <div><div></div><div>RELAY COIL XX COIL TYPE: CR - CONTROL RELAY TR - TIMER RELAY n UNIQUE COIL IDENTIFIER</div></div> <div><div></div><div>SOLENOID VALVE</div></div> <div><div></div><div>RELAY CONTACTS (COIL DE-ENERGIZED) XXn RELATED COIL IDENTIFICATION</div></div> <div><div></div><div>SURGE SUPPRESSOR</div></div> <div><div></div><div>HIGH VOLTAGE TERMINATION ASSEMBLY</div></div> <div><div></div><div>n(E) FUSE n RATING E RATED</div></div> <div><div></div><div>(NC) (NO) FLOW SWITCH CONTACT</div></div> <div><div></div><div>FLOAT TYPE LEVEL SWITCH</div></div> <div><div></div><div>TEMPERATURE SWITCH</div></div> <div><div></div><div>PRESSURE SWITCH</div></div> <div><div></div><div>LIMIT SWITCH</div></div> <div><div></div><div>2 OR 3 POSITION SELECTOR SWITCH PROVIDE THE NUMBER OF CONTACTS AND CONFIGURATION SHOWN X CONTACT IS CLOSED IN RELATED POSITION</div></div> <div><div></div><div>MOMENTARY PUSHBUTTON, NORMALLY OPENED</div></div> <div><div></div><div>MOMENTARY PUSHBUTTON, NORMALLY CLOSED</div></div> <div><div></div><div>PUSH-TO-TEST INDICATING LAMP X COLOR: G GREEN R RED A AMBER W WHITE n POINT NUMBER WHERE PUSH-TO-TEST CONNECTS</div></div> <div><div></div><div>DISCRETE PLC INPUT OR OUTPUT</div></div> <div><div></div><div>DATA/SOFTWARE LINK</div></div>			<div><div></div><div>EQUIPMENT TAG</div></div> <div><div></div><div>RACEWAY TAG (SEE DESCRIPTION OF CABLE AND RACEWAY DIAGRAMS ON THIS DRAWING).</div></div> <div><div></div><div>EXPOSED CONDUIT</div></div> <div><div></div><div>CONCEALED, EMBEDDED, OR BURIED CONDUIT</div></div> <div><div></div><div>CONDUIT TURNS UP</div></div> <div><div></div><div>CONDUIT TURNS DOWN</div></div> <div><div></div><div>CONDUIT CHANGES ELEVATION</div></div> <div><div></div><div>FENCELINE</div></div> <div><div></div><div>HOME RUN: DESIGNATIONS INDICATE A ONE-LINE DIAGRAM OR PANELBOARD REFERENCE EXAMPLE: HOME TO PANELBOARD PBD-094, CIRCUIT 20</div></div> <div><div></div><div>GROUND ROD</div></div> <div><div></div><div>GROUND ROD WITH GROUND WELL</div></div> <div><div></div><div>GROUND CONNECTION, BOLTED TYPE</div></div> <div><div></div><div>GROUND CONNECTION, EXOTHERMIC TYPE</div></div> <div><div></div><div>GROUNDING CONDUCTOR</div></div> <div><div></div><div>MOTOR</div></div> <div><div></div><div>CONTROL VALVE</div></div> <div><div></div><div>DISCONNECT SWITCH</div></div> <div><div></div><div>COMBINATION MOTOR STARTER. NOT LOCATED IN AN MCC</div></div> <div><div></div><div>LOCAL CONTROL STATION</div></div> <div><div></div><div>FIELD MOUNTED INSTRUMENT OR DEVICE</div></div> <div><div></div><div>JUNCTION (PULL) BOX</div></div> <div><div></div><div>HORN</div></div> <div><div></div><div>TELEPHONE OUTLET</div></div> <div><div></div><div>DATA OUTLET</div></div> <div><div></div><div>CAMERA</div></div>			<div><div></div><div>LIGHT FIXTURE IDENTIFICATION FW TYPE PER FIXTURE SCHEDULE 3/35 QTY OF LAMPS PER FIXTURE / LAMP WATTAGE 6 QTY OF THE INDICATED TYPE OF LAMP ON THE DRAWING P MOUNTING STYLE: P PENDANT R RECESSED W WALL L POLE S SURFACE 8' MOUNTING HEIGHT (BOTTOM OF FIXTURE) 3a FIXTURE CIRCUITING AND SWITCHING 3 PANELBOARD CIRCUIT FEEDING THE FIXTURE, TYPICAL OF ALL FIXTURES a IDENTIFIER FOR THE SWITCH CONTROLLING THE FIXTURE (FIXTURE IS UNSWITCHED OR SELF-SWITCHED IF OMITTED), TYPICAL OF ALL FIXTURES</div></div> <div><div></div><div>LED FIXTURE</div></div> <div><div></div><div>WALL MOUNTED FIXTURE</div></div> <div><div></div><div>POLE MOUNTED FIXTURE</div></div> <div><div></div><div>EMERGENCY LIGHTING FIXTURE</div></div> <div><div></div><div>ILLUMINATED EXIT SIGN, DARKENED QUADRANTS INDICATE ILLUMINATED FACES, DIRECTIONAL ARROWS INDICATE DIRECTIONAL ARROWS BE PROVIDED ON THE ILLUMINATED FACE</div></div> <div><div></div><div>TOGGLE SWITCH (20A UNLESS OTHERWISE SHOWN) a UNIQUE SWITCH IDENTIFICATION 3 TYPE: 2 DOUBLE POLE 3 3-WAY 4 4-WAY K KEY OPERATED MC MOMENTARY CONTACT, 3 POSITION MS MANUAL (MOTOR) STARTER PC PHOTOCELL CONTROLLED R RHEOSTAT (DIMMER, SPEED CONTROL) WP WEATHERPROOF</div></div> <div><div></div><div>DUPLEX RECEPTACLE (20A, 3 WIRE) 3 PANELBOARD CIRCUIT FEEDING THE RECEPTACLE</div></div> <div><div></div><div>GF GF TYPE: GF GROUND FAULT WP WEATHERPROOF XP HAZARDOUS (CLASSIFIED) EXPLOSION PROOF</div></div>			<div>1. THIS DRAWING IS GENERAL IN NATURE. SOME SYMBOLS SHOWN HEREON MAY NOT BE USED ON THE CONTRACT DRAWINGS.</div> <div>2. IDENTIFICATIONS (ID), SIZES, RATINGS, LOCATIONS AND SIMILAR INFORMATION SHOWN ASSOCIATED WITH SYMBOLS ARE OPTIONAL; EXAMPLES OF SUCH INFORMATION ARE SHOWN WITH SOME SYMBOLS FOR CLARITY.</div> <div>3. THE ELECTRICAL DRAWINGS USE THE ONE LINE DIAGRAMS AND PANEL SCHEDULES IN CONJUNCTION WITH SHOWING THE LOCATION OF THE ELECTRICAL/ INSTRUMENTATION SOURCES AND LOADS/DEVICES ON THE PLAN DRAWINGS TO DEPICT THE WORK. THE CONTRACTOR SHALL USE THESE DOCUMENTS TO DETERMINE AND PROVIDE THE NECESSARY RACEWAY AND WIRING SYSTEM FOR EACH CIRCUIT. ALL INDOOR RACEWAY SHALL BE RUN EXPOSED, AND ROUTED BY THE CONTRACTOR, UNLESS OTHERWISE NOTED. THE TYPE OF RACEWAY AND WIRE USED SHALL BE AS SPECIFIED.</div> <div>4. IF EQUIPMENT SUPPLIED BY MANUFACTURER HAS A LARGER LOAD THAN INDICATED ON THE SINGLE LINE DIAGRAM, THE CONSTRUCTION MANAGER SHALL BE NOTIFIED. THE CABLE, CONDUIT AND ELECTRICAL EQUIPMENT SHALL BE SIZED AS REQUIRED, TO ACCOMMODATE THE HIGHER VALUE.</div> <div>5. IN AREAS WHERE THERE ARE OVERHEAD BRIDGE CRANES, HOISTS, ETC., OR WHERE EQUIPMENT IS LIFTED AND MOVED FOR MAINTENANCE OR REPLACEMENT, NO CONDUITS SHALL BE RUN OVERHEAD THAT WILL INTERFERE WITH THE OPERATION OF THE EQUIPMENT OR ACCESS TO EQUIPMENT.</div> <div>6. THE LOCATION OF THE CONTROL STATIONS SHOWN ON THE PLAN DRAWINGS ARE DIAGRAMMATIC AND THE ACTUAL LOCATION SHALL BE COORDINATED IN THE FIELD WITH THE CONSTRUCTION MANAGER. THE EXACT LOCATION OF THE MOTORS AND ACCESSORIES ARE NOT SHOWN.</div> <div>7. THE CONTRACTOR SHALL COORDINATE WITH THE STRUCTURAL AND MECHANICAL DRAWINGS FOR CONDUIT STUB UP AND TERMINATION LOCATIONS.</div> <div>8. THE STANDARD DETAILS SHALL BE USED WHERE APPLICABLE.</div> <div>9. ALL EQUIPMENT SHALL BE LABELED WITH NAMEPLATES. PROVIDE A DESCRIPTION OF THE EQUIPMENT AND THE EQUIPMENT NUMBER ON NAMEPLATES.</div> <div>10. FOR WIRING AND CABLE INSTALLATION REQUIREMENTS, SEE PROJECT SPECIFICATION SECTION 16000. SINCE LIGHTING AND RECEPTACLE CONDUITS AND CABLES ARE NOT SHOWN, THE CONTRACTOR SHALL USE PANELBOARD CIRCUIT SCHEDULES FOR PROVIDING CONDUIT AND CABLE INSTALLATION, SIZE PER NEC.</div>		
B	CABLE AND RACEWAY DIAGRAMS														
C	<div>EXAMPLES: P101A: 3#12, #12G, 1°C C101A: 1-7#14, 3/4 C S101A: 1#16TSP, 3/4 C A. SINGLE CONDUCTOR B. MULTI-CONDUCTOR C. TWISTED SHIELDED PAIR (OR TRIAD)</div> <div>CABLE AND RACEWAY IDENTIFICATION P101A UNIQUE CIRCUIT IDENTIFIER (CABLE AND RACEWAY), LETTER PREFIX INDICATES TYPE: P POWER, 120V OR HIGHER C CONTROL, 120V S SIGNAL, LESS THAN 120V X SPARE H HIGH VOLTAGE, OVER 600V #12 SIZE OF CONDUCTOR OR GROUND IN AWG OR KCMIL 1°C SIZE OF RACEWAY IN INCHES</div>														
D															
E															
F															
G	<div>DESIGNED DRAWN CHECKED REV DATE BY DESCRIPTION</div>						<div></div>			<div></div>			<div>CITY OF PALO ALTO PALO ALTO HORIZONTAL LEVEE PILOT PROJECT 1 LEGEND AND SYMBOLS</div>	<div>VERIFY SCALES BAR IS ONE INCH ON ORIGINAL DRAWING 0 1" IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY</div>	<div>DATE NOVEMBER 3, 2023 DRAWING NO. E01 SHEET NO. 38 OF 45</div>
	1	2	3	4	5	6	7	8	9	10	11	12	13		






KEYNOTES

- 1 MOUNT TERMINAL BOX AND JUNCTION BOXES ON THE SIDE OF THE WALL AT +48" AFF. TERMINAL BOX SHALL BE NEMA 4X, 316 STAINLESS STEEL AND BE A MINIMUM OF 24" x 24" x 12"D. PROVIDE WITH PIANO-TYPE HINGE AND THREE-POINT LATCH. JUNCTION BOXES SHALL BE NEMA 4X, 316 STAINLESS STEEL AND BE A MINIMUM OF 12" x 12" x 8"D, SCREW COVERS.
- 2 SAW CUT EXISTING PAVEMENT AND CONCRETE AS REQUIRED TO ROUTE CONDUITS OVER TO THE TANK, AS SHOWN ON THE SITE PLAN. REPAIR PAVEMENT OR CONCRETE TO MATCH EXISTING.
- 3 ROUTE CONDUITS UNDERGROUND A MIN OF 24", AROUND THE EXISTING TANK. THERE IS EXISTING RIVER ROCK AND DIRT THAT WILL NEED TO BE REMOVED OR RELOCATED FOR TRENCHING.
- 4 THERE IS EXISTING EQUIPMENT AND CONCRETE INSTALLED IN THE AREA. CONTRACTOR SHALL FIELD ROUTE CONDUITS AS REQUIRED TO REACH ALL NEW EQUIPMENT. CONTRACTOR MAY DAYLIGHT TO TANK WALL, AND ROUTE EXPOSED AS REQUIRED. EXPOSED CONDUIT SHALL BE GRS.
- 5 PROVIDE TWO PULLBOXES. ONE FOR POWER AND CONTROL AND ONE FOR SIGNAL. CONTRACTOR TO DETERMINE IN THE FIELD THE OPTIMAL LOCATION OF PULLBOXES.
- 6 THERE ARE EXISTING UTILITIES IN THE AREA ROADWAY. CONTRACTOR SHALL IDENTIFY ALL EXISTING UNDERGROUND UTILITIES PRIOR TO CONSTRUCTION. CONTRACTOR SHALL FIELD ROUTE CONDUITS AND PULLBOXES ACCORDING TO EXISTING FIELD CONDITIONS.
- 7 MOUNT HAND SWITCH, HS-1001, NEMA 4X, 316 STAINLESS STEEL, NEXT TO TERMINAL BOX. MOUNT AT +48" AFF.

DESIGNED				DRAWN				CHECKED				DATE			
REV				DATE				BY				DESCRIPTION			
1				2				3				4			
5				6				7				8			
9				10				11				12			
13				14				15				16			

CITY OF PALO ALTO PALO ALTO HORIZONTAL LEVEE PILOT PROJECT				VERIFIED SCALES BAR IS ONE INCH ON ORIGINAL DRAWING 0 1" IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY				DATE NOVEMBER 3, 2023 DRAWING NO. E03 SHEET NO. 40 OF 45			
---	--	--	--	---	--	--	--	---	--	--	--





KEYNOTES

- 1 PROVIDE 40A CIRCUIT BREAKER AND INSTALL INSIDE EXISTING MCC BUCKET SPACE. PROVIDE EQUIPPED SPACE AS REQUIRED. PROVIDE NAMEPLATE FOR BREAKER.
- 2 CORE DRILL THRU EXISTING STEEL WALL OF UV BUILDING. SEAL AROUND CONDUIT WITH FOAM. CONTRACTOR MAY NEED TO COME OUT OF THE CONCRETE WALL AND CORE DRILL THRU THE EXISTING CONCRETE WALL. SEAL AROUND CONDUITS WITH NON-SHRINK GROUT AND PAINT TO MATCH EXISTING.
- 3 SAW CUT EXISTING PAVEMENT AND CONCRETE AS REQUIRED TO ROUTE CONDUITS OVER TO THE TANK, AS SHOWN ON THE SITE PLAN. REPAIR PAVEMENT OR CONCRETE TO MATCH EXISTING.
- 4 MOUNT THE VFD ON THE EXISTING WALL AT +48" AFF. WHERE REQUIRED, PROVIDE A NEMA 1 WIREWAY ABOVE THE VFD. CONDUCTORS CAN BE COMBINED IN ONE CONDUIT FROM WIREWAY TO VFD, POWER AND CONTROL SEPARATE FROM SIGNAL OR DATA.



EXISTING MAIN CONTROL PANEL MCP-1

EXISTING MOTOR CONTROL CENTER SPACE



EXISTING MCC PHOTO



EXISTING ALLEN-BRADLEY CONTROLLOGIX PLC AND I/O

EXISTING ETHERNET SWITCH



EXISTING PLC PANEL MCP-1 PHOTO

FILENAME: BA\_9-08-23 01:09pm SLAR XREFS: X-TBK-PaloAlto-Border X-CHLORLEDO K-C

REV	DATE	BY	DESCRIPTION

DESIGNED	
DRAWN	
CHECKED	



CITY OF  
PALO ALTO

CITY OF PALO ALTO  
PALO ALTO HORIZONTAL LEVEE PILOT PROJECT

UV ELECTRICAL ROOM PLAN

VERIFY SCALES

BAR IS ONE INCH ON ORIGINAL DRAWING

0 1"

IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY

DATE

NOVEMBER 3, 2023

DRAWING NO.


E04

SHEET NO.


41 OF 45














SEEDING LEGEND

- SEASONAL WET MEADOW PLANTING AND SEEDING AREA
- RIPARIAN SCRUB PLANTING AND SEEDING AREA
- UPLAND SEEDING AREA
- RIPARIAN BUFFER PLANTING AND SEEDING AREA
- FRESHWATER MARSH PLANTING AND SEEDING AREA
- PERENNIAL WET MEADOW PLANTING AND SEEDING AREA

- LUPINUS ALBIFRONS
- PHYSOCARPUS CAPITATUS
- ROSA CALIFORNICA
- RUBUS URSINUS
- SAMBUCUS NIGRA
- SALIX LASIOLEPIS

NOTES

- SAVE THE BAY SHALL PROPAGATE, INSTALL, AND MAINTAIN ALL PLANTING AND SEEDING SHOWN ON SHEET L01 AND MAINTAIN ALL SEEDING SHOWN ON SHEET L04 PER THE AGREEMENT BETWEEN SAVE THE BAY AND ABAG DATED APRIL 25, 2023.
- PLANT HERBACEOUS CONTAINER PLANTS IN GROUPS OF 7-11 OF THE SAME SPECIES.
- RIPARIAN SCRUB SEEDING AND EROSION CONTROL FABRIC INSTALLATION BY OTHERS, SEE SHEETS L05 AND L06.
- INSTALL TEMPORARY IRRIGATION SYSTEM FOR RIPARIAN SCRUB PLANTING AREA. TEMPORARY IRRIGATION TO BE SUPPLIED TO FRESHWATER MARSH, PERENNIAL WET MEADOW, AND SEASONAL WET MEADOW PLANTING AND SEEDING AREAS UNTIL EFFLUENT SUPPLY LINE IS ONLINE. SUPPLEMENTAL IRRIGATION MAY BE NEEDED TO ESTABLISH PLANTS IN ALL PLANTING ZONES.

REV	DATE	BY	DESCRIPTION

DESIGNED  
MRL  
DRAWN  
DPH/AGHC  
CHECKED  
MRL



575 MARKET STREET  
SUITE 3700  
SAN FRANCISCO, CA 94105  
T 415.896.5900  
WWW.ESASSOC.COM



CITY OF PALO ALTO  
PALO ALTO HORIZONTAL LEVEE PILOT PROJECT  
REVEGETATION PLANS

PLANTING AND SEEDING PLAN


VERIFY SCALES  
BAR IS ONE INCH ON ORIGINAL DRAWING  
0 1" IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY


DATE  
NOVEMBER 10, 2023  
DRAWING NO.  
L01  
SHEET NO.  
2 OF 5

FILENAME: L02 PLANTING AND SEEDING SCHEDULES 11-17-23 11:36am C:\oscom\ X:\PA\Proposed\Hatchers X-TBLK-PaloAlto-Border L02

A  
B  
C  
D  
E  
F  
G




	Freshwater Marsh					0.07	acres
	Botanical Name	Common Name	Form/Container	Spacing	Quantity	Notes	
	Eleocharis macrostachya	common spikerush	plug	3 FT OC	24	plant in groups of 5-7	
	Juncus effusus	soft rush	plug	3 FT OC	12		
	Helianthus californicus	California sunflower	deepot	4 FT OC	2		
	Schoenoplectus americanus	three-square bulrush	plug	3 FT OC	46	one container per planting area	
	Schoenoplectus acutus	hardstem tule	plug	4 FT OC	145		
	Typha latifolia	broadleaf cattail	plug	3 FT OC	2		
Total					231		

	Perennial Wet Meadow					0.36	acres
	Botanical Name	Common Name	Form/Container	Spacing	Quantity	Notes	
	Artemisia douglasiana	mugwort	deepot	3 FT OC	80		
	Baccharis glutinosa	saltmarsh baccharis	deepot	5 FT OC	107		
	Carex barbarae	basket sedge	plug	3 FT OC	320		
	Carex praegracilis	clustered field sedge	plug	3 FT OC	107		
	Eleocharis macrostachya	common spikerush	plug	3 FT OC	213		
	Elymus triticoides	creeping wild rye	sod fragment	3 FT OC	53		
	Euthamia occidentalis	western goldenrod	deepot	4 FT OC	160		
	Glycyrrhiza lepid	wild licorice	deepot	3 FT OC	27		
	Helenium puberulum	sneezeweed	deepot	3 FT OC	27		
	Helianthus californicus	California sunflower	deepot	4 FT OC	53		
	Juncus balticus	baltic rush	plug	3 FT OC	320		
	Juncus effusus	soft rush	plug	3 FT OC	53		
	Symphyotrichum lentum	Suisun marsh aster	deepot	3 FT OC	53		
Total					1,573		

		Riparian Scrub				0.03	acres
		Botanical Name	Common Name	Form/Container	Spacing	Quantity	Notes
Trees	Salix lasiolepis	arroyo willow	tp-4	10 - 15 FT OC	3	peripheral slopes only	
	Total				3		
Shrubs	Physocarpus capitatus	ninebark	deepot	8 - 10 FT OC	15	plant on margins - away from canopy	
	Rubus ursinus	California blackberry	deepot/sprig	3 FT OC	60	understory with C. barbarae	
	Sambucus nigra	black elderberry	tp-4	8 - 15 FT OC	13	peripheral slopes only	
	Total				88		
Sedges	Carex barbarae	basket sedge	plug/division	3 FT OC	80	understory with blackberry	
	Total				80		

Herbaceous/ Sedges, Rushes	Seasonal Wet Meadow				0.18	acres
	Botanical Name	Common Name	Form/Container	Spacing	Quantity	Notes
	Ambrosia psilostachya	western ragweed	sod fragment	3 FT OC	10	
	Artemisia douglasiana	mugwort	deepot	3 FT OC	20	
	Baccharis glutinosa	marsh baccharis	deepot	3 FT OC	60	
	Carex barbarae	basket sedge	plug/division	3 FT OC	120	
	Carex praegracilis	clustered field rush	plug/division	3 FT OC	40	
	Elymus triticoides	creeping wild rye	sod fragment	3 FT OC	160	
	Euthamia occidentalis	western goldenrod	deepot	4 FT OC	40	
	Glycyrrhiza lepid	wild licorice	deepot	3 FT OC	10	
	Helianthus californicus	California sunflower	deepot	4 FT OC	20	
	Juncus mexicanus	Mexican rush	plug/division	3 FT OC	80	
	Symphyotrichum chilense	common aster	deepot	3 FT OC	40	
	Total				600	

	Riparian Buffer				0.05	acres	
	Botanical Name	Common Name	Form/Container	Spacing	Quantity	Notes	
	Shrubs	Baccharis glutinosa	marsh baccharis	deepot	3 FT OC	50	low scrub zone along trail boundary
		Rosa californica	California rose	deepot/sprig	10 FT OC	8	low scrub zone along trail boundary
		Lupinus albusfrons	Silver lupine	deepot	5 FT OC	30	low scrub zone along trail boundary
	Total				81		
	Herbaceous	Symphyotrichum chilense	common aster	deepot	3 FT OC	50	low scrub zone along trail boundary
Total				50			

Seed Mix - Freshwater Marsh and Perennial Wet Meadow		0.43	acres
Botanical Name	Common Name	PLS Lbs/Ac	Total PLS lb
Bidens frondosa	devil's beggartick	2.5	1.1
Epilobium ciliatum	willow-herb	10	4.3
Persicaria punctata	dotted smartweed	12.5	5.4
Hordeum brachyantherum	meadow barley	8	3.4
Total		25	14.2

Seed Mix - Seasonal Wet Meadow & Riparian Scrub/Buffer		0.26	acres
Botanical Name	Common Name	PLS Lbs/Ac	Total PLS lb
Amsinckia intermedia	fiddleneck	6.5	1.7
Centromadia pungens	spikeweed	6	1.6
Hemizonia congesta spp. luzuifolia	hayfield tarweed	6.5	1.7
Helenium puberulum	sneezeweed	1	0.3
Madia sativa	coast tarweed	6.5	1.7
Hordeum brachyantherum	meadow barley	8	2.1
Total		26.5	9.0

Seed Mix - Upland		0.54	acres
Botanical Name	Common Name	PLS lb/ac	Total PLS lb
Bromus carinatus	California brome	10	5.4
Elymus glaucus	blue wldrye	10	5.4
Festuca (Vulpia) microstachys	small fescue	10	5.4
Festuca rubra Molate	red fescue	6	3.3
Stipa pulchra	purple needle grass	8	4.3
Achillea millefolium	yarrow	0.25	0.1
Eschscholzia californica	California poppy	1.5	0.8
Total		45.75	24.7

REV	DATE	BY	DESCRIPTION

DESIGNED  
MRL  
DRAWN  
DPH/AGHC  
CHECKED  
MRL



575 MARKET STREET  
SUITE 3700  
SAN FRANCISCO, CA 94105  
T 415.896.5900  
WWW.ESASOC.COM



CITY OF  
PALO ALTO

CITY OF PALO ALTO  
PALO ALTO HORIZONTAL LEVEE PILOT PROJECT  
REVEGETATION PLANS


PLANTING AND SEEDING SCHEDULES

VERIFY SCALES  
BAR IS ONE INCH ON  
ORIGINAL DRAWING  
0 1" IF NOT ONE INCH ON  
THIS SHEET, ADJUST  
SCALES ACCORDINGLY

DATE  
NOVEMBER 10, 2023  
DRAWING NO.  
L02  
SHEET NO.  
3 OF 5



DESIGNED	MRL
DRAWN	DPH/AGHC
CHECKED	MRL





CITY OF  
**PALO ALTO**

## PLANTING DETAILS

DATE NOVEMBER 10, 2023
DRAWING NO. L03
SHEET NO. 4 OF 5








1. WORKING SHOWN ON THIS SHEET TO BE COMPLETED BY OTHERS AND PROVIDED FOR REFERENCE ONLY.

SEDIMENT AND EROSION CONTROL PLAN BY OTHERS

---

PLAN SCALE:



G				
REV	DATE	BY	DESCRIPTION	

DESIGNED	MRL
DRAWN	DPH/AGHC
CHECKED	MRL



575 MARKET STREET  
SUITE 3700  
SAN FRANCISCO, CA 94105  
T 415.896.5900  
WWW.ESASSOC.COM




CITY OF PALO ALTO  
PALO ALTO HORIZONTAL LEVEE PILOT PROJECT  
REVEGETATION PLANS

## SEDIMENT AND EROSION CONTROL PLAN BY OTHERS

VERIFY SCALES

BAR IS ONE INCH ON  
ORIGINAL DRAWING

0  1"

IF NOT ONE INCH ON  
THIS SHEET, ADJUST  
SCALES ACCORDINGLY

DATE  
NOVEMBER 10, 2023

DRAWING NO.  
L05

SHEET NO.  
--- OF 5