
ZHAO RESIDENCE

NEW SINGLE FAMILY RESIDENCE + ATTACHED ADU

2451 COWPER STREET PALO ALTO, CA 94301

APN: 132-07-012



OMNER
ZHENSHU ZHAO

2451 COMPER STREET
PALO ALTO, CA 94301

(650) 505-6666

EMAIL: zhaozhenshu@gmail.com

CIVIL ENGINEER

WEC & ASSOCIATES

2625 MIDDLEFIELD ROAD, #658

PALO ALTO, CA 94306

(650) 823-6466

EMAIL: ed@weceng.com

MARCH DESIGN
569 CLYDE AVENUE, UNIT 520
MOUNTAIN VIEW, CA 94043
(650) 302-1987
EMAIL: mma.aia@gmail.com

GREEN POINT RATER & CONSULTANT

JBRCY LLC

P.O. BOX 60792

PALO ALTO, CA 94306

(408) 677-6588

EMAIL: richardyyang@yahoo.com

ARCHITECTURAL

AI.O TITLE SHEET

AI.I CONTEXTUAL FRONT SETBACK & GARAGE PLACEMENT ANALYSIS

AI.2 SITE PHOTOS

AI.3 SITE PHOTOS

AI.4 PROPOSED SITE PLAN

A2.1 PROPOSED FLOOR PLANS

A2.2 PROPOSED ROOF PLAN AND STREET ELEVATION

A2.3 FLOOR AREA & LOT COVERAGE

A3.3 BUILDING SECTIONS

T-I SPECIAL TREE PROTECTION INSTRUCTION SHEET

T-2 ARBORIST REPORT

PROPOSED ELEVATIONS

PROPOSED ELEVATIONS

GB-I GREEN POINTS REQUIREMENTS & CHECKLIST

CIVIL

C.O TOPOGRAPHIC SURVEY

APPLICABLE CODES

PROJECT SCOPE

I. DEMOLISH EXISTING HOUSE. 955 S.F. AND DETACHED 331 S.F. GARAGE.

2. NEW CONSTRUCTION OF A 2,167.6 S.F. TWO-STORY WOOD FRAMED HOUSE AND ATTACHED I-CAR GARAGE WITH 213.1 S.F. MAIN EXTERIOR BUILDING MATERIALS ARE CEMENT PLASTER AND METAL ROOF.

3. ATTACHED ADU WITH 798.7 S.F.

2022 CRC, CBC (FOR STRUCTURAL), CPC, CMC, CEC, CALIFORNIA ENERGY CODE (CEnC), CITY OF PALO ALTO ORDINANCES (PAMC)
2022 CALIFORNIA FIRE CODE, AND 2019 CALIFORNIA GREEN BUILDING STANDARD CODE.

APN: I32-07-012

USE: SINGLE FAMILY RESIDENCE

ZONING DISTRICT: R-I

TYPE OF CONSTRUCTION: V-B

OCCUPANCY GROUP: R3/ U

SIZE OF LOT: +/-5,435 S.F. (O.12 ACRE)

ALLOWABLE LOT COVERAGE:
(1,902 S.F.+ 5% OF PARCEL FOR PATIO & PORCH)

PROPOSED LOT COVERAGE:
(EXCLUDING ADU)

MAX. ALLOWABLE FLOOR AREA:

2,174 S.F.

1,899.0 S.F.

2,899.0 S.F.

FLOOR AREA BREAKDOWNS

ATTACHED GARAGE:

GROUND FLOOR:

SECOND FLOOR

TOTAL FLOOR AREA:

ATTACHED ADU FLOOR AREA:

MAXIMUM BUILDING HEIGHT:

213.1 S.F.

1,250.2 S.F.

917.5 S.F.

2,380.7 S.F.

30'-0"

(45%×5000 s.f.+30%×435 s.f.)

MAXIMUM BUILDING HEIGHT:

PROPOSED BUILDING HEIGHT:

REQUIRED PARKING:

I

PARKING PROVIDED
(ATTACHED I CAR GARAGE)

I

PROJECT IN SPECIAL HAZARD AREA:

NO

CONTEXTUAL FRONT YARD SETBACK:

NOT SUBJECT TO

CONTEXTUAL GARAGE PLACEMENT:

NOT SUBJECT TO

HISTORIC DESIGNATION:

NONE

FIRE SPRINKLER SYSTEM:

YES

TOTAL PERMEABLE AREA IN FRONT YARD

617 S.F. (62.5%). SEE AI.3 SITE PLAN FOR ADDITIONAL INFORMATION

PROPOSED ADU COMPLIES WITH PAMC SECTIN 18.09.030 (TABLE 2)

MArch DESIGN ARCHITECTURE | INTERIOR | PLANNING

111 MAIN STREET, SUITE J3 LOS ALTOS, CA 94022
16 650. 302. 1987
16 mike@march.design

TTACHED ADU

SINGLE FAMILY RESIDENCE +
2451 COWPER STREET
PALO ALTO, CA 94301
APN: 132-07-012


DATE
06/06/25
CHECKED

DRAWN
MM

TITLE SHEET


JOB NO.

A A O




NOTE: AVERAGE FRONT SETBACKS IS LESS THAN 30'. THUS, CONTEXUTAL SETBACK DOES NOT APPLY.

() CONTEXTUAL FRONT SETBACK ANALYSIS



NOTE: 4 LOTS OF THE 5 LOTS (ENTIRE BLOCK) HAVE FRONT GARAGE.

THEREFORE, THE FRONT-HALF PATTERN IS PREDOMINANT AND THE CONTEXTUAL GARAGE PLACEMENT REGULATION DOES NOT APPLY.



2 CONTEXTUAL GARAGE PLACEMENT

 111 MAIN STREET, SUITE J3
 LOS ALTOS, CA 94022
 650. 302. 1987
 mike@march.design REVISIONS ZHAO RESIDENCE +

E FAMILY RESIDENCE +

2451 COWPER STREET

PALO ALTO, CA 94301

APN: 132-07-012

DATE
06/06/25
CHECKED

DRAWN MM

JOB NO.

1/30"=1'-0"

CONTEXTUAL
FRONT SETBACK &
GARAGE PLACEMENT



8) VIEW FROM REAR YARD TO (E) DETACHED GARAGE

(9) VIEW TO THE RIGHT SIDE YARD

REVISIONS


06/06/25

DRAWN

JOB NO.

7 VIEW TO THE SIDE YARD (LEFT SIDE)

SITE PHOTOS




111 MAIN STREET, SUITE J3
 LOS ALTOS, CA 94022
 650. 302. 1987
 mike@march.design

REVISIONS

ZHAO R E FAMILY RE 2451 CO¹ PALO AI APN: 1 NEW SINGLE

06/06/25 CHECKED

SITE PHOTOS





ARCHITECTURE | INTERIOR | PLANNING

LOS ALTOS, CA 94022 650. 302. 1987 mike@march.design

ADU CHED

132-07-012

SIDEN

ESIDENCE


FAMILY RE

2451 COWPER ST PALO ALTO, CA 9 APN: 132-07-01

06/06/25 CHECKED

DRAWN


PROPOSED SITE PLAN





	ZHAO RESIDENCE	NEW SINGLE FAMILY RESIDENCE + ATTACHED ADU	2451 COWPER STREET	PALO ALTO, CA 94301	APN: 132-07-012
DATE		06/0	06/25		


PROPOSED **FLOOR PLANS**


A2.1











City of Palo Alto


Tree Protection - It's Part of the Plan!


Make sure your crews and subs do the job right!


Fenced enclosures around trees are essential to protect them by keeping the foliage canopy and branching structure clear from contact by equipment, materials and activities, preserving roots and soil conditions in an intact and non-compacted state, and identifying the Tree Protection Zone (TPZ) in which no soil disturbance is permitted and activities are restricted, unless otherwise approved. An approved tree protection report must be added to this sheet when project activity occurs within the TPZ of a regulated tree.

7. Other (please describe)

For detailed information on Palo Alto's regulated trees and protection during development, review the City Tree Technical Manual (TTM) found at www.cityofpaloalto.org/trees/.







02	D.D.	08/10/06		Date 2006
cale: N	ITC		City of Palo Alto Standard	Dwg 605
cale: N	113		2.0, 2.1 2.2 2.2 2.2 2.2 2.2	No. 003
*	OF PALO	70	PALO ALTO STREET TREE PROTECTION INSTRUCTION SECTION 31	APPENDIX J
31-1	Gene			
	a. b.	from conta non-comp permitted The Tree	ection has three primary functions, 1) to keep the foliage canopy and be act by equipment, materials and activities; 2) to preserve roots and soil con acted state and 3) to identify the Tree Protection Zone (TPZ) in which and activities are restricted, unless otherwise approved. Protection Zone (TPZ) is a restricted area around the base of the tree with error of the tree's trunk or ten feet; whichever is greater, enclosed by fencing.	ditions in an intact and no soil disturbance is
31-2	Refer	ence Docume		
	a. b.	Tree Tech 1. Trenc 2. Arbor 3. Site P 4. Tree I	in Illustration of situations described below. Inical Manual (TTM) Forms (http://www.cityofpaloalto.org/trees/) Inical Manual (TTM) Forms (http://www.cityofpaloalto.org/trees/) Inical Manual (TTM) Forms (http://www.cityofpaloalto.org/trees/) Inical Manual (TTM) Section 2.20(C)) Inical Requirements (TTM, Section 6.30) Inical Requirements (TTM, Section 6.35) Inical Requirements (TTM, Appendix J) Inical Requirements (TTM) Form (http://www.cityofpaloalto.org/trees/forms)	
31-3	Execu	ıtion		
	a. b.	life of the be demolis Public Wo Type II T the TPZ sl	ee Protection: The fence shall enclose the entire TPZ of the tree(s) to be proconstruction project. In some parking areas, if fencing is located on paving shed, then the posts may be supported by an appropriate grade level concrete parks Operations. ree Protection: For trees situated within a planting strip, only the planting shall be enclosed with the required chain link protective fencing in order to ken for public use.	or concrete that will not base, if approved by strip and yard side of
	c.	tree well of the first brinto the bar branches.	Tree Protection: To be used only with approval of Public Works Operations of sidewalk planter pit, shall be wrapped with 2-inches of orange plastic fencianch and overlaid with 2-inch thick wooden slats bound securely (slats shall rk). During installation of the plastic fencing, caution shall be used to avoid Major limbs may also require plastic fencing as directed by the City Arbori	ing from the ground to I not be allowed to dig I damaging any st.
	d.	link fence a depth of specificall	and area to be fenced. All trees to be preserved shall be protected with six s. Fences are to be mounted on two-inch diameter galvanized iron posts, dri at least 2-feet at no more than 10-foot spacing. Fencing shall extend to the cy approved on the STV Form.	ven into the ground to outer branching, unless
	e.	intervals. "WARNII	'signs. A warning sign shall be weather proof and prominently displayed of The sign shall be minimum 8.5-inches x 11-inches and clearly state in half in the Protection Zone - This fence shall not be removed and is subject to tion 8.10.110."	nch tall letters:
	f.	Duration . place until disturbance	Tree fencing shall be erected before demolition; grading or construction befinal inspection of the project, except for work specifically allowed in the Te in the TPZ requires approval by the project arborist or City Arborist (in the Ses). Excavations within the public right of way require a Street Work Permi	FPZ. Work or soil e case of work around
	g.	During co	onstruction	
		2. The a that a Munio 3. The form	sighbors' trees that overhang the project site shall be protected from impact of pplicant shall be responsible for the repair or replacement plus penalty of an re damaged during the course of construction, pursuant to Section 8.04.070 cipal Code. Soliowing tree preservation measures apply to all trees to be retained: No storage of material, topsoil, vehicles or equipment shall be permitted. The ground under and around the tree canopy area shall not be altered. Trees to be retained shall be irrigated, aerated and maintained as necessal.	y publicly owned trees of the Palo Alto within the TPZ.
			END OF SECTION dard Drawings and Specifications rotection, PWE, Section 31 Revised 08	3/06

	ARBORIST INSPECTION SCHEDULE
	(T)
	All Checked Items Apply to this project:
1.	Inspection of Protective Tree Fencing. The Street Tree Verification Form shall be signed by the City Arborist. For other Protected Trees, the project arborist shall provide a written statement with a photograph verifying that he has conducted a field inspection of the trees and that the protective tree fencing is in place prior to issuance of a demolition, grading, or building permit. (see Verification of Tree Protection, Section 1.39).
2.	☐ Pre-Construction Meeting . Prior to commencement of construction, the applicant or contractor shall conduct a pre-construction meeting to discuss tree protection with the job site superintendent, grading equipment operators, project arborist, City Arborist, and, if a city maintained irrigation system exists, the Parks Manager (Contact 650-496-6962).
3.	☐ Inspection of Rough Grading. The project arborist shall perform an inspection during the course of rough grading adjacent to the TPZ to ensure trees will not be injured by compaction, cut or fill, drainage and trenching, and if required, inspect aeration systems, tree wells, drains and special paving. The contractor shall provide the project arborist at least 48 hours advance notice of such activity.
4.	☐ Monthly Inspections. The project arborist shall perform a monthly activity inspection to monitor and advise for conditions and tree health. The City Arborist shall be in receipt of the activity report during the first week of each calendar month or, immediately if there are <i>any revisions</i> to the approved plans or protection measures. Fax to (650) 329-2154. (see Monthly Inspection Report, Section 1.17).
5.	☐ Special activity within the Tree Protection Zone. Work in this area (TPZ - described in #7 below) requires the direct onsite supervision of the project arborist (see Trenching, Excavation and Equipment, TTM Section 2.20 C).
6.	Landscape Architect Inspection. For discretionary development projects, prior to temporary or final occupancy the applicant or contractor shall arrange for the Landscape Architect to perform an on site inspection of all plant stock, quality of the materials and planting (see Quality, Section 5.20.1 A) and that the irrigation is functioning consistent with the approved construction plans. The City shall be in receipt of written verification of Landscape Architect approval prior to scheduling the final inspection, unless otherwise approved.

Tree Department Public Works Operations PO Box 10250 Palo Alto, CA 650/496-5953 FAX: 650/852	. 94303 2-9289			
ctions: Complete upper port ement to Public Works Dept.	ion of this fo Public Wor	orm. Mail or FAX this	form along with signed Tree pect and notify applicant.	
DATE:				
CATION OF STREET PROTECTED:				
NAME:				
ADDRESS:				
TELEPHONE :RS:				
be filled out by City Tree Sta	nff			
Trees at the above) are adequately The type of protection		YES ☐ * If NO,	NO* □ go to #2 below	
<i>y</i> :				
Trees at the above e NOT adequately The following ns are required: w the required ns were communicated cant.				
spection				
above address were found ly protected:	*	YES f NO, indicate in "Notes	NO* ☐	
tion:				
y street trees by species, and type of tree protection note if pictures were ck of sheet if necessary.				
	Tree Department Public Works Operations PO Box 10250 Palo Alto, CA 650/496-5953 FAX: 650/852 treeprotection@CityofPaloAl ctions: Complete upper portement to Public Works Dept. DATE: CATION OF STREET PROTECTED: NAME: ADDRESS: TELEPHONE ERS: be filled out by City Tree State Trees at the above) are adequately The type of protection //: ection: Trees at the above a NOT adequately The following ns are required: where the required are were communicated cant. spection above address were found by protected: etion: y street trees by species, and type of tree protection note if pictures were	Public Works Operations PO Box 10250 Palo Alto, CA 94303 650/496-5953 FAX: 650/852-9289 treeprotection@CityofPaloAlto.org ctions: Complete upper portion of this forment to Public Works Dept. Public Works DATE: CATION OF STREET PROTECTED: NAME: ADDRESS: TELEPHONE ERS: be filled out by City Tree Staff Trees at the above) are adequately The type of protection //: ection: Trees at the above end NOT adequately The following ins are required: where the communicated cant. Spection above address were found by protected: * In the protection of this for the protection * In the protection of the protection * In the protection of	Tree Department Public Works Operations PO Box 10250 Palo Alto, CA 94303 6501496-5953 FAX: 650/852-9289 treeprotection@CityofPaloAlto.org ctions: Complete upper portion of this form. Mail or FAX this iment to Public Works Dept. Public Works Tree Staff will institute to Public Works Dept. Public Works Tree Staff will institute to Public Works Dept. Public Works Tree Staff will institute to Public Works Tr	Tree Department Public Works Operations PO Box 10250 Palo Alto, CA 94303 650498-5935 FAX: 650/852-9289 treeprotection@CityofPaloAlto.org

---WARNING---**Tree Protection Zone**

This fencing shall not be removed without City Arborist approval (650-496-5953)

Removal without permission is subject to a \$500 fine per day*

*Palo Alto Municipal Code Section 8.10.110 City of Palo Alto Tree Protection Instructions are located at http://www.city.palo-alto.ca.us/trees/technical-manual.html

Use additional T1 sheets as needed

Tree Protection Report

Proj



All other tree-related reports shall be added to the space provided on this sheet (adding as needed) Include this sheet(s) on Project Sheet Index or Legend Page. A copy of T-1 can be downloaded at www.cityofpaloalto.org/arb/forms

Special Tree Protection Instruction Sheet City of Palo Alto



9 Page

Date: 2/13/24

Robert Weatherill

2451 Cowper St., Palo Alto

February 13, 2025

Certified Arborist WE 1936a

Terms and Conditions(3)

The following terms and conditions apply to all oral and written reports and correspondence pertaining to consultations, inspections and activities of Advanced Tree Care: . All property lines and ownership of property, trees, and landscape plants and fixtures are assumed to be accurate and reliable as presented and described to the consultant, either verbally or in writing. The consultant assumes no responsibility for verification of ownership or locations of property lines, or for results of any actions or recommendations based on inaccurate information. 2. It is assumed that any property referred to in any report or in conjunction with any services

performed by Advanced Tree Care, is not in violation of any applicable codes, ordinances, statutes, or other governmental regulations, and that any titles and ownership to any property are assumed to be good and marketable. Any existing liens and encumbrances have been disregarded. 3. All reports and other correspondence are confidential, and are the property of Advanced Tree Care and it's named clients and their assignees or agents. Possession of this report or a copy thereof does not imply any right of publication or use for any purpose, without the express permission of the consultant and the

client to whom the report was issued. Loss, removal or alteration of any part of a report invalidates the 4. The scope of any report or other correspondence is limited to the trees and conditions specifically mentioned in those reports and correspondence. Advanced Tree Care and the consultant assume no liability for the failure of trees or parts of trees, either inspected or otherwise. The consultant assumes no responsibility to report on the condition of any tree or landscape feature not specifically requested by the

All inspections are limited to visual examination of accessible parts, without dissection, excavation, probing, boring or other invasive procedures, unless otherwise noted in the report. No warrantee or guarantee is made, expressed or implied, that problems or deficiencies of the plants or the property will not occur in the future, from any cause. The consultant shall not be responsible for damages caused by any tree defects, and assumes no responsibility for the correction of defects or tree related problems. . The consultant shall not be required to provide further documentation, give testimony, be deposed, or attend court by reason of this appraisal/report unless subsequent contractual arrangements are made, including payment of additional fees for such services as described by the consultant or in the fee schedules


Advanced Tree Care has no warrantee, either expressed or implied, as to the suitability of the information contained in the reports for any purpose. It remains the responsibility of the client to determine applicability to his/her particular case. 8. Any report and the values, observations, and recommendations expressed therein represent the

professional opinion of the consultants, and the fee for services is in no manner contingent upon the reporting of a specified value nor upon any particular finding to be reported. Any photographs, diagrams, graphs, sketches, or other graphic material included in any report, being intended solely as visual aids, are not necessarily to scale and should not be construed as engineering reports or surveys, unless otherwise noted in the report. Any reproductions of graphs material or the work product of any other persons is intended solely for the purpose of clarification and ease of reference. Inclusion of said information does not constitute a representation by Advanced Tree Care or the consultant as to the sufficiency or accuracy of that information.

10 | Page

Advanced Tree Care 965 East San Carlos Ave, San Carlos

2451 Cowper St., Palo Alto February 13, 2025



Location of proposed new house, protected trees and their Tree Protection Zones

965 East San Carlos Ave, San Carlos

Advanced Tree Care 965 East San Carlos Ave, San Carlos

2451 Cowper St., Palo Alto February 13, 2025



· Type I Tree Protection The fences shall enclose the entire area under the canopy dripline or TPZ of the tree(s) to be saved throughout the life of the project, or until final improvement work within the area is required, typically near the end of the project (see Images 15-1 and 2.15-2). Parking Areas: If the ncing must be located on paving or dewalk that will not be demolished, the osts may be supported by an appropriite grade level concrete base.

2. Any pruning and maintenance of the trees shall be carried out before construction begins. This should allow for any clearance requirements for both the new structure and any construction machinery. This will eliminate the possibility of damage during construction. The pruning should be carried out by an arborist, not by construction personnel. No limbs greater than 4" in diameter shall be removed.

3. Any excavation in ground where there is a potential to damage roots of 1" or more in diameter should be carefully hand dug. Where possible, roots should be dug around rather than cut.

4. If roots are broken, every effort should be made to remove the damaged area and cut it back to its closest lateral root. A clean cut should be made with a saw or pruners. This will prevent any infection from damaged roots spreading throughout the root system and into the tree. (3)

5. Do Not:. (4

a. Allow run off or spillage of damaging materials into the area below any tree canopy. b. Store materials, stockpile soil, park or drive vehicles within the TPZ of the tree. c. Cut, break, skin or bruise roots, branches or trunk without first obtaining permission from the

 Allow fires under any adjacent trees. e. Discharge exhaust into foliage.

f. Secure cable, chain or rope to trees or shrubs. g. Apply soil sterilants under pavement near existing trees.

5 | Page

6 | Page

Advanced Tree Care 965 East San Carlos Ave, San Carlos

Liquidambar styraciflua

Tree Survey Good health and condition 29.5" 60/40 65 Good health and condition

36"est 80/40 60 Good health and condition Cedrus deodara neighbor's tree, Regulated Fair health and condition, neighbor's tree, Not Regulated 8"est 15/10 55 9.8"/9.5"/9.7"/11.3" 40/30 40 Brush cherry Fair health, poor condition Brush cherry 5.2"/5.4" 40/10 50 Fair health and condition, codominant at grade, Not Regulated Syzygium paniculatum

2451 Cowper St., Palo Alto

February 13, 2025

Street tree, Regulated

Fair health and condition

The trees on the site are a variety of natives and non-natives.

Tree #s 1 and 2 are Street trees. Tree # 1 is a smaller tree in front of the neighbor's property and does not require protection. Tree # 2 is a larger tree in front of this property and should be protected during construction.

Tree # 3 is a Protected mature tree on the neighbor's property. The tree should be protected during construction.

The remaining trees on this property are not protected and can be removed if desirted. Any tree that is removed should be replaced in accordance with Palo Alto's Municipal Code such that there is zero net canopy loss on the property.

Tree # 5 is a Protected mature tree on this property and should be protected during construction.

3 | Page

Advanced Tree Care 965 East San Carlos Ave, San Carlos

2451 Cowper St., Palo Alto February 13, 2025

Zhenshu Zhao 2451 Cowper St., Palo Alto, CA 94301

Site: 2451 Cowper St., Palo Alto

At your request I visited the above site for the purpose of inspecting and commenting on the regulated trees around the property. A new home is planned, prompting the need for this tree protection report.

Dear Zhenshu,

Palo Alto regulates the following trees:

Locally Native Protected Species Trees

 <u>Big Leaf Maple (Acer macrophyllum)</u> 11.5" or more DBH California Incense Cedar (Calocedrus decurrens) 11.5" or more DBH

Coast Live Oak (Quercus agrifolia) 11.5" or more DBH
 Blue Oak (Quercus douglasii) 11.5" or more DBH

<u>California Black Oak (Quercus kelloqqii)</u> 11.5" or more DBH
 <u>Valley Oak (Quercus lobata)</u> 11.5" or more DBH

Coast Redwood (Sequoia sempervirens) 18" or more DBH

Protected Mature Trees

 Any mature tree measuring 15" or more DBH Invasive species trees and high water use trees are excluded.

Any tree designated for protection during review and approval of a development project.

Public Trees / Street Trees

 "Public trees" include any tree, in any street, park, or public place in the city of Palo Alto. "Street Tree" refers to the Public Trees located in the city road right of way.

Palo Alto requests that all trees with a trunk diameter greater than 6 inches at standard height be included in the report including all street trees and trees on neighboring properties that might be impacted.

1 | Page

Advanced Tree Care 965 East San Carlos Ave, San Carlos

2451 Cowper St., Palo Alto February 13, 2025

The part of the crown composed of leaves and small twigs. (2)

An open wound, characterized by the presence of extensive decay and resulting in a hollow.(1)

decomposition of cellulose and lignin⁽¹⁾ The width of the crown as measured by the lateral extent of the foliage. (1)

A classification of plants showing similar characteristics.

A Classification that identifies a particular plant.

(1) Matheny, N.P., and Clark, J.P. Evaluation of Hazard Trees in Urban Areas.

and Structural Condition. Tree Tech Consulting, 1998.

(4) Extracted from a copy of Tree Protection guidelines. Anon

(6) D Dockter, Tree Technical Manual. City of Palo Alto, June, 2001

International Society of Arboriculture, 1994.

8 | Page

Advanced Tree Care

2451 Cowper St., Palo Alto February 13, 2025

Process of degradation of woody tissues by fungi and bacteria through the

The point at which the trunk flares out at the base of the tree to become the root

Height at which the girth of the tree is measured. Typically 4 1/2 feet above

(2) Harris, R.W., Matheny, N.P. and Clark, J.R.. <u>Arboriculture: Integrated Management of Landscape Trees, Shrubs and Vines.</u> Prentice Hall, 1999.

(3) Carlson, Russell E. Paulownia on The Green: An Assessment of Tree Health

(5) T. D. Sydnor, Arboricultural Glossary. School of Natural Resources, 2000

Advanced Tree Care 965 East San Carlos Ave, San Carlos

2451 Cowper St., Palo Alto February 13, 2025

6. Where roots are exposed, they should be kept covered with the native soil or four layers of wetted, untreated burlap. Roots will dry out and die if left exposed to the air for too long. (4)

Route pipes into alternate locations to avoid conflict with roots. (4)

8. Where it is not possible to reroute pipes or trenches, the contractor is to bore beneath the dripline of the tree. The boring shall take place no less than 3 feet below the surface of the soil in order to avoid encountering "feeder" roots. (4)

9. Compaction of the soil within the dripline shall be kept to a minimum. (2) If access is required to go through the TPZ of a protected tree, the area within the TPZ should be protected from compaction either with steel plates or with 4" of wood chip overlaid with plywood.

10. Any damage due to construction activities shall be reported to the project arborist or city arborist within 6 hours so that remedial action can be taken.

11. Ensure upon completion of the project that the original ground level is restored

Advanced Tree Care

965 East San Carlos Ave, San Carlos

2451 Cowper St., Palo Alto February 13, 2025

Tree Protection Plan

4 | Page

1. The Tree Protection Zone (TPZ) should be defined with protective fencing. This should be cyclone or chain link fencing on 11/2" or 2" posts driven at least 2 feet in to the ground standing at least 6 feet tall. Normally a TPZ is defined by the dripline of the tree. I recommend the TPZ's

Tree # 2: TPZ should be at 24 feet from the trunk of the tree, shown as a thin red line. This can be reduced to edge of sidewalk and driveway in accordance with Type I Tree Protection as outlined and illustrated in image 2.15-1 and 2⁽⁶⁾. Shown as a thick red line.

The small area of foundation within the TPZ should be hand dug. Any roots encountered can be cut without jeopardizing the health or stability of the tree. The roots should be cut with hand saw or

Excavation of the driveway within the TPZ should be done with hand tools. Any roots encountered can be cut without jeopardizing the health or stability of the tree. The roots should be cut with hand

Tree #3: TPZ should be at 30 feet from the trunk of the tree, shown as a thin red line. This can be and illustrated in image 2.15-1 and 2 (6). This is marked on the drawing with a thick red line.

Excavation of the driveway within the TPZ should be done with hand tools. Any roots encountered

can be cut without jeopardizing the health or stability of the tree. The roots should be cut with hand Tree # 5: TPZ should be at 21 feet from the trunk of the tree, shown as a thin red line. This can be

reduced to the edge of proposed construction in accordance with Type I Tree Protection as outlined

and illustrated in image 2.15-1 and 2 (6). This is marked on the drawing with a thick red line. The foundation within the TPZ should be hand dug. Any roots encountered greater than 2" in diameter should be worked around and not cut.

Advanced Tree Care 965 East San Carlos Ave, San Carlos

2451 Cowper St., Palo Alto February 13, 2025

The location of the regulated trees on this site can be found on the plan provided by you. Each tree is given an identification number. The trees are measured at 54 inches above ground level (DBH or Diameter at Breast Height). A condition rating of 1 to 100 is assigned to each tree representing form and vitality on the following scale:

Very Poor 30 to 49 50 to 69 Fair 70 to 89

90 to 100 Excellent The height and spread of each tree is estimated. A Comments section is provided for any significant

observations affecting the condition rating of the tree. A Summary and Tree Protection Plan are at the end of the survey providing recommendations for maintaining the health and condition of the trees during and after construction.

If you have any questions, please don't hesitate to call.

Sincerely



Certified Arborist WE 1936A

2 | Page

ADU TACH

DESIGN

ARCHITECTURE | INTERIOR | PLANNING

111 MAIN STREET, SUITE J3

LOS ALTOS, CA 94022

650. 302. 1987

REVISIONS

mike@march.design

94301 SIDENCE STREE S **OWPER** ALTO, Ш FAMILY RE 2451 CO PALO A

132-07-012

SINGLE

06/06/25 CHECKED

JOB NO.

DRAWN

ARBORIST REPORT

94

							liance Pa	ui verii	ilcation		
				Plan	Check		gh GB	Fina	al Inspecti	on IVR	# 153
			Plan Sheet, Spec or	i iaii	Officer		ection # 152	Part 1	Part 1	Part 2	Parf
Planning a	and Design	Code Section Y	Attachment Reference	CORR	INITIAL				INITIAL		
	Storm water drainage and retention during construction (less than one acre)	4.106.2 X									
	. Topsoil protection - Tier 2 requirements	PAMC 16.16.070 and 16.14.80/ A4.106.2.3 X									
	Grading and paving EV Charging for additions and alterations of parking facilities serving existing multifamily buildings [AA][MF]	4.106.3 X 4.106.4.3 X		1							
	All-electric: Outdoor grills, outdoor stoves, outdoor barbecues	PAMC 16.14.090 / 4.106.5	<								
Tier 2 Mand.	. Water Permeble Surface for 30%	A4.106.4 X									-
Tier 2 Mand.	. Cool roof for reduction of heat island effect -Tier 2 requirements	PAMC 16.16.070 & 16.14.080 / A4.106.5 X									-
Tier 2 Mand.	Electric vehicle (EV) charging for residential structures (Locally amended)	PAMC 16.14.160 / A4.106.8 X									
	EV Charging: New one-family, two-family and townhouse dwellings	PAMC 16.14.160/ A4.106.8.1 X									
	EV Charging: New multi-family residential structures	PAMC 16.14.160/ A4.106.8.2									
	EV Charging: New Hotels and Motels Picuses Porting (locally arranded))//hon an addition as abanga of use requite in increased parting (ME)	PAMC 16.14.160/ A4.106.8.3									
	Bicycle Parking (locally amended)When an addition or change of use results in increased parking [MF] Reinforcement for grab bars [N]	PAMC 18.54.060/ A4.106.9 CBSC R327.1.1 X			-						
Elective	Site selection	A4.103.1 X		П							
Elective	Community connectivity	A4.103.2	(
Elective	Supervision and education by a Special Inspector (Locally amended)	PAMC 16.14.140/ A4.104.1 X									
Elective	Deconstruction (Locally amended, Mandatory on or after July 1, 2020)	PAMC 16.14.150/ A4.105.1									
Elective	Reuse of existing materials (Locally amended)	PAMC 16.14.150/ A4.105.2									
Elective	Soil analysis	A4.106.2.1	(
Elective Elective	Soil protection Landscape design	A4.106.2.2 X A4.106.3	4								
Elective	Vegetated roof Reduction of host island effect for percent areas	A4.106.6				<u> </u>		-			
Elective Elective	Reduction of heat island effect for nonroof areas Light pollution reduction (Locally amended)	A4.106.7 X PAMC 16.14.180/ A4.106.10	/								
					1	1					
Elective	Innovative concepts and local environmental conditions	A4.108.1	<u> </u>								
	Energy Reach Code Effective Date 10/4/2024: Energy Performance Standards	NMC 46 47 400 46 47 420 40 47 440 4000 T''' 04 5			1					ı	
wandatory	•-	AMC 16.17.100, 16.17.130, 16.17.140 / 2022 Title 24, Part									
	New buildings and substantial remodels must comply with the performance standards specified in PAMC 16.17 - Energy Reach Code. (Title 24 must demonstrate the following compliance margin based on			П							
	occupancy type: Single-family EDR1 of at least 8 (with exceptions), Low-rise MF source energy margin 9%,	^									
	High-rise MF source energy margin 1%)										
Mandatory	Effective Date 10/4/2024: Electric-Readiness	PAMC 16.17.090 Section 130.6 / 2022 Title 24, Part 6									
	The electric readiness requirements of Sections 150.0 (n) HPWH-ready, (t) HP Space Heater-ready, (u)										
	Electric Cooktop-ready and (v) Electric clothes dryer-ready apply to residential remodels or additions when										
	the applicable system is included in the remodel.										
	ciency and Conservation										
	Indoor Water Use: Water closets (1.28 gpf)	4.303.1.1 X									
	Indoor Water Use: Urinals (Wall Mounted 0.125 gpf, all others 0.5 gpf)	4.303.1.2	(
	Indoor Water Use: Single showerhead (1.8 gpm at 80 psi) Indoor Water Use: Multiple showerheads serving one shower (1.8 gpm at 80 psi)	4.303.1.3.1 X 4.303.1.3.2 X									
•	Indoor Water Use: Residential lavatory faucets (1.2 gpm at 60 psi)	4.303.1.4.1 X									
	Indoor Water Use: Lavatory faucets in common and public use areas (0.5 gpm at 60 psi) [MF]	4.303.1.4.2	/								
	Indoor Water Use: Metering faucets (0.2 gallons per cycle)	4.303.1.4.3									
-	Indoor Water Use: Kitchen faucets (1.8 gpm at 60 psi)	4.303.1.4.4									
	Indoor Water Use: Submeters for multifamily and mixed use buildings [MF]	4.303.2									
	Indoor Water Use: Standards for plumbing fixtures and fittings (Meet 2022 Plumbing Code)	4.303.3 X									
	Outdoor potable water use in landscape areas (MWELO)	4.304.1									
	. Recycled water for landscape irrigation (when landscape >1,000 sq. ft) [MF only][AA]	PAMC 16.14.210/ A4.305.3									
	Swimming pool and spa covers (Provide vapor retardant cover) Kitchen faucets (1.5 gpm at 60 psi)	PAMC 16.14.100/ Section 4.306	(
Elective Elective	Alternate water sources for nonpotable applications	A4.303.1 X A4.303.2	(
Elective	Appliances	A4.303.3 X		П							
Elective	Nonwater supplied urinals and waterless toilets	A4.303.4	(
Elective	Hot water recirculation systems	A4.303.5 X									
Elective	Rainwater catchment systems	A4.304.1									
Elective	Potable water elimination	A4.304.2									
Elective	Irrigation metering device (locally amended)	PAMC 16.14.200/ A4.304.3				1		1			
Elective Elective	Graywater (Locally amended, Whole house graywater system counts as 3 electives) Recycled water piping (Locally amended)	PAMC 16.14.210/ A4.305.1 PAMC 16.14.210/ A4.305.2				1		1		-	
Elective	Recycled water for landscape irrigation (Locally amended)	PAMC 16.14.210/ A4.305.2		<u> </u>	1	1		1			
Elective	Innovative concepts and local environmental conditions	A4.306.1		_				1			
Material Co	onservation and Resource Efficiency										
Tier 2 Mand.	Recycled content - 15% - Tier 2 requirements	PAMC 16.14.070 & 16.14.080 / A4.405.3.1 X									
	Low carbon concrete requirements	PAMC 16.14.240/ A4.403.2 X									
		4.406.1 X									
Mandatory	Rodent proofing fill annular spaces around pipes, cables, conduits or other openings to protect against roden				1						
Mandatory Tier 2 Mand.	. Enhanced construction waste reduction (80% Diversion w/ job valuation >\$25,000 or meet state standards of	PAMC 16.14.250/ 4.408.1 X				8		-			
Mandatory Tier 2 Mand. Mandatory	Enhanced construction waste reduction (80% Diversion w/ job valuation >\$25,000 or meet state standards of Construction waste management plan in Green Halo	PAMC 16.14.250/ 4.408.1 X PAMC 16.14.250/Section A4.408.1 X									
Mandatory Tier 2 Mand. Mandatory Mandatory	Enhanced construction waste reduction (80% Diversion w/ job valuation >\$25,000 or meet state standards of Construction waste management plan in Green Halo Waste management company	PAMC 16.14.250/ 4.408.1 X PAMC 16.14.250/Section A4.408.1 X 4.408.3 X									
Mandatory Tier 2 Mand. Mandatory Mandatory Mandatory	Enhanced construction waste reduction (80% Diversion w/ job valuation >\$25,000 or meet state standards of Construction waste management plan in Green Halo Waste management company Documentation	PAMC 16.14.250/ 4.408.1 X PAMC 16.14.250/Section A4.408.1 X 4.408.3 X 4.408.5 X									
Mandatory Tier 2 Mand. Mandatory Mandatory Mandatory Mandatory Mandatory	Enhanced construction waste reduction (80% Diversion w/ job valuation >\$25,000 or meet state standards of Construction waste management plan in Green Halo Waste management company	PAMC 16.14.250/ 4.408.1 X PAMC 16.14.250/Section A4.408.1 X 4.408.3 X									
Mandatory Tier 2 Mand. Mandatory Mandatory Mandatory Mandatory Mandatory Mandatory	Enhanced construction waste reduction (80% Diversion w/ job valuation >\$25,000 or meet state standards of Construction waste management plan in Green Halo Waste management company Documentation Operation and maintenance manual provided to the building owner	PAMC 16.14.250/ 4.408.1 X PAMC 16.14.250/Section A4.408.1 X 4.408.3 X 4.408.5 X 4.410.1 X									
Mandatory Tier 2 Mand. Mandatory Mandatory Mandatory Mandatory Mandatory Mandatory	Enhanced construction waste reduction (80% Diversion w/ job valuation >\$25,000 or meet state standards of Construction waste management plan in Green Halo Waste management company Documentation Operation and maintenance manual provided to the building owner Recycling by occupants (≥ 5 multi-family units) [MF] Efficient framing techniques - Lumber size Efficient framing techniques - Dimensions and layouts	PAMC 16.14.250/ 4.408.1 X PAMC 16.14.250/Section A4.408.1 X 4.408.3 X 4.408.5 X 4.410.1 X 4.410.2 A4.404.1 A4.404.2	<								
Mandatory Tier 2 Mand. Mandatory Mandatory Mandatory Mandatory Mandatory Elective Elective	Enhanced construction waste reduction (80% Diversion w/ job valuation >\$25,000 or meet state standards of Construction waste management plan in Green Halo Waste management company Documentation Operation and maintenance manual provided to the building owner Recycling by occupants (≥ 5 multi-family units) [MF] Efficient framing techniques - Lumber size Efficient framing techniques - Dimensions and layouts Efficient framing techniques - Building systems	PAMC 16.14.250/ 4.408.1 X PAMC 16.14.250/Section A4.408.1 X 4.408.3 X 4.408.5 X 4.410.1 X 4.410.2 A4.404.1 A4.404.2 A4.404.3 X	Κ								
Mandatory Tier 2 Mand. Mandatory Mandatory Mandatory Mandatory Mandatory Elective Elective Elective	Enhanced construction waste reduction (80% Diversion w/ job valuation >\$25,000 or meet state standards of Construction waste management plan in Green Halo Waste management company Documentation Operation and maintenance manual provided to the building owner Recycling by occupants (≥ 5 multi-family units) [MF] Efficient framing techniques - Lumber size Efficient framing techniques - Dimensions and layouts Efficient framing techniques - Building systems Efficient framing techniques - Pre-cut materials and details	PAMC 16.14.250/ 4.408.1 X PAMC 16.14.250/Section A4.408.1 X 4.408.3 X 4.408.5 X 4.410.1 X 4.410.2 A4.404.1 A4.404.2 A4.404.3 X A4.404.4 A4.404.4	(
Mandatory Tier 2 Mand. Mandatory Mandatory Mandatory Mandatory Mandatory Elective Elective Elective Elective	Enhanced construction waste reduction (80% Diversion w/ job valuation >\$25,000 or meet state standards of Construction waste management plan in Green Halo Waste management company Documentation Operation and maintenance manual provided to the building owner Recycling by occupants (≥ 5 multi-family units) [MF] Efficient framing techniques - Lumber size Efficient framing techniques - Dimensions and layouts Efficient framing techniques - Building systems Efficient framing techniques - Pre-cut materials and details Prefinished building materials	PAMC 16.14.250/ 4.408.1 X PAMC 16.14.250/Section A4.408.1 X 4.408.3 X 4.408.5 X 4.410.1 X 4.410.2 A4.404.1 A4.404.2 A4.404.3 X A4.404.3 X A4.404.4 A4.405.1 X	(
Mandatory Tier 2 Mand. Mandatory Mandatory Mandatory Mandatory Mandatory Elective Elective Elective Elective Elective	Enhanced construction waste reduction (80% Diversion w/ job valuation >\$25,000 or meet state standards of Construction waste management plan in Green Halo Waste management company Documentation Operation and maintenance manual provided to the building owner Recycling by occupants (≥ 5 multi-family units) [MF] Efficient framing techniques - Lumber size Efficient framing techniques - Dimensions and layouts Efficient framing techniques - Building systems Efficient framing techniques - Pre-cut materials and details Prefinished building materials Concrete floors	PAMC 16.14.250/ 4.408.1 X PAMC 16.14.250/Section A4.408.1 X 4.408.3 X 4.408.5 X 4.410.1 X 4.410.2 A4.404.1 A4.404.2 A4.404.3 X A4.404.3 X A4.404.4 A4.405.1 X A4.405.2	(
Mandatory Tier 2 Mand. Mandatory Mandatory Mandatory Mandatory Mandatory Elective Elective Elective Elective Elective Elective	Enhanced construction waste reduction (80% Diversion w/ job valuation >\$25,000 or meet state standards of Construction waste management plan in Green Halo Waste management company Documentation Operation and maintenance manual provided to the building owner Recycling by occupants (≥ 5 multi-family units) [MF] Efficient framing techniques - Lumber size Efficient framing techniques - Dimensions and layouts Efficient framing techniques - Building systems Efficient framing techniques - Pre-cut materials and details Prefinished building materials Concrete floors Use of building materials from rapidly renewable sources	PAMC 16.14.250/ 4.408.1 X PAMC 16.14.250/Section A4.408.1 X 4.408.3 X 4.408.5 X 4.410.1 X 4.410.2 A4.404.1 A4.404.2 A4.404.3 X A4.404.4 A4.404.2 A4.405.1 X A4.405.1 X A4.405.4 A4.405.4	<								
Mandatory Tier 2 Mand. Mandatory Mandatory Mandatory Mandatory Mandatory Elective Elective Elective Elective Elective Elective Elective Elective	Enhanced construction waste reduction (80% Diversion w/ job valuation >\$25,000 or meet state standards of Construction waste management plan in Green Halo Waste management company Documentation Operation and maintenance manual provided to the building owner Recycling by occupants (≥ 5 multi-family units) [MF] Efficient framing techniques - Lumber size Efficient framing techniques - Dimensions and layouts Efficient framing techniques - Building systems Efficient framing techniques - Pre-cut materials and details Prefinished building materials Concrete floors Use of building materials from rapidly renewable sources Drainage around foundations	PAMC 16.14.250/ 4.408.1 X PAMC 16.14.250/Section A4.408.1 X 4.408.3 X 4.408.5 X 4.410.1 X 4.410.2 A4.404.1 A4.404.2 A4.404.3 X A4.404.4 A4.405.1 X A4.405.1 X A4.405.1 X A4.405.1 A4.40	<								
Mandatory Tier 2 Mand. Mandatory Mandatory Mandatory Mandatory Mandatory Elective Elective Elective Elective Elective Elective Elective Elective Elective	Enhanced construction waste reduction (80% Diversion w/ job valuation >\$25,000 or meet state standards of Construction waste management plan in Green Halo Waste management company Documentation Operation and maintenance manual provided to the building owner Recycling by occupants (≥ 5 multi-family units) [MF] Efficient framing techniques - Lumber size Efficient framing techniques - Dimensions and layouts Efficient framing techniques - Building systems Efficient framing techniques - Pre-cut materials and details Prefinished building materials Concrete floors Use of building materials from rapidly renewable sources Drainage around foundations Roof drainage	PAMC 16.14.250/ 4.408.1 X PAMC 16.14.250/Section A4.408.1 X 4.408.3 X 4.408.5 X 4.410.1 X 4.410.2 A4.404.1 A4.404.2 A4.404.3 X A4.404.4 A4.405.1 X A4.405.1 X A4.405.2 A4.407.1 A4.407.2 X	<								
Mandatory Tier 2 Mand. Mandatory Mandatory Mandatory Mandatory Mandatory Elective Elective Elective Elective Elective Elective Elective Elective	Enhanced construction waste reduction (80% Diversion w/ job valuation >\$25,000 or meet state standards of Construction waste management plan in Green Halo Waste management company Documentation Operation and maintenance manual provided to the building owner Recycling by occupants (≥ 5 multi-family units) [MF] Efficient framing techniques - Lumber size Efficient framing techniques - Dimensions and layouts Efficient framing techniques - Building systems Efficient framing techniques - Pre-cut materials and details Prefinished building materials Concrete floors Use of building materials from rapidly renewable sources Drainage around foundations	PAMC 16.14.250/ 4.408.1 X PAMC 16.14.250/Section A4.408.1 X 4.408.3 X 4.408.5 X 4.410.1 X 4.410.2 A4.404.1 A4.404.2 A4.404.3 X A4.404.4 A4.405.1 X A4.405.1 X A4.405.2 A4.405.4 A4.407.1 A4.407.2 X A4.407.3 X A4.407.3 X	<								
Mandatory Tier 2 Mand. Mandatory Mandatory Mandatory Mandatory Mandatory Elective	Enhanced construction waste reduction (80% Diversion w/ job valuation >\$25,000 or meet state standards of Construction waste management plan in Green Halo Waste management company Documentation Operation and maintenance manual provided to the building owner Recycling by occupants (≥ 5 multi-family units) [MF] Efficient framing techniques - Lumber size Efficient framing techniques - Dimensions and layouts Efficient framing techniques - Building systems Efficient framing techniques - Pre-cut materials and details Prefinished building materials Concrete floors Use of building materials from rapidly renewable sources Drainage around foundations Roof drainage Flashing details	PAMC 16.14.250/ 4.408.1 X PAMC 16.14.250/Section A4.408.1 X 4.408.3 X 4.408.5 X 4.410.1 X 4.410.2 A4.404.1 A4.404.2 A4.404.3 X A4.404.4 A4.405.1 X A4.405.1 X A4.405.2 A4.407.1 A4.407.2 X	<								

								Comp	iance Pa	ttii VCIII	ication		
						Plan	Check			Final	Inspectio	n IVR‡	# 153
				F	Plan Sheet. Spec or	ı ıaıı	Onoon			Part 1	Part 1	Part 2	Part 2
A !	5 Environmer	otal Quality CO	de Section v			CORR	INITIAI						
7.0		and the same of th						001		00		001	
				, · ·		П							
						П							
		·				П							
				Х									
	Mandatory	Verification - documentation to verify complaint VOC limit on finish materials	4.504.2.4 X			П							
			4.504.3	Х		П							
			4.504.3.1	Χ		П							
>			4.504.3.2	X									
ō													
dai			4.504.5 X										
au	Mandatory	Composite wood products: documentation	4.504.5.1 X										
Σ	Mandatory	Concrete slab foundations - vapor retarder required	4.505.2 X										
	Mandatory	Capillary break for slab-on-grade foundations	4.505.2.1 X										
	Mandatory		4.505.3 X										
			4.506.1 X										
	Mandatory		X										
	Manuatory		X										
	Mandatory	Indoor Air Quality Management Plan [MF] PAMC 16.14	.390/5.506.4	X									1 1
1	Elective	Compliance with formaldehyde limits PAMC 16.14.2	60/ A4.504.1	Х									
s (Elective	Thermal insulation PAMC 16.14.2	70/ A4.504.3 X										
<u>i</u>	Elective	Construction filters [HR]	A4.506.2	X				_					
ect	Elective	Direct-vent appliances	A4.506.3	Х									
Ш	Elective	Innovative concepts and local environmental conditions.	A4.509.1	Х									
	lectives (1) Mandatory	Mandatory	Mandatory Fireplaces shall be direct-vent sealed combustion type PAMC 16.14. Mandatory Covering of duct openings, protection of mechanical equipment during constructio Mandatory Adhesives, sealants and caulks - Table 4.504.1 and 4.504.2 for VOC limits Mandatory Paints and coatings - Table 4.504.3 for VOC limits Mandatory Aerosol paints and coatings Mandatory Verification - documentation to verify complaint VOC limit on finish materials Mandatory Carpet systems- Documentation to verify compliant with VOC limits Mandatory Carpet systems: Carpet adhesive - Table 4.504.1 for VOC limits Tier 2 Mand. Resilient flooring systems for 100% - Tier 2 requirements Mandatory Composite wood products Mandatory Composite wood products: documentation Mandatory Moisture content of building materials ≤ 19% for wall and floor framing Bathroom exhaust fans (when required) shall be provided with the following: 1. ENERGY STAR fans ducted to outside of building. 2. Humidity controlled OR functioning as a component of a whole-house ventilation system 3. Humidity controlled OR functioning as a component of a whole-house ventilation system 4. Heating and air conditioning system design Mandatory Indoor Air Quality Management Plan [MF] PAMC 16.14.2 Elective Compliance with formaldehyde limits PAMC 16.14.2 Elective Thermal insulation PAMC 16.14.2 Elective Direct-vent appliances	Mandatory Fireplaces shall be direct-vent sealed combustion type PAMC 16.14.090/ 4.503.1	Mandatory Fireplaces shall be direct-vent sealed combustion type PAMC 16.14.090/ 4.503.1 X Mandatory Adhesives, sealants and caulks - Table 4.504.1 and 4.504.2 for VOC limits 4.504.2.1 X Mandatory Paints and coatings - Table 4.504.3 for VOC limits 4.504.2.1 X Mandatory Paints and coatings - Table 4.504.3 for VOC limits 4.504.2.2 X Mandatory Paints and coatings - Table 4.504.3 for VOC limits 4.504.2.3 X Mandatory Paints and coatings - Table 4.504.3 for VOC limits 4.504.2.3 X Mandatory Verification - documentation to verify complaint VOC limits 4.504.2.4 X Mandatory Verification - documentation to verify complaint vith VOC limits 4.504.3.1 X Mandatory Carpet systems- Documentation to verify compliant with VOC limits 4.504.3.1 X Mandatory Carpet systems: Carpet adhesive - Table 4.504.1 for VOC limits 4.504.3.1 X Mandatory Carpet systems for 100% - Tier 2 requirements PAMC 16.16.070 & 16.14.080/A4.504.2 X Mandatory Composite wood products 4.504.5 X Mandatory Composite wood products 4.504.5 X Mandatory Composite wood products 4.504.5 X Mandatory Capillary break for slab-on-grade foundations 4.504.5 X Mandatory Capillary break for slab-on-grade foundations 4.504.5 X Mandatory Capillary break for slab-on-grade foundations 4.505.2 X Mandatory Moisture content of building materials ≤ 19% for wall and floor framing 4.505.3 X Mandatory Mandatory Moisture content of building materials ≤ 19% for wall and floor framing 4.506.3 X Mandatory Mandatory Heating and air conditioning system design 4.507.2 X Mandatory Mandatory Heating and air conditioning system design 4.507.2 X Mandatory Mandatory Heating and air conditioning system design 4.507.2 X Mandatory Mandatory Heating and air conditioning system design 4.507.2 X Mandatory Mandatory Heating and air conditioning system design 4.507.2 X Mandatory Mandatory Heating and	Mandatory Fireplaces shall be direct-vent sealed combustion type PAMC 16.14.090/ 4.503.1 X Mandatory Covering of duct openings, protection of mechanical equipment during constructio 4.504.2.1 X Mandatory Adhesives, sealants and caulks - Table 4.504.1 and 4.504.2 for VOC limits 4.504.2.1 X Mandatory Aerosol paints and coatings 4.504.2.2 X Mandatory Verification - documentation to verify complaint VOC limit on finish materials 4.504.2.4 X Mandatory Carpet systems- Documentation to verify complaint VOC limits 4.504.3.1 X Mandatory Carpet systems- Documentation to verify complaint with VOC limits 4.504.3.1 X Mandatory Carpet systems: Carpet adhesive - Table 4.504.1 for VOC limits 4.504.3.2 X Mandatory Carpet systems: Carpet adhesive - Table 4.504.1 for VOC limits PAMC 16.16.070 & 16.14.080/ Al.504.2 X Mandatory Mandatory Composite wood products: PAMC 16.16.070 & 16.14.080/ Al.504.5 X Mandatory Mandatory	## A.5 Environmental Quality	A.5 Environmental Quality	4.5 Environmental Quality Code Section Y N Plan Sheet, Spoc or Attachment Reference Mandatory M	4.5 Environmental Quality Code Section y N Randatory Fireplaces shall be direct-vent sealed combustion type Mandatory Andreadroy Andr	4.5 Environmental Quality Code Section Y N Attachment Reference Mandatory Fireplaces shall be direct-vent sealed combustion type PAMC 16 14.090/ 4.503.1 X D Path 14.090/ 4.503.	4.5 Environmental Quality Mandatory Fireplaces shall be direct-vent sealed combustion type PAMC 10.14 090 4.503.1 X	4.5 Environmental Quality Code Section Y N Mandatory Fireplaces shall be direct-vent sealed combustion type Mandatory Covering of duct openings, protection of mechanical equipment during constructio Mandatory Mandatory Adhesives, sealenians and cauties - Table 4.504 at 1 and 4.504 2 for VOC limits Mandatory Mandatory Adhesives, sealenians and cauties - Table 4.504 3 for VOC limits Mandatory Mandatory Mandatory Mandatory Mandatory Mandatory Mandatory Mandatory Covering of fluct openings, protection of mechanical equipment during constructio Mandatory Mandatory Adhesives, sealenians and cauties - Table 4.504 3 for VOC limits Mandatory Mandatory Mandatory Mandatory Mandatory Covering of such period of the mandatory Corpet systems—Documentation to verify complaint VOC limits Mandatory Corpet sushion Mandatory Corpetition (Mandatory Corpe

Legend:

Y - Yes; the measure is in the scope of work N - No; the measure is not in the scope of work PAMC - Palo Alto Municipal Code; locally amended [N] - New Construction [MF] - Multi-family dwellings [AA] - Additions and alterations [HR] - High-rise building

The Green Building Survey is a required project submittal. The survey can be found at the following link. The online survey shall be completed and a Green Building Survey Report will be sent in an email. Include a copy of the survey report on a separate page in this plan set. Please indicate the reference page

	١	
		Special Inspector Acknowledgement
2 L		The project will be verified by a RESIDENTIAL GREEN BUILDING SPECIAL INSPECTOR
		I have reviewed the project plans and specifications, and they are in conformance with the CALGreen mandatory and elective measures claimed. I have reviewed and understand the after-construction requirements below. Signature (Green Building Special Inspector)
		Richard Yang Print Name richard@jbrcyllc.com Phone or Email 3/11/2025

Certified Energy Analyst Acknowledgement

The project will be verified by a CERTIFIED ENERGY ANALYST REQUIREMENT EFFECTIVE

10/4/2024

The Certificate of Compliance shall be prepared and signed by a Certified Energy Analyst and the energy budget for the Proposed Design shall be no greater than the Standard Design Building.

I am a Certified Energy Analyst with the California Association of Building Energy Consultants as of the date of submission of a Certificate of Compliance as required under Section 10-103 of the Building Energy Efficiency Standards for Residential and Non-Residential Buildings.

Signature (Certified Energy Analyst)

Phone or Email

SECTION TO BE COMPLETED AFTER CONSTRUCTION

CALGreen inspections were performed throughout construction. All mandatory CALGreen measures and required electives

new checklist is provided along with support for alternative electives claimed. The home has met the CALGreen measures as claimed on this sheet. Those required for landscaping may be excluded from this confirmation if verified within 6 months of final inspection.

noted in the checklist have been implemented, unless a

I have thoroughly reviewed these plans and ensured all Green Building Code requirements are addressed during construction implementation and prior to signing the plans (Code of Conduct Section B1).

I have completed field inspections diligently and accurately to ensure compliance with applicable Green Building Code requirements throughout the project (Code of Conduct I have maintained open and effective communication with

City staff, clients, and stakeholders (Code of Conduct Section D). I have maintained timely reports and furnished detailed records to the City of Palo alto Building Inspector during the Green Building Final Inspection (Code of Conduct Section C1).


Signature (Green Building Special Inspector)

Sign only after project is complete

CITY STAMPS ONLY

owper 245 Address:





ZHAO

2451 COWPER STREET

PALO ALTO, CA

APN: 132-07-012

RESIDENCE

WEC & ASSOCIATES

2625 MIDDLEFIELD RD #658 PALO ALTO, CA 94306 TEL: (650) 823-6466 FAX: (650) 887-1294

LICENSE STAMPS AND SIGNATURE



No. Description Date

Date

DATE:

JAN 2, 2025

SCALE:

1/8"=1'-0"

DRAWN:

BG

JOB:

10078

TOPOGRAPHIC SURVEY

SHEET NO.

SHEET TITLE:

C.