

660 UNIVERSITY AVE.

PALO ALTO, CA



PLANNING RESUBMITTAL #7
02.07.2024

PROJECT TEAM:

OWNER
SMITH DEVELOPMENT
682 VILLA STREET, SUITE G
MOUNTAIN VIEW, CA 94041
PHONE: 650.493.5314
LUND SMITH: LUND@SMITHDEVELOPMENT.COM
BOYD SMITH: BOYD@SMITHDEVELOPMENT.COM

ARCHITECT
KORTH SUNSERI HAGEY ARCHITECTS
349 SUTTER STREET
SAN FRANCISCO, CA 94108
PHONE: 415.954.1960
TED KORTH: TKORTH@KSHA.COM
AMANDA BORDEN: ABORDEN@KSHA.COM

LANDSCAPE ARCHITECT
THE GUZZARDO PARTNERSHIP INC.
PIER 9, THE EMBARCADERO, SUITE 115
SAN FRANCISCO, CA 94111
PHONE: 415.433.4672
PAUL LETTIERI: PLETTIERI@TGP-INC.COM

CIVIL ENGINEER
BKF ENGINEERS
255 SHORELINE, SUITE 200
REDWOOD CITY, CA 94065
PHONE: 650.482.6477
MONA SADEGHIAN: MSADEGHIAN@BKF.COM

ELECTRICAL ENGINEER
INTERFACE ENGINEERING INC.
135 MAIN STREET, SUITE 400
SAN FRANCISCO, CA 94105
PHONE: 415.489.7240
WESLEY LAU: WESLEYL@INTERFACEENG.COM
KRISTINA SANTI: KRISTINAS@INTERFACEENG.COM

SHEET INDEX:

PLAN 1				PLAN 2					
ARCHITECTURAL				LANDSCAPE				BIKE PARKING	
A0.1	PROJECT INFORMATION		A3.0	CONTEXT ELEVATIONS		L1.1	LANDSCAPE PLAN - GROUND FLR	SD1.0	EXISTING CONDITIONS & DEMO PLAN
A0.2A - C	CODE COMPLIANCE & EGRESS		A3.1A	WEST (BYRON ST) BUILDING ELEVATION		L1.1A	LANDSCAPE PLAN - (GF) COLORED	SD2.0	SITE PLAN
A0.3	EXISTING SITE PHOTOS							SD3.0	GRADING PLAN
A1.0	EXISTING SITE PLAN		A3.1B	EAST (MIDDLEFIELD RD) BUILDING ELEVATION		L1.2	LANDSCAPE PLAN - ROOF	SD4.0	UTILITY PLAN
A1.1	PROPOSED SITE PLAN		A3.2A	SOUTH BUILDING ELEVATION		L1.2A	LANDS. PLAN - (ROOF) COLORED	SD5.0	STORMWATER MANAGEMENT PLAN
A1.1B - C	OVERALL NEIGHBORHOOD CONTEXT SITE PLAN		A3.2B	NORTH (UNIVERSITY AVE) BUILDING ELEVATION		L2.1	LANDSCAPE IMAGERY	SD6.0	SECTIONS
			A3.3	OVERALL BUILDING SECTIONS		L3.1	PLANTING PLAN - SITE	SD7.0	DETAILS
			A3.3B	OVERALL BUILDING SECTION @ (E) OAK		L3.2	PLANTING PALETTE IMAGERY & WELO	SD7.1	DETAILS
						L3.3	PLANTING PLAN - ROOF DECK	JOINT TRENCH	
								JT-1 JOINT TRENCH TITLE SHEET	
								JT-2 JOINT TRENCH INTENT	
A2.P2	PARKING LEVEL P2 PLAN					L4.1	TREE DISPOSITION PLAN - SITE	TRASH MANAGEMENT	
A2.P1	PARKING LEVEL P1 PLAN					L4.2-6	TREE PROTECTION PLAN	TR0.1 OVERALL SITE PLAN	
A2.1	FIRST FLOOR PLAN						SITE ARBORIST REPORT	TR0.2 STAGING & BIN PATH	
A2.2A	SECOND FLOOR PLAN		A4.0A	ENLARGED PLANS & ELEVATION				TR1.0 TRASH ROOM COLLECTION DTLS	
A2.2B	THIRD FLOOR PLAN		A4.0B	ENLARGED SECTION				TR2.0 CHUTE DETAILS	
A2.3	FOURTH FLOOR PLAN		A4.1A	ENLARGED PLANS & ELEVATION				TR3.1 TRASH MANAGEMENT PLAN	
A2.4	ROOF PLAN							TR3.2 TRASH MANAGEMENT PLAN	
			A5.1	ENLARGED UNIT PLANS				TR3.3 TRASH MANAGEMENT PLAN	
								TR3.4 TRASH MANAGEMENT PLAN	
			A8.10	ENL. EXTERIOR DETAILS					
								PLAN 3 RENDERINGS	
								R1	RENDERING PERSPECTIVE
								R2	RENDERING PERSPECTIVE
								R3	RENDERING PERSPECTIVE
								R4	RENDERING PERSPECTIVE

[illegible]

PROJ
NORTH



TN



SCALE: 1" = 10'-0"



0' 5' 10' 20'

SHEET NUMBER

L 1.1

[illegible]

PROJ
NORTH



TN


SCALE: 1" = 10'-0"



0' 5' 10' 20'

SHEET NUMBER

L 1.1A





ISSUES AND REVISIONS		
NO.	DATE	DESCRIPTION
	12.01.21	PLANNING SUBMITTAL
	05.13.22	PLANNING RESUBMITTAL #1
	08.15.22	PLANNING RESUBMITTAL #2
	11.02.22	PLANNING RESUBMITTAL #3
	08.28.23	PLANNING RESUBMITTAL #4
	10.31.23	PLANNING RESUBMITTAL #5
	12.21.23	PLANNING RESUBMITTAL #6
	02.07.24	PLANNING RESUBMITTAL #7

PROJECT NUMBER
21003

SHEET TITLE
LANDSCAPE PLAN - ROOF

SCALE






ISSUES AND REVISIONS		
NO.	DATE	DESCRIPTION
12.01.21		PLANNING SUBMITTAL
05.13.22		PLANNING RESUBMITTAL #1
08.15.22		PLANNING RESUBMITTAL #2
11.02.22		PLANNING RESUBMITTAL #3
08.28.23		PLANNING RESUBMITTAL #4
10.31.23		PLANNING RESUBMITTAL #5
12.21.23		PLANNING RESUBMITTAL #6
02.07.24		PLANNING RESUBMITTAL #7

PROJECT NUMBER
21003

SHEET TITLE
LANDSCAPE PLAN - ROOF

SCALE



L 1.2 A

Site



Pedestrian Unit Paver Pattern




Pedestrian Accent Paving Color




Open Wire Omega Fence near Public Rights of Way for Pedestrian and Vehicular Visibility-6' Height



Existing Concrete Foundation Wall (Along Property Line Near Large Coast Live Oak) to Remain




Horizontal Wood Slat Screen Fence - 7' Height



Wood Deck on Grade




Welle Circular Bike Rack-Silver



Bollard Light



Bollard Light



Precast Planter on Decorative Gravel over Existing Asphalt



Precast Planter on Decorative Gravel over Existing Asphalt



Raised Concrete Treatment Planter
Height above grade varies in different site conditions. See plans

Roof Deck



Light and Raised Planter on Roof Deck



Light and Planter on Roof Deck



Low Bowl Planter on Roof Deck



Low Bowl Planter on Roof Deck



Unit Paving on Pedestals and Wood Deck

ISSUES AND REVISIONS		
NO.	DATE	DESCRIPTION
	12.01.21	PLANNING SUBMITTAL
	05.13.22	PLANNING RESUBMITTAL #1
	08.15.22	PLANNING RESUBMITTAL #2
	11.02.22	PLANNING RESUBMITTAL #3
	08.28.23	PLANNING RESUBMITTAL #4
	10.31.23	PLANNING RESUBMITTAL #5
	12.21.23	PLANNING RESUBMITTAL #6
	02.07.24	PLANNING RESUBMITTAL #7


660 UNIVERSITY
PALO ALTO, CA 94301

 **THE
Guzzardo
Partnership, INC.**
Landscape Architects | Land Planners
Pier 9, The Embarcadero, Suite 115
San Francisco, CA 94111 | www.tgp-inc.com

ISSUES AND REVISIONS		
NO.	DATE	DESCRIPTION
	12.01.21	PLANNING SUBMITTAL
	05.13.22	PLANNING RESUBMITTAL #1
	08.15.22	PLANNING RESUBMITTAL #2
	11.02.22	PLANNING RESUBMITTAL #3
	08.28.23	PLANNING RESUBMITTAL #4
	10.31.23	PLANNING RESUBMITTAL #5
	12.21.23	PLANNING RESUBMITTAL #6
	02.07.24	PLANNING RESUBMITTAL #7

PROJECT NUMBER
21003

SHEET TITLE
PLANTING PLAN - SITE



SHEET NUMBER

L 3.1

PLANT PALETTE

TREES- all 36" box							HABITAT FORMING	
KEY	QTY	BOTANICAL NAME	COMMON NAME	COMMENTS/SPACING	WUCOLS	NOTES		
PLA ACE	4	Platanus acerifolia "Columbia"	Columbia London Plane Tree	Standard	Medium	Regionally Appropriate		
PRU ILI	2	Prunus ilicifolia ssp. lyonii	Catalina Cherry	Standard	Low	California Native	Food	
ARB MAR	7	Arbutus 'Marina'	Marina Strawberry Tree	Multi	Low	California Native	Food	
SHRUBS, GROUNDCOVERS AND GRASSES --all 5 gallon size								
KEY	QTY	BOTANICAL NAME	COMMON NAME	COMMENTS/SPACING	WUCOLS	CALIFORNIA NATIVE		
AGV	31	Anigozanthos 'Gold Velvet'	Gold Kangaroo Paw	24" o.c.	Low	Regionally Appropriate	Food	
CAC	75	Carex californica	California Sedge	24" o.c.	Low	California Native		
CEO	4	Cephalanthus occidentalis	Buttonbush	48" o.c.	Medium	California Native	Food	
HET	5	Heteromeles arbutifolia	Toyon	48" o.c.	Low	California Native	Food	
IRD	67	Iris douglasiana	Pacific Coast Iris	12" o.c.	Low	California Native		
MCA	6	Myrica californica	California Wax Myrtle	36" o.c.	Medium	California Native	Food	
RSA	26	Ribes sanguineum	Red Flowering Currant	30" o.c.	Low	California Native	Food	
SAL	136	Salvia clevelandii 'Winfred Gillman'	Cleveland Sage	24" o.c.	Low	California Native	Food	
ACCENT SHRUBS, GRASSES AND PERENNIALS- all one gallon size								
CK	8	Calamagrostis x a. 'Karl Foerster'	Feather Reed Grass	36" o.c.	Medium	California Native	Food	
ST	66	Stipa arundinacea	New Zealand Wind Grass	18" o.c.	Low	Regionally Appropriate	Food	
SM	34	Senecio madraliscae	Blue Chalk Sticks	24" o.c.	VeryLow	Regionally Appropriate		
GROUNDCOVERS- all one gallon size								
SS	63	Sedum spectabile 'Crystal Pink'	Stonecrop	24" o.c.	VeryLow	Regionally Appropriate		
STORMWATER TREATMENT PLANT								
CH	10	5 Gal	Chondropetalum tectorum	Small Cape Rush	36" o.c.	Low	Regionally Appropriate	Food
DB	36	5 Gal	Dietes irioides	Fortnight Lily	24" o.c.	Low	Regionally Appropriate	
FC	220	5 Gal	Festuca californica	California Fescue	24" o.c.	Low	California Native	Food
JP	36	1 Gal	Juncus patens 'Elk Blue'	Elk Blue Gray Rush	48" o.c.	Low	California Native	
ME	12	1 Gal	Mahonia repens	Creeping Oregon Grape	24" o.c.	Low	California Native	Food
MR	26	1 Gal	Muhlenbergia rigens	Deer Grass	36" o.c.	Low	California Native	Food
SB	25	1 Gal	Sisyrinchium bellum	Blue-eyed grass	24" o.c.	VeryLow	California Native	

- Notes:
- Plants with low WUCOLS ratings are drought tolerant and regionally appropriate species. Plants noted are Native to California. Other plants, not in either of these two categories are well adapted to Palo Alto. Habitat forming column refers to food value of flowers or fruit for small animals, birds, butterflies and other insects in addition to shelter for some insects.
 - Do not use chemical fertilizers, pesticides, herbicides or commercial soil amendment. Use Organic Materials Review Institute (OMRI) materials and compost. Refer to the Bay-Friendly Landscape Guidelines: <http://www.stopwaste.org/resource/brochures/bay-friendly-landscape-guidelines-sustainable-practices-landscape-professional-for-guidance>
 - Avoid compacting soil in areas that will be unpaved. All planting areas to receive 3" layer of bark mulch.

The approximate total quantity of plants proposed is 894. Of these plants, 755 are native which totals 84.4% Native plantings.



Festuca californica



Helictotrichon sempervirens



Heteromeles arbutifolia



Lomandra 'Lime Turf'



Muhlenbergia rigens



Myrica californica



Rhamnus c. 'Mound San Bruno'



Salvia c. 'Winfred Gilman'



Stipa arundinacea



Sisyrinchium angustifolium



Calamagrostis acutiflora 'Stricta'



Anigozanthos 'Gold Velvet'



Sisyrinchium bellum



Mahonia repens

Reference Evapotranspiration (Eto) 43.1 City of Palo Alto							
Hydrozone # /Planting Description ^a	Plant Factor (PF)	Irrigation Method ^b	Irrigation Efficiency (IE) ^c	ETAF (PF/IE)	Landscape Area (sq. ft.)	ETAF x Area	Estimated Total Water Use (ETWU) ^d
Regular Landscape Areas							
Low Water-Use Plants	0.30	Drip	0.81	0.37	3,125	1,156	30,897
Moderate Water- Use Plants	0.50	Drip	0.81	0.62	322	200	5,335
					(A)	(B)	
				Totals	3,447	1,356	36,232
Special Landscape Areas							
Water Feature					77		
					(C)	(D)	
				Totals	0	0	
						ETWU Total	36,232
						Maximum Allowed Water Allowance (MAWA) ^e	41,450

^aHydrozone #/Planting Description
E.g
1.) front lawn
2.) low water use plantings
3.) medium water use planting

^dETWU (Annual Gallons Required) = Eto x 0.62 x ETAF x Area
where 0.62 is a conversion factor that converts acre- inches per acre per year to gallons per square foot per year.

^eMAWA (Annual Gallons Allowed) = (Eto) / (0.62) [(ETAF x LA) + ((1-ETAF) x SLA)]
where 0.62 is a conversion factor that converts acre-inches per acre per year to gallons per square foot per year, LA is the total landscape area in square feet, SLA is the total special landscape area in square feet, and ETAF is .55 for residential areas and 0.45 for non-residential areas.

ETAF Calculations
Average ETAF for Regular Landscape Areas must be 0.55 or below for residential areas, and 0.45 or below for non-residential areas.

Regular Landscape Areas	
Total ETAF x Area (B)	1,356
Total Area (A)	3,447
Average ETAF	0.393353640

All Landscape Areas	
Total ETAF x Area (B+D)	1,356
Total Area (A+C)	3,447
Sitewide ETAF (B+D) ÷ (A+C)	0.393353640847113

SMITH DEVELOPMENT

660 UNIVERSITY
PALO ALTO, CA 94301

THE
Guzzardo
Partnership, INC.
Landscape Architects| Land Planners
Pier 9, The Embarcadero, Suite 115
San Francisco, CA 94111 | www.tgp-inc.com

ISSUES AND REVISIONS

NO.	DATE	DESCRIPTION
	12.01.21	PLANNING SUBMITTAL
	05.13.22	PLANNING RESUBMITTAL #1
	08.15.22	PLANNING RESUBMITTAL #2
	11.02.22	PLANNING RESUBMITTAL #3
	08.28.23	PLANNING RESUBMITTAL #4
	10.31.23	PLANNING RESUBMITTAL #5
	12.21.23	PLANNING RESUBMITTAL #6
	02.07.24	PLANNING RESUBMITTAL #7

PROJECT NUMBER
21003

SHEET TITLE
PLANTING PALETTE & IMAGERY &
WELO CALCULATIONS

SCALE

SHEET NUMBER

L 3.2


660 UNIVERSITY
PALO ALTO, CA 94301

THE
Guzzardo
Partnership, INC.
Landscape Architects | Land Planners
Pier 9, The Embarcadero, Suite 115
San Francisco, CA 94111 | www.tgp-inc.com

MIDDLEFIELD ROAD

UNIVERSITY AVE

BYRON STREET



ISSUES AND REVISIONS		
NO.	DATE	DESCRIPTION
12.01.21		PLANNING SUBMITTAL
05.13.22		PLANNING RESUBMITTAL #1
08.15.22		PLANNING RESUBMITTAL #2
11.02.22		PLANNING RESUBMITTAL #3
08.28.23		PLANNING RESUBMITTAL #4
10.31.23		PLANNING RESUBMITTAL #5
12.21.23		PLANNING RESUBMITTAL #6
02.07.24		PLANNING RESUBMITTAL #7

PROJECT NUMBER
21003

SHEET TITLE
PLANTING PLAN - ROOF DECK

SCALE
PROJ NORTH
SCALE: 1" = 10'-0"
0' 5' 10' 20'
SHEET NUMBER


L 3.3

TREE DISPOSITION LEGEND

Total Existing Trees on Site	24
Disposition	Regulated Trees
Tree to be Preserved	0
Tree to be Preserved Off-Site	5
Total Trees Preserved	5
Removed, Poor Condition	3
Removed, Project Re-Design	16
Total Trees Removed	19
Total Proposed Trees	13
Total Trees on Future Site	16

Note:
- See Arborist Report by Arbor Resources dated February 07, 2024 for specific information about existing trees. Contact project Arborist prior to performing any work within the Tree Protection Zones noted in the Arborist report and shown on this drawing as well.

UNIVERSITY AVE



SMITH DEVELOPMENT

660 UNIVERSITY
PALO ALTO, CA 94301


THE
Guzzardo
Partnership, INC.
Landscape Architects | Land Planners
Pier 9, The Embarcadero, Suite 115
San Francisco, CA 94111 | www.tgp-inc.com

ISSUES AND REVISIONS

NO.	DATE	DESCRIPTION
12.01.21		PLANNING SUBMITTAL
05.13.22		PLANNING RESUBMITTAL #1
08.15.22		PLANNING RESUBMITTAL #2
11.02.22		PLANNING RESUBMITTAL #3
08.28.23		PLANNING RESUBMITTAL #4
10.31.23		PLANNING RESUBMITTAL #5
12.21.23		PLANNING RESUBMITTAL #6
02.07.24		PLANNING RESUBMITTAL #7

PROJECT NUMBER
21003

SHEET TITLE
TREE DISPOSITION PLAN - SITE



SHEET NUMBER

L 4.1

660 UNIVERSITY
PALO ALTO, CA 94301

THE
Guzzardo
Partnership, INC.
Landscape Architects | Land Planners
Pier 9, The Embarcadero, Suite 115
San Francisco, CA 94111 | www.tgp-inc.com

City of Palo Alto Tree Protection - It's Part of the Plan!

Make sure your crews and subs do the job right!

Fenced enclosures around trees are essential to protect them by keeping the foliage canopy and branching structure clear from contact by equipment, materials and activities, preserving roots and soil conditions in an intact and non-compacted state, and identifying the Tree Protection Zone (TPZ) in which no soil disturbance is permitted and activities are restricted, unless otherwise approved. **An approved tree protection report must be added to this sheet when project activity occurs within the TPZ of a regulated tree.**
For detailed information on Palo Alto's regulated trees and protection during development, review the **City Tree Technical Manual (TTM)** found at www.cityofpaloalto.org/trees/.



TREE DISCLOSURE STATEMENT

CITY OF PALO ALTO
Planning Division, 250 Hamilton Avenue
Palo Alto, CA 94301
(650) 329-2441
<http://www.cityofpaloalto.org>

Palo Alto Municipal Code, Chapter 8.10.040, requires disclosure and protection of certain trees located on private and public property, and that they be shown on approved site plans. A completed disclosure statement must accompany all building permit applications that include exterior work, all demolition or grading permit applications, or other development activity.

PROPERTY ADDRESS: _____

Are there Regulated trees on or adjacent to the property? **YES** **NO** (If no, proceed to Section 4)

[Sections 1-4 MUST be completed by the applicant. Please circle and/or check where applicable.]

1. Where are the trees? Check those that apply. (Plans must be submitted showing over 4" diameter trees)
☐ On the property
☐ On adjacent property overhanging the project site
☐ In the City planter strip or right-of-way easement within 30' of property line (Street Trees)*

*Street trees require special protection by a fenced enclosure, per the attached instructions. Prior to receiving any permit, you must provide an authorized Street Tree Protection Verification form by calling Public Works Operations at 493-5953 for inspection of required type I, II or III fencing (see attached Detail #605).

2. Are there any Protected or Designated Trees? **YES** (Check where applicable) **NO**
☐ Protected Tree (s)
☐ Designated Tree (s)
☐ On or overhanging the property

3. Is there activity or grading within the dripline? (radius 10 times the trunk diameter) of these trees? **YES** **NO**
If Yes, a **Tree Preservation Report** must be prepared by an ISA certified arborist and submitted for staff review (see TTM, Section 6.25). Attach this report to Sheet T-1, "Tree Protection, its Part of the Plan", per Site Plan Requirements.

4. Are the Site Plan Requirements** completed? **YES** **NO**
**Protection of Regulated trees during development require the following: (1) Plans must show the measured trunk diameter and canopy dripline; (2) Plans must denote, as a bold dashed line, a fenced enclosure area out to the dripline, per Sheet T-1 and Detail #605 - <http://www.cityofpaloalto.org/trees/forms.html> (See also TTM, Section 2.15 for area to be fenced)

I, the undersigned, agree to the conditions of this disclosure. I understand that knowingly or negligently providing false or misleading information in response to this disclosure requirement constitutes a violation of the Palo Alto Municipal Code Section 8.10.040, which can lead to criminal and/or civil legal action.

Signature: _____ Print: _____ Date: _____
(Prop. Owner or Agent)

FOR STAFF USE:
Protective Fencing
Sections 5-6 must be completed by staff for the issuance of any development permit (demolition, grading or building permit).

5. Protected Trees. The specified tree fencing is in place. A written statement is attached verifying that protective fencing is correctly in place around protected and/or designated trees. **YES** **NO**
(N/A if there are no protected trees, check here C)

6. Street Trees. A signed Public Works Street Tree Protection Verification form is attached. **YES** **NO**
(N/A if there are no street trees, check here C).

Regulated Trees - a) Street trees - trees on public property; b) Protected trees - Coast Live Oaks or Valley Oaks which are 11-15" in diameter or larger, Coast Redwoods which are 18" in diameter or larger, when measured 5'4" above natural grade, and Heritage trees are trees designated by City Council; and c) Designated Trees - commercial or non-residential property trees, which are part of an approved landscape plan.
Palo Alto Tree Technical Manual (TTM) contains instructions for all requirements on this form, available at http://www.cityofpaloalto.org/planning-community/tree_technical_manual.html

S:Plan/Plots/Accounts/Tree Protection Info/Tree Disclosure Statement
Revised 08/06

For written specifications associated with illustrations below, see Public Works Specifications Section 31
Detailed specifications are found in the Palo Alto Tree Technical Manual (TTM) (www.cityofpaloalto.org/trees/)

Tree Protection Zone (TPZ) shown in gray (radius of TPZ equals 10 times the diameter of the tree at 10-foot, whichever is greater).
• Restricted activity area - see Tree Technical Manual Sec 2.15(E).
• Restricted treeing area - see Tree Technical Manual Sec 2.20(C,D), any proposed trench or form work within TPZ of a protected tree requires approval from Public Works Operations. Call 650-496-5953.

Type I Tree Protection
For all Ordinance Protected and Designated trees, as defined in the site specific tree preservation report (TPR) prepared by the applicant's project arborist as designated on the plans.
Note: Ordinance Protected & Designated Trees. Issuance of a permit requires applicant's project arborist written verification Type I is installed correctly according to the plan and Tree Preservation Report.
6.5/11-inch Warning Tape one each side
6 feet high chain link fence
Over 10" Tree Diameter - 10' radius in plan
Any installation identical to each replacement or trenching requires approval.
Tree diameter
Fencing must provide public passage while protecting all other land in TPZ.

Type II Tree Protection
2-inch Orange Plastic Fencing installed with 2-inch Tree Winder Stake
Any proposed trench in TPZ requires approval per TTM 2.20 (C,D) for enclosure in plan.
Note: Street Trees. Issuance of a permit requires Public Works Operations inspection and signed approval on the Street Tree Verification (STV) form provided.
Tree diameter
Fencing must provide public passage while protecting all other land in TPZ.
To be used only with approval of Public Works Operations.

Type III Tree Protection
Tree fencing is required and shall be erected before demolition, grading or construction begins.

Tree Protection During Construction
City of Palo Alto Standard

Approved by: Dave Docket
PE No. _____
Date: 2006
Drawn by: _____
No. 605

Scale: NTS



**PALO ALTO
STREET TREE PROTECTION INSTRUCTIONS
-SECTION 31-**

31-1 General
a. Tree protection has three primary functions: 1) to keep the foliage canopy and branching structure clear from contact by equipment, materials and activities; 2) to preserve roots and soil conditions in an intact and non-compacted state and 3) to identify the Tree Protection Zone (TPZ) in which no soil disturbance is permitted and activities are restricted, unless otherwise approved.
b. The Tree Protection Zone (TPZ) is a restricted area around the base of the tree with a radius of ten-times the diameter of the tree's trunk or ten feet, whichever is greater, enclosed by fencing.

31-2 Reference Documents
a. Detail 605 - Illustration of situations described below.
b. Tree Technical Manual (TTM) Form (<http://www.cityofpaloalto.org/trees/>)
1. Trenching Restriction Zones (TTM, Section 2.20(C))
2. Adjacent Property Fencing (TTM, Section 6.10)
3. Site Plan Requirements (TTM, Section 6.25)
4. Tree Disclosure Statement (TTM, Appendix J)
c. Street Tree Verification (STV) Form (<http://www.cityofpaloalto.org/trees/forms>)

31-3 Execution
a. **Type I Tree Protection:** The fence shall enclose the entire TPZ of the tree(s) to be protected throughout the life of the construction project. In some parking areas, if fencing is located on paving or concrete that will not be demolished, then the posts may be supported by an appropriate grade level concrete base, if approved by Public Works Operations.
b. **Type II Tree Protection:** For trees situated within a planting strip, only the planting strip and yard side of the TPZ shall be enclosed with the required chain link protective fencing in order to keep the sidewalk and street open for public use.
c. **Type III Tree Protection:** To be used only with approval of Public Works Operations. Trees situated in a tree well or sidewalk planter pit, shall be wrapped with 2 inches of orange plastic fencing from the ground to the first branch and overlaid with 2-inch thick wooden chain board securely (chain shall not be allowed to dig into the bark). During installation of the plastic fencing, caution shall be used to avoid damaging any branches. Major limbs may also require plastic fencing as directed by the City Arborist.
d. **Site, type and area to be fenced.** All trees to be preserved shall be protected with an (6') foot high chain link fence. Fences are to be mounted on two-inch diameter galvanized iron posts, driven into the ground to a depth of at least 2 feet or more than 10-foot spacing. Fencing shall extend to the outer branching, unless specifically approved on the STV Form.
e. **"Warning" signs.** A warning sign shall be weather proof and prominently displayed on each fence at 20-foot intervals. The sign shall be minimum 8.5 inches x 11 inches and clearly state in half inch tall letters "WARNING: Tree Protection Zone - This fence shall not be removed and is subject to a fine according to PAMC Section 8.10.110."
f. **Barriers.** Tree fencing shall be erected before demolition, grading or construction begins and remain in place until final inspection of the project, except for work specifically allowed in the TPZ. Work or soil disturbance in the TPZ requires approval by the project arborist or City Arborist (in the case of work around Street Trees). Excavation within the public right-of-way requires a Street Tree Form from Public Works.
g. **During construction**
1. All neighbors' trees that overhang the project site shall be protected from impact of any kind.
2. The applicant shall be responsible for the repair or replacement plus penalty of any publicly owned trees that are damaged during the course of construction, pursuant to Section 8.6A(5)(F) of the Palo Alto Municipal Code.
3. The following tree preservation measures apply to all trees to be retained:
a. No storage of material, spoil, vehicles or equipment shall be permitted within the TPZ.
b. The ground under and around the tree canopy area shall not be altered.
c. Trees to be retained shall be irrigated, aerated and maintained as necessary to ensure survival.

City of Palo Alto 2004 Standard Drawings and Specifications
Street Tree Verification of Protection, PWS, Section 31
Revised 08/06

END OF SECTION

Table 2-2 Palo Alto Tree Technical Manual

ARBORIST INSPECTION SCHEDULE

All Checked Items Apply to this project:

1. ☒ **Inspection of Protective Tree Fencing.** The Street Tree Verification Form shall be signed by the City Arborist. For other Protected Trees, the project arborist shall provide a written statement with a photograph verifying that he has conducted a field inspection of the trees and that the protective tree fencing is in place prior to issuance of a demolition, grading, or building permit. (see Verification of Tree Protection, Section 1.39).

2. ☐ **Pre-Construction Meeting.** Prior to commencement of construction, the applicant or contractor shall conduct a pre-construction meeting to discuss tree protection with the job site superintendent, grading equipment operators, project arborist, City Arborist, and, if a city maintained irrigation system exists, the Parks Manager (Contact 650-496-6962).

3. ☐ **Inspection of Rough Grading.** The project arborist shall perform an inspection during the course of rough grading adjacent to the TPZ to ensure trees will not be injured by compaction, cut or fill, drainage and trenching, and if required, inspect aeration systems, tree wells, drains and special paving. The contractor shall provide the project arborist at least 48 hours advance notice of such activity.

4. ☐ **Monthly Inspections.** The project arborist shall perform a monthly activity inspection to monitor and advise for conditions and tree health. The City Arborist shall be in receipt of the activity report during the first week of each calendar month or, immediately if there are any *variations* to the approved plans or protection measures. Fax to (650) 329-2154. (see Monthly Inspection Report, Section 1.17).

5. ☐ **Special activity within the Tree Protection Zone.** Work in this area (TPZ - described in #7 below) requires the direct onsite supervision of the project arborist (see Trenching, Excavation and Equipment, TTM Section 2.20 C).

6. ☐ **Landscape Architect Inspection.** For discretionary development projects, prior to temporary or final occupancy the applicant or contractor shall arrange for the Landscape Architect to perform an on site inspection of all plant stock, quality of the materials and planting (see Quality, Section 5.20.1 A) and that the irrigation is functioning consistent with the approved construction plans. The City shall be in receipt of written verification of Landscape Architect approval prior to scheduling the final inspection, unless otherwise approved.

7. ☐ **Other** (please describe) _____

---WARNING---
Tree Protection Zone

This fencing shall not be removed without City Arborist approval (650-496-5953)

Removal without permission is subject to a \$500 fine per day*
***Palo Alto Municipal Code Section 8.10.110**
City of Palo Alto Tree Protection Instructions are located at <http://www.city.palo-alto.ca.us/trees/technical-manual.html>

ISSUES AND REVISIONS		
NO.	DATE	DESCRIPTION
	12.01.21	PLANNING SUBMITTAL
	05.13.22	PLANNING RESUBMITTAL #1
	08.15.22	PLANNING RESUBMITTAL #2
	11.02.22	PLANNING RESUBMITTAL #3
	08.28.23	PLANNING RESUBMITTAL #4
	10.31.23	PLANNING RESUBMITTAL #5
	12.21.23	PLANNING RESUBMITTAL #6
	02.07.24	PLANNING RESUBMITTAL #7

PROJECT NUMBER
21003

SHEET TITLE
TREE DISPOSITION PLAN - SITE
ARBORIST REPORT

SCALE

SHEET NUMBER

T-1

All other tree-related reports shall be added to the space provided on this sheet (adding as needed)
Include this sheet(s) on Project Sheet Index or Legend Page.
A copy of T-1 can be downloaded at www.cityofpaloalto.org/arb/forms

Special Tree Protection Instruction Sheet
City of Palo Alto

T-1

L 4.2

City of Palo Alto Tree Protection - It's Part of the Plan!

Make sure your crews and subs do the job right!

Fenced enclosures around trees are essential to protect them by keeping the foliage canopy and branching structure clear from contact by equipment, materials and activities, preserving roots and soil conditions in an intact and non-compacted state, and identifying the Tree Protection Zone (TPZ) in which no soil disturbance is permitted and activities are restricted, unless otherwise approved. **An approved tree protection report must be added to this sheet when project activity occurs within the TPZ of a regulated tree.**
For detailed information on Palo Alto's regulated trees and protection during development, review the **City Tree Technical Manual (TTM)** found at www.cityofpaloalto.org/trees/.

David L. Bobby, Registered Consulting Arborist® February 7, 2024

Table continued:

TREE #	COMMON NAME	DISPOSITION		DIAM (in.)	CAN (ft.)	SUITABILITY FOR PRESERVATION
		RETAIN	RMV			
19	Crape myrtle	-	X	5	10	Moderate
20	Crape myrtle	-	X	3, 3, 2	5	Moderate
21	Crape myrtle	-	X	6	10	Moderate
22	Crape myrtle	-	X	6	10	Moderate
23	Crape myrtle	-	X	6	15	Moderate
24	Crape myrtle	-	X	4, 3, 2	10	Moderate
25	Yew pine	-	X	8	10	Moderate

LEGEND:
RMV = Remove
DIAM = Diameter (trunk)
CAN = Canopy spread (average)

5.2 Proposed Removals

The 19 trees proposed for removal include #4-6, 8 and 11-25. Trees #4 thru 6 are street trees aligning University Avenue, and will be removed due to their poor condition and low suitability for preservation. Trees #4 and 5 are small privets with advanced and extensive decline and decay. Tree #6 is a London plane which has partially uprooted, leans towards the street, and opposite the lean, has formed a pronounced buttress root causing extensive and somewhat dramatic hardscape damage. Removing #4 thru 6 provides the opportunity to significantly improve the future, long-term tree landscape and site/public safety.

Tree #8 is a street tree of moderate suitability for preservation, and requires removal to accommodate the future drive aisle off Byron Street.

Trees #11 thru 25 are located onsite and within the proposed building and parking garage footprint. Each represents a relatively small, non-native assigned either a low or moderate suitability for preservation.

For replacement sizes, amounts and species, refer to the CPA's recommendations.

660 University Avenue, Palo Alto
Smith Development Page 8 of 18

David L. Bobby, Registered Consulting Arborist® February 7, 2024

5.3 Retained Trees

Trees planned for retention include #1-3, 7, 9 and 10. This section provides my analysis for those exposed to impacts, to include all but #9, and discusses general recommendations to minimize described impacts.

Additional and more detailed mitigation measures are presented within the next section of this report. They should be incorporated into project plans; carefully followed throughout the entire demolition, grading and construction stages; and are subject to revision upon reviewing any revised plans.

Trees #1-3 and 7

These street trees align the project site, and their protection zones can be regarded as being from their trunks up to the existing back of sidewalks and street curbs, and 10 feet in all other directions. Each tree will sustain an estimated 15- to 20-percent canopy loss to achieve building construction. Shoring installation for the parking garage may require an additional 5- to 10-percent of additional canopy removal.

Overall, I find the trees will not be adversely impacted provided these items are followed: pruning is judiciously performed through limited and highly-selective cuts by a California State licensed tree-service company approved by the CPA; scaffolding is minimized in width, and manlifts are utilized, when needed, to avoid unnecessary limb removal; and the shoring methodology is carefully studied and locations for drilling or driving piles are strategically placed to minimize canopy loss. Protection for these trees should include what the CPA defines as Type III Protection (aka trunk wrap), plus plywood to cover unpaved ground (i.e. planters) within their TPZ.

Tree #10

The architectural design substantially conforms to my recommendations provided in January 2021, which stipulates a minimum 30-foot setback from the oak's trunk to construct the future building and parking garage, and a minimum setback of 20 feet from the trunk for all ground disturbance beneath the existing asphalt surface.

The CPA's Tree Protection Zone (TPZ) standard is a radial distance from the trunk equal to 10 times its diameter, which for oak #10, identifies a TPZ of 41 feet from the trunk. The proposed project establishes the TPZ to be 30 feet from the trunk, which equates to a multiplier of 7 times the trunk diameter (and 11 feet inside). Information regarding anticipated impacts to the canopy and roots are discussed on the next page.

660 University Avenue, Palo Alto
Smith Development Page 9 of 18

David L. Bobby, Registered Consulting Arborist® February 7, 2024

Canopy

The 30-foot setback from #10's trunk considers an additional 5 to 6 feet towards the tree where pruning would occur to establish clearances from the building, scaffolding, manlifts, and any shoring equipment. The proposed balconies do encroach inside the 30-foot setback by 5 to 6 feet, but provided construction scaffolding does not need to be erected beyond the balconies' edges (i.e. between the balconies and tree's trunk), then the building remains in conformance with the setback. During construction of the parking garage, strategically placing shoring and highly-selective pruning can limit impacts.

The estimated total canopy loss to construct the proposed building is 15-percent, the extent of which will not adversely affect the oaks' existing form. This considers removing a low, 17-inch diameter limb overhanging the lot (see page C-3 of Exhibit C for a photo); an 8-inch diameter branch emerging from a 14-inch diameter limb growing mostly upright at a slight westerly angle; and roughly a dozen smaller branches ranging in size from 1 to 6 inches in diameter. All cuts will be highly selective, occur beyond the main trunk, and performed under direct supervision of the project arborist.

Additional and minor sections of canopy may also require removal to facilitate shoring installation to build the underground parking garage; based on my site analysis, I estimate only 5- to 10-percent, provided the shoring methodology is carefully studied and locations for drilling or driving piles are strategically placed.

Roots

The 20-foot setback from #10's trunk for ground disturbance applies to any soil compaction, grading, subexcavation, overexcavation, trenching, drilling/auguring, storm drains, swales, etc. My review of proposed plans reveals this has been achieved, and a large section of existing asphalt within this area will be retained, a wood deck built on top, and section of existing retaining wall within the TPZ kept in place. Exhibit D includes both Sheet L1.1 and a detailed section of the proposed deck.

Based on my site analysis and plan review, I estimate implementing the proposed design will affect approximately 15- to 20-percent of its root zone, a level considered highly tolerable, particularly for inherently resilient species of coast live oaks.

Protection for #10 would consist of CPA Type I Protection (aka chain link mounted on driven posts).

660 University Avenue, Palo Alto
Smith Development Page 10 of 18

David L. Bobby, Registered Consulting Arborist® February 7, 2024

6.0 TREE PROTECTION MEASURES

Recommendations presented within this section are based on my review of the 10/31/23 plan set, and serve as measures to help mitigate or avoid impacts to trees anticipated for retention. I (hereinafter, "project arborist") should be consulted in the event any cannot be feasibly implemented. Please note, unless otherwise stated, all referenced distances from trunks are intended to be from the closest edge, face of, their outer perimeter at soil grade.

6.1 Design Guidelines

1. Consider each Tree Protection Zone (TPZ) as those minimum distances specified within Section 5.0 of this report. The TPZ is the area where the following minimum activities should be avoided: trenching, soil scraping, compaction, mass and finish-grading, overexcavation, subexcavation, tilling, ripping, swales, bioswales, storm drains, dissipaters, equipment cleaning, removal of underground utilities and vaults, altering existing water/drainage flows, stockpiling and dumping of materials, and equipment and vehicle operation. Where an impact encroaches slightly within a setback, it can be reviewed on a case-by-case basis by the project arborist to determine appropriate mitigation measures.

2. The CPA requires all design changes occurring near retained trees are reviewed by the project arborist prior to resubmitting plans, for purposes of identifying potential impacts and any possible mitigation measures.

3. Per CPA requirements, incorporate this report into the project plan set, following the CPA T-1 sheet, and copying onto T-2, T-3, etc. until its entirety is shown (and in a manner which all report text can be clearly read on the plan sheets).

4. On all architectural, civil, landscape and electrical site-related plans, show the trunk locations, trunk diameters (as circles to scale), and assigned numbers of all inventoried trees (see map in Exhibit B). Also, add notes instructing contractors to comply with recommendations presented in this report and on Sheet T-1, and to contact the project arborist prior to permitted work being performed within a TPZ.

660 University Avenue, Palo Alto
Smith Development Page 11 of 18

David L. Bobby, Registered Consulting Arborist® February 7, 2024

5. On L4.1 and SD1.0, include the following: the notes mentioned in item 4 (second sentence), identify which trees are proposed for removal by placing an "X" across their trunks, and identify the Tree Protection Zones and protection fencing types as shown on the map in Exhibit B.

6. On SD1.0, add a note specifying to abandon any underground portions of existing and unused lines, pipes and manholes, etc. within a TPZ (prescribe they are cut off at existing soil grade versus being dug up and causing root damage). Also, to comply with this, modify the utility demolition currently prescribed within #1's TPZ.

7. Route underground utilities and services beyond TPZs, and per CPA guidelines for street trees, establish at least 10 feet from their trunks. Where this is not feasible, consider the following alternative trenching or installation methods (listed in order of least to most impactful): directionally bore by at least 3.5 to 4 feet below grade, tunnel using a pneumatic air device (e.g. an AirSpade®), or manually dig with a shovel (i.e. no jackhammer); these assume pipe bursting, an optimal method, does not apply to this project. For boring, establish access pits and above-ground infrastructure (e.g. splice boxes, meters and vaults) beyond TPZs.

8. Where within 30 feet from #10's trunk, ensure specifications by the geotechnical, soils and structural engineers do not require compaction, overexcavation, subexcavation or fill beyond 2 feet from the parking garage wall (towards the tree) and 5 feet beyond the building's foundation. Shoring utilized to achieve these setbacks, such as a pile driver or drill rig, shall not be used where significant damage to a tree's canopy would occur (can be determined on a case-by-case basis).

9. The proposed sidewalks within the trees' TPZs should be designed and built entirely above existing soil grade and surface roots (i.e. a no-dig design), including for base material, edging and forms. Also, direct compaction of soil shall be avoided (levels comparable to foot-tamping are acceptable), and soil fill used to bevel the top of walk to existing grade should not exceed 18 to 24 inches from a walk's edge, not be compacted, nor placed closer than 10 feet from a tree's trunk. Tensor® BX Geogrid (www.tensorcorp.com) is a material which can help address these limited excavation and compaction requirements.

660 University Avenue, Palo Alto
Smith Development Page 12 of 18

David L. Bobby, Registered Consulting Arborist® February 7, 2024

10. For any retaining or landscape wall within a TPZ, utilize a pier and above-grade beam system, establish the beam spanning between footings to be above-grade (i.e. a no-dig design except for footings), and avoid fill and compaction between footings.

11. Design any new bioswales, storm drains and swales well-beyond TPZs.

12. The permanent and temporary drainage design, including downspouts, should not require water being discharged beneath #10's canopy.

13. All electrical routes should be designed and represented on the electrical site plan to be beyond TPZs.

14. Any new light poles should be established beyond tree canopies, or at a minimum, only where minor branch clearance is needed. The proximity of tree trunks should also be considered, and placed as far from them as possible.

15. The future staging area and route(s) of access should be shown on the final site plan and avoided on unpaved areas beneath or near canopies.

16. The erosion control design should represent silt fence and/or straw rolls at locations beyond TPZs, and at a minimum, not against a tree's trunk. Where within a TPZ, the material should not be embedded into the ground by more than 2 inches, nor require the severance of surface or shallow roots.

17. Avoid specifying the use of herbicides use within a TPZ; where used on site, they should be labeled for safe use near trees. Also, liming shall not occur or be prescribed within 50 feet from a tree.

18. The landscape design should conform to the following additional guidelines:
a. Tilling, ripping, surface scraping and compaction within TPZs should be avoided.
b. Irrigation should not strike within 12 inches from trunks of existing trees, nor applied against trunks of new trees.
c. Plant material installed beneath tree canopies should be >12 to 24 inches from their trunks.

660 University Avenue, Palo Alto
Smith Development Page 13 of 18

David L. Bobby, Registered Consulting Arborist® February 7, 2024

d. New street tree(s) should be designed to be at least 10 feet from any existing or new utility (per CPA guidelines).

e. All new trees should be installed, including necessary irrigation, by an experienced California state-licensed landscape contractor (C-27) or tree service company (D-49), and performed to professional industry standards. Only if necessary to stand upright, they should be double-staked (no cross-brace) with rubber tree ties or equivalent, and the support stakes cut below the first main lateral branch. All nursery stakes shall be removed. Root crowns of new trees shall be visible and absent of encircling roots.

f. Irrigation and lighting features (e.g. main line, laterals, valve boxes, wiring and controllers) should not require trenching inside TPZs, including header/lateral lines. In the event this is not feasible, they may require being installed in a radial direction to, and terminate a specific distance from a trunk (versus crossing past it). In certain instances, a pneumatic air device may be needed to avoid root damage, and any Netafim tubing placed on grade.

g. Irrigation for new trees should be supplied through an automatic timer, separate from other plant material, and supplied by one to two bubblers (minimum two for a 48-inch box). The bubblers should be placed and staked on the rootball's surface (not against a trunk, in a sleeve or on mulch), at around 1/2 to 1/3 the distance between the trunk and rootball edge. Additionally, an 8-inch tall circular berm formed by soil should be established around a rootball's perimeter, and a 3-inch layer of mulch spread over their tops, kept 1-inch from the trunks' bases.

h. Ground cover beneath canopies of existing trees should be comprised of a 3-inch layer of coarse wood chips or other high-quality mulch (gorilla hair, rock, stone, gravel, black plastic or other synthetic ground cover should be avoided). Mulch should kept off the trees' trunks or visible root collars.

i. Bender board or other edging material proposed beneath the canopies should be established on top of existing soil grade (such as by using vertical stakes).

j. Herbicides should be avoided within a TPZ, and where used on site, labeled for safe use near trees. Liming shall not occur within 50 feet from a trunk.

660 University Avenue, Palo Alto
Smith Development Page 14 of 18

David L. Bobby, Registered Consulting Arborist® February 7, 2024

6.2 Before Demolition, Grading and Construction

19. Several weeks prior to mobilizing equipment for demolition, and again, prior to shoring, grading and utility work, conduct a site meeting between the general contractor, applicable subcontractors, and project arborist. The purpose for these meetings is to review tree protection, demolition procedures, shoring methodology and vertical clearances needed for the pile driver or drill rig, and excavation for the underground garage, trench routes, limits of grading, supplemental watering, mulching, pruning, routes of access, staging, and other items and protection measures presented in this report.

20. The project arborist must also regularly inspect the project site as outlined on page 2-14 of the Tree Technical Manual (Section 2.30 Inspection Schedule), and verify conformance to tree protection measures. Inspections shall occur at least once per month and continue through final inspection, and additional site visits are necessary to observe/advise regarding tree care and/or services. A summary of pertinent observations and recommendations shall coincide with each inspection.

21. Avoid interrupting any existing irrigation. In the event interruption does occur, supplemental with potable water, and discuss the methodology, frequency and amount with the project arborist beforehand.

22. Prior to mobilizing equipment to the site, install tree protection to enclose all unpaved sections of the TPZs. For tree #10, utilize Type I Protection, which include affixing 5- to 6-foot tall chain link onto 2-inch diameter steel posts spaced apart as needed to remain upright. For all street trees, utilize Modified Type III Protection, which consists of wrapping a single straw wattle horizontally around the trunk at roughly 10 feet high and another around its base (loosely); placing boards (2"x4") vertically around the outside, from ground to 10 feet high; then wrapping orange-plastic fencing around the boards two to three times and tying together. Additionally, lay 3/4- to 1-inch thick plywood over unpaved sections of the planters within the TPZs, or if better, chain link panels mounted on concrete blocks or metal stands. All protection shall remain in place until otherwise instructed by the project arborist, and Sheet T-1 for additional information. Note that should fencing for #10 require being temporarily opened, conduct work under supervision by the project arborist.

660 University Avenue, Palo Alto
Smith Development Page 15 of 18

David L. Bobby, Registered Consulting Arborist® February 7, 2024

23. Affix warning signs every 10± feet of #10's fencing, and one onto the trunk wrap of each street tree. The signs shall be at least 8-½ by 11 inches in size, and refer to Sheet T-1 for a CPA template.

24. Prior to utility installation and grading, review the staked locations with the project arborist where within or near a TPZ. Also, identify the precise locations of where underground utilities within TPZs will be capped (i.e. where being abandoned).

25. All pruning shall be performed under the direction of the project arborist, conducted in accordance with the most recent ANSI A300 standards, and implemented by a California licensed tree-service contractor (D-49) with an ISA certified arborist in a supervisory role. All pruning work on oak #10 shall be supervised directly by the project arborist.

6.3 During Demolition, Grading and Construction

26. Where within the assigned TPZs, all work must performed under the presence of and direct supervision by the project arborist; by foot-traffic only without the travel or operation of heavy equipment, including small tractors; and any approved excavation manually conducted using hand tools only (no jackhammers) and/or utilizing a pneumatic air device operated by a tree service.

27. Great care is needed during demolition and construction to avoid excavating into the ground and disturbing roots within TPZs, and equipment shall not travel over newly exposed ground/roots during the process. Additionally, equipment and truck operators must also be aware of existing trees (both along the street and onsite) to avoid damaging limbs, branches and trunks, as well as the scorching of foliage. Contact the project arborist well in advance of a potential conflict (wrap protection around limbs may be necessary before potential damage occurs).

28. Removing existing asphalt and base material located beyond the proposed deck and within #10's TPZ shall be performed under direct supervision by the project arborist. Once work is completed, restrict heavy equipment from traveling over the newly exposed ground, manually spread a 4- to 6-inch layer of coarse wood chips (or as determined by the project arborist), and expand protection fencing.

660 University Avenue, Palo Alto
Smith Development Page 16 of 18

David L. Bobby, Registered Consulting Arborist® February 7, 2024

29. The removal of any existing plant material within a TPZ must be manually performed, and the work reviewed with the project arborist beforehand.

30. Digging for any bollards or permanent fencing within a TPZ, such as for #10, shall be manually performed using a shovel or post-hole digger. For any root encountered during the process with a diameter ≥2 inches, shift the hole over by 12 inches and repeat the process.

31. Spoils generated during demolition, excavation and trenching must not be piled or spread over unpaved ground within a TPZ. If necessary, temporarily pile on existing concrete, plywood or a tarp.

32. Any authorized digging within a TPZ should retain and protect roots encountered with diameters of ≥2 inches. Once exposed, cover with wet burlap and keep continually moist until they can be assessed by the project arborist; note that roots of street trees must be evaluated by the CPA arborist prior to severing. If authorized by the project arborist and/or CPA arborist for cutting, cleanly sever at 90° to the angle of root growth against the cut line using a fine tooth saw, and then immediately after, bury the cut end with soil or keep continually moist by burlap until the dug area is backfilled. Roots encountered with diameters <2 inches can be cleanly severed at a 90° angle to the direction of root growth.

33. All electrical and irrigation routes shall be staked, reviewed and approved by the project arborist prior to trenching occurring within a TPZ.

34. Avoid using tree trunks as winch supports for moving or lifting heavy loads, or for tying rope, cables, chains, signs or other items around.

35. Dust accumulating on trunks and canopies during dry weather periods may need to be periodically washed away (e.g. every three to four months).

36. Where beneath canopies, avoid disposing harmful products (such as cement, paint, chemicals, oil and gasoline) anywhere on site that allows drainage within or near TPZs; do not wash any equipment; and avoid applying herbicides (if applied, they should be labeled for safe use near trees). Avoid liming within 50 feet from a canopy.

660 University Avenue, Palo Alto
Smith Development Page 17 of 18

T-2



All other tree-related reports shall be added to the space provided on this sheet (adding as needed). Include this sheet(s) on Project Sheet Index or Legend Page. A copy of T-1 can be downloaded at www.cityofpaloalto.org/arb/forms

Special Tree Protection Instruction Sheet
City of Palo Alto



T-2

L 4.4

City of Palo Alto Tree Protection - It's Part of the Plan!

Make sure your crews and subs do the job right!

Fenced enclosures around trees are essential to protect them by keeping the foliage canopy and branching structure clear from contact by equipment, materials and activities, preserving roots and soil conditions in an intact and non-compacted state, and identifying the Tree Protection Zone (TPZ) in which no soil disturbance is permitted and activities are restricted, unless otherwise approved. **An approved tree protection report must be added to this sheet when project activity occurs within the TPZ of a regulated tree.**
For detailed information on Palo Alto's regulated trees and protection during development, review the **City Tree Technical Manual (TTM)** found at www.cityofpaloalto.org/trees/.

EXHIBIT A:

TREE INVENTORY TABLE

(four sheets)



TREE INVENTORY TABLE

TREE/ TAG NO.	TREE NAME	Trunk Diameter (in.)	Height (ft.)	Canopy Spread (ft.)	Health Condition	Structural Integrity	Form	Overall Condition	Suitability for Preservation	Proposed for Removal	Protected Tree	Street Tree
1	European hollyherry (<i>Celtis australis</i>)	20	35	40	60%	40%	30%	Fair	Moderate	-	-	X
Comments: Within a 4' wide planter strip between street and sidewalk. Trunk's base abuts curb. Highly elevated canopy. Sidewalk is slightly raised, now and historically. Codominant leaders emerge at 8' high. Has three large, partial girdling roots, one of which grows over a buttress root and can be pruned away.												
2	London plane tree (<i>Platanus</i> sp.)	15	25	50	60%	70%	60%	Fair	Moderate	-	-	X
Comments: Dorman. With a narrow, 3' wide by 4.5' long planter. Adjacent sidewalk is raised now and historically, and adjacent curb is cracked. Asymmetrical canopy with excessive limb weight, and lowest limb is elongated and grows towards the building. Surface root in lawn adjacent sidewalk.												
3	London plane tree (<i>Platanus</i> sp.)	14	50	40	60%	70%	80%	Fair	Moderate	-	-	X
Comments: Dorman. Within a 3' wide by 15' long planter. Adjacent sidewalk is cracked at E corner of planter. Surface root in lawn adjacent sidewalk. Vertical form.												
4	Glossy privet (<i>Ligustrum lucidum</i>)	6	15	15	30%	30%	30%	Poor	Low	X	-	-
Comments: Within a 2' wide by 3.5' long planter. Leans slightly NW. Significant decline, and top section is dead. Prior leader cut at 6' cut, the resulting wound is decaying. At high pole and adjacent concrete is raised.												
5	Glossy privet (<i>Ligustrum lucidum</i>)	13	20	20	20%	20%	20%	Poor	Low	X	-	-
Comments: Within a 2' wide by 4' long planter. Adjacent curb is buckled and raised, and adjacent sidewalk has been historically raised at multiple locations. Significant decline, w/ 50%+ being dead. Large decaying wounds at 6' and 9' high. Asymmetrical canopy with multiple large dead limbs.												
6	London plane tree (<i>Platanus</i> sp.)	10	45	35	70%	30%	60%	Poor	Low	X	-	-
Comments: Dorman. Within a 2.5' wide by 3.5' long planter. Has a 16" NW lean, and opposite the lean is a large buttress root. Sidewalk and curb have been historically raised at multiple locations. Codominant top. Asymmetrical canopy with an extended limb over street, as well as a low branch lying on top of #22. Deadwood, including a small dead trunk suspended in canopy.												

Site: 660 University Avenue, Palo Alto
Prepared for: Smith Development
Prepared by: David L. Babby, RCA #399

4 of 4

February 7, 2024



TREE INVENTORY TABLE

TREE/ TAG NO.	TREE NAME	Trunk Diameter (in.)	Height (ft.)	Canopy Spread (ft.)	Health Condition	Structural Integrity	Form	Overall Condition	Suitability for Preservation	Proposed for Removal	Protected Tree	Street Tree
7	Southern magnolia (<i>Magnolia grandiflora</i>)	21	30	35	40%	50%	50%	Poor	Moderate	-	-	X
Comments: Within a 3.5' wide by 15' long planter. Root crown occupies entire planter width. Adjacent curb is buckled at multiple locations, including historically. Advanced and extensive decline. Canopy has been reduced sometime ago.												
8	Chinese pistache (<i>Prosopis chinensis</i>)	14	30	35	60%	60%	70%	Fair	Moderate	X	-	-
Comments: At NW edge of a 2' wide by 9' long planter. Adjacent sidewalk historically raised at multiple locations. Large old wound at canopy's bottom. Low canopy over street and roof. Buried root collar.												
9	Southern magnolia (<i>Magnolia grandiflora</i>)	20	35	35	30%	30%	30%	Poor	Low	-	-	X
Comments: Along footage of adjacent SE property (office), its trunk being nearly 22' from the property's fence. Within a narrow 2.5' wide planter. Trunk is 4' from CPA electrical and PacificBell vaults. Sidewalk bulbs out near trunk. Asymmetrical, highly elevated canopy, and a large amount of foliage within its lower canopy consists of watersprouts (rapidly-growing, weakly-attached shoots). Has several large girdling roots over a buttress root. Advanced, extensive decline, and prior deadwood from 2021 was removed.												
10	Coast live oak (<i>Quercus agrifolia</i>)	50	60	90	70%	40%	50%	Fair	High	-	X	-
Comments: Offsite on the adjacent SE property. Its base is 6" from a 2' tall wall and buried by leaf litter. Trunk divides into 5 leaders at 10' high and are favorably spaced apart. Canopy is highly elevated over the site (existing parking lot). Low branches overhang neighbor's roof. Dead branches in canopy's upper S side is very minor and from squirrel damage.												
11	Olive tree (<i>Olea europaea</i>)	8, 8	15	10	70%	50%	40%	Poor	Moderate	X	-	-
Comments: Canopy is needed. Sucker growth has creatively been formed into a shrub surrounding the lower trunk. Trunk bifurcates at 2.5' high and forms a narrow attachment.												
12	Raywood ash (<i>Fraxinus</i> sp.)	2	15	10	70%	30%	20%	Poor	Low	X	-	-
Comments: Dorman. Within a square planter in parking lot. Trunk curves, and has a mostly one-sided canopy due to being suppressed and growing out from beneath #10.												

Site: 660 University Avenue, Palo Alto
Prepared for: Smith Development
Prepared by: David L. Babby, RCA #399

2 of 4

February 7, 2024



TREE INVENTORY TABLE

TREE/ TAG NO.	TREE NAME	Trunk Diameter (in.)	Height (ft.)	Canopy Spread (ft.)	Health Condition	Structural Integrity	Form	Overall Condition	Suitability for Preservation	Proposed for Removal	Protected Tree	Street Tree
13	Raywood ash (<i>Fraxinus</i> sp.)	12	25	20	30%	30%	30%	Poor	Low	X	-	-
Comments: Within a square planter. Trunk bifurcates at 6' high. Significant dieback with deadwood. Adjacent asphalt is cracked and forms a short mound. Asymmetrical canopy at multiple tops.												
14	Raywood ash (<i>Fraxinus</i> sp.)	11	20	20	40%	30%	30%	Poor	Low	X	-	-
Comments: Within a square planter. Has many large decaying cuts. Deadwood. Adjacent asphalt is cracked and slightly raised. Has multiple tops.												
15	Raywood ash (<i>Fraxinus</i> sp.)	6	15	10	20%	10%	20%	Poor	Low	X	-	-
Comments: Small tree within a square planter. Has a large decay column along entire trunk, as well as a large decaying wound at 6' high where a prior leader was cut away. Advanced levels of dieback and deadwood. Asymmetrical canopy and multiple tops.												
16	Raywood ash (<i>Fraxinus</i> sp.)	15	25	20	30%	20%	20%	Poor	Low	X	-	-
Comments: Within a square planter. Has a pronounced E lean. Low limb overhangs adjacent parking space. Significant decay throughout. Deadwood. Adjacent asphalt forms a mound. Has multiple tops.												
17	Purple Robin locust (<i>Robinia</i> sp.)	6	35	20	60%	40%	70%	Fair	Moderate	X	-	-
Comments: Dorman. Single support stake should be removed. Overhangs adjacent building.												
18	Purple Robin locust (<i>Robinia</i> sp.)	5	25	20	60%	40%	40%	Poor	Moderate	X	-	-
Comments: Dorman. Excessive limb weight overhangs parking lot. Asymmetrical form away from #17 and the adjacent building.												
19	Crape myrtle (<i>Lagerstroemia indica</i>)	5	10	10	60%	40%	50%	Fair	Moderate	X	-	-
Comments: Is of Tuscara variety (as well as #20 thru 24). Within a 2' raised planter. Dorman. Multiple trunks originate 8" high. Canopy is slightly asymmetrical.												

Site: 660 University Avenue, Palo Alto
Prepared for: Smith Development
Prepared by: David L. Babby, RCA #399

3 of 4

February 7, 2024



TREE INVENTORY TABLE

TREE/ TAG NO.	TREE NAME	Trunk Diameter (in.)	Height (ft.)	Canopy Spread (ft.)	Health Condition	Structural Integrity	Form	Overall Condition	Suitability for Preservation	Proposed for Removal	Protected Tree	Street Tree
20	Crape myrtle (<i>Lagerstroemia indica</i>)	3, 3, 2	10	5	60%	40%	50%	Fair	Moderate	X	-	-
Comments: Within a 2' raised planter. Dorman. Multiple trunks emerge at grade. Canopy is asymmetrical.												
21	Crape myrtle (<i>Lagerstroemia indica</i>)	6	15	10	60%	40%	50%	Fair	Moderate	X	-	-
Comments: Within a 2' raised planter. Dorman. Multiple trunks originate 6" high. Canopy is slightly asymmetrical.												
22	Crape myrtle (<i>Lagerstroemia indica</i>)	6	15	10	60%	40%	50%	Fair	Moderate	X	-	-
Comments: Within a 2' raised planter. Dorman. Multiple trunks originate 5" high. Canopy is slightly asymmetrical.												
23	Crape myrtle (<i>Lagerstroemia indica</i>)	6	15	15	60%	40%	60%	Fair	Moderate	X	-	-
Comments: Within a 2' raised planter. Dorman. Multiple trunks originate 5" high. Canopy is slightly asymmetrical.												
24	Crape myrtle (<i>Lagerstroemia indica</i>)	4, 3, 2	15	10	60%	40%	60%	Fair	Moderate	X	-	-
Comments: Within a 2' raised planter. Dorman. Multiple trunks emerge at grade. Canopy is asymmetrical.												
25	Yew pine (<i>Podocarpus neriifolius</i>)	8	10	10	70%	40%	30%	Poor	Moderate	X	-	-
Comments: Adjacent to building. Shrub form and shaped into a cube. Trunk bifurcates at 7' high.												

Site: 660 University Avenue, Palo Alto
Prepared for: Smith Development
Prepared by: David L. Babby, RCA #399

4 of 4

February 7, 2024

EXHIBIT B:

SITE MAP (one sheet)




EXHIBIT C:

PHOTOGRAPHS

(five sheets)

Photo Index

Page C-1: Trees #1 thru 6
Page C-2: Trees #7 thru 9
Page C-3: Tree #10

Page C-4: Trees #11 thru 18
Page C-5: Trees #19 thru 25

Site: 660 University Avenue, Palo Alto
Smith Development
David L. Babby, Registered Consulting Arborist®



Site: 660 University Avenue, Palo Alto
Smith Development

Page C-3

David L. Babby, Registered Consulting Arborist®



Site: 660 University Avenue, Palo Alto
Smith Development

David L. Babby, Registered Consulting Arborist®



Site: 660 University Avenue, Palo Alto
Smith Development

Page C-4

February 7, 2024

David L. Babby, Registered Consulting Arborist®



Site: 660 University Avenue, Palo Alto
Smith Development

David L. Babby, Registered Consulting Arborist®



Site: 660 University Avenue, Palo Alto
Smith Development

Page C-5

ISSUES AND REVISIONS

NO.	DATE	DESCRIPTION
12.01.21	12.01.21	PLANNING SUBMITTAL
05.13.22	05.13.22	PLANNING RESUBMITTAL #1
08.15.22	08.15.22	PLANNING RESUBMITTAL #2
11.02.22	11.02.22	PLANNING RESUBMITTAL #3
08.28.23	08.28.23	PLANNING RESUBMITTAL #4
10.31.23	10.31.23	PLANNING RESUBMITTAL #5
12.21.23	12.21.23	PLANNING RESUBMITTAL #6
02.07.24	02.07.24	PLANNING RESUBMITTAL #7

PROJECT NUMBER
21003

SHEET TITLE
TREE DISPOSITION PLAN - SITE
ARBORIST REPORT

SCALE

SHEET NUMBER

T-2



All other tree-related reports shall be added to the space provided on this sheet (adding as needed).
Include this sheet(s) on Project Sheet Index or Legend Page.
A copy of T-1 can be downloaded at www.cityofpaloalto.org/arb/forms

Special Tree Protection Instruction Sheet
City of Palo Alto



T-2

L 4.5

City of Palo Alto
Tree Protection - It's Part of the Plan!

Make sure your crews and subs do the job right!

Fenced enclosures around trees are essential to protect them by keeping the foliage canopy and branching structure clear from contact by equipment, materials and activities, preserving roots and soil conditions in an intact and non-compacted state, and identifying the Tree Protection Zone (TPZ) in which no soil disturbance is permitted and activities are restricted, unless otherwise approved. **An approved tree protection report must be added to this sheet when project activity occurs within the TPZ of a regulated tree.**
For detailed information on Palo Alto's regulated trees and protection during development, review the **City Tree Technical Manual (TTM)** found at www.cityofpaloalto.org/trees/.

EXHIBIT D:


LANDSCAPE PLANS - DECK BENEATH TREE #10
(two sheets)

Plan Index

Sheet L1.1 (one page)

Landscape Section at Wood Deck (one page)

660 University Avenue, Palo Alto
Smith Development



SMITH DEVELOPMENT


660 UNIVERSITY
PALO ALTO, CA 94301

THE
Guzzardo
Partnership, INC.
Landscape Architects | Land Planners
Pier 9, The Embarcadero, Suite 115
San Francisco, CA 94111 | www.tgp-inc.com


ISSUES AND REVISIONS		
NO.	DATE	DESCRIPTION
12.01.21	12.01.21	PLANNING SUBMITTAL
05.13.22	05.13.22	PLANNING RESUBMITTAL #1
08.15.22	08.15.22	PLANNING RESUBMITTAL #2
11.02.22	11.02.22	PLANNING RESUBMITTAL #3
08.28.23	08.28.23	PLANNING RESUBMITTAL #4
10.31.23	10.31.23	PLANNING RESUBMITTAL #5
12.21.23	12.21.23	PLANNING RESUBMITTAL #6
02.07.24	02.07.24	PLANNING RESUBMITTAL #7

PROJECT NUMBER
21003

SHEET TITLE
LANDSCAPE PLAN - GROUND FLOOR



L 1.1



Landscape Section at Wood Deck

ISSUES AND REVISIONS

NO.	DATE	DESCRIPTION
12.01.21	12.01.21	PLANNING SUBMITTAL
05.13.22	05.13.22	PLANNING RESUBMITTAL #1
08.15.22	08.15.22	PLANNING RESUBMITTAL #2
11.02.22	11.02.22	PLANNING RESUBMITTAL #3
08.28.23	08.28.23	PLANNING RESUBMITTAL #4
10.31.23	10.31.23	PLANNING RESUBMITTAL #5
12.21.23	12.21.23	PLANNING RESUBMITTAL #6
02.07.24	02.07.24	PLANNING RESUBMITTAL #7

PROJECT NUMBER

21003

SHEET TITLE

TREE DISPOSITION PLAN - SITE
ARBORIST REPORT

SCALE

SHEET NUMBER


L 4.6

LEGEND:

- PROPERTY LINE
- ADJACENT PROPERTY LINE
- EX FENCE
- EX SANITARY SEWER LINE
- EX STORM DRAIN LINE
- EX DOMESTIC WATER LINE
- EX COMMUNICATIONS LINE
- EX ELECTRIC LINE
- EX OVERHEAD LINE
- EX GAS LINE
- EX TREE
- EX SANITARY SEWER MANHOLE
- EX COMMUNICATIONS MANHOLE
- EX WATER VALVE
- EX STREET LIGHT
- EX SIGN
- BUILDING TO BE DEMOLISHED
- PAVEMENT TO BE DEMOLISHED
- TREE PROTECTION ZONE (SEE NOTE 4)
- TREE TO BE REMOVED

NOTES:

- DEACTIVATION AND REMOVAL OF GAS AND ELECTRIC LINES TO BE COORDINATED WITH CPAU PRIOR TO DEMOLITION.
- SERVICE DISCONNECTION REQUIREMENT: WATER, GAS, AND ELECTRIC SERVICES AND METERS MUST BE DISCONNECTED WHENEVER A CONTRACTOR IS PLANNING FOR COMPLETE/PARTIAL BUILDING DEMOLITION OR ANY EXCAVATION. WHERE TO APPLY FOR SERVICE DISCONNECTION: THE APPLICANT SHALL FIRST SUBMIT AN "APPLICATION FOR UTILITIES DISCONNECTION PRIOR TO BUILDING DEMOLITION/REMODELING" INCLUDING A SIGNED "DECLARATION CONCERNING TENANCY OF BUILDING" TO CITY OF PALO ALTO UTILITIES CUSTOMER SERVICE CENTER 250 HAMILTON AVE. (CITY HALL) GROUND FLOOR, PALO ALTO, CA 94301. TELEPHONE (650) 329-2161. FORMS ARE AVAILABLE ONLINE.
- BENCHMARK STATEMENT: THE ELEVATIONS SHOWN ON THIS SURVEY ARE NORTH AMERICAN VERTICAL DATUM OF 1988 (NAVD 88), U.S. SURVEY FEET, PER A LEVEL LOOP PERFORMED BY BKF ON JANUARY 23, 2021 FROM CITY OF PALO ALTO BENCHMARK NO. 2189, A CHISELED SQUARE AT THE NORTHWEST CORNER OF THE INTERSECTION OF BYRON STREET AND HAMILTON AVENUE, HAVING A PUBLISHED ELEVATION OF 40.73' (NGVD 29), AND APPLYING A CONVERSION FACTOR (FROM NGVD 29 TO NAVD 88) OF +2.75 FEET AS DIRECTED BY THE CITY OF PALO ALTO ELEVATION = 43.48'
- CONTRACTOR TO COMPLY WITH RECOMMENDATIONS PRESENTED IN ARBORIST REPORT BY ARBOR RESOURCES DATED DECEMBER 20, 2023, AND ON SHEET T-1. CONTRACTOR TO CONTACT PROJECT ARBORIST PRIOR TO PERMITTED WORK BEING PERFORMED WITHIN A TREE PROTECTION ZONE.
- ABANDON ANY UNDERGROUND PORTIONS OF UTILITY PIPES AND STRUCTURES WITHIN A TREE PROTECTION ZONE. CUT OFF AT EXISTING SOIL GRADE TO AVOID CAUSING ROOT DAMAGE. SEE ARBORIST REPORT FOR MORE INFORMATION.



660 UNIVERSITY AVENUE
EXISTING CONDITIONS AND DEMOLITION PLAN

SANTA CLARA COUNTY
CITY OF PALO ALTO



Date	No.	Revisions
10/31/2023	2	PLANNING RESUBMITTAL #2
08/15/2022	3	PLANNING RESUBMITTAL #3
11/02/2022	4	PLANNING RESUBMITTAL #4
08/28/2023	5	PLANNING RESUBMITTAL #5
10/31/2023	6	PLANNING RESUBMITTAL #6

Drawing Number: SD1.0



CALIFORNIA

660 UNIVERSITY AVENUE SITE PLAN



SANTA CLARA COUNTY

CITY OF PALO ALTO

No.	Date	Revisions
1	10/31/2023	PLANNING RESUBMITTAL #2
2	Scale 1" = 10'	PLANNING RESUBMITTAL #3
3	Design	PLANNING RESUBMITTAL #4
4	Drawn	PLANNING RESUBMITTAL #5
5	Approved	PLANNING RESUBMITTAL #6
6	Job No. 2021213	

Drawing Number:

SD2.0



DRAWING NAME: \\Bkfr-c\vol4\2021\212113_660_University_Ave\ENG\SD\SD2.0-Site_Plan.dwg
PLOT DATE: 12-21-23
PLOTTED BY: monu

DRAWING NAME: \\Bkf-r\c\12-21-23

No.	Date	Revisions
1	10/31/2023	PLANNING RESUBMITTAL #2
2	Scale 1" = 10'	PLANNING RESUBMITTAL #3
3	Design	PLANNING RESUBMITTAL #4
4	Drawn	PLANNING RESUBMITTAL #5
5	Approved	PLANNING RESUBMITTAL #6
6	Job No. 2021213	

TC X.X
FL X.X

EXISTING GRADE


TC X.X
FL X.X

PROPOSED GRADE

----- GRADE BREAK


BFE	BASE FLOOD ELEVATION
BOW	BOTTOM OF WALL
BS	BOTTOM OF STEP
BW	BACK OF WALK
EG	EXISTING GRADE
FF	FINISHED FLOOR
FG	FINISHED GRADE
FL	FLOW LINE
GD	GROUND
TC	TOP OF CURB
TOW	TOP OF WALL
TS	TOP OF STEP

1. BASE FLOOD ELEVATION (BFE) FOR PROJECT SITE IS 47. PROPOSED FINISHED FLOOR IS 1 FOOT ABOVE BFE, PLUS APPROXIMATELY 2 INCHES TO ACCOUNT FOR CONSTRUCTION TOLERANCE.



DRAWING NAME: K:\2021\212113_660_University_Ave\ENG\SD\SD3.0-Grading_Plan.dwg
PLOT DATE: 12-21-23
PLOT BY: inou

DRAWING NAME: K:\2021\212113_660_University_12-21-23
PLOT DATE: 12-21-23
PLOTTED BY: inou




- LEGEND:**
- PROPERTY LINE
 - ADJACENT PROPERTY LINE
 - EX FENCE
 - EX SANITARY SEWER LINE
 - EX STORM DRAIN LINE
 - EX DOMESTIC WATER LINE
 - EX COMMUNICATIONS LINE
 - EX ELECTRIC LINE
 - EX OVERHEAD LINE
 - EX GAS LINE
 - EX SANITARY SEWER MANHOLE
 - EX COMMUNICATIONS MANHOLE
 - EX VALVE
 - EX STREET LIGHT
 - EX FIRE HYDRANT

- ABBREVIATIONS:**
- SS PR SANITARY SEWER LINE
 - DW PR STORM DRAIN LINE
 - FW PR DOMESTIC WATER LINE
 - IR PR DOMESTIC WATER LINE
 - LT PR CLEANOUT
 - PR WATER VALVE
 - PR FDC
 - PR MANHOLE


- ABBREVIATIONS:**
- CB CATCH BASIN
 - CO CLEANOUT
 - DW DOMESTIC WATER
 - FDC FIRE DEPARTMENT CONNECTION
 - FW FIRE WATER
 - IRR IRRIGATION
 - LT LATERAL
 - MH MANHOLE
 - RPDA REDUCED PRESSURE DETECTOR ASSEMBLY
 - RPPA REDUCED PRESSURE PRINCIPLE ASSEMBLY
 - SD STORM DRAIN
 - SS SANITARY SEWER
 - WM WATER METER

- NOTES:**
1. RPPA BACKFLOW PREVENTER TO BE LOCATED IN BASEMENT.
 2. RPDA BACKFLOW PREVENTER TO BE LOCATED IN BASEMENT.
 3. STORMWATER BEST MANAGEMENT PRACTICES (BMPs) ASSOCIATED WITH REFUSE MANAGEMENT (INCLUDING ACTIONS RELATED TO REFUSE PICK-UP AND THE ENCLOSURE ITSELF) SHALL BE FOLLOWED TO ENSURE POLLUTION PREVENTION AND PREVENTING POTENTIAL DISCHARGES TO THE CITY'S STORM DRAIN SYSTEM. STORMWATER BMPs INCLUDE, BUT ARE NOT LIMITED TO, POWER WASHING THE PAVEMENT ON BOTH THE PRIVATE PROPERTY AND IN THE RIGHT-OF-WAY AND SIDEWALK A MINIMUM OF ONCE A YEAR BEFORE THE WET SEASON BEGINS ON OCTOBER 1ST; UTILIZING A POWER WASHING CONTRACTOR THAT IS A RECOGNIZED SURFACE CLEANER BY THE BAY AREA STORMWATER MANAGEMENT AGENCIES ASSOCIATION (BASMAA); DISPOSING OF WASH WATER ACCORDING TO THE RECOGNIZED SURFACE CLEANER CERTIFICATION REQUIREMENTS; AND REMOVING ANY POTENTIAL TRASH BUILD-UP ON A REGULAR BASIS.
 4. PER CITY OF PALO ALTO UTILITIES RULES & REGULATION 15 METERING, THE CITY WILL PROVIDE A MASTER METER AT AN APPROVED LOCATION NEAR TO THE PUBLIC WATER MAIN AND RIGHT OF WAY TO SERVE THE WHOLE DEVELOPMENT OR BUILDING. THE MULTIUNIT RESIDENTIAL STRUCTURE MUST COMPLY WITH CALIFORNIA WATER METERING FOR MULTI-UNIT STRUCTURES WATER CODE AS AMENDED BY LAW SENATE BILL 7 (WATER CODE, DIVISION 1, CHAPTER 8, ARTICLE 5, SECTION 537-537.5) THAT REQUIRES INDIVIDUAL WATER METERS OR SUBMETERS FOR EACH UNIT FOR STRUCTURES CONSTRUCTED AFTER JANUARY 1, 2018.



660 UNIVERSITY AVENUE
UTILITY PLAN

DRAWING NAME: K:\2021\212113_660_University_Ave\ENG\SD\5_0-Stormwater_Management_Plan.dwg
PLOT DATE: 12-21-23 PLOTTED BY: inou



LEGEND

STRA SELF TREATING/RETAINING AREA

--- DMA BOUNDARY


NOTE:

- DO NOT USE CHEMICAL FERTILIZERS, PESTICIDES, HERBICIDES OR COMMERCIAL SOIL AMENDMENT. USE ORGANIC MATERIALS REVIEW INSTITUTE (OMRI) MATERIALS AND COMPOST. REFER TO THE BAY-FRIENDLY LANDSCAPE GUIDELINES FOR GUIDANCE.
- AVOID COMPACTING SOIL IN AREAS THAT WILL BE UNPAVED.
- FOR ALL C.3 FEATURES, VENDOR SPECIFICATIONS REGARDING INSTALLATION AND MAINTENANCE SHOULD BE FOLLOWED AND PROVIDED TO CITY STAFF. COPIED MUST BE SUBMITTED TO PAM BOYLE RODRIGUEZ AT PAMELA.BOYLERODRIGUEZ@CITYOFPALOALTO.ORG.
- STAFF FROM STORMWATER PROGRAM (WATERSHED PROTECTION DIVISION) MAY BE PRESENT DURING INSTALLATION OF STORMWATER TREATMENT MEASURES. CONTACT PAM BOYLE RODRIGUEZ, STORMWATER PROGRAM MANAGER, AT (650) 239-2421 BEFORE INSTALLATION.

STORMWATER QUALITY SIZING SUMMARY

DMA ID	DMA (SF)	TREATMENT ID	TREATMENT AREA (SF)	TREATMENT AREA REQUIRED (SF)	MEETS REQUIREMENT?
DMA 1	3,956	FTP 1	237	158	YES
DMA 2	7,913	FTP 2	343	317	YES
DMA 3	152	FTP 3	69	6	YES
DMA 4	5,359	FTP 4	343	214	YES
DMA 5	144	FTP 5	50	6	YES
DMA 6	88	FTP 6	59	4	YES
DMA 7*	6,370	—	SEE NOTE	255	SEE NOTE

* THE APPLICANT AND THE CITY SHALL ENTER INTO AN AGREEMENT ACCEPTABLE TO THE PUBLIC WORKS DIRECTOR OR DESIGNATED REPRESENTATIVE TO PROVIDE ALTERNATIVE COMPLIANCE WITH PAYMENT OF IN-LIEU FEES TO COMPLY WITH THE REGULATED PROJECTS STORMWATER TREATMENT OBLIGATIONS.



255 SHORELINE DRIVE
SUITE 200
PALO ALTO, CA 94065
(650) 492-5300
www.bkf.com



CALIFORNIA

**660 UNIVERSITY AVENUE
STORMWATER MANAGEMENT PLAN**

SANTA CLARA COUNTY

CITY OF PALO ALTO





Revisions		No.		Date	
PLANNING RESUBMITTAL #2	08.15.2022	2	10/31/2023	10/31/2023	10/31/2023
PLANNING RESUBMITTAL #3	11.02.2022	3	11/02/2022	11/02/2022	11/02/2022
PLANNING RESUBMITTAL #4	08.28.2023	4	08/28/2023	08/28/2023	08/28/2023
PLANNING RESUBMITTAL #5	10.31.2023	5	10/31/2023	10/31/2023	10/31/2023
PLANNING RESUBMITTAL #6	12.22.2023	6	12/22/2023	12/22/2023	12/22/2023

Drawing Number:

SD5.0

DRAWING NAME: K:\2021\212113_660_University Ave\ENG\SD\SD6_0-Sections.dwg
PLOT DATE: 12-21-23 PLOTTED BY: inou

ABBREVIATIONS:
C&G CURB AND GUTTER
L/S LANDSCAPE
S/W SIDEWALK



Date	10/31/2023	No.	No.	Revisions	
Scale	1" = 10'	2	PLANNING RESUBMITTAL #2	08.15.2022	
Design	MS	3	PLANNING RESUBMITTAL #3	11.02.2022	
Drawn	TKI	4	PLANNING RESUBMITTAL #4	08.28.2023	
Approved	TRM	5	PLANNING RESUBMITTAL #5	10.31.2023	
Job No	2021213	6	PLANNING RESUBMITTAL #6	12.22.2023	

Drawing Number:
SD6.0

**660 UNIVERSITY AVENUE
SECTIONS**

CITY OF PALO ALTO


SANTA CLARA COUNTY

CALIFORNIA




255 SHORELINE DRIVE
SUITE 200 SAN JOSE, CITY, CA 94065
(408) 482-6300
www.bkf.com


DRAWING NAME: \\BKF-r-c\vol4\2021\212113_660_University_Ave\ENG\SD7_0-Details.dwg
PLOT DATE: 12-21-23
PLOTTED BY: monu




1
-
SIDEWALK
NOT TO SCALE




2
-
CURB AND GUTTER
NOT TO SCALE



3
-
DRIVEWAY
NOT TO SCALE




3
-
DRIVEWAY
NOT TO SCALE




4
-
CURB RAMP
NOT TO SCALE

Date	10/31/2023	No.	2	PLANNING RESUBMITTAL #2	08.15.2022
Scale	1" = 10'	Design	MS	PLANNING RESUBMITTAL #3	11.02.2022
Drawn	TKI	Approved	TRM	PLANNING RESUBMITTAL #4	08.28.2023
Job No	2021213	Job No	2021213	PLANNING RESUBMITTAL #5	10.31.2023
				PLANNING RESUBMITTAL #6	12.22.2023



212



221

1

4' WATER METER

NOT TO SCALE

2

COMBINED WATER METER

NOT TO SCALE

Date	10/31/2023	No.	2	Revisions	PLANNING RESUBMITTAL #2	08.15.2022
Scale	1" = 10'	MS	3		PLANNING RESUBMITTAL #3	11.02.2022
Design		TKI	4		PLANNING RESUBMITTAL #4	08.28.2023
Drawn		TRM	5		PLANNING RESUBMITTAL #5	10.31.2023
Approved			6		PLANNING RESUBMITTAL #6	12.22.2023
Job No	20212113					

Drawing Number:


SD7.1

660 UNIVERSITY AVENUE
DETAILS

CITY OF PALO ALTO

SANTA CLARA COUNTY

CALIFORNIA



WORK RESPONSIBILITY JOINT TRENCH

TRENCHING EXCAVATE & BACKFILL.....	☐ CPAU ELECTRIC ☐ CPAU GAS ☐ TELEPHONE ☐ C.A.T.V. ☒ CONTRACTOR
GAS MATERIAL SUPPLY & INSTALL.....	☐ ☐ ☐ ☐
*CPAU ELECTRIC CABLE SUPPLY & INSTALL.....	☒ ☐ ☐ ☐
ELECTRIC CONDUIT SUPPLY & INSTALL.....	☐ ☐ ☐ ☒
ELECTRIC BOXES SUPPLY & INSTALL..... EXCAVATION.....	☐ ☐ ☐ ☒
ELECTRIC PADS SUPPLY & INSTALL..... EXCAVATION.....	☐ ☐ ☐ ☒
ELECTRIC TRANSFORMERS SUPPLY & INSTALL.....	☒ ☐ ☐ ☐
ELECTRIC INTERRUPTERS SUPPLY & INSTALL.....	☐ ☐ ☐ ☐
CPAU ELECTRIC SWITCHES SUPPLY & INSTALL.....	☐ ☐ ☐ ☐
TELEPHONE CONDUIT SUPPLY & INSTALL.....	☐ ☐ ☐ ☒
TELEPHONE CABLE SUPPLY & INSTALL.....	☐ ☐ ☒ ☐
TELEPHONE SPLICE BOXES SUPPLY & INSTALL..... EXCAVATION.....	☐ ☐ ☐ ☒
TELEPHONE S.A.I. PADS SUPPLY & INSTALL..... EXCAVATION.....	☐ ☐ ☐ ☐
C.A.T.V. CONDUIT SUPPLY & INSTALL.....	☐ ☐ ☐ ☒
C.A.T.V. SPLICE BOXES SUPPLY & INSTALL..... EXCAVATION.....	☐ ☐ ☐ ☒
C.I.E.C. FIBER CONDUIT _____ACCEPTED _____DECLINED SUPPLY & INSTALL.....	☐ ☐ ☐ ☒
C.I.E.C. FIBER SPLICE BOXES _____ACCEPTED _____DECLINED SUPPLY & INSTALL..... EXCAVATION.....	☐ ☐ ☐ ☒
☒ WORK TO BE PERFORMED BY THE RESPECTIVE CONTRACTOR & UTILITY COMPANIES ☒ ASSUME CONTRACTOR RESPONSIBILITY UNLESS OTHERWISE SPECIFIED ☐ NOT APPLICABLE UNLESS OTHERWISE SPECIFIED * CPAU TO PULL CABLE INTO ENERGIZED ENCLOSURES NOTE: FOR A MORE DETAILED WORK RESPONSIBILITY BREAKDOWN, SEE CORRESPONDING MATERIAL LIST.	

THESE PLANS WERE PREPARED IN CONJUNCTION WITH THE FOLLOWING PLANS:

	RECEIVED	APPROVED
CIVIL IMPROVEMENT PLANS/GRADING PLANS	08-25-2023	PRELIMINARY
ARCHITECTURAL ELECTRONIC FILE	10-27-2023	PRELIMINARY
APPLICANT DESIGN (GAS)		
APPLICANT DESIGN (ELECTRIC)		
TELEPHONE		
C.A.T.V.		
LANDSCAPE	08-25-2023	PRELIMINARY
LIGHT LOCATIONS		
TRAFFIC SIGNAL LOCATIONS		

RADIUS DESIGN is not responsible for any subsequent changes or revisions.

OTHER UTILITIES SHOWN ARE APPROXIMATE AND BASED ON FIELD SURVEY AND AVAILABLE UTILITY INFORMATION. IT IS THE CONTRACTORS' RESPONSIBILITY TO VERIFY THE ACTUAL LOCATION AND EXTENT OF UTILITIES PRIOR TO THE COMMENCEMENT OF WORK. PHYSICAL VERIFICATION OF UTILITY LOCATIONS SHALL BE PERFORMED BY CAREFUL PROBING OR HAND DIGGING IN ACCORDANCE WITH ARTICLE 6 OF THE CAL/OSHA CONSTRUCTION SAFETY ORDERS.

CONSTRUCTION NOTES

- ALL TRENCHING, BACKFILLING AND INSTALLATION BY CONTRACTOR MUST COMPLY WITH CITY OF PALO ALTO STANDARDS.
- ALL WORK MUST COMPLY WITH CITY OF PALO ALTO(CPA), TELEPHONE, C.A.T.V. STANDARDS AND PRACTICES. ALL WORK MUST BE INSPECTED AND APPROVED BY RESPECTIVE INSPECTORS. RANDOM SOIL SAMPLES SHALL BE TAKEN FROM A MINIMUM OF THREE LOCATIONS PER 1,000' OF TRENCH. 100% OF THE SAMPLE MUST PASS THROUGH A 1/2" SIEVE AND 75% MUST PASS THROUGH A #4 SCREEN. ADDITIONAL SAMPLES MUST BE TAKEN IF EXISTING SOIL CONDITIONS CHANGE AND IS TO BE AT THE DISCRETION OF THE CPA REPRESENTATIVE ON SITE. THE SOILS MUST NOT CONTAIN ANY ROCKS THAT HAVE SHARP EDGES OR THAT MAY OTHERWISE BE ABRASIVE. THE SOILS MUST NOT CONTAIN CLODS LARGER THAN 1/2" IF TO BE USED AS SHADING, BEDDING OR LEVELING MATERIALS. COMPACTION REQUIREMENTS MUST MEET ANY APPLICABLE CPA FEDERAL, STATE, COUNTY OR LOCAL REQUIREMENTS. ANY NATIVE SOILS OR IMPORT MATERIALS USED MUST NOT HINDER THOSE EFFORTS.
- BACKFILL SHALL BE APPROVED BY THE UTILITY COMPANIES AND THE CITY. COMPACTION WILL BE TESTED AND PASSED BY THE SOILS ENGINEER.
- IF SOIL IS NOT ROCK FREE, ADD 4" DEPTH OF TRENCH FOR SAND BEDDING.
- VERIFY SPLICE BOX EXCAVATION SIZES WITH SUPPLIER(S).
- THE TRENCHING CONTRACTOR SHALL COORDINATE THE UTILITY COMPANIES' INSTALLATION.
- CONTRACTOR SHALL MAKE HIMSELF FAMILIAR WITH THE PROJECT IMPROVEMENT PLANS AND CONDUCT HIS WORK ACCORDINGLY.
- IT IS THE TRENCHING CONTRACTOR'S RESPONSIBILITY TO PROTECT IN PLACE ALL EXISTING FACILITIES. NO EXTRA PAYMENT WILL BE CONSIDERED FOR CROSSING OTHER SYSTEMS.
- RADIUS DESIGN ASSUMES NO RESPONSIBILITY FOR THE PROJECT CONDITIONS. THESE DRAWINGS WERE PREPARED USING DATA SUPPLIED BY CPA, TELEPHONE, C.A.T.V., IMPROVEMENT PLANS AND THE CITY'S VARIOUS "AS BUILT" INFORMATION. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO PHYSICALLY REVIEW THE PROJECT PRIOR TO SUBMITTING HIS BID.
- CONTRACTOR WILL COMPLY WITH ALL LAWS, ORDINANCES AND REGULATIONS. CONTRACTOR SHALL BE FAMILIAR WITH O.S.H.A., INDUSTRIAL SAFETY ORDERS AND SHALL CONDUCT HIS WORK ACCORDINGLY. WHEN WORKING NEAR ENERGIZED OR "HOT" EQUIPMENT, THE UTILITY OWNER SHALL BE NOTIFIED TO SUPPLY THE APPROPRIATE MAX POWER. PUBLIC SAFETY AND TRAFFIC CONTROL MEASURES ARE THE CONTRACTOR'S RESPONSIBILITY.
- THE CONTRACTOR SHALL PROTECT CONSTRUCTION STAKING. HE SHALL COORDINATE STAKING WITH THE PROJECT'S CIVIL ENGINEER.
- CONTRACTOR SHALL NOTIFY UNDERGROUND SERVICE ALERT (USA) TWO WORKING DAYS PRIOR TO START OF WORK. (800) 227-2600.
- CONTRACTOR SHALL NOTIFY INSPECTORS OF ANY POTENTIAL CONFLICTS PRIOR TO START OF WORK.
- THIS PLAN IS TO BE USED FOR SOLE PURPOSE OF DIGGING THE JOINT TRENCH. SEE CPA, AT&T, AND COMCAST PLANS FOR EXACT SIZE AND NUMBER OF CONDUITS INSTALLED IN THE JOINT TRENCH. IT IS THE CONTRACTOR'S RESPONSIBILITY TO ENSURE THE CORRECT NUMBER, SIZE AND TYPES OF CONDUITS ARE INSTALLED PER THE ENGINEERED PLANS BY EACH UTILITY COMPANY.
- NOTE PLANS ISSUED AT THE PRE-CONSTRUCTION MEETING MAY BE SUBJECT TO REVISIONS, IF FINAL PLANS FROM EACH UTILITY COMPANY WERE NOT AVAILABLE AT THE START OF CONSTRUCTION.
- WATER, SEWER, DRAINS, SANITARY WASTE, FUELS (INCLUDING DIESEL AND GASOLINE), OIL, PROPANE AND OTHER VOLATILE HEAVIER THAN AIR GASES, SPRINKLER, IRRIGATION, STEAM AND OTHER "WET" FACILITIES SHALL MAINTAIN A MINIMUM OF FOUR FEET FROM THE NEAREST OUTER SURFACE OF CPA DRY FACILITIES WITH NO LESS THAN ONE FOOT OF EARTH (SOIL BARRIER) BETWEEN THE ADJACENT SIDES OF THE INDIVIDUAL TRENCHES.
- IN THE EXTRAORDINARY CASE THAT THE MINIMUM FOUR FOOT HORIZONTAL SEPARATION CANNOT BE ATTAINED BETWEEN "WET" UTILITIES AND COMPANY DRY FACILITIES, A VARIANCE MAY APPROVED BY THE LOCAL INSPECTION SUPERVISOR AND SUBMITTED TO SERVICE PLANNING SUPPORT PROGRAM MANAGER FOR APPROVAL.
- THIS JOINT TRENCH PLAN WAS PREPARED BASED ON TOPOGRAPHICAL SURVEY AS PROVIDED BY A CIVIL ENGINEER. THE CONTRACTOR IS CAUTIONED THAT EXPLORATORY WORK IS REQUIRED TO DETERMINE THE ACTUAL LOCATION OF ANY EXISTING UTILITY. RADIUS STRONGLY RECOMMENDS THAT ALL UTILITIES BE PHYSICALLY LOCATED ON THE SITE BEFORE THE ONSET OF SITE WORK. SUBSTRUCTURE LOCATIONS MAY REQUIRE FIELD ADJUSTMENT TO COMPENSATE FOR ACTUAL EXISTING UTILITY LOCATIONS.

CONDUIT NOTES

- DIRECT BURIED PRIMARY CONDUIT IS NOT AN APPROVED CONSTRUCTION METHOD. PRIMARY CONDUITS SHALL BE CONCRETE ENCASED, UNLESS OTHERWISE APPROVED BY CPA UTILITIES ENGINEER. APPROVED CONDUIT MATERIALS:
 - SCHEDULE 40 PVC
 - TYPE "DB 60" (SECONDARY) OR "DB 120" (PRIMARY) PLASTIC CONDUIT
 - GALVANIZED RIGID STEEL CONDUIT.
- EVERY EFFORT MUST BE MADE TO OBTAIN STRAIGHT WATER-TIGHT CONDUIT LINE.
- SHARP TURNS MUST BE AVOIDED, PER THE TABLE BELOW. NORMALLY, THE PRIMARY DUCT RADIUS IS SPECIFIED. UNLESS APPROVED BY THE PROJECT ENGINEER, FACTORY OFFSETS WILL NOT BE USED.
- ALL BENDS AND SWEEPS (90 DEGREES) MUST BE ENCASED IN CONCRETE (MINIMUM 3") ALONG THE INSIDE RADIUS.
- IF THE ELECTRIC UNDERGROUND INSPECTOR DETERMINES THAT THE BOTTOM OF THE TRENCH IS ROCKY, THEN A 2" SAND BEDDING MUST BE INSTALLED BEFORE CONDUIT.
- BACKFILL IN UNIMPROVED AREAS SHALL BE 12" OF CLEAN NATURAL SAND PER CALTRANS STD SPECS SEC 19-3.025B ON TOP OF THE UPPERMOST CONDUIT, 90% COMPACTION; TOPPED WITH EXCAVATED NATIVE SOIL, 85% COMPACTION.
- BACKFILL IN IMPROVED AREAS MUST BE IN ACCORDANCE WITH CITY OF PALO ALTO STANDARD SPECIFICATIONS FOR BACKFILLING IN IMPROVED AREAS. (SECTION 21)
- ALL CONDUITS MUST BE MANDEILLED (STD. DWG DT-SS-U-1025). THIS TEST MUST BE WITNESSED BY THE ELECTRIC UNDERGROUND INSPECTOR.
- A 3/8" POLYPROPYLENE PULL LINE (MIN. 150 LBS. TEST) MUST BE INSTALLED IN EACH CONDUIT.
- CONDUIT SPACING SHALL BE MAINTAINED BY SPACERS, APPROVED BY CPA, INSTALLED NO MORE THAN 7" APART. CONDUIT MUST BE SECURELY BOUND TO THE SPACERS.
- MINIMUM COVER FOR DIRECT BURIED CONDUIT:

-SECONDARY (NOT TRAFFIC)	24"
-COMMUNICATION (NOT TRAFFIC)	24"
-SECONDARY (TRAFFIC)	30"
-COMMUNICATION (TRAFFIC)	30"
-PRIMARY	42"

- COVER MAY BE REDUCED TO 18" FOR SECONDARY UNDER SIDEWALKS, WITH THE PROJECT ENGINEER'S APPROVAL.
- HORIZONTAL SPACING BETWEEN SECONDARY, COMMUNICATION, TELEPHONE, AND STREET LIGHTING CABLES OR DUCTS MAY BE RANDOM UNLESS OTHERWISE SPECIFIED.
 - IN EVERY CASE, VERTICAL CLEARANCE BETWEEN ELECTRIC LINES AND UTILITY LINE CROSSINGS MUST BE AT LEAST 12".
- * DIRECT PRIMARY CONDUIT IS NO LONGER AN APPROVED CONSTRUCTION METHOD.

ELECTRIC UTILITIES DEPARTMENT COMMENTS & CONDITIONS


- ALL ELECTRICAL VAULT INSTALLATIONS, REMOVALS AND RELOCATION'S SHALL BE AT CUSTOMER/DEVELOPER'S EXPENSE.
- PRIMARY CONDUIT SHALL BE CONCRETE ENCASED PER CPA REQUIREMENTS.
- THE FINAL JOINT TRENCH AND VAULT DETAILS MUST BE APPROVED BY THE CITY'S ELECTRICAL ENGINEERING DEPARTMENT.
- APPLICANT SHALL NOTIFY THE ELECTRIC UTILITY INSPECTOR PRIOR TO CONSTRUCTION OF ANY ELECTRICAL UTILITY SUBSTRUCTURE.
- NO STRUCTURES PERMITTED TO BE BUILT WITHIN EXISTING PUBLIC UTILITY EASEMENTS.
- THE CONTRACTOR SHALL MAINTAIN 12" CLEAR, ABOVE AND BELOW FROM THE EXISTING UTILITIES TO NEW UNDERGROUND FACILITIES.
- APPLICANTS SHALL PROVIDE PROTECTION FOR UTILITY LINES SUBJECT TO DAMAGE. EXPOSED ELECTRIC CONDUIT OR DUCT SHALL BE INSPECTED BY THE ELECTRICAL UTILITY INSPECTOR PRIOR TO BACKFILLING.
- ANY EXTENSION OR RELOCATION OF EXISTING DISTRIBUTION LINES OR EQUIPMENT SHALL BE DONE AT CUSTOMER/DEVELOPER'S EXPENSE.

ELECTRIC CONDUIT MINIMUM BEND RADIUS FOR NEW CONSTRUCTION SERVICE			
CONDUIT DIAMETER	VERTICAL	RADIUS	HORIZONTAL RADIUS
3"	24"		36"
4"	36"		36"
5"	36"		60"

NOTE:
NO MORE THAN 270 DEGREES OF BENDS ARE ALLOWED BETWEEN PULL BOXES IN A SECONDARY CONDUIT RUN.

NO MORE THAN 180 DEGREES OF BENDS ARE ALLOWED BETWEEN PULL BOXES IN A PRIMARY CONDUIT RUN.

Direct Buried Conduit



CONCRETE TRANSFORMER PAD NOTES:

- DISTURBED EARTH UNDER THE PAD SHALL BE REPLACED BY SAND OR OTHER SUITABLE MATERIAL COMPACTED TO 95% OF MAXIMUM DRY DENSITY (ASTM D-1557).
- PLACE 6" DEPTH ONE SACK PER CUBIC YARD, SLURRY IMMEDIATELY BELOW THE PAD.
- CONCRETE IS REQUIRED BETWEEN ALL CONDUITS, LEVEL TO TOP OF THE PAD.
- CONCRETE SHALL BE DESIGNED TO ATTAIN STRENGTH OF 3000 PSI IN 28 DAYS.
- AFTER PLACING, MOIST CURE CONCRETE FOR 7 DAYS.
- WOOD FLOAT FINISH TOP OF SLAB. ALL SHARP EDGES AND CORNERS TO BE FINISHED SMOOTH.
- EXPOSED HORIZONTAL SURFACES TO BE SLOPED SLIGHTLY FOR DRAINAGE.
- A MINIMUM OF 6 FEET SHALL BE MAINTAINED BETWEEN GROUND RODS.
- CAP ALL CONDUITS.
- A MINIMUM OF 3 FEET OF RADIAL CLEARANCE BETWEEN THE TRANSFORMER PAD AND ANY OTHER STRUCTURE SHALL BE PROVIDED.
- IF THE TRANSFORMER IS TO BE LOCATED IN AN AREA SUBJECTED TO VEHICULAR TRAFFIC, BARRIERS SHALL BE REQUIRED PER DT-SS-C-1005. CITY OF PALO ALTO WILL DETERMINE THE TYPE, NUMBER REQUIRED, AND LOCATION.
- PLASTIC CONDUITS SHALL BE TERMINATED WITH END BELLS. GALVANIZED STEEL CONDUITS SHALL BE TERMINATED WITH GROUND BUSHINGS. ALL CONDUITS AND ENDS WILL BE TO THE FINAL GRADE OF THE PAD.
- PRIMARY CONDUIT BENDS SHALL HAVE A MINIMUM RADIUS OF 36".
- PRIMARY CONDUITS SHALL BE LOCATED IN THE LEFT HALF OF THE CONDUIT OPENING. SECONDARY CONDUITS SHALL OCCUPY THE RIGHT HALF.
- THE TRANSFORMER PAD SHALL BE LOCATED A MINIMUM OF 3 FEET FROM ANY BUILDING OR OVERHANG.
- ALL REBAR SHALL BE A-615 GRADE 40. REBAR JOINTS SHALL BE FIRMLY AND SECURELY HELD IN POSITION BY WIRING AT INTERSECTIONS WITH NO. 16 GAGE WIRE.
- MAXIMUM NUMBER OF CONDUITS ENTERING SECONDARY SLOT SHALL BE FOUR. CONTACT THE ELECTRIC UTILITY PROJECT ENGINEER FOR DESIGN WITH MORE THAN FOUR SECONDARY.
- GROUND ROD AND CLAMP, 5/8"x8". SEE CPA STANDARD DRAWING #DT-SS-U-1001.
- TRANSFORMER ANCHORS SHALL BE INSTALLED ACCORDING TO MANUFACTURER'S INSTRUCTIONS. EXPANSION BOLT SHALL BE "PARABOLT" BY MOLY OR APPROVED EQUAL. MINIMUM EMBEDMENT LENGTH AND EDGE DISTANCE SHALL MEET THE MANUFACTURER'S REQUIREMENTS.
- A MINIMUM OF 8 FEET CLEARANCE SHALL BE MAINTAINED FROM THE FRONT SIDE OF THE PAD. A MINIMUM OF 3 FEET CLEARANCE SHALL BE MAINTAINED ON UNOPERABLE SIDES AND BACK. ALL MEASUREMENTS ARE TAKEN FROM THE PAD.

OTHER NOTES

- EASEMENTS MUST BE GRANTED TO THE CITY OF PALO ALTO FOR SWITCH, TRANSFORMERS, AND CONDUIT ON-SITE.
- ELECTRIC METERS MUST BE IN AN AREA READILY ACCESSIBLE TO CAPU DURING ALL HOURS.
- UTILITY VAULTS, TRANSFORMERS, UTILITY CABINETS, CONCRETE BASES, OR OTHER STRUCTURES CAN NOT BE PLACED OVER EXISTING WATER, GAS OR WASTEWATER MAIN/SERVICES. MAINTAIN 1' HORIZONTAL CLEAR SEPARATION FROM THE VAULT/CABINET/CONCRETE BASE TO EXISTING UTILITIES AS FOUND IN THE FIELD. IF THERE IS A CONFLICT WITH EXISTING UTILITIES, CABINETS/VAULTS/BASES SHALL BE RELOCATED FROM THE PLAN LOCATION AS NEEDED TO MEET FIELD CONDITIONS.

GENERAL NOTES:

- JOINT TRENCH MUST BE INSTALLED ENTIRELY WITHIN AN EASEMENT. EASEMENTS FOR JOINT TRENCH SERVICE LATERALS WITHIN PROJECT ON PRIVATE PROPERTY ARE AT THE DISCRETION OF THE UTILITY COMPANIES.
- ALL DEPTHS AND RESULTING COVER REQUIREMENTS ARE MEASURED FROM FINAL GRADE.
- COVER, CLEARANCES, AND SEPARATION SHALL BE AS GREAT AS PRACTICABLE UNDER THE CIRCUMSTANCES, BUT UNDER NO CIRCUMSTANCES SHALL BE LESS THAN THE MINIMUM COVER, CLEARANCE, AND SEPARATION REQUIREMENTS SET FORTH IN GENERAL ORDER 128 AND 490TR 192.327. ALL FACILITIES SHALL BE ANCHORED IN PLACE PRIOR TO COMPACTION, OR OTHER MEANS SHALL BE TAKEN TO ENSURE NO MOTION OF THE FACILITIES. DIMENSIONAL REQUIREMENTS FOR SHADING, LEVELING, AND BACKFILLING SHALL BE DETERMINED SUBSEQUENT TO COMPACTION.
- TRENCH DIMENSIONS SHOWN ARE TYPICAL. TRENCH SIZES AND CONFIGURATIONS MAY VARY DEPENDING UPON OCCUPANCY AND/OR FIELD CONDITIONS. TRENCH SIZE AND CONFIGURATION MUST AT ALL TIMES BE CONSTRUCTED IN A MANNER THAT ENSURES PROPER CLEARANCES AND COVER REQUIREMENTS ARE MET. ANY "CHANGE" TO THE TRENCH WIDTH AND CONFIGURATIONS AS SHOWN IN THIS EXHIBIT MUST BE DESIGNED TO ENSURE THIS REQUIREMENT.
- IT IS PREFERRED TO HAVE NON-CPA OWNED STREETLIGHTS AT A LEVEL OTHER THAN THE GAS OR ELECTRIC LEVEL. NON-CPA OWNED STREETLIGHTS MAY BE AT THE ELECTRIC LEVEL OF THE TRENCH AS LONG AS MINIMUM CLEARANCES ARE PROVIDED AND COMPLY WITH ALL SPECIAL NOTES FOR A JOINT TRENCH WITH A SECOND ELECTRIC UTILITY.
- NON-UTILITY FACILITIES ARE NOT ALLOWED IN ANY JOINT UTILITY TRENCH. E.G., IRRIGATION CONTROL LINES, BUILDING FIRE ALARM SYSTEMS, PRIVATE TELEPHONE SYSTEMS, OUTDOOR ELECTRICAL CABLE, ETC.
- PROVIDE SEPARATION FROM TRENCH WALL AND OTHER FACILITIES SUFFICIENT TO ENSURE PROPER COMPACTION.
- MAINTAIN PROPER SEPARATION BETWEEN CPA FACILITIES AND "WET" UTILITY LINES AS DESCRIBED IN CITY OF PALO ALTO STANDARDS.
- SEPARATIONS SHALL BE MAINTAINED AT ABOVEGROUND TERMINATION POINTS.
- PROCEDURES FOR APPROVING NATIVE BACKFILL FOR SHADING OF CPA GAS FACILITIES:
 - RANDOM SOIL SAMPLES SHALL BE TAKEN FROM A MINIMUM OF 3 LOCATIONS PER 1,000' OF TRENCH. 100% OF THE SAMPLE MUST PASS THROUGH A 1/2" SIEVE AND 75% MUST PASS THROUGH A #4 SCREEN.
 - SAMPLES MUST BE TAKEN IF EXISTING SOIL CONDITIONS CHANGE AND ARE TO BE TAKEN AT THE DISCRETION OF THE CPA REPRESENTATIVE ON SITE.
 - THE SOILS MUST NOT CONTAIN ANY ROCKS THAT HAVE SHARP EDGES OR THAT MAY OTHERWISE BE ABRASIVE.
 - THE SOILS MUST NOT CONTAIN CLODS LARGER THAN 1/2" IF TO BE USED AS SHADING, BEDDING, OR LEVELING MATERIALS.
 - COMPACTION REQUIREMENTS MUST MEET ANY APPLICABLE CPA, FEDERAL, STATE, COUNTY, OR LOCAL REQUIREMENTS.
 - AT NO TIME SHALL THE OVER SATURATION OF NATIVE SOILS BE USED TO ACHIEVE THESE REQUIREMENTS.
- THE SIEVES AND SCREENS SHALL BE:
 - 1/2" SIEVE: 8" DIAMETER BY 2" DEEP, STAINLESS STEEL MESH SCREEN.
 - #4 SCREEN: 8" DIAMETER BY 2" DEEP, STAINLESS STEEL MESH SCREEN.
- PROCEDURES FOR APPROVING NATIVE BACKFILL FOR SHADING AT CPA ELECTRIC FACILITIES:
 - RANDOM SOIL SAMPLES SHALL BE TAKEN FROM A MINIMUM OF 3 LOCATIONS PER 1,000' OF TRENCH. ADDITIONAL SAMPLES MUST BE TAKEN IF EXISTING SOIL CONDITIONS CHANGE AND ARE TO BE TAKEN AT THE DISCRETION OF THE CPA REPRESENTATIVE ON SITE.
 - SHADING MATERIAL CONTAINING LARGE ROCK, PAVING MATERIAL, CINDERS, SHARPLY ANGULAR SUBSTANCES, OR CORROSIVE MATERIAL SHALL NOT BE PLACED IN THE TRENCH WHERE SUCH MATERIAL MAY DAMAGE THE AND/OR PREVENT PROPER COMPACTION OVER OR AROUND THE CONDUITS.
 - NATIVE SOILS CONTAINING CLODS NOT TO EXCEED 6" IN DIAMETER MAY BE INCLUDED IN THE SHADING MATERIAL PROVIDED THE CLODS ARE READILY BREAKABLE BY HAND.
- NOTE: SOILS CONSISTING PRIMARILY OF ADDBE, HARD COMPACT (DENSE) CLAY, AND BAY MUDS SHALL NOT BE USED AS SHADING MATERIAL.
 - AT NO TIME SHALL THE OVER SATURATION OF NATIVE SOILS BE USED TO ACHIEVE THESE REQUIREMENTS.
 - REFER TO ENGINEERING DOCUMENT 062288, ITEM 13 ON PAGE 2.
- COMPETENT NATIVE SOILS ARE PREFERRED TO BE USED FOR SHADING, BEDDING, AND BACKFILLING THROUGHOUT THE TRENCH.
 - WHERE NATIVE SOILS EXCEED 1/2" MINUS AND/OR WHERE GAS IS TO BE PLACED AT THE BOTTOM OF A TRENCH IN AREAS THAT EXCEED 1/2" MINUS SOIL CONDITIONS, OR WHERE THE BOTTOM OF A TRENCH IS CONSIDERED TO CONSIST OF HARD PAN, CPA APPROVED 1/2" MINUS IMPORT MATERIAL SHALL BE USED FOR SHADING BEDDING OF GAS FACILITIES.
 - CPA APPROVED IMPORT MATERIAL IS PER CGT ENGINEERING GUIDELINE 4123.
 - IF A LEVELING COURSE IS REQUIRED FOR GAS FACILITIES, THE USE OF NATIVE SOILS IS PREFERRED, BUT IF 1/2" MINUS CONDITIONS ARE NOT ATTAINABLE WITH THE NATIVE SOILS, THEN THE USE OF CPA APPROVED IMPORT MATERIAL IS REQUIRED. BEDDING UNDER GAS FACILITIES WILL BE A MINIMUM OF 2" OF COMPACTED 1/2" MINUS NATIVE SOILS OR CPA APPROVED IMPORT MATERIAL.
 - FOR ELECTRIC FACILITIES, REFER TO NOTE 12. THIS APPLIES TO LEVELING COURSES AS WELL AS SHADING.
 - THE MINIMUM CPA APPROVED BEDDING MATERIAL MAY BE INCREASED AT THE DISCRETION OF CPA WHEN WARRANTED BY EXISTING FIELD CONDITIONS (E.G., ROCKY SOILS, HARD PAN, ETC.).
 - THE USE OF ANY IMPORTED MATERIAL FOR BACKFILLING PURPOSES SHALL BE LIMITED TO THOSE SITUATIONS WHEN NATIVE SOILS DO NOT ALLOW FOR REQUIRED COMPACTION.
- THE APPLICANT IS RESPONSIBLE FOR THE REMOVAL OF EXCESS SPOIL AND ASSOCIATED COSTS.
- SERVICE SADDLES ARE THE PREFERRED SERVICE FITTINGS FOR USE THROUGHOUT THE JOINT TRENCH PROJECT. ALL PROJECTS WILL BE DESIGNED AND ESTIMATED USING SERVICE SADDLES. HOWEVER, SERVICE TEES MAY BE USED IF ALL CLEARANCES, SEPARATION, AND COVERAGE REQUIREMENTS ARE MAINTAINED.
- ELECTRIC GENERATION EQUIPMENT IS NOT PART OF RADIUS SCOPE. ALL RELATED DESIGNS, APPLICATIONS, AND COORDINATION WITH INTERCONNECTION/NET METERING DEPARTMENT SHALL BE HANDLED BY THE EQUIPMENT VENDOR OR OTHERS.

- AND/OR
- CPA APPROVED IMPORT MATERIAL IS PER CGT ENGINEERING GUIDELINE 4123.
 - IF A LEVELING COURSE IS REQUIRED FOR GAS FACILITIES, THE USE OF NATIVE SOILS IS PREFERRED, BUT IF 1/2" MINUS CONDITIONS ARE NOT ATTAINABLE WITH THE NATIVE SOILS, THEN THE USE OF CPA APPROVED IMPORT MATERIAL IS REQUIRED. BEDDING UNDER GAS FACILITIES WILL BE A MINIMUM OF 2" OF COMPACTED 1/2" MINUS NATIVE SOILS OR CPA APPROVED IMPORT MATERIAL.
 - FOR ELECTRIC FACILITIES, REFER TO NOTE 12. THIS APPLIES TO LEVELING COURSES AS WELL AS SHADING.
 - THE MINIMUM CPA APPROVED BEDDING MATERIAL MAY BE INCREASED AT THE DISCRETION OF CPA WHEN WARRANTED BY EXISTING FIELD CONDITIONS (E.G., ROCKY SOILS, HARD PAN, ETC.).
 - THE USE OF ANY IMPORTED MATERIAL FOR BACKFILLING PURPOSES SHALL BE LIMITED TO THOSE SITUATIONS WHEN NATIVE SOILS DO NOT ALLOW FOR REQUIRED COMPACTION.


- THE APPLICANT IS RESPONSIBLE FOR THE REMOVAL OF EXCESS SPOIL AND ASSOCIATED COSTS.
- SERVICE SADDLES ARE THE PREFERRED SERVICE FITTINGS FOR USE THROUGHOUT THE JOINT TRENCH PROJECT. ALL PROJECTS WILL BE DESIGNED AND ESTIMATED USING SERVICE SADDLES. HOWEVER, SERVICE TEES MAY BE USED IF ALL CLEARANCES, SEPARATION, AND COVERAGE REQUIREMENTS ARE MAINTAINED.
- ELECTRIC GENERATION EQUIPMENT IS NOT PART OF RADIUS SCOPE. ALL RELATED DESIGNS, APPLICATIONS, AND COORDINATION WITH INTERCONNECTION/NET METERING DEPARTMENT SHALL BE HANDLED BY THE EQUIPMENT VENDOR OR OTHERS.

UTILITY APPROVALS		
UTILITY	APPROVED BY	DATE
AT&T (PHONE)		
COMCAST (CATV)		

FOR RADIUS USE ONLY QA REVIEW		
INTENT	INITIALS	REVIEW DATE
COMPOSITE		
PRE-CON		
PRE-CON		

DEVELOPER: KSH ARCHITECTS
349 SUTTER STREET
SAN FRANCISCO, CA 94108
AMANDA BORDEN
(415) 954-1960
ABORDEN@KSHA.COM

SHEET INDEX	
JT-1	JOINT TRENCH TITLE SHEET
JT-2	JOINT TRENCH INTENT



SMITH DEVELOPMENT

660 UNIVERSITY
PALO ALTO, CA 94301




RADIUS
DESIGN LLC
UTILITY DESIGN CONSULTANTS & ENGINEERS
1460 MARIA LANE, SUITE 420, WALNUT CREEK, CA 94596
Tel (925) 269-4575

ISSUES AND REVISIONS		
NO.	DATE	DESCRIPTION
12.01.21		PLANNING SUBMITTAL
05.13.22		PLANNING RESUBMITTAL #1
08.15.22		PLANNING RESUBMITTAL #2
11.02.22		PLANNING RESUBMITTAL #3
08.28.23		PLANNING RESUBMITTAL #4
10.31.23		PLANNING RESUBMITTAL #5
12.21.23		PLANNING RESUBMITTAL #6
02.07.24		PLANNING RESUBMITTAL #7

PROJECT NUMBER
21003

SHEET TITLE
JOINT TRENCH TITLE SHEET



SCALE
N.T.S

SHEET NUMBER

JT-1



ARCHITECTS
KORTH SUNSERI HAGEY



UTILITY DESIGN CONSULTANTS & ENGINEERS
1460 MARIA LANE, SUITE 420, WALNUT CREEK, CA 94596
Tel (925) 269-4575

ISSUES AND REVISIONS		
NO.	DATE	DESCRIPTION
	12.01.21	PLANNING SUBMITTAL
	05.13.22	PLANNING RESUBMITTAL #1
	08.15.22	PLANNING RESUBMITTAL #2
	11.02.22	PLANNING RESUBMITTAL #3
	08.28.23	PLANNING RESUBMITTAL #4
Δ	10.31.23	PLANNING RESUBMITTAL #5
	12.21.23	PLANNING RESUBMITTAL #6
	02.07.24	PLANNING RESUBMITTAL #7

PROJECT NUMBER
21003

SHEET TITLE
JOINT TRENCH INTENT

SCALE
1' = 20"



SHEET NUMBER

JT-2

NOTE TO CONTRACTOR:
FOR CONTRACTOR'S WORK RESPONSIBILITY,
REFER TO JOINT TRENCH TITLE SHEET (JT-1)

LEGEND:

NEW


- JT ——— JOINT TRENCH
- 6.3x8.3 100' x 100' TRANSFORMER PAD (CPAU).
WORKING SPACE SHOWN.
MAINTAIN 30' UNOBSTRUCTED
OVERHEAD CLEARANCE OVER PAD.
- 88x74 88' x 74' TRANSFORMER PAD (CPAU).
WORKING SPACE SHOWN.
MAINTAIN 30' UNOBSTRUCTED
OVERHEAD CLEARANCE OVER PAD.
- 466 78' x 48' x 60' JUNCTION BOX (CPAU).
WORKING SPACE SHOWN.
MAINTAIN 20' UNOBSTRUCTED OVERHEAD
CLEARANCE OVER ENCLOSURE

EXISTING - TO REMAIN

- EL ——— E ——— ELECTRIC LINE
- UB UTILITY BOX
- CP CATV PEDESTAL
- CB CATV BOX
- TB PHONE BOX
- TL PHONE LINE
- COM ——— COMMUNICATIONS LINE
- GV GAS VALVE
- GL GAS LINE
- TSL TRAFFIC SIGNAL LIGHT
- SLB STREET LIGHT BOX
- SL STREET LIGHT




EXISTING - TO BE REMOVED OR RELOCATED

- GL GAS LINE TO BE REMOVED
- GM GAS METER TO BE REMOVED
- EL ELECTRIC LINE TO BE REMOVED



SEE BUILDING PLANS FOR CONDUIT ENTRY INTO BUILDING.
DEVELOPER'S RESPONSIBILITY TO BUILD ELECTRIC METER
ROOM IN COMPLIANCE WITH CURRENT PG&E GREENBOOK
SECTIONS 5 AND 10. CONDUIT STUB OUT MUST BE
COORDINATED WITH BUILDING CONTRACTORS TO AVOID
EXCEEDING MAXIMUM ALLOWABLE CONDUITS BENDS! DO
NOT BOTTOM FEED ELECTRIC CONDUITS INTO PANEL
WHEN PANEL IS BELOW GRADE.

NOTE TO DEVELOPER: POTHOLE NEW VAULT LOCATIONS TO
CONFIRM ACTUAL LOCATION OF EXISTING UNDERGROUND
UTILITIES PRIOR TO START OF TRENCHING WORK.



NOTE TO DEVELOPER: POTHOLE TO DETERMINE
THE ACTUAL LOCATION OF ALL EXISTING
UNDERGROUND UTILITIES DURING DESIGN PHASE.
POTHOLE SUBSTRUCTURE LOCATIONS TO
CONFIRM THE ACTUAL LOCATION OF EXISTING
UNDERGROUND UTILITIES PRIOR TO THE START
OF TRENCHING WORK.


SUBSTRUCTURE LOCATIONS MUST BE STAKED BY A
LICENSED SURVEYOR PRIOR TO CONSTRUCTION.
SEE CONSTRUCTION NOTES ON JOINT TRENCH TITLE
SHEET (JT-1) REGARDING EXISTING CONDITIONS.

REFER TO PG&E DOCUMENT 094683 FOR SMART
METER ANTENNA CONSTRUCTION REQUIREMENTS.

NOTE FOR UNDERGROUND ELECTRIC INSTALLATION:
USE OF PVC DB-120 IS NO LONGER APPROVED BY
PG&E FOR ANY CONDUIT SIZES, BENDS, AND
FITTINGS. RIGID PVC SCHEDULE 40 MUST BE USED
IN PLACE OF PVC DB-120 CONDUIT. FOR ALL
APPROVED CONDUITS, BENDS, AND FITTINGS, SEE
PG&E DOCUMENT 062288.

SHEET INDEX

JT-1 JOINT TRENCH TITLE SHEET
JT-2 JOINT TRENCH INTENT



PROJECTED RESIDENTIAL TRASH COLLECTION SCHEDULE / WK							
SERVICE	M	T	W	T	F	S	SU
COMPACT WASTE (2CY)	1				1		
COMPACT RECYCLE (2CY)	1				1		
COMPOST (64G)	2				2		
TOTAL	4				4		

PROJECTED RETAIL OFFICE TRASH SCHEDULE / WK							
SERVICE	M	T	W	T	F	S	SU
LOOSE WASTE (96G)	2						
LOOSE RECYCLE (96G)	1	1		1	1		
COMPOST (64G)	1				1		
TOTAL	5				3		

UNIVERSITY AVE

SMITH DEVELOPMENT

660 UNIVERSITY
PALO ALTO, CA 94301

ARCHITECTS
KORTH SUNSERI HAGEY



AMERICAN TRASH MANAGEMENT
1900 POWELL STREET, SUITE 220
EMERYVILLE, CALIFORNIA 94608
P: 415.292.5400
F: 415.292.5410
CONSULTINGPROJECTS@TRASHMANAGE.COM

ISSUES AND REVISIONS

NO.	DATE	DESCRIPTION
12.01.21		PLANNING SUBMITTAL
05.13.22		PLANNING RESUBMITTAL #1
08.15.22		PLANNING RESUBMITTAL #2
11.02.22		PLANNING RESUBMITTAL #3
08.28.23		PLANNING RESUBMITTAL #4
10.31.23		PLANNING RESUBMITTAL #5
12.21.23		PLANNING RESUBMITTAL #6
02.07.24		PLANNING RESUBMITTAL #7

PROJECT NUMBER
21003

SHEET TITLE
OVERALL SITE PLAN
LEVEL 1

SCALE


3/32" = 1'-0"



0 10'-8" 21'-4"

SHEET NUMBER

TR0.1



SIDE LOAD
PICK UP VEHICLE

MUST HAVE SIGN
INDICATING NO
PARKING DURING
SERVICE HOURS

BYRON STREET

FRONT LOAD
PICK UP VEHICLE

Bins shall be staged by
maintenance staff and will be
responsible for bringing back
the containers to the trash
room immediately after service.

SPEED RAMP DOWN TO P1

SMITH DEVELOPMENT

660 UNIVERSITY
PALO ALTO, CA 94301

ARCHITECTS
KORTH SUNSERI HAGEY


**AMERICAN
TRASH MANAGEMENT**


AMERICAN TRASH MANAGEMENT
1900 POWELL STREET, SUITE 220
EMERYVILLE, CALIFORNIA 94608
P: 415.292.5400
F: 415.292.5410
CONSULTINGPROJECTS@TRASHMANAGE.COM

ISSUES AND REVISIONS

NO.	DATE	DESCRIPTION
12.01.21		PLANNING SUBMITTAL
05.13.22		PLANNING RESUBMITTAL #1
08.15.22		PLANNING RESUBMITTAL #2
11.02.22		PLANNING RESUBMITTAL #3
08.28.23		PLANNING RESUBMITTAL #4
10.31.23		PLANNING RESUBMITTAL #5
12.21.23		PLANNING RESUBMITTAL #6
02.07.24		PLANNING RESUBMITTAL #7


PROJECT NUMBER
21003

SHEET TITLE
STAGING & BIN PATH





SHEET NUMBER

TR0.2



PROJECTED RESIDENTIAL TRASH COLLECTION SCHEDULE / WK							
SERVICE	M	T	W	T	F	S	SU
COMPACT WASTE (2CY)	1				1		
COMPACT RECYCLE (2CY)	1				1		
COMPOST (64G)	2				2		
TOTAL	4				4		

PROJECTED RETAIL OFFICE TRASH SCHEDULE / WK							
SERVICE	M	T	W	T	F	S	SU
LOOSE WASTE (96G)	2						
LOOSE RECYCLE (96G)	2				2		
COMPOST (64G)	1				1		
TOTAL	5				3		



SMITH DEVELOPMENT

660 UNIVERSITY
PALO ALTO, CA 94301


ARCHITECTS
KORTH SUNSERI HAGEY



ISSUES AND REVISIONS		
NO.	DATE	DESCRIPTION
12.01.21		PLANNING SUBMITTAL
05.13.22		PLANNING RESUBMITTAL #1
08.15.22		PLANNING RESUBMITTAL #2
11.02.22		PLANNING RESUBMITTAL #3
08.28.23		PLANNING RESUBMITTAL #4
10.31.23		PLANNING RESUBMITTAL #5
12.21.23		PLANNING RESUBMITTAL #6
02.07.24		PLANNING RESUBMITTAL #7

PROJECT NUMBER
21003

SHEET TITLE
TRASH COLLECTION ROOM DETAILS



TR1.0

1 RESIDENTIAL TRASH VESTIBULES | UPPER LEVELS
3/8" = 1'-0"

2 TRASH COLLECTION AND CHUTE TERMINATION ROOMS | GROUND LEVEL
1/4" = 1'-0"

ISSUES AND REVISIONS		
NO.	DATE	DESCRIPTION
12.01.21		PLANNING SUBMITTAL
05.13.22		PLANNING RESUBMITTAL #1
08.15.22		PLANNING RESUBMITTAL #2
11.02.22		PLANNING RESUBMITTAL #3
08.28.23		PLANNING RESUBMITTAL #4
10.31.23		PLANNING RESUBMITTAL #5
12.21.23		PLANNING RESUBMITTAL #6
02.07.24		PLANNING RESUBMITTAL #7


PROJECT NUMBER
21003

SHEET TITLE
CHUTE DETAILS


SCALE
NTS

SHEET NUMBER


TR2.0




1 CHUTE INTAKE DOOR



3 WALL PROTECTION CONCRETE CURB




5 CHUTE AIR AND SOUND ISOLATION




6 TRASH CHUTE JANITOR




7 FIRE SPRINKLER DETAILS AND CHUTE SANITATION UNIT




9 FLOOR SUPPORT FRAME ANCHORING




11 CHUTE VENT




12 FLOOR SUPPORT FRAME ANCHORING



10 CHUTE SHAFT AT INTAKE



11 CHUTE VENT



12 FLOOR SUPPORT FRAME ANCHORING



1900 Powell Street, Suite 220
Emeryville, CA 94608
(800) 488-7274 Toll Free USA
(415) 292-5400
(415) 292-5410 Fax
www.trashmanage.com

Smith Development 660 University Palo Alto, CA Trash Management Plan

Task: Design a waste and recycling system for a mixed-use project consisting of 70 residential units and 9,115 square feet of office space that minimizes costs, staffing requirements, and environmental impacts, while providing convenient trash disposal for the building's residents. Please note the word "trash" when used in this plan covers both waste and recycling.

Waste and Recycling Removal: The City of Palo Alto has granted GreenWaste of Palo Alto a license to provide residential and commercial Waste and Recycling services to residents and businesses located within the city and county. This license is a de facto exclusive franchise for trash removal for any property located within city limits. GreenWaste provides three types of service: waste, commingled recycling, and compost collection.

The City Council has approved the Recycling and Composting Ordinance. Starting January 1, 2017 businesses generating 2 or more cubic yards of garbage per week will be required to subscribe to recycling and compost services, as well as sort all waste into the appropriate containers. Currently, commercial customers generating 8 or more cubic yards of garbage per week, multifamily buildings, and food service establishments are already composting and recycling under the Ordinance.

Palo Alto Municipal Code 5.20.030 (b) states that "all persons shall separate their refuse according to its characterization as solid waste, compostable materials or recyclable materials."

Additionally, Palo Alto has a noise ordinance, 9.10.030 Residential Property Noise Limits that states (a) No person shall produce, suffer or allow to be produced by any machine, animal device, or any combination of same, on residential property, a noise level more than six dB above the local ambient at any point outside of the property plane.

(b) No person shall produce, suffer, or allow to be produced by any machine, animal, or device, or any combination of same, on multi-family residential property, a noise level more than six dB above the local ambient three feet from any wall, floor, or ceiling inside any dwelling unit on the same property, when the windows and doors of the dwelling unit are closed, except within the dwelling unit in which the noise source or sources may be located.
(Ord. 4634 § 2 (part), 2000)

NOTE: While Palo Alto has this noise ordinance given the data we have on trash truck noise, every location in the city with trash collection violates this rule.

State and Local Recycling Mandates: Statewide the passage of AB341 (July 1st, 2012) and subsequent AB1826 & SB 1383 required all businesses that have more than 5 residential units or generate more than 4 cubic yards of municipal solid waste to separate recyclable and compostable materials from the waste stream. This law directs local jurisdictions to implement recycling and composting regulations and programs.



1900 Powell Street, Suite 220
Emeryville, CA 94608
(800) 488-7274 Toll Free USA
(415) 292-5400
(415) 292-5410 Fax
www.trashmanage.com

	SF	Loose Waste Volume CY/WK	Loose Recycle Volume CY/WK	Loose Compost Volume CY/WK	Total # of Loose 96G Compost Carts/WK	Total # of Loose 96G Compost Carts/WK	Total # of Loose 64G Compost Carts/WK
Office	9,115	0.9	1.5	0.4	2	4	2

Residential Trash Handling System

To comply with City ordinances, residential trash will be collected in 3 different streams: waste, mixed recyclables (paper, cardboard & containers), and compost.

Chutes. The project will have 2 - 30" diameter trash chutes with 15x18 intake doors in each trash chute core: one for waste, and the other for mixed recycling. The chutes shall be made of 16 gauge galvaneal steel. The project will have a 1-24" diameter trash chute with 15x18 intake doors in each trash chute core for compost. The chute shall be made of 304 stainless steel. All materials will be collected at the ground level of the building.

Increasing the chute size for waste and recycling to 30" above the 24" minimum required by CBC will slightly increase the chute system cost but it will reduce the possibility of chute jams due to large objects (e.g., super size pizza, Amazon, and Costco boxes) being thrown down the chute. This will reduce ongoing maintenance costs while increasing tenant convenience.

The waste and recycling chutes should be 16 gauge galvaneal or aluminized steel and be isolated from the building structure using Mason BRA-Read mounts or equivalent. The chute should be coated with a sound-dampening compound (Soundcoat GP-1 or equivalent) equal to the thickness of the metal.

The compost chute must be 304 stainless steel with an automated wash-down system to minimize the problem of chute collection of compost.

NOTE: We recommend limiting the chute intake doors to 15"x18" to minimize residents putting large, bulky items down the trash chute. Based on input from property managers, tenants have been known to dispose of ironing boards, ficus trees, chairs, and crutches down chutes. The recommended 15"x18" intake door will easily handle large kitchen trash bags while discouraging potentially problematic bulky items.

Compactors. Waste and recycling will be collected in 2CY chute-fed compactors. Compactors will reduce space requirements, staffing needs, and disposal fees, while minimizing truck traffic, thereby lowering the project's operational costs and overall environmental impact. All compactor bins will have locks on the lids and other openings to reduce access by vagrants. We recommend compactor bins be moved using a Waste Caddy.


Example of savings from compactors:

Service	Compaction Ratio	Monthly Fee
(1) 3-CY loose bin 4 times per week	N/A	\$1,864.39



1900 Powell Street, Suite 220
Emeryville, CA 94608
(800) 488-7274 Toll Free USA
(415) 292-5400
(415) 292-5410 Fax
www.trashmanage.com

Site Plan



Project Summary:

First, **local ordinance requires the collection of trash in three separate streams: waste, mixed recycling, and compost.**

Second, **a three-chute design as designed will be used for the residential trash collection room.** The compost chute should be 24" in diameter and must be 304 stainless steel with an automated wash-down system to minimize the problem of chute collection of compost. The waste and recycling chutes can be galvaneal steel, but we recommend increasing the diameter of the waste and recycling chute to 30". CBC minimum required 24" chutes have a higher probability of chute jams due to large objects (super-size pizza boxes, Costco boxes, ironing boards, crutches, etc.) being thrown down the chute.

Third, due to the projected residential trash volumes, **waste and recycling will be collected in chute-fed compactors with 2CY bins.** Compactors will reduce the number of trash bins the project will need to store, reduce the development's trash bill, and reduce the number of trash truck trips to the property. Compost will be collected in 64G Toter carts under the chute.

Fourth, **commercial retail tenants will be responsible for handling their own trash. A dedicated trash room has been designed for trash collection.**



1900 Powell Street, Suite 220
Emeryville, CA 94608
(800) 488-7274 Toll Free USA
(415) 292-5400
(415) 292-5410 Fax
www.trashmanage.com

Service	Compaction Ratio	Monthly Fee
(1) 2-CY compacted bin 2 times per week	4:1	\$1,269.56

Note: Analysis for waste stream.

Lower Waste Disposal costs. Front-load compaction is less expensive than front-load loose waste services. (See cost-benefit analysis on page 20).

Compaction and Recyclables. The City of Palo Alto does not charge for loose or compacted recycling. Even though there will be no trash bill savings with compacted recycling we still recommend compaction for this project due to the automated handling of materials, its lower space requirements, and lower environmental impact (noise and litter) even though there is less savings.

Lower labor costs: A 3-cubic yard loose waste bin serviced Monday through Sunday must be moved from the trash chute to the trash service location 4x per week. Comparable compacted service a single 2-cubic yard bin picked up 2x per week. That represents 50% fewer times to move the bin from the trash area to the street for pickup. (See cost-benefit analysis on page 20).

Compost. Compost will be collected in loose 64-gallon carts under the chute.

NOTE: The compostable waste chute system creates unique sanitation issues, so a 304 stainless steel chute is recommended (to prevent corrosion), as is a special wash-down system to minimize the sanitation and odor problems that will arise from loose food waste being disposed down the chute.

ATM does not normally recommend collecting apartment compostable materials using gravity chutes due to sanitation issues, collection issues, the corrosive properties of the material, and the odorous nature of putrefying household food waste, which is the primary component of organic waste from apartments. The compostable materials will adhere to the sides of the chutes and require frequent chute washdowns. This will increase the project's water usage and sewage loads. The acidic nature of fermenting compost will cause the chute to rust prematurely unless they are made of 304 stainless steel. It is important that proper sanitation protocols are followed since the compostable material that will adhere to the chute wall is an excellent medium to grow fruit flies, maggots, molds, fungus, yeast, and bacteria which can cause insect infestations, allergic reactions, and malodors.

Cardboard. Due to the number of units, this project is projected to generate ~245 cardboard boxes per day. While diverting cardboard will not result in any direct disposal savings at this time, it can help reduce the number of large boxes creating chute jams. We recommend providing a space adjacent to the trash rooms for residents to place their large, flattened cardboard boxes. These boxes will need to be moved by building staff daily into a spare recycling bin.

Odor Control. To mitigate malodors in the trash room(s), a four-pronged approach is recommended including cleaning, proper ventilation, and installing a deodorizer system.

1. **Mechanical Exhaust of Trash Collection Room.** The mechanical ventilation required rate is 1 CFM/ SF, however, ATM recommends increasing this rate as needed, especially in areas with a warmer climate. Exhaust should vent through the roof. ATM does not recommend a chilled/refrigerated trash room. A cooled space will not delay decomposition and will have minimal impacts on odorous trash.



1900 Powell Street, Suite 220
Emeryville, CA 94608
(800) 488-7274 Toll Free USA
(415) 292-5400
(415) 292-5410 Fax
www.trashmanage.com

Fifth, **staging will occur on Byron St. Front-load** bins require 25' vertical clearance which is typically used in a project of this size. Bins must be moved by staff to this location so the trash bins to be emptied by Green Waste with minimal impact on the residents and the project's neighbors.

Sixth, **add 1 CFM/SF mechanical ventilation per CBC, floor drain, hose bib, and odor control to the trash collection rooms.**

Projected Residential Waste and Recycling Levels: The following metrics were used to project residential waste and recycling levels:

Residential Waste: 0.16 Cubic Yard (32 gallon) per week/unit. **NOTE: This is the equivalent of 2.5 large kitchen garbage cans per unit week (3 - 13 gallon bags).**

Residential Recycling: 0.16 Cubic Yard (32 gallon) per week/unit. **NOTE: This is the equivalent of almost 2 large kitchen garbage cans per unit week (2 - 13 gallon bags).**

Residential Compost: 0.012 Cubic Yard (2.4 gallon) per week/unit. **NOTE: This is the equivalent of small compost pail per unit week.**

Residential LOOSE Trash Volume Projections. See detailed analysis on page 20.

Units	Projected Waste Volume CY/ WK	Projected Recycle Volume CY/WK	Projected Compost Volume CY/WK	Total # of Loose 3CY Waste Bins/ WK	Total # of Loose 3CY Recycle Bins/ WK	Total # of Loose 96G Compost Carts/WK
70	11.2	11.2	0.8	4	4	3

Residential COMPACTED Trash Volume Projections. See detailed analysis on page 20.

Units	Projected Waste Volume CY/ WK	Projected Recycle Volume CY/WK	Projected Compost Volume CY/WK	Total # of Compacted 2CY Waste Bins/WK	Total # of Compacted 2CY Recycle Bins/WK	Total # of Loose 96G Compost Carts/WK
70	2.8	2.8	0.8	2	2	3

Commercial Office Trash Volume Projections:

Studies cited by CalRecycle estimate office building trash generation at 5.44 lb. of trash per 1000 SF, nearly 70% of which can be diverted. Although past studies had low diversion rates for office buildings, more recent evidence points to large increases in diversion, as firms and their employees become more active recyclers. (This is supported both by outside studies and ATM's data). It is assumed, therefore, that comparable diversion rates for this office space will hold.

Using these metrics, the following levels of waste, recyclables, and compost are projected for the office space in this project.



1900 Powell Street, Suite 220
Emeryville, CA 94608
(800) 488-7274 Toll Free USA
(415) 292-5400
(415) 292-5410 Fax
www.trashmanage.com

- Cleaning the Trash Room.** Trash rooms should be swept clean of debris on a weekly basis. Trash room wash-downs should be scheduled quarterly. These should include cleaning any trash equipment such as compactors, as well as floors and walls. If possible, bins or compactor receiver containers should be cleaned at the same time, assuming the containers are empty. (Bins should be cleaned by onsite staff. If hauler-provided dumpsters become especially dirty, they should be replaced by the hauler).
- Cleaning the Trash Chute.** Almost all trash chutes are equipped with deodorizing and sanitizing (D&S) units, located on the top floor behind an access door. These should be operated on a WEEKLY basis, for ~5 minutes. Trash chutes that are designed for a high level of food waste often also have a "Chute Janitor" built-in wash-down system. These should be operated less often, such as 1x per month. When turned on, they should be allowed to run through their normal Rinse-Wash-Rinse cycle. Even with the presence of the D&S and Chute Janitor systems, all trash chutes should be pressure washed at least once a year to clean materials that adhere to the sides of the chutes. In areas with a warmer climate, we recommend quarterly washdowns. The chute wash-down service should include cleaning the trash discharge room, specifically the floors, walls, and the trash compactor.
- Odor Control Systems.** Odor control systems can be helpful in controlling odors, but most have limited effectiveness or create other problems. Popular low-cost systems that spray a masking agent into the air, only serve to hide odors in the trash room and not eliminate them. Ozone generators are more effective, but the odor-destroying product they create — ozone — can have a deleterious effect on human health and can also destroy compactor hoses and seals. One odor control system that avoids these problems is the Plian Mini Vaporizer. It creates a very fine 50-micron mist that bonds with — and ultimately destroys — odor-causing molecules. And unlike ozone, the entirely natural blend of plant extracts, essential oils, and emulsifiers which is safe and does not damage equipment.

Residential Trash System Equipment

Below is a summary of the recommended trash system equipment.

Compacted Service

Gravity Chutes	Diameter	Chute Material	Compactor Count	Bin Type	# of Bins	Bin Size Cubic Yards
3	2-30" 1-24"	2-16 gauge galvaneal steel 1-304 SS	2	Front Load	2 waste 2 recycle 2 compost	2CY waste & recycling 64G compost

-odor control, Waste Caddy for bin moving

SMITH DEVELOPMENT

660 UNIVERSITY
PALO ALTO, CA 94301



ARCHITECTS
KORTH SUNSERI HAGEY

ISSUES AND REVISIONS

NO.	DATE	DESCRIPTION
12.01.21		PLANNING SUBMITTAL
05.13.22		PLANNING RESUBMITTAL #1
08.15.22		PLANNING RESUBMITTAL #2
11.02.22		PLANNING RESUBMITTAL #3
08.28.23		PLANNING RESUBMITTAL #4
10.31.23		PLANNING RESUBMITTAL #5
12.21.23		PLANNING RESUBMITTAL #6
02.07.24		PLANNING RESUBMITTAL #7

PROJECT NUMBER
21003

SHEET TITLE


TRASH MANAGEMENT PLAN

SCALE


N.T.S.

SHEET NUMBER

TR3.1




1 RESIDENTIAL TRASH VESTIBULES | UPPER LEVELS
3/8" = 1'-0"






FF 48.16'



Monday, August 28, 2023



Location	Decibel Levels
Banging on Bins when Emptying	100
Behind Garbage Truck (while compacting)	89



Monday, August 28, 2023



Monday, August 28, 2023



Diagram illustrating the movement of a waste caddy in a hallway. The caddy is shown in two positions: one at the entrance of the hallway and another further inside, having moved forward. The diagram includes the following labels and dimensions:

- WASTE CADDY 36V DUMPSTER MOVER
- 2 CY WASTE DUMPSTER
- MIN. OUTSIDE TURNING RADIUS= 11'-6"
- MIN. INSIDE TURNING RADIUS= 8'-6 1/2"
- TRAVEL PATH ~3'-6" WIDE
- MIN. HALL WIDTH= 5'-11"

 AMERICAN TRASH MANAGEMENT	DESCRIPTION TURNING RADIUS WASTE CADDY / CONTAINER	NO.	REVISION	DATE	REV	ISS
					ISSN	ATM-TRWC
					HWG	FILE
					SCALE	DATE 1/18/2017

Monday, August 28, 2023



1-4 Cubic Yard Containers

Size	Length	Width	Height	Pocket Height
1 cu. yd.	51"	29.5"	37.0"	26.0"
1.5 cu. yd.	81"	32.5"	44.5"	37.5"
2 cu. yd.	81"	31.5"	51.5"	32.5"
3 cu. yd.	81"	46.5"	61.5"	39.5"
4 cu. yd.	81"	55.5"	66.5"	39.5"

*Measurements include carrier wheels.
 †To determine additional space needed for the enclosure for proper venting container at time of service, add 1 to 2 inches to length.

5-8 Cubic Yard Containers					
	Size	Length	Width	Height	Interior Height
	5 cu. yd.	81"	67.5"	63.6"	33.6"
	6 cu. yd.	81"	68.25"	71.5"	41"
	8 cu. yd.	81"	72"	92"	41"

Debris Box/Roll-Off Box			
Size	Length	Width	Height
7 cu. yd.	14'	8'	2'
15 cu. yd.	18'	8'	4'
20 cu. yd.	16'	8'	5.3'
30 cu. yd.	21'	8'	4.5'
40 cu. yd.	21'	8'	7.5'

	Wheeled Cart			
	Size	Depth	Width	Height
	20 gallons	21 1/2"	19 1/2"	38 1/2"
	32 gallons	24 7/8"	19 1/2"	38 1/2"
	48 gallons	30"	22 1/2"	39 1/2"
	96 gallons	34 1/2"	29 1/2"	46 7/8"



Green Waste of Palo Alto
2000 Geng Road
Palo Alto, CA 94300
650.493.4894



greenwaste
of palo alto

GreenWaste of Palo Alto
2000 Geng Road
Palo Alto, CA 94303

650.493.4894

Monday, August 28, 2023



KSH
ARCHITECTS
KORTH SUNSERI HAGEY

ISSUES AND REVISIONS		
NO.	DATE	DESCRIPTION
	12.01.21	PLANNING SUBMITTAL
	05.13.22	PLANNING RESUBMITTAL #1
	08.15.22	PLANNING RESUBMITTAL #2
	11.02.22	PLANNING RESUBMITTAL #3
	08.28.23	PLANNING RESUBMITTAL #4
	10.31.23	PLANNING RESUBMITTAL #5
	12.21.23	PLANNING RESUBMITTAL #6
	02.07.24	PLANNING RESUBMITTAL #7

PROJECT NUMBER
21003

SHEET TITLE

TRASH MANAGEMENT PLAN

SCALE

I.T.S.

SHEET NUMBER

TR3.3

ALL DRAWINGS AND WRITTEN MATERIAL APPEARING HEREIN CONSTITUTE ORIGINAL AND UNPUBLISHED WORK OF THE ARCHITECT AND MAY NOT BE DUPLICATED, USED OR DISCLOSED WITHOUT WRITTEN CONSENT OF THE ARCHITECT



1900 Powell Street, Suite 220
Emeryville, CA 94608
(800) 488-7274 Toll Free USA
(415) 292-5400
(415) 292-5410 Fax
www.trashmanage.com

Sample Residential Bin Moving Schedule. (Actual schedule to be determined by building management and hauler)

Residential - Compacted Service

	Monday	Tuesday	Wednesday	Thursday	Friday	Saturday	Sunday
Compacted 2CY Waste	1				1		
Compacted 2CY Recycle	1				1		
Compost 64G					4		
Total	2	0	0	0	6	0	0

Commercial Office - Loose Service

	Monday	Tuesday	Wednesday	Thursday	Friday	Saturday	Sunday
96G Loose Waste	2						
96G Loose Recycle	2				2		
64G Loose Compost	1				1		
Total	5	0	0	0	3	0	0

TRASH SYSTEM SPECIFICATIONS: Provided separately.

1. Section 14 91 00 - Trash Chutes & Intake Doors
2. Section 44 31 00 - Odor Control
3. Section 44 53 62 - Waste & Recycling Compactors
4. Section 41 63 23 - Waste Caddy for Bin Moving

© American Trash Management, Inc. 2023

Page 19 of 22

Monday, August 28, 2023



1900 Powell Street, Suite 220
Emeryville, CA 94608
(800) 488-7274 Toll Free USA
(415) 292-5400
(415) 292-5410 Fax
www.trashmanage.com

WASTE AND RECYCLING RATES (PARTIAL) CURRENT RATES - REFLECT CHANGES EFFECTIVE 7/1/16

City:	Palo Alto	Key Charge	\$15.00		
Franchise:	GreenWaste				
Multi-Family/Commercial Loose Front Load Waste Rates:					
Frequency/Size: x/wk-CY Size	2	4	64G Cart		
1 x Week	\$309.02	\$437.20	\$581.41	\$73.25	
2 x Week	\$638.63	\$913.31	\$1,174.26	\$163.66	
3 x Week	\$970.54	\$1,388.28	\$1,825.48	\$254.08	
4 x Week	\$1,301.30	\$1,864.39	\$2,448.09	\$344.49	
5 x Week	\$1,630.91	\$2,341.65	\$3,068.40	\$434.91	
6 x Week	\$1,961.67	\$2,817.76	\$3,689.87	\$525.33	
Multi-Family/Commercial Compacted Front Load Waste Rates:					
Frequency/Size: x/wk-CY Size	2	4			
1	\$634.78	\$1,269.56			
Compost Carts					
1 x Week		64-gal cart	96-gal cart	2CY	\$247.21
2 x Week		\$58.60	\$87.90		\$510.90
3 x Week		\$130.96	\$189.53		\$776.43
4 x Week		\$203.26	\$291.16		\$1,041.04
5 x Week		\$275.60	\$392.79		\$1,304.73
6 x Week		\$347.93	\$494.42		\$1,569.34
Stationary Compactor Cost	\$21,360.00	A1000, 1-4CY Towable bins, tax, ship Install			
Stationary Compactor Cost	\$24,655.00	A1000, 2-4CY Towable bins, tax, ship Install			
Vertical Compactor Cost	\$26,086.00	P200, 1-2CY front load bin-8" penolic casters, tax, ship Install			
Chute Fed Compactor Cost	\$20,960.00	A500, 2-2CY Towable bins, tax, ship Install			
Chute Fed Compactor Cost	\$23,440.00	A500, 3-2CY Towable bins, tax, ship Install			

© American Trash Management, Inc. 2023

Page 22 of 22

Monday, August 28, 2023



1900 Powell Street, Suite 220
Emeryville, CA 94608
(800) 488-7274 Toll Free USA
(415) 292-5400
(415) 292-5410 Fax
www.trashmanage.com

Volume Projections and Analysis Below is a comparative analysis of the disposal costs and labor costs of handling waste and recycling in loose bins or compacted bins. Please note that the projections below are estimates derived from actual audits of comparable multifamily complexes in the San Francisco Bay area. They are not guaranteed. They are to be used for planning purposes only and may be higher or lower than projected.

TOTAL RESIDENTIAL WASTE AND RECYCLING ANALYSIS

ASSUMPTIONS:	UNITS:	70	GALLONS	32
Volume Waste:	0.16	cubic yard/week/unit	32	
Volume Recycling:	0.16	cubic yard/week/unit	32	
Volume Compost:	0.012	cubic yard/week/unit	2	
Compaction Ratio	4	to 1		
Staff Labor Rate	\$21.00	per hour - 1 person		
Time move bins	0.25	hr to move to unloading area & back		
Rake-Rotate bins	0.15	hr to go to each bin rake or rotate		
# of Trash Rooms	1			
Compacted Waste Service	2	cubic yard front load bins		
Compacted Recycle Service	2	cubic yard front load bins		
Loose Waste Service	3	cubic yard front load bins		
Loose Recycling Service	3	cubic yard front load bins		
Loose Compost Service	0.32	cubic yard carts (64 G Toter Carts)		

COST BENEFIT CALCULATION	PROJECTED	PROJECTED	PROJECTED
SERVICE-Waste	Loose	Compacted	Compacted
SERVICE-Recycling	Loose	Compacted	Compacted
Loose Waste Volume - CY	11.2	2.8	2.8
Compacted Waste Volume - CY			
Loose Recycling Volume - CY	11.2	11.2	
Compacted Recycling Volume - CY			
Loose Compost Volume - CY	0.8	0.8	
Compacted Compost Volume - CY			
Waste Bins/week	4	2	2
Recycling Bins/week	4	4	2
Compost Bins/week	3	3	1
Containers/week/trash room	11	9	5
SYSTEM CAPITAL COST	\$0.00	\$20,960.00	\$41,920.00
WASTE COST/MONTH	\$1,864.39	\$1,269.56	\$1,269.56
RECYCLING COST/MONTH	\$0.00	\$0.00	\$0.00
COMPOST COST/MONTH	\$203.26	\$203.26	\$203.26
TRASH COST/MONTH	\$2,067.65	\$1,472.82	\$1,472.82
COMPACTION SAVINGS/MONT	\$0.00	\$594.83	\$594.83
STAFF LABOR COST/MONTH	\$13.89	\$11.20	\$6.22
STAFF SAVINGS/MONTH	\$0.00	\$2.49	\$7.47
NET MONTHLY TRASH COSTS	\$2,081.34	\$1,484.02	\$1,479.04
Monthly Trash Cost per Unit	\$13,008.40	\$9,275.15	\$9,244.03
PAYBACK-MONTHS	N/A	35	70

RESIDENTIAL CARDBOARD ANALYSIS

245

© American Trash Management, Inc. 2023

Page 20 of 22

Monday, August 28, 2023



1900 Powell Street, Suite 220
Emeryville, CA 94608
(800) 488-7274 Toll Free USA
(415) 292-5400
(415) 292-5410 Fax
www.trashmanage.com

OFFICE WASTE AND RECYCLING SYSTEM ANALYSIS

ASSUMPTIONS:	Square Feet	9,115
Lbs/day per 1000 SF	5.44	
% waste	30%	
% recycling	50%	
% compost	20%	
waste lb/CY	80	
recycling lb/CY	80	
compost lb/CY	125	
Compaction Ratio	4	to 1
Loose Waste Service	0.475	cubic yard carts (96 G Toter Carts)
Loose Recycling Service	0.475	cubic yard carts (96 G Toter Carts)
Loose Compost Service	0.32	cubic yard carts (64 G Toter Carts)

COST BENEFIT CALCULATION	PROJECTED	PROJECTED
SERVICE-Waste	Loose	Compacted
SERVICE-Recycling	Loose	Compacted
Loose Waste Volume - CY	0.9	
Compacted Waste Volume - CY		
Loose Recycling Volume - CY	1.5	0.2
Compacted Recycling Volume - CY		
Loose Compost Volume - CY	0.4	
Compacted Compost Volume - CY		0.1
Waste Bins/week	2	
Recycling Bins/week	4	
Compost Bins/week	2	
Containers/week/trash room	8	

© American Trash Management, Inc. 2023

Page 21 of 22

Monday, August 28, 2023

SMITH DEVELOPMENT

660 UNIVERSITY
PALO ALTO, CA 94301



ARCHITECTS
KORTH SUNSERI HAGEY

ISSUES AND REVISIONS

NO.	DATE	DESCRIPTION
12.01.21		PLANNING SUBMITTAL
05.13.22		PLANNING RESUBMITTAL #1
08.15.22		PLANNING RESUBMITTAL #2
11.02.22		PLANNING RESUBMITTAL #3
08.28.23		PLANNING RESUBMITTAL #4
10.31.23		PLANNING RESUBMITTAL #5
12.21.23		PLANNING RESUBMITTAL #6
02.07.24		PLANNING RESUBMITTAL #7

PROJECT NUMBER
21003

SHEET TITLE

TRASH MANAGEMENT PLAN

SCALE

N.T.S.

SHEET NUMBER

TR3.4



Dero Decker


The Dero Decker takes bike parking to the next level – literally. By stacking bikes on a two-tiered system, capacity doubles. Unlike other two-tier systems our lift-assist top trays slide down inches from the ground, thus requiring only minimal lifting of the bike into the tray. The Dero Decker has a front wheel safety locking lever and tray dampers to provide safe lowering of upper trays. The near vertical lowered trays also reduce the required aisle space, giving the Dero Decker the smallest footprint on the market.

Patent #8,950,592

©2021

DERO **DERO Decker**


Setbacks Single Sided



©2021

DERO **DERO Decker**



Setbacks Double Sided



©2021

2 HORIZONTAL BIKE RACK CUT SHEETS

N.T.S.



1 ENLARGED OFFICE BIKE ROOM

1/4"=1'-0"

3 ENLARGED OFFICE BIKE ROOM

1/4"=1'-0"

SMITH DEVELOPMENT

660 UNIVERSITY
PALO ALTO, CA 94301



ARCHITECTS
KORTH SUNSERI HAGEY

ISSUES AND REVISIONS		
NO.	DATE	DESCRIPTION
05.13.22		PLANNING RESUBMITTAL #1
08.15.22		PLANNING RESUBMITTAL #2
11.02.22		PLANNING RESUBMITTAL #3
08.28.23		PLANNING RESUBMITTAL #4
10.31.23		PLANNING RESUBMITTAL #5
12.21.23		PLANNING RESUBMITTAL #6
02.07.24		PLANNING RESUBMITTAL #7

PROJECT NUMBER
21003

SHEET TITLE
**LONG TERM BIKE STORAGE
PARKING LEVEL P1**

SCALE
1/4" = 1'-0"

PROJ NORTH
0 4'-0" 8'-0"

SHEET NUMBER

A2.P0-A




Ultra Space Saver™ Squared

Submittal Sheet



Ultra Space Saver™ Squared

Setbacks




Ultra Space Saver™ Squared


Dero's Ultra Space Saver Squared offers high-security, vertical bike parking. Adjustable sliding arms make it easy for customers to best utilize their space. It also creates flexibility to make sure bike spacing follows city requirements as they evolve. Pipe-cutter resistant squared steel tubing makes the Ultra Space Saver Squared more secure than the original Ultra Space Saver.

Patent D774,441


©2023



(Examples above show 62" long crossbar sections)



Ultra Space Saver Squared sections vary in length to fit most spaces. Above are common crossbar lengths for arms spaced 16"OC.



As a general guideline, the above space can fit approximately 60 bicycles.

The Ultra Space Saver Squared parks one bike every 16" with a typical bike extending out 42" from the wall.

CAPACITY Modular construction
1 bike per arm

MATERIALS **Hanger:** 1" square tube with steel slider head with tamperproof locking bolts.
Upright: 2" square tube.
Feet: AISI C3 x 4.1 galvanized steel channel.
Crossbeams: 1.25" sched. 40 galvanized pipe.


FINISHES ☒ **Black Powder Coat (Interior Use)**
Our interior powder coat finish assures a high level of adhesion and durability for indoor use by following these steps:
1. Sandblast
2. Final thick TGIC polyester powder coat
☐ **Black Powder Coat (Exterior Use)** Additional Cost
Our exterior powder coat finish assures a high level of adhesion and durability for outdoor or exposed air use by following these steps:
1. Sandblast
2. Epoxy primer electrostatically applied
3. Final thick TGIC polyester powder coat

MOUNT OPTIONS ☒ **Floor mount**
Ultra Space Saver Squared have steel channel feet (30" for single sided and 56" for double sided units) which must be anchored to the floor.
☐ **Wall mount**
A wall mounted unit which contains special brackets is also available for CMU or solid concrete walls. Cannot be used on sheetrock without additional support.

WHEEL STOPS ☐ **Include wheel stops**
Optional wheel stops are available for both floor and wall mounted racks for an additional cost

CANE STOPS ☐ **Include cane stops**
Optional cane-detectable stops are available for both floor and wall mounted racks for an additional cost


©2023



©2023


3 VERTICAL BIKE RACK CUT SHEETS

N.T.S.



1 ENLARGED RESIDENTIAL BIKE ROOM #1 PLAN (P2 LEVEL)

1/4"=1'-0"



2 ENLARGED RESIDENTIAL BIKE ROOM #2 (P1 LEVEL)

1/4"=1'-0"

SMITH DEVELOPMENT

660 UNIVERSITY
PALO ALTO, CA 94301



ISSUES AND REVISIONS

NO.	DATE	DESCRIPTION
05.13.22		PLANNING RESUBMITTAL #1
08.15.22		PLANNING RESUBMITTAL #2
11.02.22		PLANNING RESUBMITTAL #3
08.28.23		PLANNING RESUBMITTAL #4
10.31.23		PLANNING RESUBMITTAL #5
12.21.23		PLANNING RESUBMITTAL #6
02.07.24		PLANNING RESUBMITTAL #7

PROJECT NUMBER
21003

SHEET TITLE
LONG TERM BIKE STORAGE
PARKING LEVEL P1 & P2

SCALE
1/4" = 1'-0"
0 4'-0" 8'-0"



SHEET NUMBER

A2.P0-B

data sheet **DE-48**



DE-48 is our aesthetically designed, interactively controlled, parking-system with easy access of the parking surface for both car and driver.


A2

EASY TO PLAN with space saving construction.


EASY TO INSTALL with minimized parts construction.

EASY TO USE due to barrier free construction.


DE-48 data sheet



DE-48 data sheet



DE-48 data sheet



DE-48 data sheet



DE-PARK IS MAKING YOUR LIFE EASY:

GERMAN MADE WITH A SLIM & MODULAR DESIGN
EASY PLANNING AND SETUP

LOW MAINTENANCE CONSTRUCTION
EASY TO USE WITH LOW NOISE EMISSIONS

NO PILLARS IN THE ENTRY AND PEDESTRIAN AREA
EASY MANOEUVERING AND SENSORLESS POSITIONING

FLAT & CONTINUOUS PLATFORM
EASY TO CLEAN AND COMFORTABLE TO WALK ON



DE-PARK GmbH
Brühl 6
04109 Leipzig
Germany

Phone: 0049 (0)341 - 24700 131
Fax: 0049 (0)341 - 24700 132
Email: info@de-park.com
Web: www.de-park.com

SMITH DEVELOPMENT

660 UNIVERSITY
PALO ALTO, CA 94301



ISSUES AND REVISIONS

NO.	DATE	DESCRIPTION
	05.13.22	PLANNING RESUBMITTAL #1
	08.15.22	PLANNING RESUBMITTAL #2
	11.02.22	PLANNING RESUBMITTAL #3
	08.28.23	PLANNING RESUBMITTAL #4
	10.31.23	PLANNING RESUBMITTAL #5
	12.21.23	PLANNING RESUBMITTAL #6
	02.07.24	PLANNING RESUBMITTAL #7

PROJECT NUMBER
21003

SHEET TITLE
**PARKING LIFT CUT SHEETS
PARKING LEVEL P2**

SCALE
N.T.S.

SHEET NUMBER

A2.P0-C



NOTE:
ALL PROPOSED STACKER STALLS (2 EA. STACKER) TO INCORPORATE EV CHARGER OR BE PROVIDED WITH AN EV CHARGER READY OUTLET, TYP. AT ALL P2 LEVEL STALLS AS REQUIRED. IMAGE ABOVE IS AN EXAMPLE OF A SIMILAR INSTALLATION. DETAILS & CONFIGURATION WILL BE PROVIDED IN THE FUTURE BUILDING PERMIT SUBMITTAL.