APN 127-35-200

LANDS OF SUTTER 739

ASSOCIATES, LLC

(RESIDENTIAL USE)

SUTTER AVENUE

LOCATION MAP

SCALE: 1"=40'

1. OWNER/SUBDIVIDER: 739 SUTTER ASSOCIATES, LLC

> P.O. BOX 6563 SAN MATEO, CA 94403 CONTACT: GRACE LI PHONE: (510) 857-4567

EMAIL: GRACELI_1999@YAHOO.COM

2. MAP PREPARED BY:

1730 N. FIRST STREET, SUITE 600 SAN JOSE, CA, 95112 CONTACT: PHONG KIET

PHONE: (408) 467-9100 EMAIL: PKIETOBKF.COM

3. APN: 127-35-200

MULTI-FAMILY RESIDENTIAL: 4. GENERAL PLAN USE: 16,720 SF

5. NEIGHBORHOOD: **MIDTOWN**

6. EXISTING LAND USE: RESIDENTIAL

7. PROPOSED LAND USE: MULTI-FAMILY RESIDENTIAL

8. EXISTING ZONING: MULTI-FAMILY RESIDENTIAL (RM-20): 16,720± SF

9. WATER SUPPLY: CITY OF PALO ALTO

10. POWER AND GAS SUPPLY: CITY OF PALO ALTO 11. TELEPHONE: COMCAST

13. NO. OF EXISTING LOTS:

12. INTERNET:

14. NO. OF PROPOSED LOTS: 1

15. TOTAL GROSS ACREAGE: 0.38± ACRES


FATTY CLAY/LEAN CLAY WITH SAND 16. SOIL TYPE:

AT&T

17. DEPTH TO GROUNDWATER: 10' TO 15'

18. FLOOD ZONE ELEVATION: ZONE X

19. NO. OF UNITS PROPOSED: 12 RESIDENTIAL CONDOMINIUM UNITS



VICINITY MAP

SHEET INDEX

C6.0 PRELIMINARY UTILITY PLAN	<u>SHEET</u>	<u>DESCRIPTION</u>
THE ENWINDER OF THE PARTY OF TH	C2.0 C3.0 C4.0 C5.0	VESTING TENTATIVE MAP EXISTING CONDITIONS PRELIMINARY SITE PLAN PRELIMINARY GRADING AND DRAINAGE PLAN

LEGEND

PROPERTY LINE ADJACENT LOT LINE STREET CENTER LINE PROJECT AREA

BASIS OF BEARINGS:

THE BEARINGS SHOWN ON THIS MAP ARE BASED ON THE GPS OBSERVATION.

ELEVATION DATUM:

THE ELEVATIONS SHOWN ARE BASED ON FOUND EXISTING CONTROL POINTS PROVIDED BY TOPOGRAPHIC SURVEY PREPARED BY LC ENGINEERING IN MAY, 2021.

ABBREVIATIONS

<u>SYMBOL</u>	DESCRIPTION	<u>SYMBOL</u>	<u>DESCRIPTION</u>
CVC DIA DWG ECR EL EP E.V.A.E. EVC EX	BUILDING BENCH MARK BACK OF WALK/ BOTTOM OF WALL CURB & GUTTER CENTERLINE CONCRETE CURB RETURN	LG MH MON (N) N.G.V.D. NO., # NTS PCC PL PT PV R RCP RT ROW (S) ST. STD SW TYP. VC VIF W/ (W)	LIP OF GUTTER MANHOLE MONUMENT NORTH/NEW NATIONAL GEODETICS VERTICAL DATUM NUMBER NOT TO SCALE PORTLAND CEMENT CONCRETE PROPERTY LINE POINT PAVEMENT RADIUS REINFORCED CONCRETE PIPE RIGHT RIGHT OF WAY SOUTH STREET STANDARD SIDEWALK TYPICAL VERTICAL CURVE VERIFY IN FIELD WITH WEST

NTS **DESCRIPTION**

VESTING 739 SU

BKF ENGINEERS1730 N. FIRST STREET

BK

Scale: AS SHOWN	Design: CA/JH	Drawn: JH	Approved: PK	Job No: C20220187

Drawing Number: **C1.0**


NOTES:


1. THE FILING OF THIS VESTING TENTATIVE MAP IS CONCURRENT TO THE 739 SUTTER AVENUE ARCHITECTURAL REVIEW BOARD PACKAGE (PLN# 22PLN-00201).

2. THIS MAP PROVIDES FOR THE CREATION OF A SINGLE, DEVELOPABLE LOT TO BE FURTHER SUBDIVIDED VIA SEPARATE RESIDENTIAL CONDOMINIUM MAP INTO 12 RESIDENTIAL CONDOMINIUM UNITS.

3. UTILITY DEDICATIONS: THE ON-SITE STORM DRAIN, SANITARY SEWER, AND WATER SYSTEMS WILL BE PRIVATELY MAINTAINED.

4. A WAIVER IS REQUESTED UNDER STATE DENSITY BONUS LAW TO THE REQUIRED STREET WIDTH.





BKF ENGINEERS1730 N. FIRST STREET
SUITE 600
SAN JOSE, CA 95112
(408) 467-9100






ENCE EX 39





Design: CA/JH	Drawn: JH	Approved: PK	Job No: C20220187

Drawing Number:

C3.0














PRELIMIN

Drawing Number:


C6.0 6 of 7







TRANSVERSE SECTION



LONGITUDINAL SECTION N.T.S.

NOTE:

- 1. BACKFILL BIORETENTION ONLY WITH PERMEABLE PLANTING MATERIAL AND DRAIN ROCK AS SPECIFIED IN THIS DETAIL. ABSOLUTELY NO NATIVE MATERIAL SHALL BE USED FOR BACKFILL. CONTRACTOR MUST COORDINATE WITH CIVIL ENGINEER PRIOR TO CONSTRUCTION.
- 2. DRAIN ROCK TO BE CLASS 2 PERMEABLE MATERIAL PER CALTRANS STANDARD SPECIFICATIONS, SECTION 68-2.02F.
- 3. PERFORATED PIPE SHALL BE SOLVENT WELD PVC SDR 35 (OR APPROVED EQUAL) WITH PERFORATIONS FACED
- DOWN. LOCATION OF THE PIPE VARIES, SEE PLAN.
- 4. FOR ANY HORIZONTAL LINER PENETRATIONS, RADIAL—CUT THE LINER FOR PIPE. MASTIC AND SEAL WITH PIPE CLAMP TO INSURE WATER—TIGHT SEAL.

BIORETENTION BASIN SECTION

LEGEND

BOUNDARY LINE

LOT LINE

EASEMENT LINE

ROADWAY CENTER LINE


ASPHALT CONCRETE

PCC CONCRETE

GRASS PAVER

BIORETENTION BASIN

DRAINAGE MANAGEMENT AREA



STORM DRAIN (TREATED)

STORM DRAIN JUNCTION BOX

FLOW DIRECTION (PLANTING AREA)

NOTES:

1. STORMWATER BEST MANAGEMENT PRACTICES (BMPS) ASSOCIATED WITH REFUSE MANAGEMENT (INCLUDING ACTIONS RELATED TO REFUSE PICK-UP AND THE ENCLOSURE ITSELF) SHALL BE FOLLOWED TO ENSURE POLLUTION PREVENTION AND PREVENTING POTENTIAL DISCHARGES TO THE CITY'S STORM DRAIN SYSTEM. STORMWATER BMPS INCLUDE, BUT ARE NOT LIMITED TO, POWER WASHING THE PAVEMENT ON BOTH THE PRIVATE PROPERTY AND IN THE RIGHT-OF-WAY AND SIDEWALK A MINIMUM OF ONCE PER YEAR BEFORE THE WET SEASON BEGINS ON OCTOBER 1ST; UTILIZING A POWER WASHING CONTRACTOR THAT IS A RECOGNIZED SURFACE CLEANER BY THE BAY AREA STORMWATER MANAGEMENT AGENCIES ASSOCIATION (BASMAA); DISPOSING OF WASH WATER ACCORDING TO THE RECOGNIZED SURFACE CLEANER CERTIFICATION REQUIREMENTS; AND REMOVING ANY POTENTIAL TRASH BUILD-UP ON A REGULAR BASIS.

2. DURING THE BEGINNING OF THE CONSTRUCTION, THE PROJECT APPLICANT SHALL ARRANGE FOR A SITE VISIT (INSPECTION) BY A THIRD-PARTY REVIEWER ACCEPTABLE TO THE CITY OF PALO ALTO THAT THE INSTALLED STORMWATER TREATMENT MEASURES HAVE BEEN CONSTRUCTED IN ACCORDANCE WITH THE APPROVED BUILDING PLANS. THE THIRD-PARTY REVIEWER WILL RECOMMEND THE REQUIRED NUMBER OF SITE INSPECTIONS AT DIFFERENT INTERVALS OF CONSTRUCTION. THE THIRD-PARTY REVIEWER MUST BE A CIVIL ENGINEER. ARCHITECT OR LANDSCAPE ARCHITECT REGISTERED IN THE STATE OF CALIFORNIA AND MUST HAVE A CURRENT TRAINING ON STORMWATER TREATMENT DESIGN. A LIST OF QUALIFIED THIRD-PARTY REVIEWERS CAN BE FOUND ON THE SANTA CLARA VALLEY URBAN RUNOFF POLLUTION PREVENTION PROGRAM (SCVURPPP) WEBSITE AT WWW.SCVURPPP-W2K.COM/CONSULTANTS_LIST.SHTML.

3. PERMEABLE PLANTING MATERIAL SHOULD MEET THE BIOTREATMENT SOIL MIX (BSM) SPECIFICATIONS PER SCYURPPP C.3 STORMWATER HANDBOOK, APPENDIX C.

4. CITY TO APPROVE SURFACE RELEASE FROM BUBBLER ASSEMBLY TO STREET OVER SIDEWALK.

5. PAMC 16.09.165(H) STORM DRAIN LABELING: STORM DRAIN INLETS SHALL BE CLEARLY MARKED WITH THE WORDS "NO DUMPING — FLOWS TO [CREEK]," OR EQUIVALENT.

VESTING TENTATI 739 SUTTER AN PRELIMINARY STORMWATER

BKF ENGINEERS1730 N. FIRST STREET
SUITE 600
SAN JOSE, CA 95112
(408) 467-9100
www.bkf.com

 \mathbf{m}

Z

4

7

ONTR

ス 山

PROFESSIONAL CHAZAN - I FO

Scale: AS SHUWIN	Design: CA/JH	Drawn: JH	Approved: PK	; ;
ë	igr	Ň	ပ	-
Sca	Desi	Dra	Арр	-

Drawing Number:

C7.0

	TREATMENT CONTROL MEASURE SUMMARY													
DRAINAGE AREAS	DRAINAGE AREA SIZE (SF)	PERVIOUS SURFACE PERVIOUS PAVEMENT (SF)	PERVIOUS SURFACE OTHER (SF)	TYPE OF PERVIOUS SURFACE	IMPERVIOUS SURFACE (SF)	IMPERVIOU ROOF (C=0.90)	SURFACE CONCRETE (C=0.90)	TYPE (SF) PAVING (C=0.90)	SIZING CALCULATION	PONDING DEPTH (IN)	TREATMENT REQUIRED (SF)	TREATMENT PROVIDED (SF)	PROPOSED TREATMENT CONTROLS	NOTES
A-1	18,354	2,240	3,364	LANDSCAPE (C=0.30)	12,750	7,955	2,088	2,707	4% RULE	6	510	515	<u>BR-1</u> BIORETENTION BASIN 1	


City of Palo Alto


Tree Protection - It's Part of the Plan!


Make sure your crews and subs do the job right!

Fenced enclosures around trees are essential to protect them by keeping the foliage canopy and branching structure clear from contact by equipment, materials and activities, preserving roots and soil conditions in an intact and non-compacted state, and identifying the Tree Protection Zone (TPZ) in which no soil disturbance is permitted and activities are restricted, unless otherwise approved. An approved tree protection report must be added to this sheet when project activity occurs within the TPZ of a regulated tree.

For detailed information on Palo Alto's regulated trees and protection during development, review the City Tree Technical Manual (TTM) found at www.cityofpaloalto.org/trees/.







5	1	APPENDIX J PALO ALTO
*()	# *	STREET TREE PROTECTION INSTRUCTIONSSECTION 31
 1-1	Genera	
	a.	Tree protection has three primary functions, 1) to keep the foliage canopy and branching structure clear from contact by equipment, materials and activities; 2) to preserve roots and soil conditions in an intact and non-compacted state and 3) to identify the Tree Protection Zone (TPZ) in which no soil disturbance is permitted and activities are restricted, unless otherwise approved.
	b.	The Tree Protection Zone (TPZ) is a restricted area around the base of the tree with a radius of ten-times the diameter of the tree's trunk or ten feet; whichever is greater, enclosed by fencing.
1-2	Referen	ce Documents
	a. b.	Detail 605 – Illustration of situations described below. Tree Technical Manual (TTM) Forms (http://www.cityofpaloalto.org/trees/)
	υ.	Trenching Restriction Zones (TTM, Section 2.20(C))
		2. Arborist Reporting Protocol (TTM, Section 6.30)
		 Site Plan Requirements (<u>TTM, Section 6.35</u>) Tree Disclosure Statement (<u>TTM, Appendix J</u>)
	c.	Street Tree Verification (STV) Form (http://www.cityofpaloalto.org/trees/forms)
1-3	Executi	on
1-3	a.	Type I Tree Protection: The fence shall enclose the entire TPZ of the tree(s) to be protected throughout the life of the construction project. In some parking areas, if fencing is located on paving or concrete that will not be demolished, then the posts may be supported by an appropriate grade level concrete base, if approved by Public Works Operations.
	b.	Type II Tree Protection: For trees situated within a planting strip, only the planting strip and yard side of the TPZ shall be enclosed with the required chain link protective fencing in order to keep the sidewalk and street open for public use.
	c.	Type III Tree Protection: To be used only with approval of Public Works Operations. Trees situated in a tree well or sidewalk planter pit, shall be wrapped with 2-inches of orange plastic fencing from the ground to the first branch and overlaid with 2-inch thick wooden slats bound securely (slats shall not be allowed to dig into the bark). During installation of the plastic fencing, caution shall be used to avoid damaging any branches. Major limbs may also require plastic fencing as directed by the City Arborist.
	d.	Size, type and area to be fenced. All trees to be preserved shall be protected with six (6') foot high chain link fences. Fences are to be mounted on two-inch diameter galvanized iron posts, driven into the ground to a depth of at least 2-feet at no more than 10-foot spacing. Fencing shall extend to the outer branching, unless specifically approved on the STV Form.
	e.	'Warning' signs. A warning sign shall be weather proof and prominently displayed on each fence at 20-foot intervals. The sign shall be minimum 8.5-inches x 11-inches and clearly state in half inch tall letters: "WARNING - Tree Protection Zone - This fence shall not be removed and is subject to a fine according to PAMC Section 8.10.110."
	f.	Duration . Tree fencing shall be erected before demolition; grading or construction begins and remain in place until final inspection of the project, except for work specifically allowed in the TPZ. Work or soil disturbance in the TPZ requires approval by the project arborist or City Arborist (in the case of work around Street Trees). Excavations within the public right of way require a Street Work Permit from Public Works.
	g.	During construction
		 All neighbors' trees that overhang the project site shall be protected from impact of any kind. The applicant shall be responsible for the repair or replacement plus penalty of any publicly owned trees that are damaged during the course of construction, pursuant to Section 8.04.070 of the Palo Alto Municipal Code.
		 3. The following tree preservation measures apply to all trees to be retained: a. No storage of material, topsoil, vehicles or equipment shall be permitted within the TPZ. b. The ground under and around the tree canopy area shall not be altered. c. Trees to be retained shall be irrigated, aerated and maintained as necessary to ensure survival.

Table	2-2 Palo Alto Tree Technical Manual
	CONTRACTOR & ARBORIST INSPECTION SCHEDULE
	Reference: the Palo Alto Tree Technical Manual is available at www.cityofpaloalto.org/environment/
ALL CI	HECKED ITEMS APPLY TO THIS PROJECT:
1.	Inspection of Protective Tree Fencing. For Public Trees, the Street Tree Verification Form sha signed by the City Arborist. For Protected Trees, the project site arborist shall provide an initial Monthly Tree Activity Report form with a photograph verifying that he has conducted a field inspection of the trees and that the correct type of protective fencing is in place around the designated tree protection zone (TPZ) prior to issuance of a demolition, grading, or building per (See TTM, Verification of Tree Protection, Section 1.39).
2. 🛂	Pre-Construction Meeting. Prior to commencement of construction, the applicant or contractor conduct a pre-construction meeting to discuss tree protection with the job site superintendent, grading operators, project site arborist, City Arborist, and, if a city maintained irrigation system involved, the Parks Manager (Contact 650-496-6962).
3. 🗹	Inspection of Rough Grading or Trenching. Contractor shall ensure the project site arborist performs an inspection during the course of rough grading or trenching adjacent to or within the TPZ to ensure trees will not be injured by compaction, cut or fill, drainage and trenching, and if required, inspect aeration systems, tree wells, drains and special paving. The contractor shall prothe project arborist at least 24 hours advance notice of such activity.
4. 🗹	Monthly Tree Activity Report Inspections. The project site arborist shall perform a minimum monthly activity inspection to monitor and advise on conditions, tree health and retention or, immediately if there are <i>any revisions</i> to the approved plans or protection measures. The Tree Technical Manual Monthly Tree Activity Report format shall be used and sent to the Planning D landscape review staff no later than 14 days after issuance of building permit date. Fax to (650) 3 2154. (See TTM, Monthly Tree Activity Inspection Report, Addendum 11 & section 1.17).
5. 🗹	Special activity within the Tree Protection Zone. Work in the TPZ area (see also #7 below) requires the direct onsite supervision of the project arborist (see TTM, Trenching, Excavation & Equipment, Section 2.20 C).
6.	Landscape Architect Inspection. For discretionary development projects, prior to temporary or final occupancy the applicant or contractor shall arrange for the Landscape Architect to perform on site inspection of all plant stock, quality of the materials and planting (see TTM, Planting Quality, Section 5.20.1 A) and that the irrigation is functioning consistent with the approved construction plans. The Planning Dept. landscape review staff shall be in receipt of written verification of Landscape Architect approval prior to scheduling the final inspection, unless otherwise approved.
7.	List Other (please describe as called out in the site Tree Preservation Report, Sheet T-1, T-2, et

City of Palo Al Tree Department Public Works Operations PO Box 10250 Palo Alto, CA 650/496-5953 FAX: 650/85; treeprotection@CityofPaloA	A 94303 2-9289	Verification of Street Tree Protection
		form. Mail or FAX this form along with signed Tree orks Tree Staff will inspect and notify applicant.
APPLICATION DATE:		
ADDRESS/LOCATION OF STREET TREES TO BE PROTECTED:		
APPLICANT'S NAME:		
APPLICANT'S ADDRESS:		
APPLICANT'S TELEPHONE & FAX NUMBERS:		
This section to be filled out by City Tree St	aff	
The Street Trees at the above address(es) are adequately protected. The type of protection used is:		YES NO* \(\bigcap \) * If NO, go to #2 below
Inspected by:		
Date of Inspection:		
The Street Trees at the above address are <u>NOT</u> adequately protected. The following modifications are required: Indicate how the required modifications were communicated to the applicant.		
Subsequent Inspection		
Street trees at above address were found to be adequately protected:	*	YES NO* If NO, indicate in "Notes" below the disposition of case.
Inpsected by:		
Date of Inspection:		
Notes: List City street trees by species, site, condition and type of tree protection installed. Also note if pictures were taken. Use back of sheet if necessary.		
Return approved sheet to Applicant for S:PWD/OPS/Tree/DS/St.TreeProtect	demolition	or building permit issuance.

	Firm Data Here		e RCA/ISA Certified Arborist #WE Contact C
	Monthly Tree /	Activity Repo	rt- Construction Site
Inspection Date:		Contractor- Main Site Contact	#1: Job site superintendent Company: Email:
Inspection #	Palo Alto, CA	Information	Job site Office: Cell: Mail:
		Also present:	:
Distributio	n: 1. City of Palo Alto 2. Others	Attn: Dave Dockter	Dave.dockter@cityofpaloalto.org 650-329-2440
			stomize as necessary. To be completed by proje project completion. Use additional sheets as
2. Field Ob a. Tre b. Tre 3. Action It a. Tre b. Roo c. Sch 4. Photogra	servations (general site-weel Protection Fences (TPF) inching has/will occur sems (list site-wide, by treel Protection Fence (TPF) of zone buffer material (weel weel to be sewer trench, found the sewer trench, found the sewer trench (weel the sewer trench) is at ion Map (mandatory 8.3) included the sewer trench (weel the sewer trench) is at ion Map (mandatory 8.3) included the sewer trench (weel the sewer trench) is at ion Map (mandatory 8.3) included the sewer trench (weel the sewer trench) is at ion Map (mandatory 8.3) included the sewer trench (weel the sewer	ride and list by individe) are e number and date to be needs adjusting (tree stood chips) can be instead attion dig with 5 x 11 sheet)	ual tree number) pe satisfied) and Date Due # x, x, x) alled next
		or nems for projects sa	and the second
6. Recomm	ts (list carry-over items sa		
6. Recomm 7. Past visit	ts (list carry-over items sa y submitted,		
6. Recomm 7. Past visit Respectfull Project site	y submitted,	tisfied/still outstandin	g)

---WARNING--Tree Protection Zone

This fencing shall not be removed without City Arborist approval (650-496-5953)

Removal without permission is subject to a \$500 fine per day*

*Palo Alto Municipal Code Section 8.10.110

City of Palo Alto Tree Protection Instructions are located at http://www.city.palo-alto.ca.us/trees/technical-manual.html

SPECIAL INSPECTIONS	PLANNING DEPARTMENT
TREE PROTECTION INSPECTIONS MA	ANDATORY
PAMC 8.10 PROTECTED TREES. CONTRACTOR SHALL ENSURE PROJE REQUIRED TREE INSPECTION AND SITE MONITORING. PROVIDE WRIT REPORTS TO THE PLANNING DEPARTMENT LANDSCAPE REVIEW STA BUILDING PERMIT ISSUANCE.	TEN MONTHLY TREE ACTIVITY
BUILDING PERMIT DATE:	
DATE OF 1 ST TREE ACTIVITY REPORT:	
CITY STAFF:	
REPORTING DETAILS OF THE MONTHLY TREE ACTIVITY REPORT SHA VERIFY THAT ALL TREE PROTECTION MEASURES ARE IMPLIMENTED A ACTIVITY, SCHEDULED OR UNSCHEDULED, WITHIN A TREE PROTEC IS SUBJECT TO VIOLATION OF PAMC 8.10.080. REFERENCE: PAL SECTION 2.00 AND ADDENDUM 11.	AND WILL INCLUDE ALL CONTRACTOR TION ROOT ZONE. NON-COMPLIANCE

Apply Tree Protection Report on sheet(s) T-2

Use addtional "T" sheets as needed

Project Data



All other tree-related reports shall be added to the space provided on this sheet (adding as needed) Include this sheet(s) on Project Sheet Index or Legend Page.

A copy of T-1 can be downloaded at

http://www.cityofpaloalto.org/civica/filebank/blobdload.asp?BlobID=6460





City of Palo Alto Tree Protection - It's Part of the Plan!

Make sure your crews and subs do the job right!

Fenced enclosures around trees are essential to protect them by keeping the foliage canopy and branching structure clear from contact by equipment, materials and activities, preserving roots and soil conditions in an intact and non-compacted state, and identifying the Tree Protection Zone (TPZ) in which no soil disturbance is permitted and activities are restricted, unless otherwise approved. An approved tree protection report must be added to this sheet when project activity occurs within the TPZ of a regulated tree. For detailed information on Palo Alto's regulated trees and protection during development, review the City Tree Technical Manual (TTM) found at www.cityofpaloalto.org/trees/.

> Apply Tree Protection Report on sheet(s) T-2 Use additional "T" sheets as needed